# 1 Q. Reference: Reliability and Resource Adequacy Study 2022 Update, Volume III, page 42, line 17 2 to page 43, line 5.

Describe all studies and analyses performed of alternatives considered for comparison of the generation/capacity addition alternatives, including comparisons of costs, schedules, needed operating characteristics and risks. Include in the response the date each generation addition alternative was first studied and when it was last revised and updated. Provide copies of any performed.

- 8
- 9

| 10 | Α. | Most of Newfoundland and Labrador Hydro's ("Hydro") portfolio of available resource options             |
|----|----|---|
| 11 |    | has consistently been included in resource planning assessments spanning decades. Most                  |
| 12 |    | recently, in the 2018 "Reliability and Resource Adequacy Study" ("2018 Filing"), <sup>1</sup> renewable |
| 13 |    | resource options, such as solar generation and battery storage technology, have been included           |
| 14 |    | in the resource mix as advances in technology have improved reliability and cost considerations.        |
| 15 |    | The following resource options were discussed at length in the 2018 Filing and the costs                |
| 16 |    | escalated in the "Reliability and Resource Adequacy Study – 2019 Update" ("2019 Update"). <sup>2</sup>  |
| 17 |    | Hydro contracted external consultants to provide cost estimates and schedule updates for the            |
| 18 |    | "Reliability and Resource Adequacy Study – 2022 Update" ("2022 Update"). <sup>3</sup> The resource      |
| 19 |    | alternatives listed herein have been considered in the Reliability and Resource Adequacy                |
| 20 |    | Studies.  |

<sup>&</sup>lt;sup>1</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018).

<sup>&</sup>lt;sup>2</sup> "Reliability and Resource Adequacy Study – 2019 Update," Newfoundland and Labrador Hydro, November 15, 2019.

<sup>&</sup>lt;sup>3</sup> "Reliability and Resource Adequacy Study – 2022 Update," Newfoundland and Labrador Hydro, October 3, 2022.

#### 1 Wind Generation

2 Wind generation has been studied as a generation alternative by Hydro for several decades and 3 is updated on a regular basis. The "NL Hydro Wind Generation Alternative: Project Development 4 Estimate,"<sup>4</sup> was provided in support of the 2018 Filing.<sup>5</sup> Project costs were escalated to 2019 5 dollars in support of the 2019 Update. Please refer to PUB-NLH-288, Attachment 1 for the 6 updated cost estimate Hydro received from Hatch Ltd. ("Hatch") in support of the 2022 Update.<sup>6</sup>

#### 7 Solar Generation

- 8 Solar generation as a resource expansion alternative was first included in the 2018 Filing.<sup>7,8</sup>
- 9 Project costs were escalated to 2019 dollars in support of the 2019 Update. Please refer to PUB-
- 10 NLH-288, Attachment 2 for the updated cost estimate Hydro received from Wood Canada
- 11 Limited ("Wood") in support of the 2022 Update.<sup>9</sup>

#### 12 Battery Generation

- 13 Batteries as a resource expansion alternative were first included in the 2018 Filing.<sup>10,11</sup> Project
- 14 costs were escalated to 2019 dollars in support of the 2019 Update. Please refer to PUB-NLH-
- 15 288, Attachment 3 for the updated cost estimate Hydro received from Wood in support of the
- 16 2022 Update.<sup>12</sup>

<sup>9</sup> "Solar Project Preliminary Cost Estimate," Wood Canada Limited, August 22, 2022.
 <sup>10</sup> "NL Hydro Battery Storage Alternative: Project Development Estimate," New Colliers Ltd., November 2, 2018.

<sup>&</sup>lt;sup>4</sup> "NL Hydro Wind Generation Alternative: Project Development Estimate," New Colliers Ltd., November 3, 2018.

<sup>&</sup>lt;sup>5</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018), vol. III, att. 5.

<sup>&</sup>lt;sup>6</sup> "Wind Integration Study – Project Cost Estimate," Hatch Ltd., July 14, 2022.

<sup>&</sup>lt;sup>7</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018), vol. III, att. 6.

<sup>&</sup>lt;sup>8</sup> "NL Hydro Solar Generation Alternative: Project Development Estimate," New Colliers Ltd., November 2, 2018.

 <sup>&</sup>lt;sup>11</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018), vol. III, att. 7.

<sup>&</sup>lt;sup>12</sup> "BESS Project Preliminary Cost Estimate," Wood Canada Limited, August 22, 2022.

#### 1 New Hydroelectric Generation Developments

- 2 Hydro has considered the following new hydroelectric generation developments as potential
- 3 resource options since before the 1980s:

#### 4 Island Pond Hydroelectric Development

- 5 The cost estimate for the construction of the Island Pond Hydroelectric Generating Station was
- 6 derived from the report, "Studies for Island Pond Hydroelectric Project,"<sup>13</sup> and updated by SNC-
- 7 Lavalin in 2012. To support the 2018 Filing, the 2012 estimate was derived by escalating the
- 8 2012 costs to 2018 dollars.<sup>14</sup> The cost was further escalated to 2019 dollars in support of the
- 9 2019 Update. Please refer to PUB-NLH-288, Attachment 4 for the "Evaluation of Island
- 10 Hydroelectric Generation Expansion Alternatives."

### 11 Portland Creek Hydroelectric Development

- 12 The cost estimate for the construction of the Portland Creek Hydroelectric Generating Station
- 13 was derived from the 2007 SNC-Lavalin report, "Feasibility Study for Portland Creek
- 14 Hydroelectric Project,"<sup>15</sup> and updated by SNC-Lavalin in 2012. To support the 2018 Filing, the
- 15 2012 estimate was derived by escalating the 2012 costs to 2018 dollars.<sup>16</sup> The cost was further
- 16 escalated to 2019 dollars in support of the 2019 Update. Please refer to PUB-NLH-288,
- 17 Attachment 4 for the "Evaluation of Island Hydroelectric Generation Expansion Alternatives."
- 18 Round Pond Hydroelectric Development

20

- 19 The cost estimate for the construction of the Round Pond Hydroelectric Generating Station was
  - derived from the report, "Round Pond Feasibility Study."<sup>17</sup> To support the 2018 Filing, the
- 21 estimate was derived by escalating the 2012 costs to 2018 dollars.<sup>18</sup> The cost was further

<sup>&</sup>lt;sup>13</sup> "Studies for Island Pond Hydroelectric Project," SNC-Lavalin, December 2006,

<sup>&</sup>lt;https://www.assembly.nl.ca/business/electronicdocuments/MuskratFalls/Exhibit5b-IslandPond.pdf>. <sup>14</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018), vol. III, att. 8.

<sup>&</sup>lt;sup>15</sup> "Feasibility Study for Portland Creek Hydroelectric Project," SNC-Lavalin, 2007.

<sup>&</sup>lt;sup>16</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018), vol. III, att. 9.

<sup>&</sup>lt;sup>17</sup> "Round Pond Feasibility Study," Shawinigan Newfoundland Ltd., 1988.

<sup>&</sup>lt;sup>18</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018), vol. III, att. 10.

- 1 escalated to 2019 dollars in support of the 2019 Update. Please refer to PUB-NLH-288, 2 Attachment 4 for the "Evaluation of Island Hydroelectric Generation Expansion Alternatives." 3 Exploits River Hydroelectric Generation Expansion: Badger Chute and Red Indian Falls The cost estimate for the construction of the Badger Chute and Red Indian Falls Hydroelectric 4 5 Generation alternatives were originally developed in 1979 as part of an Exploit's River Hydro Inventory Study, completed by Shawmont Newfoundland Ltd. for Price (Newfoundland) Pump 6 7 and Paper Ltd. The Badger Chute alternative was revisited in 2002 by AMEC E&C Services Ltd, 8 where it was the subject of a high-level concept review and cost update. The estimate was later 9 updated in 2005 by SGE Acres Ltd. To support the 2018 Filing, the estimate was derived by escalating the 2012 costs to 2018 dollars.<sup>19</sup> The cost was further escalated to 2019 dollars in 10 support of the 2019 Update. Please refer to PUB-NLH-288, Attachment 4 for the "Evaluation of 11 Island Hydroelectric Generation Expansion Alternatives." 12 13 Additional Generation at Existing Hydroelectric Generation Facilities 14 Hydro has considered the following hydroelectric generation developments at existing hydroelectric generation facilities as potential resource options since the 1980s: 15 Unit 8 at the Bay d'Espoir Hydroelectric Generating Facility ("Bay d'Espoir Unit 8") 16 The cost estimate for the construction of Bay d'Espoir Unit 8 is an AACE<sup>20</sup> Class 3 Estimate 17 completed by SNC-Lavalin in 2017.<sup>21</sup> The cost was further escalated to 2019 dollars in support of 18 19 the 2019 Update. Please refer to PUB-NLH-288, Attachment 4 for the "Evaluation of Island 20 Hydroelectric Generation Expansion Alternatives."
- 21 Unit 3 at the Cat Arm Hydroelectric Generating Station ("Cat Arm Unit 3")
- 22 The original cost estimate for the addition of Cat Arm Unit 3 was originally prepared by
- 23 Shawmont Newfoundland Ltd. in 1985. The cost estimate for the construction of the Round

<sup>&</sup>lt;sup>19</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018), vol. III, att. 11.

<sup>&</sup>lt;sup>20</sup> Association for the Advancement of Cost Engineering ("AACE").

<sup>&</sup>lt;sup>21</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018), vol. III, att. 12.

Pond Hydroelectric Generating Station was derived from the report, "Round Pond Feasibility
 Study," Shawinigan Newfoundland Ltd. in 1988. To support the 2018 Filing, the estimate was
 derived by escalating the 2012 costs to 2018 dollars.<sup>22</sup> The cost was further escalated to 2019
 dollars in support of the 2019 Update. Please refer to PUB-NLH-288, Attachment 4 for the
 "Evaluation of Island Hydroelectric Generation Expansion Alternatives."

#### 6 Thermal Generation

Hydro has consistently considered simple-cycle and combined-cycle combustion gas turbines as 7 a potential resource options. A "Gas Turbine Alternatives Report"<sup>23</sup> was provided In support of 8 the 2018 Filing.<sup>24</sup> Project costs were escalated to 2019 dollars in support of the 2019 Update. 9 The proposed federal "Clean Electricity Standard" has raised questions about resource options 10 that would traditionally have been recommended, including whether they will be a viable future 11 12 resource option (i.e., fossil fuel-burning combustion turbine). In the 2022 Update, Hydro 13 committed to continue to assess thermal generation as a resource option in relation to the proposed Clean Electricity Standard and investigate gas turbines with a renewable fuel source as 14 15 a resource option in the Reliability and Resource Adequacy Study – 2023 Update ("2023 Update"). 16

Hydro reached out to Hatch to review the availability and estimates for combustion turbines
that could utilize bio-diesel or hydrogen fuel. The "Combustion Turbine Screening Final Study
Report,"<sup>25</sup> provided as PUB-NLH-288, Attachment 5, was received after the filing of the 2022
Update. The report considers the use and sourcing of biodiesel, ethanol, and hydrogen to
generate electricity, including technical limitations as well as a Class 5 cost estimate. This report
will be included in the 2023 Update.

- 23 Hydro notes that although it now has further information with respect to gas turbine
- 24 alternatives, in particular the use, sourcing and cost of biofuel technology, a comprehensive
- 25 feasibility review of gas turbine alternatives is necessary to determine whether it is a viable,

<sup>&</sup>lt;sup>22</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018), vol. III, att. 10.

<sup>&</sup>lt;sup>23</sup> "Gas Turbine Plant Alternatives," Newfoundland and Labrador Hydro, November 2018.

<sup>&</sup>lt;sup>24</sup> "Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. September 6, 2019 (originally filed November 16, 2018), vol. III, att. 14.

<sup>&</sup>lt;sup>25</sup> "Combustion Turbine Screening Final Study Report," Hatch Ltd., rev. October 28, 2022 (originally issued October 17, 2022).

| 1  | least-cost option that would fit Hydro's need as a resource. The range of additional analysis          |
|----|--|
| 2  | includes determination of possible site locations, land purchase requirements, fuel supply             |
| 3  | considerations, water supply considerations, engine selection, and electrical interconnection          |
| 4  | and environmental impacts in the Northeast Avalon area. Hydro will continue with the analysis          |
| 5  | in preparation for the 2023 Update as well as to consider in the preparation of documents              |
| 6  | necessary for any future application for construction of Bay d'Espoir Unit 8.                          |
| 7  | Capacity Assistance and Curtailable Load   |
| 8  | Please refer to the 2022 Update <sup>26</sup> for Hydro's assumptions on Capacity Assistance and       |
| 9  | Curtailable Load.  |
| 10 | Rate Structure and Customer Demand Management  |
| 11 | Please refer to the 2022 Update <sup>27</sup> for details and reports on this resource option.         |
| 12 | Market Purchases   |
| 13 | As discussed in the 2022 Update, <sup>28</sup> to date Hydro has not secured any firm capacity support |
| 14 | from external markets for a duration of more than one month and does not have the                      |
| 15 | information to assume that such solutions would be available to meet long-term planning                |
| 16 | requirements. Market purchases were excluded in the analysis as a potential firm resource              |
| 17 | option. Hydro will continue to evaluate this option in future updates.                                 |

<sup>&</sup>lt;sup>26</sup> "Reliability and Resource Adequacy Study – 2022 Update," Newfoundland and Labrador Hydro, October 3, 2022, vol. I, sec. 4.2.2.

<sup>&</sup>lt;sup>27</sup> "Reliability and Resource Adequacy Study – 2022 Update," Newfoundland and Labrador Hydro, October 3, 2022, vol. III, sec. 7.1.1.

<sup>&</sup>lt;sup>28</sup> "Reliability and Resource Adequacy Study – 2022 Update," Newfoundland and Labrador Hydro, October 3, 2022, vol. III, sec. 7.1.2.



# H-369130 14th July 2022 Newfoundland and Labrador Hydro Wind Integration Study (24 Ea x 4.26 MW = 100 MW) Enercon E115: 4.26 MW, Class 1A Machine, 77/92 m hub, 115.7 m rotor Project Cost Estimate

| Item | Description   | Total, CA\$ | Comments                             |
|------|---|-------------|--------------------------------------|
|      | Construction Costs  |             |                                      |
|      |   |             |                                      |
| 1    | Turbine Generators  |             |                                      |
|      | Turbine supply, inc. transport from port to site                | 65,000,000  | For 24 turbines                      |
|      | Turbine transport from Germany to<br>Canada                     | 6,441,492   | For 24 turbines                      |
|      | Turbine assembly, crane cost and tower erection                 | 5,473,500   | For 24 turbines                      |
|      | Turbine assembly, in-tower mechanical/electrical                | 3,204,000   | For 24 turbines                      |
|      |   |             |                                      |
|      | Total - Turbine Generators                                      | 80,118,992  | 3,338,000 \$ / turbine               |
|      |   |             |                                      |
| 2    | Construction Indirects & General Items,<br>Civil and Electrical |             |                                      |
| 2.1  | General Costs / Suppervision & Site Cost                        | 854,400     |                                      |
| 2.2  | Surveying   | 569,600     |                                      |
| 2.3  | QA/QC Subcontract   | 0           | Included in rates below              |
|      | Total Construction Indirects & General<br>Items                 | 1,424,000   |                                      |
|      |   |             |                                      |
| 3    | Civil Works   |             |                                      |
| 3.1  | New Access Roads  | 4,981,553   | 332,000 \$ / km 15 km of access road |
| 3.2  | Crane Pads and Erection Areas                                   | 1,420,013   | 59,200 \$ / turbine                  |
| 3.3  | Foundation for Wind Turbines                                    | 38,407,992  | 2,197,000 \$ / turbine               |
|      | Total Civil Works   | 44,809,557  | 1,867,000 \$ / turbine               |
| 4    | Electrical Works  |             |                                      |
| 4.1  | Tranmission line 138 kV   | 6,500,000   | 5 km                                 |
| 4.2  | Collector network 34.5 kV                                       | 22,500,000  | 15 km total collector system         |
| 4.3  | Transformer including breaker 138 kV                            | 3,500,000   |                                      |
| 4.4  | E-House c/w switchgear 34.5 kV                                  | 2,000,000   |                                      |

PUB-NLH-288, Attachment 1 Reliability and Resource Adequacy Study Review Page 2 of 2

|     | Total Electrical Works                  | 34,500,000  |                     |
|-----|---|-------------|---------------------|
|     |   |             |                     |
|     | TOTAL CONSTRUCTION COSTS                | 160,852,550 | 1,609 \$ / kW       |
|     |   |             |                     |
| 5   | Indirects                               |             |                     |
| E 4 | Engineering & Project Management & Site |             |                     |
| 5.1 | Supervision                             | 5,464,600   |                     |
| 52  | Owner Capital Investment in Operations  | 2 358 500   |                     |
| 0.2 | Support                                 | 2,000,000   |                     |
| 5.3 | Accomodation / Mess & Travel Costs      | 623,000     |                     |
| 5.4 | Temporary Construction Facilities       | 222,500     |                     |
|     |   |             |                     |
|     | TOTAL Indirects                         | 8,668,600   | 87 \$ / kW          |
|     |   |             |                     |
| 6   | Contingency                             |             |                     |
| 6.1 | Owners Contingency                      |             |                     |
|     |   |             | Contingonov of 15%  |
|     | Owners Contingency (Intended to be P50) | 29,904,930  | Contingency of 1378 |
|     | Total Owner Costs                       | 29,904,930  |                     |
|     |   |             |                     |
|     | TOTAL                                   | 199,426,079 | 1,994 \$ / kW       |





# Solar Project Preliminary Cost Estimate 254388-0000-DF00-STY-0001

August 22, 2022

Wood Canada Limited 600–2020 Winston Park Drive Oakville, ON L6H 6X7



Date

#### APPROVALS

| /gor ogic               | August 22, 2022 |
|-------------------------|-----------------|
| Prepared by: Igor Bozic | Date            |
| Levis Ham               | August 22, 2022 |
| Checked by: Lewis Hann  | Date            |
| Levis Ham               | August 22, 2022 |

Approved by: Lewis Hann

|   | Professional Stamp  |
|---|---|
| PROVINCE OF NEWFOUNDLAND AND LABRADOR<br>PERMIT DO018<br>Wood Canada Limited<br>02020<br>Signature or Member Number<br>(Member-in-Responsible Charge) | NEWIS HANN<br>SIGNATION<br>Aug. 22, 2022<br>DATE<br>MULAND & LAND |

#### IMPORTANT NOTICE

This Document was prepared exclusively for **Newfoundland and Labrador (NL) Hydro**, by Wood Canada Limited (Wood), a wholly owned subsidiary of John Wood Group PLC. The quality of information contained herein is consistent with the level of effort agreed in the scope of services and is based on: i) information available at the time of preparation, ii) data supplied by outside sources, and iii) the assumptions, conditions and qualifications set forth in this Design Basis. This Design Basis is intended to be used **Newfoundland and Labrador (NL) Hydro** only, subject to the terms and conditions of its contract with Wood Canada Limited. Any other use of, or reliance on, this (specification/report to be edited) by any third party is at that party's sole risk.

PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 3 of 35



#### **REVISION HISTORY**

| Rev. | Description       | Prepared<br>By | Checked<br>By | Approved<br>By | Date       |
|------|-------------------|----------------|---------------|----------------|------------|
| Α    | Issued for review | IB             | LH            | LH             | 07/12/2022 |
| В    | Issued for use    | IB             | LH            | LH             | 07/28/2022 |
| С    | Reissued for use  | IB √8          | LH LH         | LH LH          | 08/22/2022 |
|      |                   |                |               |                |            |
|      |                   |                |               |                |            |
|      |                   |                |               |                |            |
|      |                   |                |               |                |            |
|      |                   |                |               |                |            |



Page

# **Table of Contents**

| 1.  | Introduction                         | 1 |
|-----|--------------------------------------|---|
| 2.  | Purpose and Scope                    | 1 |
| 3.  | System Characteristics               | 1 |
| 3.1 | Solar PV System                      | 2 |
| 3.1 | 1.1 PV module                        | 2 |
| 3.1 | 1.2 DC electrical system             | 3 |
| 3.1 | 1.3 Solar racking system             | 5 |
| 3.2 | Battery Energy Storage System (BESS) | 5 |
| 3.3 | Civil Engineering Considerations     | 6 |
| 3.4 | MV Collector System                  | 6 |
| 3.5 | Terminal Station Interconnection     | 6 |
| 4.  | Cost and Schedule                    | 7 |
| 4.1 | Type of Estimate                     | 7 |
| 4.2 | Project schedule                     | 7 |
| 4.3 | Cost Summary                         | 8 |

- Appendix A: Inverter package including BESS
- Appendix B: PV module specifications
- Appendix C: Cost summary
- Appendix D: Project Schedule

# 1. Introduction

Newfoundland and Labrador (NL) Hydro is looking for an opportunity to introduce photovoltaic (PV) solar systems in Central Newfoundland and Labrador West. Solar energy projects will diversify the NL Hydro generation mix and provide an opportunity to pair with energy storage solutions. The specific locations of the solar power systems have not been determined. However, the sites are expected to be near Gander and Labrador City and connected to existing terminal station on a 69kV bus in NL or 46kV bus in Labrador.

# 2. Purpose and Scope

The purpose of the report is to provide an indicative (Class 5) cost estimate for a 10MWac and 20MWac solar farm with integrated BESS system. The solar farm would be connected to the existing terminal station at 46kV or 69kV bus. This estimate includes relevant MV substation interconnection components needed to integrate with the existing terminal stations. With the respect to equipment rating and selection, 46kV insulation class will likely fall under the same category as 69kV. Therefore, for the purpose of this estimate, 69kV voltage level have been considered. Costs associated with the Battery Energy Storage System (BESS) have been identified to enable removal of these values for projects where is BESS will not be required.

Wood has provided assumptions based on industry standards and previous experience for utility scale ground mounted PV solar farms as follows:

- Latest PV modules and inverter technologies
- MV collector system design including substation requirements
- Project scheduling and major project milestones
- Developmental activities such as field investigation (ex. Geotech report), desktop studies, permitting, preliminary & detailed engineering, environmental studies, licenses, etc.
- Major equipment costs
- Construction cost for both DC field and upgrades at the existing 69kV terminal station
- Supporting activities during the construction stage (Site management & monitoring, owner engineer costs, safety, equipment rental, etc.)

# 3. System Characteristics

This section describes technologies and technical characteristics of the major components for DC solar system, DC/AC conversion (solar inverters), DC coupled BESS, MV collector system including associated cabling, substation components required at the terminal station including main power transformer, breaker, disconnect switch, VAR compensation, protection and metering.

### 3.1 Solar PV System

#### 3.1.1 PV module

Over the course of the last few years PV solar technology has been improving exponentially and efficiency has increased from a low 15% to mid 20%. Solar PV technology voltage ratings have increased from 600Vdc to 1000Vdc and most recently PV modules rated at 1500Vdc have become available. The industry and electrical safety codes have standardized at this higher voltage level and now it is widely used for utility scale solar projects. 1000Vdc systems are still available however they are generally used for smaller applications such as residential or roof mounted installation.

PV module manufacturers will normally provide a linear power warranty which runs up to 25 to 30 years. This generally means that manufacturer guarantees 90% capacity at 10 years, and 80% at 25 years (See Figure 1 below).



#### Figure 1: PV module linear warranty

For the remainder of the solar plant, typical industry standard for a lifespan is 20 to 30 years.

There are two different technologies used for commercial projects and they are based on mono-crystalline and poly-crystalline silicone (Si) structure. Mono-crystalline technology is slightly more efficient however, and poly-crystalline design has been improving with efficiency exponentially increasing. As of today, the most common PV solar module available commercially for utility scale solar panel is based on poly technology utilizing half cell and bifacial design. In today's market, the common power output for a typical PV module, ranges from 400W to 600W range per PV module.

As PV module standard size is approximately 2m x 1m, half cell technology allowing for more modules to fit on the same area where one half operates independently of the other, allowing for additional yield due to reduced shading impact (See Figure 2 below).



Figure 2: PV module, half cell design

The PV module bi-faciality allows for additional generation from the back of the module from the reflected (indirect) irradiance. The % reflectance depends on type of the reflective elements (albedo effect). The lighter the finished grade, % yield is better and reaching as high as 25%. Considering that our Canadian climate accounts for number of days with snow on the ground, this would benefit for the overall generation (See Figure 3).



Figure 3: Bifacial module energy yield.

Consequently, the module selected for this application should be poly-crystalline, bi-facial, half-cell design. One of the typical PV modules Wood has used in their design recent project (June 2022) is provided in **Appendix B.** 

### 3.1.2 DC electrical system

PV modules are connected in series forming a string rated up to 1500Vdc. Depending on system design parameters, local weather parameters, module specifications, a typical single string would consist of 24 to 27 PV modules connected in series for 1500Vdc class as the most common voltage. It is noteworthy that there are still 1000Vdc systems on the market but for utility scale solar projects they are rarely considered.

254388-0000-DF00-STY-0001

Groups of PV strings (roughly 16 to 20 strings) are connected to a common consolidating bus called DC combiner box. A group of combiner boxes are typically connected to a recombiner box or dedicated recombiner terminal bus at the solar inverter. As indicated in the Figure 4 below, DC feeds from combiner boxes are connected to the inverter common DC bus. Depending on solar farm DC zoning, the number of inputs can vary, typically from 20-28.

The Inverter loading ratio, also called DC-to-AC ratio, defines ratio of installed DC capacity (kWdc) to inverter AC output rating (kWac). To compensate for system losses (inverter, transformer, DC and AC cabling) the DC-to-AC ratio must be greater than 1.0. In previous projects Wood has utilized ratios ranging from 1.2 to 1.5. The higher the ratio, the higher the overall kWh yield, however the capital cost of the equipment (PV modules, cabling) will be also higher. Additionally, the power purchase agreement (PPA) and government solar incentive programs may limit the project DC overbuilt. For the estimate Wood has assumed a DC-to-AC ratio of 1.3.



#### Figure 4: PV solar wiring design

DC string wiring is standardized as PV90 and RPVU90, 2kV class photovoltaic cable and is typically sized as #10 AWG Cu for strings and 350kcmil AL to #500kcmil AL for combiner to recombiner runs. Combiner boxes are relatively simple devices consisting of disconnect switch and finger-safe fuse holders for incoming strings and can be assembled in electrical shops as long as they can be CSA certified before installation (See Figure 5).



#### Figure 5: Combiner box

From Figure 4 above, a DC solar system will connect to the dedicated DC bus at the solar inverter. Considering that the sites will be rated at 10MWac and 20MWac, Wood recommends utility scale skid mounted inverter package. A typical package consists of DC/AC inverter(s) and MV step-up transformer connecting to MV collector system typically run at 25kV or 35 kV level. Based on our experiences, it is not a standard package to have an inverter station connected to voltages higher then 35 kV level.

Currently, Wood's design team is utilizing Sungrow 3600UD-MV unit, rated for a maximum 3600MVA however there are other credible vendors Wood has used in other projects such in past such as TMEIC and SMA. Refer to **Appendix A** for Sungrow unit specifications.

#### 3.1.3 Solar racking system

There are three different racking configurations considered for ground mounted solar system:

- a) fixed tilt arrangement
- b) single axis tracker
- c) dual axis tracker system

Fixed tilt arrangement is based on the most optimal fixed angle as determined by energy yield software (PVsyst or equivalent). Single axis tracker arrangement follows sun azimuth and oriented east-west for an additional yield and dual axis arrangement rotates both east-west and north-south for the maximum yield.

Most common arrangement in Canadian climate is fixed tilt and on some occasions single-axis tracker. It should be noted that tracker systems have moving parts and more potential for failure as our Canadian temperature ranges from extreme cold to extreme hot. Furthermore, weather elements such as freezing rain, snow accumulation may put additional burden and potential for premature failure to the racking structures.

# 3.2 Battery Energy Storage System (BESS)

Latest trends in solar system design considers BESS. This arrangement can be AC coupled where batteries are connected to a common MV bus at the substation. The other, more common option for a new project, is DC coupled with batteries connected directly to DC bus of the inverter. DC coupled system directly harvest excess energy production from PV system and discharge during no or low PV generation such as nighttime, dusk & dawn or a cloudy day. See Figure 6 below.



Figure 6: BESS Charging and discharging cycle

254388-0000-DF00-STY-0001



AC coupled systems are generally considered for existing solar farms where it is challenging to interface DC coupled system to an existing solar inverter but also where there is a need for grid support such as frequency response, voltage regulation and peak shaving.

For the energy arbitrage benefits, AC coupled systems do not provide the benefit of storing excess solar generation and storing clipped solar PV power as this is only possible with DC coupled systems.

Additionally, AC coupled systems are subject to an additional electrical transformation, from the DC to AC and again from the AC to DC, contributing to additional losses. For the purpose of this exercise, Wood recommends DC coupled systems.

It is necessary to perform a detailed analysis for actual BESS sizing, taking into account actual PV plant production, BESS augmentation, base capital costs and electricity rates. Wood assumptions for the size of the battery system is 100% of the actual solar farm MW rating with 4-hour reserve. Therefore, for a solar farm rated at 10MWac, BESS would be considered at 10MW/40MWh, or 20MW/80MWh for 20MWac solar farm.

# 3.3 Civil Engineering Considerations

Civil aspects can often be neglected when it comes to estimating of the civil works. Lack of geotechnical information at the early stages of the project may lead to wrong assumptions and minimize civil works scopes such as grading, grubbing and clearing. In general, 10% slope or less is recommended, so where sites are steep, additional grading may be required or sections of the land can be excluded from the layout. Elements such as the 50 year and 100 year flood plain can further reduce buildable area. Knowing type of the soil can impact the solar PV pile and racking design. Addressing actual available (buildable) area is critical as it drives the DC layout design and quantity of the PV modules which can be installed.

Minimum clearance from the waterways, residential areas and other environmental features (nesting areas, endangered species) will impact and may reduce actual construction area.

Based on previous experience, Wood assumes that approximately 5 acres is required for 1MW of solar PV installation. This also impacted by energy yield system modelling (using software tools such as PVsyst, Helioscope, Homer, etc.) which would dictate rack-to-rack spacing (pitch).

# 3.4 MV Collector System

Knowing that solar system would be connecting to 69kV bus at the terminal station, it would be recommended to connect solar collector system at 34.5kV level which is industry standard distribution voltage for the utility scale solar farms. Inverter station would be interconnected with 35kV, AL, 100% insulation, TRXLPE cable (c/w concentric neutral) cable. The cable size can range from 2/0 to 500kmil depending on circuit configuration and soil thermal characteristics. For larger solar farms, a 34.5kV single feeder (main home run) can carry in the range of 25MW to 30MW utilizing 1250kcmil cable. Depending on the solar farm layout configuration, 35kV, 600A class junction boxes may be required to connect sub-circuits.

# 3.5 Terminal Station Interconnection

At the existing MV terminal station (69kV), it will be necessary to step up from 34.5kV collector system voltage to the terminal station voltage. For the interconnection, it is required to interface with a new 69kV breaker along with 69KV voltage transformer (for relay protection purposes), main two stage fan cooled step-up transformer

254388-0000-DF00-STY-0001



(6/8/10MVA, 69kV-35kV) and 35kV pad mount switchgear with minimum two 35kV feeders c/w breaker protection. If required by NL Hydro, a separate metering structure can be considered on 69kV side of the project.

# 4. Cost and Schedule

### 4.1 Type of Estimate

This estimate is a Class 5 indicative estimate. This classification represents a rough order of magnitude estimate. It generally implies from -20% to 50% on the low side and +30% to up to 100% on the high side in accordance with AACE International Recommended Practices.

# 4.2 Project schedule

Project schedule is very important aspect in particular in today's volatile market because of longer lead time for equipment procurement. Addressing preliminary design at early stages and securing long lead items are critical for the overall project delivery. This in particular refers to: PV modules, racking & posts, inverter and BESS packages, 69kV substation equipment such as main transformer, PTs & breakers.

Utility scale solar is quite new in NL and availability of skilled resources and general labour may be limited. Construction activities shall ensure that all civil and electrical work occurs in spring to fall period. During winter months limited electrical work (such as LV wiring connections at protection building), commissioning activities and addressing minor deficiencies can occur.

Geotech field work must be performed as early as possible to enable the project team can to account for site conditions for racking system design and solar farm layout.

Solar project durations can range from approximately one year for accelerated commercial ventures to in excess of 2 years when pre-feed activities, permitting, project sanctioning, procurement of long lead items and construction season limitations are all taken into account. For an indicative project schedule please that takes these elements into consideration refer to **Appendix D**.

Following is a list of typical sequential project activities:

- a) Permitting and approval process
- b) Geotech field work
- c) Base engineering (needed for key equipment procurement)
- d) Equipment procurement
- e) Detailed engineering
- f) Construction
- g) Testing and commissioning
- h) Post construction activities (deficiencies, warranty items, etc.)



# 4.3 Cost Summary

| 10 MW Solar Farm |                                   |              |  |
|------------------|-----------------------------------|--------------|--|
|                  | Engineering and Permitting        | \$960,000    |  |
|                  | Solar Field                       | \$11,645,000 |  |
|                  | Terminal Station Upgrades (69 kV) | \$3,101,000  |  |
|                  | Contingency (10%)                 | \$1,700,000  |  |
|                  | Total Estimated Cost (Excl BESS)  | \$17,406,000 |  |
|                  | BESS System                       | \$1,380,000  |  |

| 20 MW Solar Farm |                                   |              |  |  |
|------------------|-----------------------------------|--------------|--|--|
|                  | Engineering and Permitting        | \$1,080,000  |  |  |
|                  | Solar Field                       | \$23,290,000 |  |  |
|                  | Terminal Station Upgrades (69 kV) | \$4,312,,000 |  |  |
|                  | Contingency (10%)                 | \$3,100,000  |  |  |
|                  | Total Estimated Cost (Excl BESS)  | \$31,782,000 |  |  |
|                  | BESS System                       | \$2,760,000  |  |  |

For detailed breakdown for both 10MWac solar farm + BESS and 20MWac solar farm + BESS please refer to **Appendix C**.

PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 13 of 35



# **APPENDICES**

254388-0000-DF00-STY-0001

woodplc.com

Page:9

PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 14 of 35

# wood.

# Appendix A

Inverter Package including BESS

#### PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 15 of 35

# SG3425UD-MV/ SG3600UD-MV



Turnkey Station for North America 1500 Vdc System - MV Transformer Integrated



#### **HIGH YIELD**

- Advanced three-level technology, max. efficiency 98.9%
- Full power operation at 45 ℃ (113 ℃)
- Effective cooling, wide operation temperature
- Max. DC/AC ratio up to 2.0

#### SAVED INVESTMENT

- Low transportation and installation cost due to 20-foot container size design
- DC-coupled storage interface and charging power from the grid, low system cost
- Integrated MV transformer and LV auxiliary power supplyQ at night optional

#### SMART O&M

- Integrated current, voltage and MV parameters monitoring function for online analysis and trouble shooting
- Modular design, easy for maintenance

#### **GRID SUPPORT**

- Compliance with standards:UL 1741,UL 1741 SA, IEEE 1547, Rule 21 and NEC code
- Low / High voltage ride through (L/HVRT), L/HFRT, soft start/stop
- Active & reactive power control and power ramp rate control

#### CIRCUIT DIAGRAM



#### **EFFICIENCY CURVE (SG3425UD)**





🕮 🚺 © 2020 Sungrow Power Supply Co., Ltd. All rights reserved. Subject to change without notice. Version 1.2.7

SG3425UD-MV/SG3600UD-MV

| Type designation                                       | SG3425UD-MV  | SG3600UD-MV                               |  |  |  |
|--|--|---|--|--|--|
| Input (DC)   |  |   |  |  |  |
| Max. PV input voltage                                  | 150  | 00 V                                      |  |  |  |
| Min. PV input voltage / Startup input voltage          | 875 V / 915 V  | 915 V / 955 V                             |  |  |  |
| Available DC fuse sizes                                | 250A, 315A, 400A, 450A, 500A                                   |   |  |  |  |
| MPP voltage range                                      | 875 <b>-</b> 1300 V  | 915 <b>-</b> 1300 V                       |  |  |  |
| No. of independent MPP inputs                          |  | 1   |  |  |  |
| No. of DC inputs                                       | 20 (optional: 1  | 22 / 24 / 26 / 28)                        |  |  |  |
| Max. DC short-circuit current                          | 100  | 000 A                                     |  |  |  |
| PV array configuration                                 | Negative grou  | nding or floating                         |  |  |  |
| Output (AC)  |  |   |  |  |  |
| AC output power  | 3425 kVA @ 45 ℃ (113 °F),                                      | 3600 kVA @ 45 ℃ (113 °F),                 |  |  |  |
|  | 3083 kVA @ 50 ℃ (122 °F)                                       | 3240 kVA @ 50 °C (122 °F)                 |  |  |  |
| Nominal grid frequency / Grid frequency range          | 50 Hz / 45 – 55 Hz   | z, 60 Hz / 50 – 65 Hz                     |  |  |  |
| Harmonic (THD)   | < 3 % (at no   | minal power)                              |  |  |  |
| Power factor at nominal power / Ajustable power factor | > 0.99 / 0.8 lead  | ding - 0.8 lagging                        |  |  |  |
| Efficiency   |  |   |  |  |  |
| Inverter Max. efficiency                               | 98.9   | 9%  |  |  |  |
| Inverter CEC efficiency                                | 98.5   | 5 %                                       |  |  |  |
| Transformer  |  |   |  |  |  |
| Transformer rated power                                | 3425 kVA   | 3600 kVA                                  |  |  |  |
| Transformer max. power                                 | 3425 kVA   | 3600 kVA                                  |  |  |  |
| LV / MV voltage  | 0.6 kV / (12 – 35) kV  | 0.63 kV / (12 – 35) kV                    |  |  |  |
| Transformer vector                                     | Dyl or Dyll  |   |  |  |  |
| Transformer cooling type                               | ONAN (Optic  | onal: KNAN)                               |  |  |  |
| Protection   |  |   |  |  |  |
| DC input protection                                    | Load break switch + fuse                                       |   |  |  |  |
| Inverter output protection                             | Circuit breaker  |   |  |  |  |
| AC MV output protection                                | Load break switch + fuse                                       |   |  |  |  |
| Overvoltage protection                                 | DC Type II / AC Type II  |   |  |  |  |
| Grid monitoring / Ground fault monitoring              | Yes  | s / Yes                                   |  |  |  |
| Insulation monitoring                                  | Y  | Yes                                       |  |  |  |
| Overheat protection                                    | Y  | Yes                                       |  |  |  |
| General Data   |  |   |  |  |  |
| Dimensions (W*H*D)                                     | 6058 * 2896 * 2438 mi  | m 238.5'' * 114.0'' * 96.0''              |  |  |  |
| Weight   | 18000 kg   | 39683.2 lbs                               |  |  |  |
| Degree of protection                                   | NEMA 4X( Electronic for I                                      | nverter) / NEMA 3R(Others)                |  |  |  |
| Auxiliary power supply                                 | 5kVA, 120Vac/240Vac; Opti                                      | onal: 30kVA, 480Vac/277Vac                |  |  |  |
| Operating ambient temperature range                    | -35 to 60 ℃ (> 45 ℃ derating) / opt                            | tional: −40 to 60 °C (> 45 °C derating)   |  |  |  |
|  | -22 to 140 °F (> 113 °F derating) / opt                        | tional: -40 to 140 °F (> 113 °F derating) |  |  |  |
| Allowable relative humidity range                      | 0 -  | 100 %                                     |  |  |  |
| Cooling method   | Temperature contro   | lled forced air cooling                   |  |  |  |
| Max. operating altitude                                | 1000 m (Standard) / > 1000 m (Customized)                      |   |  |  |  |
|  | (3280.8 ft (standard) / >                                      | > 3280.8 ft (Customized))                 |  |  |  |
| DC-coupled storage interface                           | Optional   |   |  |  |  |
| Charging power from the grid                           | Opt  | tional                                    |  |  |  |
| Communication  | Standard: RS485, Ether   | net; Optional: optical fiber              |  |  |  |
| Compliance   | UL 1741, IEEE 1547, UL1741 SA, NEC 2017, CSA C22.2 No.107.1-01 |   |  |  |  |
| Grid support   | Q at night function (optional), L/H                            | VRT, L/HFRT, Active & reactive power      |  |  |  |
|  | control and power ramp rate o                                  | control, Volt-var, Frequency-watt         |  |  |  |
|  |  |   |  |  |  |



( Co., Ltd. All rights reserved. Subject to change without notice. Version 1.2.7 👙 ( )



PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 17 of 35



280Ah Cell Datasheet Datasheet

# SUNGROW

# Version Record

| Version | Revision time | Revision Content         | Reviser | Reviewer |
|---------|---------------|--------------------------|---------|----------|
| V1.0    | 2020.04.29    | Initial version          | PXY     |          |
| V1.1    | 2020.06.09    | Modify Eff., Weight etc. | PXY     |          |
|         |               |                          |         |          |
|         |               |                          |         |          |

#### 1. Overview

This document describes the Cell Parameters of CATL (280Ah).

This document is intended to be used by the specific addressees. No part of this document may be reproduced or distributed in any form or by any means without the prior written permission of Sungrow Power Supply Co., Ltd.

#### 2. Cell Datasheet

| NO. | Classification       | Specification | Remarks |
|-----|----------------------|---------------|---------|
| 1.  | image                |               |         |
| 2.  | Type of Battery      | LFP           | /       |
| 3.  | Nominal Voltage(V)   | 3.2           | /       |
| 4.  | Nominal Capacity(Ah) | 280           | /       |
| 5.  | C-rate (C)           | ≤1            | /       |
| 6.  | Voltage Range(V)     | 2.5-3.65      | 25℃     |

#### PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 19 of 35 Confidential

SUNGROW

| 7.  | Cycles                                    | 7500                         | @25°C,100%DOD%,E<br>OL70%,1C/1C                  |
|-----|---|------------------------------|--|
| 8.  | Energy efficiency                         | ≥92,2%                       | @25°C,1C/1C<br>(Discharging<br>energy)/(Charging |
|     |   |                              | energy )   |
| 9.  | Dimension (VV×D×H mm)                     | 1/3.9×/1./×20/.2             | /  |
| 10. | Weight ( Kg )                             | 5.46                         | /  |
| 11. | Storage Temperature Range ( $^\circ\!C$ ) | -30-60                       | /  |
| 12. | Operating Temperature Range( $^\circ$ C)  | 0-55<br>(Charging)<br>-30-55 | /  |
|     |   | (Discharging)                |  |

Clean power for all

# - LFP Li-ion Battery System New

Over 1 hour

#### **EFFICIENT & HIGH YIELD**

- 20-year service life, 8000+ times system-level cycle life
- Support 1500V system, reduce AC side loss by 60%
- Deep charge & discharge design, initial investment saves more than 5%

#### **INTELLIGENT & FRIENDLY**

identification

- 40-foot container can hold 4.4MWh, compatible downwards
- Oneline estimation of SOC & SOH based on scenes and big data • Support cloud platform, remote real-time monitoring and fault

- SAFE & RELIABLE
- Two-level short-circuit protection, graded fast current limiting
- Fool-proof, anti-reverse connection design, safer installation and maintenance
- Patented air duct and intelligent air cooling design, temperature difference < 3°C

• Meet global high standard authoritative certification requirements



| Item                       |               |
|----------------------------|---------------|
| Model                      | M2L-M143      |
| Charge&discharge rate      | ≤ 1C          |
| Cell type                  | LFP 280Ah     |
| Configuration              | 1P16S         |
| Capacity                   | 280 Ah        |
| Nominal energy             | 14.3 kWh      |
| Charging&discharging power | ≤ 14.3 kW     |
| Nominal voltage            | 51.2 V        |
| Operating voltage range    | 43.2 V–58.4 V |
| Dimensions (W*H*D)         | 455*230*760mm |
| Weight                     | 105 kg        |
|                            |               |



| Item                       |                  |
|----------------------------|------------------|
| Model                      | M2L-R372         |
| Charge&discharge rate      | ≤ 1C             |
| Cell type                  | LFP 280Ah        |
| Configuration              | 1P416S           |
| Key component              | PACK*26+SG*1     |
| Capacity                   | 280 Ah           |
| Nominal energy             | 372,7 kWh        |
| Charging&discharging power | ≤ 372.7 kW       |
| Nominal voltage            | 1331.2 V         |
| Operating voltage range    | 1123.2V–1497.6 V |
| Dimensions (W*H*D)         | 1500*2285*760 mm |

# 

PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 21 of 35



# Switchgear Cabinet Datasheet Datasheet

# SUNGROW

# Version Record

| Version | Revision time | Revision Content | Reviser | Reviewer |
|---------|---------------|------------------|---------|----------|
| V1.0    | 2020.04.29    | Initial version  | PXY     |          |
|         |               |                  |         |          |
|         |               |                  |         |          |
|         |               |                  |         |          |

### 1. Overview

This document describes the Switchgear Cabinet Datasheet of CATL (280Ah).

This document is intended to be used by the specific addressees. No part of this document may be reproduced or distributed in any form or by any means without the prior written permission of Sungrow Power Supply Co., Ltd.

### 2. Switchgear Cabinet Datasheet

| Classification         | Specification  |
|------------------------|--|
| Image                  |  |
| Model                  | M2L-S280H  |
| Key Component          | Control BMS unit 1ea<br>Relay 2ea<br>Fuse 2ea<br>Current sensor 2ea<br>Load switch 1ea |
| Dimension<br>W x H x D | 16.1"×9.0"×29.9"   |
| Auxiliary Power        | 24V  |

SUNGROW

| Pack to Rack communication   | UART     |
|------------------------------|----------|
| Rack to System communication | CAN 2.0B |
| Voltage Accuracy             | ±5V      |
| Current Accuracy             | 0.2%FSR  |

# SD1250HV Preliminary

DC/DC Converter



- Max efficiency 99%
- Wide DC input voltage range, flexible for battery configuration
- Modular design, compatible with rack level battery management

- Bidirectional buck-boost design for better voltage matching
- Compatible with 1500V battery system
- MPPT function integrated, compatible with DC microgrid applications

#### **CIRCUIT DIAGRAM**





🚔 🙌 © 2020 Sungrow-Samsung SDI Energy Storage Power Supply Co., Ltd. All rights reserved. Subject to change without notice. Version 1.1

#### EASY O&M

- High protection degree (IP65/NEMA 4X, C5)
- Compact design and light weight for easy installation

# PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 25 of 35

SD1250HV

| Type Designation                                   | SD1250HV   |  |
|--|--|--|
| Power Rating                                       |  |  |
| Nominal power                                      | 1250 kW  |  |
| Max. power   | 1690 kW  |  |
| Battery Side                                       |  |  |
| Max. DC voltage                                    | 1500 V   |  |
| DC operating voltage range                         | 0 – 1500V  |  |
| Max. DC current                                    | 140 A * 10   |  |
| BUS Side   |  |  |
| Max. DC voltage                                    | 1500 V   |  |
| DC operating voltage range                         | 500 – 1500 V   |  |
| Max. DC current                                    | 1400 A   |  |
| Efficiency   |  |  |
| Max efficiency                                     | 99.0%  |  |
| Protection   |  |  |
| Reverse polarity protection                        | Yes  |  |
| Overvoltage protection                             | Туре II  |  |
| Insulation monitoring                              | Yes  |  |
| Overheat protection                                | Yes  |  |
| General Data                                       |  |  |
| Dimensions (W*H*D)                                 | 2150 * 2150 * 850 mm 84.6" * 84.6" * 33.5"                 |  |
| Weight   | 1200 kg 2645.5 lbs   |  |
| Degree of protection                               | IP 65 NEMA 4X  |  |
| Operating ambient temperature range                | -30 to 60 °C -22 to 140 °F                                 |  |
| Allowable relative humidity range (non-condensing) | 0 – 100 %  |  |
| Cooling concept                                    | Temperature-controlled forced air cooling                  |  |
| Max. operating altitude                            | 4,000m( > 3,000 m derating) 13123 ft (> 9,843 ft derating) |  |
| Display  | LED, Bluetooth + APP                                       |  |
| Communication                                      | RS485, Ethernet, CAN                                       |  |
| Compliance   | CE, IEC 62109-1, UL 1741                                   |  |

# SD125HV Preliminary DC/DC Converter



EASY O&M

• High protection degree(IP65/NEMA 4X, C5)

Compact design and light weight for easy installation
Easy site commissioning & monitoring via APP

- Max efficiency 99%
- Wide DC input voltage range, flexible for battery configuration
- Modular design, compatible with rack level battery management

- Bidirectional buck-boost design for better voltage matching
- Compatible with 1500V battery system
- MPPT function integrated, compatible with DC microgrid applications

#### **CIRCUIT DIAGRAM**





🚔 🙌 © 2020 Sungrow-Samsung SDI Energy Storage Power Supply Co., Ltd. All rights reserved. Subject to change without notice. Version 1.1

# PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 27 of 35

SD125HV

| Type Designation  | SD125HV  |  |
|---|--|--|
| Power Rating  |  |  |
| Nominal power   | 125 kW   |  |
| Max. power  | 169 kW   |  |
| Battery Side  |  |  |
| Max. DC voltage   | 1500 V   |  |
| DC operating voltage range                                  | 0 – 1500V  |  |
| Max. DC current   | 140 A  |  |
| BUS Side  |  |  |
| Max. DC voltage   | 1500 V   |  |
| DC operating voltage range                                  | 500 – 1500 V   |  |
| Max. DC current   | 140 A  |  |
| Efficiency  |  |  |
| Max efficiency  | 99.0%  |  |
| Protection  |  |  |
| Reverse polarity protection                                 | Yes  |  |
| Overvoltage protection                                      | Туре II  |  |
| Insulation monitoring                                       | Yes  |  |
| Overheat protection   | Yes  |  |
| General Data  |  |  |
| Dimensions (W*H*D) 650 * 650 * 300 mm 25.6" * 25.6" * 11.8" |  |  |
| Weight  | 60 kg 132.3 lbs  |  |
| Degree of protection  | IP 65 NEMA 4X  |  |
| Operating ambient temperature range                         | -30 to 60 °C -22 to 140 °F                                 |  |
| Allowable relative humidity range (non-condensing)          | 0 – 100 %  |  |
| Cooling concept   | Temperature-controlled forced air cooling                  |  |
| Max. operating altitude                                     | 4,000m( > 3,000 m derating) 13123 ft (> 9,843 ft derating) |  |
| Display   | LED, Bluetooth + APP                                       |  |
| Communication   | RS485, Ethernet, CAN                                       |  |
| Compliance  | CE, IEC 62109-1, UL 1741                                   |  |

PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 28 of 35



# Appendix B

PV module specifications

254388-0000-DF00-STY-0001
### PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 29 of 35

# Hi-MO 5

# LR5-72HBD 520~545M

- Based on M10-182mm wafer, best choice for ultra-large power plants
- Advanced module technology delivers superior module efficiency
   M10 Gallium-doped Wafer
   Smart Soldering
   9-busbar Half-cut Cell
- Globally validated bifacial energy yield
- High module quality ensures long-term reliability



12-year Warranty for Materials and Processing

30-year Warranty for Extra Linear Power Output

#### Complete System and Product Certifications

IEC 61215, IEC 61730, UL 61730 ISO 9001:2008: ISO Quality Management System ISO 14001: 2004: ISO Environment Management System TS62941: Guideline for module design qualification and type approval OHSAS 18001: 2007 Occupational Health and Safety





PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 30 of 35

### LR5-72HBD 520~545M





#### **Operating Parameters**

| Operational Temperature            | -40°C ∼ +85°C    |  |
|------------------------------------|------------------|--|
| Power Output Tolerance             | 0 ~ +5 W         |  |
| Voc and Isc Tolerance              | ±3%              |  |
| Maximum System Voltage             | DC1500V (IEC/UL) |  |
| Maximum Series Fuse Rating         | 30A              |  |
| Nominal Operating Cell Temperature | 45±2°C           |  |
| Protection Class                   | Class II         |  |
| Fire Rating                        | UL type 29       |  |
| Bifaciality                        | 70±5%            |  |

#### Mechanical Loading

| Front Side Maximum Static Loading | 5400Pa                               |
|-----------------------------------|--------------------------------------|
| Rear Side Maximum Static Loading  | 2400Pa                               |
| Hailstone Test                    | 25mm Hailstone at the speed of 23m/s |

#### Temperature Ratings (STC)

| Temperature Coefficient of Isc  | +0.050%/°C |
|---------------------------------|------------|
| Temperature Coefficient of Voc  | -0.284%/°C |
| Temperature Coefficient of Pmax | -0.350%/°C |



Floor 19, Lujiazui Financial Plaza, Century Avenue 826, Pudong Shanghai, China Tel: +86-21-80162606 Web: en.longi-solar.com Specifications included in this datasheet are subject to change without notice. LONGi reserves the right of final interpretation. (20201231V12)

PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 31 of 35

### **Appendix C** Cost Summary

254388-0000-DF00-STY-0001

### PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Ρ

|             | ·  |    |    |
|-------------|----|----|----|
| <b>Page</b> | 32 | of | 35 |

|                             | 10MM/reaction from the DECC                            |                      |                  |              |  |
|-----------------------------|--|----------------------|------------------|--------------|--|
| Class 5 Solar farm Estimate | 1000 Wac solar farm + BESS                             |                      |                  |              | newfoundland labrador  |
| DC/AC ratio                 | 1.3  |                      |                  |              |  |
| Module type                 | Longi, LR5-72W, 545W                                   |                      |                  |              | hidro  |
| Size (MWac)                 | 10   |                      |                  |              |  |
| Size (MWdc)                 | 13   |                      |                  |              |  |
| Number of Modules           | 23,853   |                      |                  |              |  |
| Development Activities      |  | Description          | PU cost (\$ CAD) | Total        | Comments   |
|                             |  |                      |                  |              |  |
| Engineering and Permitting  |  |                      |                  |              |  |
|                             |  |                      |                  |              |  |
| 1                           | Interconnection Studies                                |                      | 1                | \$50,000     |  |
| 2                           | Environmental Assessments                              |                      | 1                | \$50,000     |  |
| 3                           | Permits and licenses                                   |                      | 1                | \$50,000     |  |
| 4                           | Site surveys   |                      | 1                | \$50,000     |  |
| 5                           | Geotech  |                      | 1                | \$40,000     |  |
| 5                           | Detailed Engineering                                   |                      | 1                | \$480,000    | S120/hour. Includes construction support.  |
| 6                           | Site management (site mtg, cost<br>controller, safety) |                      | 2                | \$160,000    |  |
| 7                           | Owner Engineer Role                                    |                      | 1                | \$80,000     | Includes drawing reviews and approvals and<br>occasional site visit                                    |
|                             | Subtotal - Engineering and Permi                       | l tting              |                  |              |  |
|                             | Subtotal - Engineering and Perini                      |                      |                  | \$500,000    |  |
| Solar Field                 |  |                      |                  |              | Installed costs  |
|                             |  |                      |                  |              |  |
| 1                           | PV module  | Longi LR5-72HBD 545W | 0.45             | \$5,850,000  | Cost of PV assumed to be \$0.45/Watt based on previous project quotes                                  |
| 2                           | Inverters package                                      | Sungrow 3600UD-MV    | 3                | \$660.000    | Quote from vendor (prorated for this project)  |
| 3                           | Solar AC and DC supply &                               | Sangrow SocooD-IVIV  | 0 1              | \$1 300 000  | Includes DC harnesses, combiner hoves, AC cabling  |
|                             | installation   |                      | 0.1              | \$1,500,000  | Factor reference from another project  |
| 4                           | SCADA and fiber  |                      | 0.01             | \$130,000    | Factor reference from another project  |
| 5                           | Solar posts & racking                                  |                      | 0.18             | \$2,340,000  | \$0.13/W. Cost reference from another project as per vendor quote                                      |
| 6                           | Post, PV module and rack                               |                      | 0.05             | \$650,000    | Cost reference from another project.   |
| 7                           | Civil Works  |                      | 0.05             | \$650,000    | Includes site clearing, solar farm service roads,  |
| 8                           | DC system commissioning                                |                      | 0.005            | \$65,000     | Cost reference from another project  |
|                             |  |                      | 0.000            | \$44 AFT 000 |  |
|                             | Subtotal - Solar Field                                 |                      |                  | \$11,645,000 |  |
|                             |  |                      |                  |              |  |
| Terminal area (CO(N))       |  |                      |                  |              | Installed costs  |
| Terminal area (69kV)        |  |                      |                  |              |  |
| 1                           | Main stan un transformor                               |                      |                  | ¢600.000     | Northern Transformer reference, 10M/M  |
| 1                           | ivialitistep up transformer                            |                      |                  | \$000,000    | (6/8/10MVA) 2 stage fan cooled 35kV-69kV   |
| 2                           | 69kV Motorized Disconnect                              |                      |                  | \$25,000     | Cost reference from another project  |
| 2                           | Switch   |                      |                  | \$25,000     | cost reference from unother project.   |
| 3                           | MV Surge arresters                                     |                      |                  | \$15,000     | Cost reference from another project  |
| 4                           | 69kV circuit breaker                                   |                      |                  | \$250,000    | Cost reference from another project  |
| 5                           | 69kV Bevenue Metering                                  |                      |                  | \$150,000    | Cost reference from another project  |
| 6                           | Additions to existing protection                       |                      |                  | \$200,000    | Protection relays & racking IV DC/AC wiring nower  |
|                             | and control building                                   |                      |                  | ¥200,000     | plant controller. It is assumed that new protection<br>equipment will fit within existing P&C building |
| 7                           | SCADA and solar plant controller                       |                      |                  | \$150,000    | SCADA equipment added to the existing P&C building   |
| 8                           | 69kV support steel structures                          |                      |                  | \$300,000    |  |
| 9                           | Upgrade to station service                             |                      |                  | \$25,000     |  |
| 10                          | 35kV pad mount switchgear                              |                      |                  | \$95.000     | Reference to vendor quote (G&W)  |
| 11                          | Substation Civil works and                             |                      |                  | \$160,000    | Internal references (includes foundation for main  |
|                             | foundation   |                      |                  | ,            | transformer, MV breaker, pad mount switchgear and support structures)                                  |
| 12                          | Substation testing and commissioning                   |                      | 0.007            | \$91,000     |  |
| 13                          |  |                      | 0.08             |              | Equipment rentals, tools, etc. Cost reference from   |
|                             | Indirect Costs   |                      |                  | \$1,040,000  | another project.   |
|                             | Subtotal - Terminal Area                               |                      |                  | \$3,101,000  |  |
|                             |  |                      |                  |              |  |
|                             | Contingency  |                      | 0.1              | \$1,700,000  | Assumes 10% (reference from another project)   |
|                             |  |                      |                  |              |  |
|                             | TOTAL  |                      |                  | \$17,406,000 |  |
|                             | PESS system  |                      |                  |              |  |
|                             | DEDD SYSTEM  |                      |                  |              |  |
|                             |  |                      |                  |              |  |
| 1                           | DC BESS  | Sungrow 3.3MW/10MWh  | 3                | \$525,000    | Quote from vendor (prorated for this project)  |
| 2                           | BESS 40 foot container                                 | Sungrow              | 3                | \$525,000    | Quote from vendor (prorated for this project)  |
| 3                           | BESS and inverter foundations                          |                      |                  | \$330,000    |  |
|                             | TOTAL  |                      |                  | A4 000 000   |  |
|                             | TUTAL  |                      |                  | \$1,380,000  |  |

PUB-NLH-288, Attachment 2 **Reliability and Resource Adequacy Study Review** f 35

|           | inc.             | nability | and hesource Adequacy study hev |
|-----------|------------------|----------|---------------------------------|
|           |                  |          | Page 33 o                       |
|           |                  |          | newfoundland labrador<br>hydro  |
| scription | PU cost (\$ CAD) | Total    | Comments                        |

| Class 5 Solar farm Estimate                  | 20MWac solar farm + BESS   |                                |                      |  |   |
|--|--|--------------------------------|----------------------|--|---|
| DC/AC ratio                                  | 1.3  |                                |                      |  |   |
| Module type                                  | Longi, LR5-72W, 545W   |                                |                      |  | <b>h</b> idro   |
| Size (MWdc)                                  | 20   |                                |                      |  |   |
| Number of Modules                            | 47,706   |                                |                      |  |   |
| Development Activities                       |  | Description                    | PU cost (\$ CAD)     | Total  | Comments  |
|  |  |                                |                      |  |   |
| Engineering and Permitting                   |  |                                |                      |  |   |
| 1  | Interconnection Studies  |                                | 1                    | \$50.000   |   |
| 2  | Environmental Assessments  |                                | 1                    | \$50,000   |   |
| 3  | Permits and licenses   |                                | 1                    | \$50,000   |   |
| 4  | Site surveys   |                                | 1                    | \$50,000   |   |
| 5  | Geotech  |                                | 1                    | \$40,000   |   |
| 5  | Detailed Engineering   |                                | 1                    | \$600,000  | \$120/hour. Includes construction support and<br>occasional site visit  |
| 6  | Site management (site mtg, cost  |                                | 2                    | \$160,000  |   |
| 7  | Owner Engineer Role  |                                | 1                    | \$80,000   | Includes drawing review and approval, occasional site   |
|  | -  |                                |                      |  | visit   |
|  | Subtotal - Engineering and Permi   | tting                          |                      | \$1,080,000  |   |
|  |  |                                |                      |  | In stall a state  |
| sular Field                                  |  |                                |                      |  | Instaneu costs  |
| 1  | PV module  | Longi LR5-72HBD 545W           | 0.45                 | \$11,700,000   | Cost of PV assumed to be \$0.45/Watt based on previous project quotes   |
| 2  | Inverters package  | Sungrow 3600UD-MV              | 6                    | \$1,320,000  | Quote from vendor (prorated for this project)   |
| 3  | Solar AC and DC supply &<br>installation   |                                | 0.1                  | \$2,600,000  | Includes DC harnesses, combiner boxes, AC cabling.<br>Factor reference from another project   |
| 4  | SCADA and fiber  |                                | 0.01                 | \$260.000  | Factor reference from another proiect   |
| 5  | Solar posts & racking  |                                | 0.18                 | \$4,680,000  | \$0.13/W. Cost reference from another project as per  |
| 6  | Post, PV module and rack   |                                | 0.05                 | \$1,300,000  | vendor quote<br>Cost reference from another project.  |
| 7  | Civil Works  |                                | 0.05                 | \$1,300,000  | Includes site clearing, solar farm service roads,<br>grubbing   |
| 0  | DC system commissioning  |                                | 0.005                | \$120,000  | Cost reference from another project   |
| o<br>  | De system commissioning  |                                | 0.003                | \$130,000  | cost reference nom another project.   |
|  | Subtotal - Solar Field   |                                |                      | \$23,290,000   |   |
|  |  |                                |                      |  |   |
| Terminal area (69kV)                         |  |                                |                      |  | Installed costs   |
|  |  |                                |                      |  |   |
| 1  | Main step up transformer   |                                |                      | \$600,000  | Northern Transformer reference, 10MW (6/8/10MVA)<br>2 stage fan cooled, 35kV-69kV   |
| 2  | 69kV Motorized Disconnect<br>Switch  |                                |                      | \$25,000   | Cost reference from another project.  |
| 3  | MV Surge arresters   |                                |                      | \$15,000   | Cost reference from another project.  |
| 4  | 69kV circuit breaker   |                                |                      | \$250,000  | Cost reference from another project.  |
| 5  | 69kV PT (for protection)   |                                |                      | \$80,000<br>\$150,000  | Cost reference from another project.  |
| 7  | Additions to existing protection<br>and control building   |                                |                      | \$200,000  | Protection relays & racking, LV DC/AC wiring, power<br>plant controller. It is assumed that new protection  |
| 8  | SCADA and solar plant controller   |                                |                      | \$150,000  | equipment will fit within existing P&C building<br>SCADA equipment added to the existing P&C building   |
| 9  | 69kV support steel structures  |                                |                      | \$300,000  |   |
| 10   | Upgrade to station service<br>transformer  |                                |                      | \$25,000   |   |
| 11   | 35kV pad mount switchgear  |                                |                      | \$95,000   | Reference to vendor quote (G&W)   |
| 12   | Substation Civil works and<br>foundation   |                                |                      | \$160,000  | Internal references (includes foundation for main<br>transformer, MV breaker, pad mount switchgear and  |
| -  |  |                                |                      |  | support structures)   |
| 13   | Substation testing and   |                                |                      | \$182,000  | support structures)   |
| 13   | Substation testing and commissioning   |                                | 0.007                | \$182,000  | support structures)   |
| 13   | Substation testing and<br>commissioning<br>Indirect Costs  |                                | 0.007<br>0.08        | \$182,000<br>\$2,080,000   | support structures)<br>Equipment rentals, tools, etc. Cost reference from<br>another project.   |
| 13   | Substation testing and<br>commissioning<br>Indirect Costs<br>Subtotal - Terminal Area  |                                | 0.007<br>0.08        | \$182,000<br>\$2,080,000<br><b>\$4,312,000</b>   | support structures)<br>Equipment rentals, tools, etc. Cost reference from<br>another project.   |
| 13<br>14<br>15                               | Substation testing and<br>commissioning<br>Indirect Costs<br>Subtotal - Terminal Area<br>Contingency   |                                | 0.007<br>0.08        | \$182,000<br>\$2,080,000<br><b>\$4,312,000</b><br><b>\$3,100,000</b>                                 | support structures)<br>Equipment rentals, tools, etc. Cost reference from<br>another project.<br>Assumes 10% (reference from another project)   |
| 13<br>14<br>15                               | Substation testing and<br>commissioning<br>Indirect Costs<br>Subtotal - Terminal Area<br>Contingency   |                                | 0.007 0.08           | \$182,000<br>\$2,080,000<br>\$4,312,000<br>\$3,100,000<br>\$31,782.000                               | support structures)<br>Equipment rentals, tools, etc. Cost reference from<br>another project.<br>Assumes 10% (reference from another project)   |
| 13<br>14<br>15                               | Substation testing and<br>commissioning<br>Indirect Costs<br>Subtotal - Terminal Area<br>Contingency<br>TOTAL<br>BESS system   |                                | 0.007                | \$182,000<br>\$2,080,000<br>\$4,312,000<br>\$3,100,000<br>\$31,782,000                               | support structures)<br>Equipment rentals, tools, etc. Cost reference from<br>another project.<br>Assumes 10% (reference from another project)   |
|  | Substation testing and<br>commissioning<br>Indirect Costs<br>Subtotal - Terminal Area<br>Contingency<br>TOTAL<br>BESS system   |                                | 0.007                | \$182,000<br>\$2,080,000<br>\$4,312,000<br>\$3,100,000<br>\$31,782,000                               | support structures)<br>Equipment rentals, tools, etc. Cost reference from<br>another project.<br>Assumes 10% (reference from another project)   |
| 13<br>14<br>15<br>15                         | Substation testing and<br>commissioning<br>Indirect Costs<br>Subtotal - Terminal Area<br>Contingency<br>TOTAL<br>BESS system<br>DC BESS  | Sungrow 3.3MW/10MWh            | 0.007<br>0.08        | \$182,000<br>\$2,080,000<br>\$4,312,000<br>\$3,100,000<br>\$31,782,000<br>\$1,050,000                | support structures)<br>Equipment rentals, tools, etc. Cost reference from<br>another project.<br>Assumes 10% (reference from another project)<br>Quote from vendor (prorated for this project)  |
| 13<br>14<br>15<br>1<br>1<br>2                | Substation testing and<br>commissioning<br>Indirect Costs<br>Subtotal - Terminal Area<br>Contingency<br>TOTAL<br>BESS system<br>DC BESS<br>BESS 40 foot container                                  | Sungrow 3.3MW/10MWh            | 0.007<br>0.08<br>0.1 | \$182,000<br>\$2,080,000<br>\$4,312,000<br>\$3,100,000<br>\$31,782,000<br>\$1,050,000<br>\$1,050,000 | support structures) Equipment rentals, tools, etc. Cost reference from another project. Assumes 10% (reference from another project) Quote from vendor (prorated for this project) Quote from vendor (prorated for this project)                |
| 13<br>14<br>15<br>15<br>1<br>1<br>2<br>3     | Substation testing and<br>commissioning<br>Indirect Costs<br>Subtotal - Terminal Area<br>Contingency<br>TOTAL<br>BESS system<br>DC BESS<br>BESS 40 foot container<br>BESS and inverter foundations | Sungrow 3.3MW/10MWh<br>Sungrow | 0.007<br>0.08<br>0.1 | \$182,000<br>\$2,080,000<br>\$4,312,000<br>\$3,100,000<br>\$31,782,000<br>\$1,050,000<br>\$660,000   | support structures)<br>Equipment rentals, tools, etc. Cost reference from<br>another project.<br>Assumes 10% (reference from another project)<br>Quote from vendor (prorated for this project)<br>Quote from vendor (prorated for this project) |
| 13<br>14<br>15<br>15<br>1<br>1<br>2<br>3<br> | Substation testing and<br>commissioning<br>Indirect Costs<br>Subtotal - Terminal Area<br>Contingency<br>TOTAL<br>BESS system<br>DC BESS<br>BESS 40 foot container<br>BESS and inverter foundations | Sungrow 3.3MW/10MWh<br>Sungrow | 0.007<br>0.08<br>0.1 | \$182,000<br>\$2,080,000<br>\$4,312,000<br>\$3,100,000<br>\$31,782,000<br>\$1,050,000<br>\$660,000   | support structures) Equipment rentals, tools, etc. Cost reference from another project. Assumes 10% (reference from another project) Quote from vendor (prorated for this project) Quote from vendor (prorated for this project)                |

PUB-NLH-288, Attachment 2 Reliability and Resource Adequacy Study Review Page 34 of 35



### Appendix D

**Project Schedule** 

254388-0000-DF00-STY-0001

PUB-NLH-288, Attachment 2

SCADA

**Reliability and Resource Adequacy Study Review** Page 35 of 35

∢ Σ ⊔ Year 3  $\diamond$ \_ z 0  $\diamond$ S ∢ Year 2 -\_  $\diamond$ Σ ∢ Σ щ \_ Δ z 0 S  $\diamond$ ∢ Year 1 \_ \_ Solar Farm Project Schedule Σ ∢ Σ u. \_ z FEED Stage ÷ щ \_ Substation equipment (breaker, PT/CTs, switches, etc) Engineering support (Procurement and Construction) Electrical bulk material (cables, conduits, buswork) Electrical infrastructure (BESS/Inverter, substation) DC solar farm (PV strings, inverters/BESS) Deficiency and punch list items Inverters and DC coupled BESS **Commissioning and testing** Post construction activites Preconstruction activites Main Power transfomer Substantial completion Pile and racking install Substation equipment Engineering as builts SCADA and Controls Geotech field work Functional testing Preliminary Design Structural Design PV module install Electrical Design Racking & piles Site civil work Facility Study Procurement Construction Engineering Civil Design PV modules





# BESS Project Preliminary Cost Estimate 254388-0000-DF00-STY-0002

August 22, 2022

Wood Canada Limited 600–2020 Winston Park Drive Oakville, ON L6H 6X7



Date

### **APPROVALS**

| Igor ogic               | August 22, 2022 |
|-------------------------|-----------------|
| Prepared by: Igor Bozic | Date            |
| Levis Ham               | August 22, 2022 |
| Checked by: Lewis Hann  | Date            |
| Levie Ham               | August 22, 2022 |

Approved by: Lewis Hann

| Professional Stamp   |                   |  |  |  |
|--|-------------------|--|--|--|
| PROVINCE OF NEWFOUNDLAND AND LABRADOR<br>Pegni ENGINEERING<br>PERMIT D0018<br>Wood Canada Limited<br>02020<br>Signature or Member Number<br>(Member-in-Responsible Charge) | THE AUG. 22, 2022 |  |  |  |

#### IMPORTANT NOTICE

This Document was prepared exclusively for **Newfoundland and Labrador (NL) Hydro**, by Wood Canada Limited (Wood), a wholly owned subsidiary of John Wood Group PLC. The quality of information contained herein is consistent with the level of effort agreed in the scope of services and is based on: i) information available at the time of preparation, ii) data supplied by outside sources, and iii) the assumptions, conditions and qualifications set forth in this Design Basis. This Design Basis is intended to be used by **Newfoundland and Labrador (NL) Hydro** only, subject to the terms and conditions of its contract with Wood Canada Limited. Any other use of, or reliance on, this (specification/report to be edited) by any third party is at that party's sole risk.

PUB-NLH-288, Attachment 3 Reliability and Resource Adequacy Study Review Page 3 of 18



### **REVISION HISTORY**

| Rev. | Description       | Prepared<br>By | Checked<br>By | Approved<br>By | Date       |
|------|-------------------|----------------|---------------|----------------|------------|
| Α    | Issued for review | IB             | LH            | LH             | 07/12/2022 |
| В    | Issued for use    | IB             | LH            | LH             | 07/28/2022 |
| С    | Reissued for use  | IB √8          | LH LH         | LH LH          | 08/22/2022 |
|      |                   |                |               |                |            |
|      |                   |                |               |                |            |
|      |                   |                |               |                |            |
|      |                   |                |               |                |            |
|      |                   |                |               |                |            |



Page

### **Table of Contents**

1.

2.

3.

4.

|     | Introduction                         | 1 |
|-----|--------------------------------------|---|
|     | Purpose and Scope                    | 1 |
|     | System Characteristics               | 1 |
| 3.1 | Battery Energy Storage System (BESS) | 1 |
| 3.2 | Civil Engineering Considerations     | 2 |
| 3.3 | MV collector system                  | 3 |
| 3.4 | Terminal Station interconnection     | 4 |
|     | Cost and Schedule                    | 5 |
| 4.1 | Type of Estimate                     | 5 |
| 4.2 | Project schedule                     | 5 |
| 4.3 | Cost Summary                         | 6 |
|     |                                      |   |

- Appendix A: AC coupled BESS package
- Appendix B: Cost summary
- Appendix C: Project Schedule

### 1. Introduction

Newfoundland and Labrador (NL) Hydro is looking for an opportunity to introduce AC coupled Battery Energy Storage System (BESS) into their existing infrastructure. The specific location of the system has not yet been determined, however the site is expected to be near Avalon Peninsula connected to an existing terminal station on a 69/66kV bus.

### 2. Purpose and Scope

The purpose of the report is to provide an indicative (Class 5) cost estimate for an 20MWac and 50MWac BESS system with 4-hour reserve. The BESS would be connected to the existing terminal station at 66kV/69kV bus. This estimate includes relevant MV substation interconnection components needed to integrate with the existing terminal stations. For the purpose of this estimate, 69kV voltage level shall be considered.

Wood has made assumptions based on industry standards and previous experiences with AC coupled BESS, as follows:

- MV collector system design including substation requirements
- Project scheduling and major project milestones
- Developmental activities such as field investigation (ex. Geotech report), desktop studies, permitting, preliminary & detailed engineering, environmental studies, licenses, etc.
- Major equipment costs
- Supporting activities during the construction stage (Site management & monitoring, owner engineer costs, safety, equipment rental, etc.)
- Construction cost for both BESS and upgrades at the existing 69kV terminal station

### 3. System Characteristics

This section describes technologies and technical characterises of the major components for AC coupled BESS package, MV collector system including associated cabling, substation components required at the terminal station (such as main power transformer, breaker, disconnect switch, protection and metering).

### 3.1 Battery Energy Storage System (BESS)

The proposed BESS solution is AC coupled, where batteries are connected to a common MV bus at the substation. The system can store energy from any generation source with main purpose being to discharge during peak electricity use. Peak shaving concept is depicted on **Figure 1** below.



Figure 1: Peak shaving concept

AC coupled systems are generally considered for existing electrical infrastructure as they are easier to retrofit when compared to DC coupled solutions (typical for new solar PV installations). The drawback with AC coupled systems is the additional power conversion, from generating source to BESS and then from BESS to AC grid, resulting in additional efficiency losses. The typical industry standard for BESS lifespan is 20 years and standard warranties are 3 years. Extended warranties up to 20 years can be procured, however pricing for this was not available for this study..

### 3.2 Civil Engineering Considerations

Preliminary design approach needs to ensure that there is adequate area for BESS equipment. A typical BESS is housed in container with approximate dimensions:  $12m (L) \times 3m (W) \times 3.5m (H)$ , however every vendor provides different MW/MWh capacity per container and as a result physical sizes will vary. Wood assumes 3MW/12MWh for a typical container with dimension as noted above.

- a) Option 1: 20MW, 4 hours reserve system would require 7 containers
- b) Option 2: 50 MW, 4 hours reserve system would require 17 containers

To allow for clearance and location for AC MV connections (MV transformers, cabling, etc.), additional 2.5m around each side of the BESS container is assumed. The arrangement will require following area:

- a) Option 1: 7 containers x [12m x (3m + 2.5m + 2.5m)] + 20% contingency = 806 m<sup>2</sup>
- b) Option 2: 17 containers x [12m x (3m + 2.5m + 2.5m)] + 20% contingency = 1958 m<sup>2</sup>



Figure 2: BESS Layout

254388-0000-DF00-STY-0002

### 3.3 MV collector system

Wood recommends to have BESS system stepped up at 34.5kV level which is industry standard distribution voltage for the collector system in renewable sector; further this will be stepped up to 69kV level at the terminal station.

A typical BESS package will consist of a DC battery pack, DC-AC inverter, and 34.5kV step-up transformer connecting to point of common coupling (PCC) as per **Figure 3** below.



#### Figure 3: BESS SLD

As indicated above Wood assumed 3MW/12MWh BESS block. Units will be daisy chained and connected to a dedicated 34.5kV switchgear at the terminals station as per sample single line noted in **Figure 4**. Depending on the size of the BESS system, additional feeder breakers may be required. Further, design philosophy may dictate less BESS blocks in a circuit to ensure redundancy in case of trip or maintenance. With this approach, other blocks connected in a separate 34.5kV circuit can perform without interruption.

PUB-NLH-288, Attachment 3 Reliability and Resource Adequacy Study Review Page 8 of 18





### Figure 4: BESS AC arrangement

In addition to 34.5kV distribution, each BESS container will require external power supply for auxiliary loads (HVAC, controls, small power, etc.) and fiber optic connection to SCADA system.

### 3.4 Terminal Station interconnection

At the existing MV terminal station (69kV), it would be necessary to step up from 34.5kV switchgear to the terminal station voltage. For the interconnection, it will be necessary to interface with new 69kV breaker along with 69KV voltage transformer (for relay protection purposes), HV metering structure and main two stage fan cooled step-up transformer as follows:

- Option 1: 12/16/20MVA, 69kV-35kV
- Option 2: 30/40/50MVA, 69kV-35kV

254388-0000-DF00-STY-0002

### 4. Cost and Schedule

### 4.1 Type of Estimate

This estimate is a Class 5 indicative estimate. This classification represents a rough order of magnitude estimate. It generally implies from -20% to 50% on the low side and +30% to up to 100% on the high side in accordance with AACE International Recommended Practices.

### 4.2 Project schedule

Project schedule is very important aspect in particular in today's volatile market and much longer lead time for equipment procurement. Addressing preliminary design at early stages and securing long lead items are critical for the overall project delivery. This in particular refers to: BESS packages, 69kV substation equipment such as main transformer, PTs & breakers.

Utility scale BESS are new in NL and availability of skilled resources and general labour may be limited. Construction activities shall ensure that all civil and electrical work occurs in spring to fall period. During winter months limited electrical work (such as LV wiring connections at protection building), commissioning activities and addressing minor deficiencies can occur.

Geotech field work must be performed as soon as possible so the project team can understand the proposed land features in order to plan for proper foundation design for BESS. For indicative project schedule please refer to **Appendix C**.

Project durations for BESS installations can range from approximately one year for accelerated commercial ventures to in excess of 2 years when pre-feed activities, permitting, project sanctioning, procurement of long lead items and construction season limitations are all taken into account. For an indicative project schedule please that takes these elements into consideration refer to **Appendix D**.

Following is a list of typical sequential project activities:

- a) Permitting and approval process
- b) Geotech field work
- c) Base engineering (needed for key equipment procurement)
- d) Equipment procurement
- e) Detailed engineering
- f) Construction
- g) Testing and commissioning
- h) Post construction activities (deficiencies, warranty items, etc.)



### 4.3 Cost Summary

| 20 | 20 MW BESS (4hr @ 20 MW / 80 MWh) |              |  |  |
|----|-----------------------------------|--------------|--|--|
|    | Engineering and Permitting        | \$940,000    |  |  |
|    | BESS Area                         | \$30,975,000 |  |  |
|    | Terminal Station Upgrades (69 kV) | \$2,675,000  |  |  |
|    | Contingency (10%)                 | \$3,500,000  |  |  |
|    | Total Estimated Cost              | \$37,910,000 |  |  |

| 50 | 50 MW BESS (4hr @ 50 MW / 200 MWh) |              |  |  |
|----|------------------------------------|--------------|--|--|
|    | Engineering and Permitting         | \$1,080,000  |  |  |
|    | BESS Area                          | \$74,582,000 |  |  |
|    | Terminal Station Upgrades (69 kV)  | \$3,190,000  |  |  |
|    | Contingency (10%)                  | \$7,500,000  |  |  |
|    | Total Estimated Cost               | \$86,312,000 |  |  |

For detailed breakdown for both 20MW/80MWh and 50MW/200MWh BESS please refer to Appendix B.

PUB-NLH-288, Attachment 3 Reliability and Resource Adequacy Study Review Page 11 of 18



### **APPENDICES**

254388-0000-DF00-STY-0002

woodplc.com

Page:7

PUB-NLH-288, Attachment 3 Reliability and Resource Adequacy Study Review Page 12 of 18

### Appendix A

AC Coupled BESS package

254388-0000-DF00-STY-0002

PUB-NLH-288, Attachment 3 Reliability and Resource Adequacy Study Review Page 13 of 18

|                             |  |   | W                                     | ood.                               |
|-----------------------------|--|---|---------------------------------------|------------------------------------|
| Customer:                   | John Wood Group PLC  |   | SunGrid Solutions                     |                                    |
| Name:                       | Igor Bozic   |   | 135 George St. N                      |                                    |
| Contact:                    | Igor.bozic@woodplc.com   |   | Cambridge, ON, N1S 2M                 | 6                                  |
|                             |  |   | www.sungridsolutions.c                | om                                 |
| Project:                    | BESS in NL   |   | Contact:                              | Jacky Jiang                        |
| Prj. #:                     | 570  |   |                                       | jacky.jiang@sungridsolutions.com   |
| Quote #:                    | 01   |   |                                       | 647-865-5624                       |
| Size:                       | 23MW, 85MWh / 52MW, 210MWh   |   | Date:                                 | 30-Jun-22                          |
| Delivery:                   | Newfoundland and Labrador  |   | Valid:                                | 30 Days                            |
|                             | SunGrid Indicative   | Pricing   |                                       | Notes                              |
|                             |  | 23MW, 85MWh   | 52MW, 210MWh                          |                                    |
|                             | Description  | Total Price   | Total Price                           | Dischargeble Energy = 85MWh DC and |
| Integration                 | Engineering Services   | \$ 624,000  | \$ 1,192,000                          | 210MWh DC at Year 0                |
| Interconnec                 | tion (support only)  | TBD   | TBD                                   | 1                                  |
| Permits (su                 | pport only)  | TBD   | TBD                                   |                                    |
| Equipment                   |  |   | -                                     | - Delivery Date: TBD               |
|                             | Battery Cabinet  | Included  | l Included                            |                                    |
|                             | -Batteries, Enclosures, HVAC, FSS, DC combiner   | Included  | I Included                            | <u>Payment Terms</u>               |
|                             | -PCS   | Included  | I Included                            | - 30% Purchase Order               |
|                             | MV Transformer   | Included  | Included                              | - 30% Mfg Start                    |
|                             | EMS (Fractal or customer preference)   | Included  |                                       | - 30% Delivery                     |
|                             | MV Switchgoor Polo Mounted Disconnects Polo  | includee  | included                              |                                    |
|                             | Run Protection Minor Equanment etc   | Included  | I Included                            |                                    |
|                             | Chinning Logistics   | Includes  | h h h h h h h h h h h h h h h h h h h |                                    |
|                             |  |   |                                       |                                    |
| Constructio                 | notal Equipment  | \$ 24,686,000   | \$ 60,807,000                         |                                    |
| constructio                 | Civil(Eencing Foundations Piles Vaults etc.)   | Included  | Included                              |                                    |
|                             | Civil Site Works/ Install  | Included  | Included                              |                                    |
|                             | Mechanical Installation  | Included  | Included                              |                                    |
|                             | Electrical install (all terminations)  | Included  | l Included                            |                                    |
|                             | Total Construction/Install   | \$ 5,085,000  | \$ 11,173,000                         | 1                                  |
| Commissior                  | ning   | Included  | I Included                            | 1                                  |
| Sales Tax                   |  | Not Included  | l Not Included                        | 1                                  |
| Warranty a                  | nd Performance Guarantee   |   |                                       | 1                                  |
|                             |  |   |                                       |                                    |
|                             | 3-year workmanship   | Included  | I Included                            |                                    |
| Total                       | 3-year workmanship   | Includec<br>\$ 30,395,000   | Included \$ 73,882,000                |                                    |
| Total<br>Clarificatior      | 3-year workmanship   | Includec<br>\$ 30,395,000   | Included \$ 73,882,000                |                                    |
| Total<br>Clarificatior      | 3-year workmanship<br>15<br>- Import duties and sales tax not included   | Includec<br>\$ 30,395,000   | Included                              |                                    |
| Total<br>Clarificatior      | 3-year workmanship<br>IS<br>- Import duties and sales tax not included<br>- Assumed clear site/road access to BESS   | Includec<br>\$ 30,395,000   | I Included                            |                                    |
| ,<br>Total<br>Clarificatior | 3-year workmanship<br>IS<br>- Import duties and sales tax not included<br>- Assumed clear site/road access to BESS<br>- Non-unionized labour   | Includec<br>\$ 30,395,000   | I Included                            |                                    |
| ,<br>Total<br>Clarificatior | 3-year workmanship<br>15<br>- Import duties and sales tax not included<br>- Assumed clear site/road access to BESS<br>- Non-unionized labour<br>- Transfer trip not included   | Includec<br>\$ 30,395,000   | Included                              |                                    |
| Total<br>Clarificatior      | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site   | Includec<br>\$ 30,395,000   | Included                              |                                    |
| ,<br>Total<br>Clarificatior | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site Permit fees, application fees, etc. not included (support only)   | Includec<br>\$ 30,395,000   | Included                              |                                    |
| Total<br>Clarification      | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site Permit fees, application fees, etc. not included (support only) Final Interconnection not included  | Includec<br>\$ 30,395,000   | Included                              |                                    |
| ,<br>Total<br>Clarificatior | 3-year workmanship<br>Is<br>- Import duties and sales tax not included<br>- Assumed clear site/road access to BESS<br>- Non-unionized labour<br>- Transfer trip not included<br>- POI located within BESS site<br>- Permit fees, application fees, etc. not included (support only)<br>- Final Interconnection not included<br>- Water well or city water or city sewer connection   | Includec<br>\$ 30,395,000   | Included                              |                                    |
| ,<br>Total<br>Clarificatior | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site Permit fees, application fees, etc. not included (support only) Final Interconnection not included Water well or city water or city sewer connection Hazardous and or contaminated material removal, investigatio   | Includec<br>\$ 30,395,000   | Included                              |                                    |
| ,<br>Total<br>Clarificatior | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site Permit fees, application fees, etc. not included (support only) Final Interconnection not included Water well or city water or city sewer connection Hazardous and or contaminated material removal, investigatio Utility fees and/or interconnection costs not included Charge/Discharge signal/algorithm pot included   | Includec<br>\$ 30,395,000   | Included                              |                                    |
| Total<br>Clarificatior      | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site Permit fees, application fees, etc. not included (support only) Final Interconnection not included Water well or city water or city sewer connection Hazardous and or contaminated material removal, investigatio Utility fees and/or interconnection costs not included Charge/Discharge signal/algorithm not included, Provided by C Internet connection provided to RESS by others   | Includec<br>\$ 30,395,000   | Included                              |                                    |
| Total<br>Clarification      | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site Permit fees, application fees, etc. not included (support only) Final Interconnection not included Water well or city water or city sewer connection Hazardous and or contaminated material removal, investigatio Utility fees and/or interconnection costs not included Charge/Discharge signal/algorithm not included, Provided by C Internet connection provided to BESS by others Special situations for equipment handline. offloading. rigging a  | Included<br>\$ 30,395,000<br>n, abatement or removals not in<br>others<br>nd the installation of DC Stacks  | Included                              |                                    |
| ,<br>Total<br>Clarification | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site Permit fees, application fees, etc. not included (support only) Final Interconnection not included Water well or city water or city sewer connection Hazardous and or contaminated material removal, investigatio Utility fees and/or interconnection costs not included Charge/Discharge signal/algorithm not included, Provided by C Internet connection provided to BESS by others Special situations for equipment handling, offloading, rigging a Temporary equipment laydown area provided on worksite  | Included<br><b>\$ 30,395,000</b><br>n, abatement or removals not in<br>others<br>nd the installation of DC Stacks                                       | Included                              |                                    |
| Total<br>Clarification      | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site Permit fees, application fees, etc. not included (support only) Final Interconnection not included Water well or city water or city sewer connection Hazardous and or contaminated material removal, investigatio Utility fees and/or interconnection costs not included Charge/Discharge signal/algorithm not included Internet connection provided to BESS by others Special situations for equipment handling, offloading, rigging a Temporary equipment laydown area provided on worksite No extreme irregularities with soil quality   | Included<br><b>\$ 30,395,000</b><br>In, abatement or removals not in<br>others<br>Ind the installation of DC Stacks                                     | Included                              |                                    |
| Total<br>Clarification      | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site Permit fees, application fees, etc. not included (support only) Final Interconnection not included Water well or city water or city sewer connection Hazardous and or contaminated material removal, investigatio Utility fees and/or interconnection costs not included Charge/Discharge signal/algorithm not included Internet connection provided to BESS by others Special situations for equipment handling, offloading, rigging a Temporary equipment laydown area provided on worksite No extreme irregularities with soil quality ALL onsite commissioning maximum of 2 weeks included applic | Included<br><b>\$ 30,395,000</b><br>In, abatement or removals not in<br>thers<br>Ind the installation of DC Stacks<br>cation support, operation support | Included                              |                                    |
| Total<br>Clarification      | 3-year workmanship  Is  Import duties and sales tax not included Assumed clear site/road access to BESS Non-unionized labour Transfer trip not included POI located within BESS site Permit fees, application fees, etc. not included (support only) Final Interconnection not included Water well or city water or city sewer connection Hazardous and or contaminated material removal, investigatio Utility fees and/or interconnection costs not included Charge/Discharge signal/algorithm not included Charge/Discharge signal/algorithm not included Temporary equipment laydown area provided on worksite No extreme irregularities with soil quality ALL onsite commissioning maximum of 2 weeks included applic  | Included<br><b>\$ 30,395,000</b><br>In, abatement or removals not in<br>thers<br>and the installation of DC Stacks<br>cation support, operation support | Included                              |                                    |

PUB-NLH-288, Attachment 3 Reliability and Resource Adequacy Study Review Page 14 of 18

## Appendix B

Cost Estimate

|                             | 201444 0555 11                   |                              |                  |              | nou fermalised is been also   |
|-----------------------------|----------------------------------|------------------------------|------------------|--------------|---|
| Class 5 Solar farm Estimate | 20MWac BESS, 4 h reserve         | 4                            |                  |              | newroundland labrador   |
| Size (MW)                   | 20                               |                              |                  |              | hudro   |
| Duration (h)                | 4                                |                              |                  |              |   |
| Size (MWh)                  | 80                               |                              |                  |              |   |
|                             |                                  | 1                            |                  |              |   |
| Development Activities      |                                  | Description                  | PU cost (\$ CAD) | Total        | Comments  |
|                             |                                  |                              |                  |              |   |
| Engineering and Dermitting  |                                  |                              |                  |              |   |
| Engineering and Permitting  |                                  |                              | 4                | 650.000      |   |
| 1                           | Interconnection Studies          |                              | 1                | \$50,000     |   |
| 2                           | Environmental Assessments        |                              | 1                | \$50,000     |   |
| 3                           | Permits and licenses             |                              | 1                | \$50,000     |   |
| 4                           | Site surveys                     |                              | 1                | \$50,000     |   |
| 5                           | Geotech                          |                              | 1                | \$40,000     |   |
| 6                           | Detailed Engineering             |                              | 1                | \$480,000    | Assumes 4000 hours with an average rate of  |
|                             |                                  |                              |                  |              | \$120/hour. Includes construction support and                                       |
|                             |                                  |                              |                  |              | occasional site visits  |
| 7                           | Site management (site mtg, cost  |                              | 2                | \$160,000    |   |
|                             | controller, safety               |                              |                  |              |   |
| 8                           | Owner Engineer Role              |                              | 1                | \$60,000     | Includes drawing review and approval, occassional<br>site visit                     |
|                             | Subtotal - Engineering and Permi | l<br>tting                   |                  | \$940.000    |   |
|                             |                                  |                              |                  | \$340,000    |   |
| B566                        |                                  |                              |                  |              | la sta lla di se sta  |
| BESS area                   |                                  |                              |                  |              | Installed costs   |
|                             |                                  |                              |                  |              |   |
| 1                           | AC BESS package                  | Quotes obtained from Sungrid | 1                | \$30,395,000 | Quotes includes civil works, foundation, MV   |
|                             |                                  | solutions and Tesla          |                  |              | transfomers, HVAC, enclosures, PCS, DC connections                                  |
| 2                           | AC/fiber cabling to Substation   |                              | 100              | \$100,000    | Assume \$1000/meter   |
| 3                           |                                  |                              | 1                | \$200,000    | Includes site clearing service reads grubbing                                       |
| -                           |                                  |                              | _                | *            | includes site clearing, service roads, grubbing,                                    |
|                             |                                  |                              |                  |              | drainage, etc   |
|                             | Civil Works                      |                              |                  |              |   |
| 4                           | BESS system commissioning        |                              | 1                | \$100,000    | Cost reference from another project.  |
|                             |                                  |                              |                  |              |   |
|                             | Subtotal - BESS Areas            |                              |                  | \$30,795,000 |   |
|                             |                                  |                              |                  |              |   |
| Terminal area (69kV)        |                                  |                              |                  |              | Installed costs   |
|                             |                                  |                              |                  |              |   |
| 1                           | Main step up transformer         |                              |                  | \$750,000    | Northern Transformer reference, 20MW<br>(12/16/20MVA) 2 stage fan cooled, 35kV-69kV |
| 2                           | 69kV Motorized Disconnect        |                              |                  | \$25,000     | Cost reference from another project   |
| 2                           | Cuvitab                          |                              |                  | \$23,000     | cost reference nom another project.   |
|                             | Switch                           |                              |                  | A15 000      |   |
| 3                           | MV Surge arresters               |                              |                  | \$15,000     | Lost reference from another project.  |
| 4                           | 69kV circuit breaker             |                              |                  | \$250,000    | Cost reference from another project.  |
| 5                           | 69kV PT (for protection)         |                              |                  | \$80,000     |   |
| 6                           | 69kV Revenue Metering            |                              |                  | \$150,000    | Cost reference from another project.  |
| 7                           | Addition to existing protection  |                              |                  | \$200.000    | Protection relays & racking, LV DC/AC wiring. It is                                 |
|                             | and control building             |                              |                  |              | assumed that new protection equipment will fit                                      |
|                             |                                  |                              |                  |              | within existing B&C building  |
|                             |                                  |                              |                  | 6202.000     |   |
| 8                           | 69KV support steel structures    |                              |                  | \$300,000    |   |
| 9                           | Upgrade to station service       |                              |                  | \$50,000     | Aux power to BESS containers  |
|                             | transformer                      |                              |                  |              |   |
| 10                          | 35kV pad mount switchgear        |                              |                  | \$95,000     | Reference to vendor quote (G&W)   |
| 11                          | Substation Civil works and       |                              |                  | \$160,000    | Internal references (includes foundation for main                                   |
|                             | foundation                       |                              |                  |              | transformer. MV breaker, pad mount switchgear and                                   |
|                             |                                  |                              |                  |              | support structures)   |
| 12                          | Substation tosting and           |                              |                  | \$100.000    |   |
| 12                          | Substation testing and           |                              |                  | \$100,000    |   |
|                             | commissioning                    |                              | 1                |              |   |
| 13                          |                                  |                              | 1                |              |   |
|                             | Indirect Costs                   |                              |                  | \$500,000    | Equipment rentals, tools, etc.  |
|                             |                                  |                              |                  |              |   |
|                             | Subtotal - Terminal Area         |                              |                  | \$2.675.000  |   |
|                             |                                  |                              |                  | +=,0:0,000   |   |
|                             |                                  |                              |                  |              |   |
|                             | Cantingangu                      | 1                            |                  | 63 F00 000   | Accumac 10% (reference from eacher and act)   |
|                             | contingency                      |                              | 0.1              | \$3,500,000  | Assumes 10% (reference from another project)  |
|                             |                                  |                              |                  |              |   |
|                             | TOTAL                            |                              |                  | \$37,910,000 |   |
|                             |                                  |                              |                  |              |   |
|                             |                                  |                              |                  |              |   |
|                             |                                  | •                            |                  |              | •   |

| Class E Solar farm Estimato | EOMAWAG RESS 4 h recervo                                |   |                  |              |   |
|-----------------------------|---|---|------------------|--------------|---|
|                             | Solitivae BESS, 4 Inteserve                             | -   |                  |              |   |
| Size (IVIV)                 | 30  | -   |                  |              | budro   |
| Duration (n)                | 4   | 4   |                  |              |   |
| Size (WWN)                  | 200   | 4   |                  |              |   |
|                             |   |   |                  | <i>.</i>     |   |
| Development Activities      |   | Description   | PU cost (\$ CAD) | lotal        | Comments  |
|                             |   |   |                  |              |   |
| Engineering and Permitting  |   |   |                  |              |   |
| 1                           | Interconnection Studies                                 |   | 1                | \$50,000     |   |
| 2                           | Environmental Assessments                               |   | 1                | \$50,000     |   |
| 3                           | Permits and licenses                                    |   | 1                | \$50,000     |   |
| 4                           | Site surveys  |   | 1                | \$50,000     |   |
| 5                           | Geotech   |   | 1                | \$40,000     |   |
| 6                           | Detailed Engineering                                    |   | 1                | \$540,000    | Assumes 4500 hours with an average rate of \$120/hour. Includes construction support and  |
| 7                           | Site management (site mtg, cost controller, safety      |   | 2                | \$180,000    | occasional site visits  |
| 8                           | Owner Engineer Role                                     |   | 1                | \$80,000     | Includes drawing review and approval, occasional site visit   |
|                             | Subtotal - Engineering and Permi                        | tting   |                  | \$1,040,000  |   |
|                             |   | -   |                  | .,,,         |   |
| BESS area                   |   |   |                  |              | Installed costs   |
|                             |   |   |                  |              |   |
| 1                           | AC BESS package   | Quotes obtained from Sungrid<br>Solutions and Tesla | 1                | \$73,882,000 | Quotes includes civil works, foundation, MV<br>transformers, HVAC, enclosures, PCS, DC connections  |
| 2                           | AC/fiber cabling to Substation                          |   | 200              | \$200.000    | Assume \$1000/meter   |
| 3                           |   |   | 1                | \$350,000    | Includes site clearing, service roads, grubbing,  |
|                             | Civil Works   |   |                  |              | urumuge, etc.   |
| 4                           | BESS system commissioning                               |   | 1                | ¢150.000     |   |
| 4                           | bess system commissioning                               |   | 1                | \$150,000    |   |
|                             | Subtotal - BESS Areas                                   |   |                  | \$74,582,000 |   |
|                             |   |   |                  |              |   |
| Terminal area (69kV)        |   |   |                  |              | Installed costs   |
|                             |   |   |                  |              |   |
| 1                           | Main step up transformer                                |   |                  | \$1,250,000  | Northern Transformer reference, 20MW<br>(12/16/20MVA) 2 stage fan cooled, 35kV-69kV   |
| 2                           | 69kV Motorized Disconnect<br>Switch                     |   |                  | \$25,000     | Cost reference from another project.  |
| 3                           | MV Surge arresters                                      |   |                  | \$15,000     | Cost reference from another project.  |
| 4                           | 69kV circuit breaker                                    |   |                  | \$250.000    | Cost reference from another project.  |
| 5                           | 69kV PT (for protection)                                |   |                  | \$80,000     |   |
| 6                           | 69kV Revenue Metering                                   |   |                  | \$150,000    | Cost reference from another project   |
| 7                           | Addition to existing protection<br>and control building |   |                  | \$200,000    | Protection relays & racking, LV DC/AC wiring, power<br>plant controller. It is assumed that new protection<br>equipment will fit within existing P&C building |
| 8                           | 69kV support steel structures                           |   |                  | \$300,000    |   |
| 9                           | Upgrade to station service transformer                  |   |                  | \$50,000     | Aux power to BESS containers  |
| 10                          | 35kV pad mount switchgear                               |   |                  | \$110,000    | Reference to vendor quote (G&W)   |
| 11                          | Substation Civil works and foundation                   |   |                  | \$160,000    | Internal references (includes foundation for main<br>transformer, MV breaker, pad mount switchgear and<br>support structures)                                 |
| 12                          | Substation testing and                                  |   | 1                | \$100,000    | Includes interconnection costs  |
| 13                          | Indirect Costs  |   | 1                | \$500.000    | Equipment rentals tools etc   |
|                             | Cubtetel Temple - LAura                                 |   |                  | \$300,000    |   |
|                             | Suptotal - Terminal Area                                |   |                  | \$3,190,000  |   |
|                             | Contingency   |   | 0.1              | \$7 500 000  | Assumes 10% (reference from another project)  |
|                             | Bener   |   | 0.1              | \$7,500,000  |   |
|                             | TOTAL   |   |                  | 60C 313 000  |   |
|                             | TOTAL   |   |                  | \$86,312,000 |   |
|                             |   |   |                  |              |   |
| 1                           |   | 1   |                  | 1            |   |

PUB-NLH-288, Attachment 3 Reliability and Resource Adequacy Study Review Page 17 of 18

### Appendix C

**Project Schedule** 

254388-0000-DF00-STY-0002

#### -Σ Year 3 ∢ Σ щ -z $\diamond$ 0 S ۷ Year 2 -- $\bigcirc$ Σ ∢ Σ щ \_ z 0 S $\diamond$ **BESS Project Schedule** ∢ Year 1 -\_ Σ ∢ Σ щ \_ z FEED Stage ÷ щ \_ Substation equipment (breaker, PT/CTs, switchgear, etc) Engineering support (Procurement and Construction) Electrical bulk material (cables, conduits, buswork) Electrical infrastrcture (BESS/Inverter, substation) Deficiency and punch list items **Commissioning and testing** Post construction activites Preconstruction activites Main Power transfomer Substantial completion Substation equipment Engineering as builts SCADA and Controls Geotech field work Preliminary design Functional testing Structural Design Electrical Design **BESS Installation** Site civil work Facility Study Procurement Construction **BESS system** Engineering **Civil Design** SCADA BESS

### PUB-NLH-288, Attachment 3 Reliability and Resource Adequacy Study Review Page 18 of 18

|             | EVALUATION OF ISLAND HYDROELECTRIC   | Revision |             |      |
|-------------|--------------------------------------|----------|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev      | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01       | 21-OCT-2022 | 1    |

NEWFOUNDLAND AND LABRADOR HYDRO

### Evaluation of Island Hydroelectric Generation Expansion Alternatives

**MAIN REPORT** 

SLI Document No. 691499-0000-40ER-1-0001

Date: October 21, 2022



|               | EVALUATION OF ISLAND HYDROELECTRIC   | Revision |             |      |
|---------------|--------------------------------------|----------|-------------|------|
|               | GENERATION EXPANSION ALTERNATIVES    | Rev      | Date        | Page |
| SNC · LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01       | 21-OCT-2022 | 2    |

#### DISCLAIMER

This report was prepared for Newfoundland and Labrador Hydro ("NLH") by SNC-Lavalin Inc. ("SLI") and is subject to the following qualifications and limitations.

The report has been prepared for the exclusive use by NLH and any use a third party makes of this report, or any reliance on or decisions made based on it, are the responsibility of such third parties. SLI accepts no responsibility and denies any liability whatsoever to parties other than NLH for loss or damage suffered by any third party as a result of decisions made or actions undertaken based on this report.

This report contains the expression of the professional judgement of SLI and the information herein has been prepared for the specific purpose and use as outlined in the Contract Documents and NLH Professional Service Request. It is meant to be read as a whole, and sections or parts thereof should thus not be read or relied upon out of context.

Data required to support some engineering assessments have not always been available and in such cases engineering judgments have been made. There are, therefore, risks inherent in the project which may or may not be outlined in the report. SLI accepts no liability beyond using reasonable diligence, professional skill and care in carrying out the engineering services associated in preparing the report, based on the circumstances SLI knew or ought to have known based on the information it had at the date the design development report was prepared.

SLI has, in preparing cost estimates and schedules, as the case may be, followed methodology and procedures, and exercised due care consistent with the intended level of accuracy, using its professional judgment and reasonable care. No warranty should be implied as to the accuracy of estimates.

|                      | EVALUATION OF ISLAND HYDROELECTRIC   | Revision |             |      |
|----------------------|--------------------------------------|----------|-------------|------|
|                      | GENERATION EXPANSION ALTERNATIVES    | Rev      | Date        | Page |
| <b>SNU · LAVALIN</b> | SLI Doc. No. 691499-0000-40ER-1-0001 | 01       | 21-OCT-2022 | 3    |

SIGN-OFF PAGE

Prepared by:

11

Brad Chaulk, P.Eng. Lead Project Execution Planner

SNC-Lavalin Inc.

Reviewed by:

Kurt Kennedy, M.Sc., P.Eng. Project Execution Planner

SNC-Lavalin Inc.

Approved by:

Greg Snyder

Greg Snyder, FEC, P.Eng. Project Manager

SNC-Lavalin Inc.

### TABLE OF CONTENTS

| 1. | EXECUTIVE SUMMARY                                 | 6  |
|----|---|----|
| 2. | STUDY MANDATE                                     | 7  |
|    | 2.1. BACKGROUND                                   | 7  |
|    | 2.2. STUDY OBJECTIVES                             | 7  |
|    | 2.3. HYDROELECTRIC GENERATION EXPANSION PROSPECTS | 7  |
|    | 2.4. STUDY TASKS                                  | 8  |
|    | 2.5. STUDY TEAM                                   | 8  |
|    | 2.6. ACKNOWLEDGEMENTS                             | 8  |
|    | 2.7. DEFINITIONS                                  | 8  |
| 3. | KEY ASSUMPTIONS                                   | 10 |
|    | 3.1. INDUSTRY PRACTICE                            | 10 |
|    | 3.2. OVERALL DECISION GATE PROCESS                | 10 |
|    | 3.3. HEAVY CIVIL PROJECT EXECUTION STANDARD       | 11 |
|    | 3.4. COST AND SCHEDULE ASSUMPTIONS                | 13 |
| 4. | TASK 1 – DOCUMENT REVIEW                          | 14 |
|    | 4.1. DOCUMENT LIST                                | 14 |
|    | 4.2. REVIEW PROCESS                               | 14 |
| 5. | TASK 2: PREPARATION OF COSTS AND SCHEDULES        | 15 |
|    | 5.1. COST ESTIMATE ESCALATION TO YEAR-END 2022    | 15 |
|    | 5.2. PROJECT SCHEDULES ASSESSMENT                 | 15 |
| 6. | TASK 3: SCREENING AND RANKING OF PROSPECTS        | 19 |
|    | 6.1. PROJECT PORTFOLIO MANAGEMENT                 | 19 |
|    | 6.2. ASSESSMENT MODELS                            | 19 |
|    | 6.3. KEY RANKING CRITERIA                         | 22 |
|    | 6.4. SCREENING AND RANKING PROCESS                | 23 |
|    | 6.5. SCREENING AND RANKING BASIS                  | 23 |
|    | 6.6. SCREENING AND RANKING RESULTS SUMMARY        | 27 |
| 7. | TASK 4: OPTIMIZATION OPPORTUNITIES                | 29 |
|    | 7.1. PORTFOLIO MANAGEMENT                         | 29 |
|    | 7.2. GENERAL OPTIMIZATIONS                        | 30 |
|    | 7.3. SPECIFIC OPTIMIZATIONS                       | 30 |

|                      | EVALUATION OF ISLAND HYDROELECTRIC   | Revision |             |      |
|----------------------|--------------------------------------|----------|-------------|------|
|                      | GENERATION EXPANSION ALTERNATIVES    | Rev      | Date        | Page |
| <b>SNC · LAVALIN</b> | SLI Doc. No. 691499-0000-40ER-1-0001 | 01       | 21-OCT-2022 | 5    |
|                      |                                      |          |             |      |

| 8.  | TASK    | 5: GO-FORWARD PLAN                                   | 31 |
|-----|---------|--|----|
|     | 8.1. M  | ETHODOLOGY   | 31 |
|     | 8.2. G  | AP ANALYSIS RESULTS                                  | 31 |
|     | 8.3. W  | ORK REQUIRED TO COMPLETE FRONT-END PLANNING STAGES   | 31 |
| 9.  | CONC    | CLUSIONS   | 33 |
|     | 9.1. PF | ROSPECTS SUMMARY                                     | 33 |
|     | 9.2. SA | ANCTIONING CRITERIA                                  | 33 |
| 10. | RECO    | OMMENDATIONS   | 34 |
|     | 10.1.   | PROPOSED PROSPECT RANKING                            | 34 |
|     | 10.2.   | DECISION GATE PROCESS                                | 34 |
|     | 10.3.   | GATE 3 (PRE-SANCTION) COST ESTIMATING REQUIREMENTS   | 34 |
|     | 10.4.   | CONTRACTING STRATEGY BEST PRACTICE                   | 35 |
|     | 10.5.   | HEAVY CIVIL PROJECT EXECUTION STANDARD MODIFICATIONS | 35 |
|     | 10.6.   | ISLAND GENERATION POTENTIAL                          | 35 |
|     | 10.7.   | PORTFOLIO MANAGEMENT CONSIDERATIONS                  | 36 |
|     | 10.8.   | SANCTION PARAMETERS                                  | 36 |
|     | 10.9.   | RELIABILITY CONSIDERATIONS                           | 36 |
|     | 10.10.  | RISK CONSIDERATIONS                                  | 36 |

### APPENDICES

APPENDIX A DOCUMENT REVIEW APPENDIX B COST AND SCHEDULE CLASSIFICATIONS APPENDIX C PROSPECT OVERVIEWS, GAP ANALYSIS & RISKS APPENDIX D ENVIRONMENTAL APPROVALS AND PERMITTING

|               | EVALUATION OF ISLAND HYDROELECTRIC   | Revision |             |      |
|---------------|--------------------------------------|----------|-------------|------|
|               | GENERATION EXPANSION ALTERNATIVES    | Rev      | Date        | Page |
| SNC · LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01       | 21-OCT-2022 | 6    |

### 1. EXECUTIVE SUMMARY

As part of its System Planning strategy, Newfoundland and Labrador Hydro ("Hydro") continuously assesses the electrical generation capacity required to meet power demands. Currently, an increased interest in power demand requires Hydro to consider the potential of undeveloped generation prospects in its portfolio.

This Study, *Evaluation of Island Hydroelectric Generation Expansion Alternatives*, builds on 2018 work by Hydro by screening and ranking generation alternatives according to a pre-established set of criteria. The primary objective was to determine the gap in Project Planning maturity for a suite of prospects by comparing existing documentation against the requirements for completion of Front-End Execution Planning (FEEP). A secondary objective was identification of technical deficiencies and optimization opportunities through a review of existing documentation by the Engineering disciplines (e.g., Civil, Electrical, Mechanical, etc.).

A key assumption in this Study was that Project Planning, Screening and Ranking methods be consistent with industry practice for large capital projects (>\$50 million). Such industry practice includes the Decision Gate Process for large capital projects, the Association for Advancement of Cost Engineering (AACE) Recommended Practices, the Heavy Civil Project Execution Standard and other internal SNC-Lavalin ("SLI") experience and best practices. It was also assumed that the Study should be conducted in keeping with the recommendations of the Commission of Inquiry Respecting the Muskrat Falls Project Report (March 5, 2020).

After a data and documentation review, including the assessment of previous costs and schedules and escalation of costs to Year-end 2022, a workshop was held to Screen and Rank the six (6) generation alternatives in Hydro's current portfolio against criteria such as capacity, cost, environmental impacts, market conditions, and so on. A Gap Analysis was performed to identify the level of effort required to bring the project documentation to the industry standard for "Pre-Sanction (Gate 3)", which is the typical final project sanction gate for major capital projects. The results of the Gap Analysis were then used to prepare the Scope of Work required to complete Front-End Execution Planning (FEEP) deliverables for each prospect. Subject Matter Experts (SMEs) also provided optimization opportunities for each prospect, including technical optimizations opportunities to improve cost and schedule certainty.

The resulting ranking of Hydroelectric Generation Expansion Alternatives was recommended as follows.

- 1. Bay d'Espoir Hydro Generating Unit 8
- 4. Round Pond Hydroelectric Development
- 2. Addition of a Third Generating Unit Cat Arm
- 5. Portland Creek Hydroelectric Development
- 3. Island Pond Hydroelectric Development
- 6. Exploits River Hydroelectric Developments

It is also recommended that Hydro align the Heavy Civil Project Execution Standard used in this Study with its Decision Gate Process. Hydro should also ensure that recommended deliverables / activities in the Standard be addressed prior to the relevant Decision Gate. It is further recommended that Hydro review and adopt, in whole or modified accordingly for its business, a Contracting Strategy Best Practice.

Hydro should also align its cost estimating procedures and its expectations of contractor(s) estimates with the Association for Advancement of Cost Engineering (AACE) Best Practices. The level of detail and quality of cost estimate to meet Gate 3 (Pre-Sanction) industry requirements will require completion of 40% to 70% of Project Definition deliverables. It must be acknowledged that this front-end work will be an expense even if the P85 cost estimate (the minimum suggested by the Commission of Inquiry) prove to be uneconomic.

Among other recommendations, Hydro should also carefully consider its sanction parameters for its portfolio of projects. This should take into consideration the need for power / energy and the importance of project cost estimate accuracy. These considerations should be balanced against pre-investment expenditures and pre-sanction commitments for the purchase of long-lead items, compared to the potential "lost value" of power / energy should first power be delayed by minimizing pre-sanction expenditures.

|             | EVALUATION OF ISLAND HYDROELECTRIC   | Revision |             |      |
|-------------|--------------------------------------|----------|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev      | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01       | 21-OCT-2022 | 7    |

### 2. STUDY MANDATE

### 2.1. BACKGROUND

As part of its System Planning strategy, Newfoundland and Labrador Hydro ("Hydro") continuously assesses the electrical generation capacity required to meet power demands. Currently, an increased interest in power demand requires Hydro to consider the potential of undeveloped generation prospects in its portfolio. In 2018, Hydro compiled file information, cost and schedule estimates, and commissioned a Study to confirm that cost and schedule estimates for various generation alternatives were adequate for concept screening.

In its Professional Service Request of May 11, 2022, Hydro requested assistance with the screening and ranking of potential generation alternatives with the goal of recommending prospects for further study and evaluating the additional work required to complete Front-End Engineering Design (FEED)<sup>1</sup>.

### 2.2. STUDY OBJECTIVES

The primary objective of this Study is the recommendation of generation alternatives for further study by determining the gap in Project Planning maturity of the prospects by comparing existing documentation against the requirements for completion of Front-End Execution Planning (FEEP)<sup>1</sup>. A secondary objective is the identification of technical deficiencies and optimization opportunities through a review of existing documentation by the Engineering disciplines (e.g., Civil, Electrical, Mechanical, etc.).

### 2.3. HYDROELECTRIC GENERATION EXPANSION PROSPECTS

Six (6) generation expansion prospects provided by Hydro for this Study are summarized in **TABLE 2-1** in descending order of degree of completeness of the Front-End Execution Planning (FEEP) stage. (Note: Prospect 6 includes two (2) subprojects.) Also shown is the "approximate position" of each prospect in a typical Phase Gate project lifecycle process used by Hydro, which is discussed further in **SECTION 3.2**.

| NO. | PROSPECT NAME   | PHASE (approximate)   |
|-----|---|-----------------------|
| 1   | Bay d'Espoir Hydro Generating Unit 8  | Phase 3 (near Gate 3) |
| 2   | Addition of a Third Generating Unit Cat Arm   | Phase 1 / 2           |
| 3   | Island Pond Hydroelectric Development   | Phase 3               |
| 4   | Round Pond Hydroelectric Development  | Phase 1 / 2           |
| 5   | Portland Creek Hydroelectric Development  | Phase 2               |
| 6   | <ul><li>Exploits River Hydroelectric Developments</li><li>Red Indian Falls</li><li>Badger Chute</li></ul> | Phase 1               |

### TABLE 2-1 ISLAND HYDROELECTRIC GENERATION EXPANSION PROSPECTS

<sup>&</sup>lt;sup>1</sup> Front-End Engineering Design (FEED) is a major part of Front-End Execution Planning (FEEP), a larger Project Planning effort that is considered the industry standard for execution planning of large Heavy Civil and Earthworks developments.

|             | EVALUATION OF ISLAND HYDROELECTRIC<br>GENERATION EXPANSION ALTERNATIVES | Revision |             |      |
|-------------|---|----------|-------------|------|
| <b>•</b>    |   | Rev      | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001                                    | 01       | 21-OCT-2022 | 8    |

### 2.4. STUDY TASKS

The study was subdivided into five (5) main tasks, as follows.

#### TASK 1: Document Review

Review of documentation and data provided by Hydro for the prospects.

#### **TASK 2: Assessment of Costs and Schedules**

For each prospect, escalate the project cost to year-end (YE) 2022 and determine average project cost per installed megawatt (\$ / MW), overall project development timeline, and construction timeline.

#### **TASK 3: Screening and Ranking of Prospects**

Screen and rank prospects using an Assessment Model appropriate for the level of study.

#### **TASK 4: Identification of Optimization Opportunities**

Identify opportunities that could add value to each prospect through a review of documents and data by the engineering disciplines (Electrical, Civil, Mechanical, etc.), e.g., a quality improvement to extend life cycle, reduce maintenance costs, improve operability, etc.

#### **TASK 5: Development of a Go-Forward Plan**

Perform a Gap Analysis to identify differences between current "planning maturity" and the maturity required to meet industry standard. For this study, a Gap Analysis was performed to identify differences between the current state of Project Planning maturity against the desired state of Project Planning maturity required to meet industry standard.

Prepare scope of work required to complete Front-End Execution Planning (FEEP) deliverables for each prospect, plus a Level 3 (L3) schedule to complete that work (see below for Schedule Level definition).

### 2.5. STUDY TEAM

| Greg Snyder – Project Manager                     | Yasas Ponweera – SME Electrical  |
|---|----------------------------------|
| Brad Chaulk – Lead Project Execution Planner      | Martin Landry – SME Mechanical   |
| Kurt Kennedy – Project Execution Planner          | Alan Parker – SME Environmental  |
| Michel Tremblay – SME <sup>2</sup> Hydrotechnical | Karola Toth – Environmental Lead |

### 2.6. ACKNOWLEDGEMENTS

The Study Team would also like to acknowledge the contributions and support of the following members of Hydro's Project Team: Brian Sparkes (Project Manager), Marc Cullen, Forhad Ahmad, Stephen Parsons and Evan Broderick.

### 2.7. DEFINITIONS

*Annual Facility Usage* – Sometimes known as Capacity Factor, it is the ratio of actual electrical energy output over time against the theoretical maximum electrical energy output over the same time (typically annually).

<sup>&</sup>lt;sup>2</sup> SME = Subject Matter Expert

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
| <b>"</b>    | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 9    |

*Class (#) Cost Estimate* – A classification that describes the accuracy level of a cost estimate based on the degree of maturity of Project Definition Deliverables (see APPENDIX B).

**Decision Gate Process** – The division of the development of large capital projects into discrete Phases, separated by Decision Gates.

**Decision Gate** – A checkpoint where project status is formally reviewed by management and either (a) the project formally proceeds to the next Phase; (b) the project conditionally proceeds to the next Phase pending additional work or re-work; or (c) the project is suspended or cancelled.

DEP - Detailed Execution Planning.

*FEED* – Front-End Engineering Design

FEEP - Front-End Execution Planning.

Gap Analysis - Comparison of a "current state" against a "future state" or "desired state".

*Level (#) Schedule* – A classification that describes the level of detail shown in a particular schedule (see **APPENDIX B**).

*Management Contingency (Schedule)* – A time period added to an overall project development timeline to account for unforeseen or uncontrollable delays.

**Period of Analysis for Energy Study** – The years of hydrological data used for completion of energy study(ies) used to assess hydropower projects. Energy Studies using older data sets generally need to be updated with more recent data, perhaps also including climate change considerations.

**Project Definition** – Commonly referred to as Conceptual Design, it is when concepts evolve to a point that project facilities are identified, initial scope of work developed, project layouts / schematics prepared, and project output/value is conceptualized.

**Project Portfolio Management** – Aligning project execution with corporate strategy to maximize the value of an entire portfolio of opportunities, to balance the portfolio to ensure that risks are properly considered, and to ensure that short-term results do not become the focus

*Project Sanction* – When a project is formally given the go-ahead by management to move into the execution phase (typically making a committing to construction).

*SME* – Subject Matter Expert is an individual with specialized knowledge in a specific field, e.g., engineering, environmental science, finance, etc.

*Traffic Light Assessment Model* – A rating system that uses simple RED, YELLOW and GREEN codes for evaluating the performance of an input against a predefined standard or set of criteria.

|             | EVALUATION OF ISLAND HYDROELECTRIC<br>GENERATION EXPANSION ALTERNATIVES | Revision |             |      |
|-------------|---|----------|-------------|------|
| <b>7</b>    |   | Rev      | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001                                    | 01       | 21-OCT-2022 | 10   |

### 3. KEY ASSUMPTIONS

### 3.1. INDUSTRY PRACTICE

The Project Planning, Screening and Ranking methods used in this Study are consistent with industry practice for large capital projects (>\$50 million) and internal SNC-Lavalin ("SLI") experience and best practices. It was also assumed that the Study be conducted in keeping with the recommendations in the report of the Commission of Inquiry Respecting the Muskrat Falls Project (March 5, 2020).

### 3.2. OVERALL DECISION GATE PROCESS

A "Decision Gate" process has been used by Hydro and affiliated companies to divide the development of large capital projects into discrete Phases, separated by Decision Gates. A Decision Gate is a checkpoint where project status is formally reviewed by management and either (a) the project formally proceeds to the next Phase; (b) the project conditionally proceeds to the next Phase pending additional work or re-work; or (c) the project is suspended or cancelled.

The <u>Decision Gate Process</u> shown in the flowchart in **FIGURE 3.1** represents the overall project lifecycle for power generation projects. This process was recognized as "best in class"<sup>3</sup> by a third-party auditor. The approximate position in the lifecycle of each of the generation prospects in this study is also shown in the flowchart. "Gate 3" is commonly known as "Project Sanction", so the prospects are all currently "Pre-Sanction".



FIGURE 3.1 DECISION GATE PROCESS<sup>2</sup>

<sup>&</sup>lt;sup>3</sup> After <u>Grant Thornton LLP (July 16, 2018)</u>.

|                    | EVALUATION OF ISLAND HYDROELECTRIC<br>GENERATION EXPANSION ALTERNATIVES | Revision |             |      |
|--------------------|---|----------|-------------|------|
|                    |   | Rev      | Date        | Page |
| <b>SNC+LAVALIN</b> | SLI Doc. No. 691499-0000-40ER-1-0001                                    | 01       | 21-OCT-2022 | 11   |

### 3.3. HEAVY CIVIL PROJECT EXECUTION STANDARD

Power generation projects generally have a significant Heavy Civil and Earthworks component. Project Execution Planning for this component follows a standard "sub-process" specific to the Heavy Civil deliverables required for power projects. For this study, the <u>Heavy Civil Project Execution Standard</u> shown in **FIGURE 3.2** was adopted as the basis for comparison of the design maturity of each prospect. Substantial completion of the deliverables listed for Stages 1 and 2 of the Standard is usually a requirement to pass Gate 3.



### FIGURE 3.2 HEAVY CIVIL PROJECT EXECUTION STANDARD
|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 12   |

### **STAGE 1 – PROJECT DEFINITION**

The Project Definition stage, commonly referred to as Conceptual Design, is when concepts evolve to a point that project facilities are identified, initial scope of work developed, project layouts / schematics prepared, and project output/value is conceptualized. The key deliverable for Stage 1 is a Project Definition Statement that includes Project Definition and Scope, Conceptual Design, Timelines and Class 5 Cost Estimate<sup>4</sup>.

### STAGE 2 - FRONT-END EXECUTION PLANNING (FEEP)

The FEEP stage, commonly referred to as a *Feasibility Study*, is implemented when the Owner has decided to consider investment in a project. Depending on the Owner's risk profile (clearly stated by the Owner in a Project Charter), this stage can be undertaken as *Prefeasibility* and *Feasibility*. As a rule of thumb, undertaking this stage in two (2) separate steps usually results in approximately 30% additional planning cost.

Step 1 is Early Front-end Execution Planning, commonly referred to as *Pre-FEED*, and involves developing the project definition, undertaking minimum field investigation to quantify the earthworks components, preparation of preliminary designs, construction sequencing plan (the precursor to the full Path of Construction<sup>5</sup> developed in Stage 3 – DEP), Level 2 (L2) Schedule, and Class 4 Cost Estimate<sup>3</sup>.

Step 2 is the completion of the Front-end Execution Plan, commonly referred to as FEED, which involves undertaking a detailed field investigation sufficient to complete all engineering requirements, followed by front-end execution planning that yields a Contracting Strategy<sup>6</sup>, Level 3 (L3) Schedule and Class 3 Cost Estimate<sup>3</sup>.

### **STAGE 3 – DETAILED EXECUTION PLANNING (DEP)** For information only (not in scope of this Study)

Detailed Execution Planning (DEP), commonly referred to as Detailed Engineering, is where detailed engineering and execution planning are undertaken and procurement is implemented. Key deliverables include the Project Execution Plan (PEP), Engineering Work Packages (EWPs), Procurement Work Packages, Tender Documents, Evaluation/Award Recommendations, and Notices of Award.

### **STAGE 4 – EXECUTION**

### For information only (not in scope of this study)

The Execution stage, commonly referred to as *Construction*, is where various contracts are issued and construction of the project takes place in three (3) main steps.

- 1. Construction Readiness, i.e., the initial step where Owner and contractor project documentation is finalized, approved, and issued for construction (IFC).
- 2. Construction, i.e., implementation and execution of each contract package.
- 3. Close-out, i.e., issuing of the final completion certificate, final payment certificate, and contractual closeout of each contract package.

<sup>&</sup>lt;sup>4</sup> Cost estimate classifications are based on the Association for Advancement of Cost Engineering (AACE) <u>Recommended</u> <u>Practice (RP) 18-R-97</u>. Schedule classifications are based on <u>standard Primavera P6 practice</u>.

<sup>&</sup>lt;sup>5</sup> The *Path of Construction* is defined as the optimal sequencing of the building of a facility, developed by Construction, Engineering and Project Management Subject Matter Experts (SMEs), typically working backwards from the "end state".

<sup>&</sup>lt;sup>6</sup> A "Contracting Strategy" is the sum of three main components: Project Delivery Model, Compensation Model, and Sourcing Strategy. The individual components are not contracting strategies.

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 13   |

### 3.4. COST AND SCHEDULE ASSUMPTIONS

Cost estimate classifications adopted in this report (e.g., Class 5, Class 3) are based on the Association for Advancement of Cost Engineering (AACE) Recommended Practice (RP) 18-R-97. Additional details are presented in **APPENDIX B: COSTS AND SCHEDULES**.

Similarly, terms such as "Level 1 Schedule" or "L1" are used in this report to describe the schedule level of detail, as described in **APPENDIX B: COSTS AND SCHEDULES**. In general, Level 1 and Level 2 schedules are developed as part of conceptual studies for program management and financial decision-making purposes.

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 14   |

### 4. TASK 1 – DOCUMENT REVIEW

### 4.1. DOCUMENT LIST

The documents provided to the Study Team by Hydro are listed in **APPENDIX A**: **DOCUMENT REVIEW** (see excerpt shown in **TABLE 4-1**).

### 4.2. REVIEW PROCESS

All documents were initially reviewed and screened by the Study Team Project Manager and Lead Project Execution Planner. Only material relevant to their technical discipline was then provided to the Subject Matter Experts (SMEs) for their review and assessment.

|  |    | DOCUMENT TITLE   | DATE               | REV.   | AUTHOR(S)                     | DOCUMENT / PR   |
|--|----|--|--------------------|--|-------------------------------|-----------------|
| PROSPECT 1<br>BAY d'ESPOIR HYDRO GENERATING UNIT 8   | 1  | Proposed Bay d'Espoir Hydro Generating Unit 8<br>HYDRAULIC ANALYSIS OF THE CONVEYANCE SYSTEM                       | March 22, 2018     | 00   | SNC-Lavalin                   | 647756-0000-40E |
|  | 2  | Proposed Bay d'Espoir Hydro Generating Unit 8<br>CLASS 3 COST ESTIMATE AND PROJECT EXECUTION<br>SCHEDULE           | March 22, 2018     | 00   | SNC-Lavalin                   | 647756-0000-4   |
|  | 3  | Final Report for Hydrology and Feasibility Study for Potential<br>Bay d'Espoir Hydroelectric Generating Unit No. 8 | December 11, 2020  | 0  | Hatch                         | H363582-000     |
| PROSPECT 2   | 4  | CAT ARM DEVELOPMENT ADDITION OF UNIT # 3   | September 13, 1985 | -  | Shawmont                      | Report No. SMF  |
| ADDITION OF A THIRD GENERATING UNIT CAT ARM          | 5  | Addition of a Third Generating Unit, Cat Arm   | August 24, 2018    | -  | NL Hydro                      | -               |
|  | 6  | Cat Arm Unit #3 Cost Estimate (August 24 2018)   | August 24, 2018    | -  | Unspecified                   | -               |
| PROSPECT 3<br>ISLAND POND HYDRO ELECTRIC DEVELOPMENT | 7  | Island Pond Development Final Feasibility Study January 1988<br>Volume 1 – Report                                  | January 1988       | -  | Shawmont                      | Report No. SMR  |
|  | 8  | ISLAND POND / GRANITE CANAL<br>RE-OPTIMIZATION AND COST UPDATE STUDY   | January 14, 1997   | -  | AGRA Shawmont                 | SMR-05-96       |
|  | 9  | Studies for Island Pond Hydroelectric Project FINAL REPORT   | December 2006      | -  | SNC-Lavalin                   | Project No. 7.  |
|  | 10 | Portland Creek and Island Pond Hydroelectric Projects<br>Update Cost Estimates                                     | May 2012           | PA   | SNC-Lavalin                   | 501325-40ER-0   |
|  | 11 | Island Pond Hydroelectric Development  | August 29, 2018    | -  | NL Hydro                      | -               |
|  | 12 | Island Pond CADD Picture   | Unspecified        | -  | Unspecified                   | -               |
|  | 13 | Feasibility Study<br>Round Pond Development Summary Report   | February 1989      | -  | NL Hydro Engineering<br>Dept. |                 |
| PROSPECT 4<br>ROUND POND HYDRO ELECTRIC DEVELOPMENT  | 14 | Round Pond Hydroelectric Development – Update of the 1988<br>Cost Estimate (letter report)                         | May 7, 2012        | -  | Hatch                         | H341357-000     |
|  | 40 | Prot Estimate  |                    | -  | Unspecified                   |                 |
|  |    |  |                    | 100 million (100 m |                               |                 |

### TABLE 4-1 DOCUMENT LIST EXCERPT FROM APPENDIX A

|               | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|---------------|--------------------------------------|-----|-------------|------|
|               | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| 5NC · LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 15   |

### 5. TASK 2: PREPARATION OF COSTS AND SCHEDULES

The following cost and schedule metrics were developed or updated for each Island Hydroelectric Generation Expansion prospect.

- 1. Total cost of each prospect, escalated to year-end 2022 (YE-2022).
- 2. Average cost per megawatt (\$ / MW) of each prospect.
- 3. Overall Project Development Timeline for each prospect.
- 4. Construction Timeline for each prospect.

**TABLE 5-1** summarizes the key technical metrics for the prospects, including updated cost estimates and the resulting average cost per megawatt (\$ / MW) and other metrics. Cost estimates provided by Hydro from YE-2018 were escalated to YE-2022 as described below.

### 5.1. COST ESTIMATE ESCALATION TO YEAR-END 2022

In 2018, Hydro engaged a third-party consultant to conduct a cost and schedule estimate peer review to confirm if previous estimates for the generation alternatives were adequate for concept screening. As part of that peer review, cost estimates were escalated from the original date of the estimate to YE-2018. For this Study, the YE-2018 cost estimates were escalated to YE-2022 based on information from two (2) sources.

- 1. Statistics Canada Canadian Construction Price Index (CCPI) for the years 2019-21.
  - 2019: 2.2% 2020: 1.2% 2021: 11.4%
- 2. SLI Cost Estimating Department's inflation projection for 2022 for Newfoundland and Labrador. The projection was based on trends identified in construction works in which SLI is involved.
  - 2022: 15% (projection)

The net escalation to YE-2022 was, therefore, estimated at 132.5% of YE-2018 costs.

### 5.2. PROJECT SCHEDULES ASSESSMENT

Existing schedules for each prospect were assessed and adjustments made for Environmental Assessment timeline considerations and to reflect the requirements of the Heavy Civil Project Execution Standard for planning and executing a typical Heavy Civil project. Construction timelines were based on existing data and the Project Team's familiarity with the scope and type of work.

The adjusted schedules developed for each prospect, except for the Exploits River developments, are shown in **FIGURE 5.1** below.

As noted in **APPENDIX C – PROSPECT 6**, the level of planning and engineering required to support the Environmental Assessment Process for the Exploits River prospects will likely be very significant in terms of definition and scoping, but also very challenging in determining the cost and schedule implications. This is beyond the scope of the current study. As a result, the 1985 era schedules for Exploits River prospects were not included in FIGURE 5.1.

 
 SNC•LAVALIN
 EVALUATION OF ISLAND HYDROELECTRIC GENERATION EXPANSION ALTERNATIVES
 Revision

 SNC•LAVALIN
 SLI Doc. No. 691499-0000-40ER-1-0001
 01
 21-OCT-2022

Page 16

E 5-1 KEY METRICS SUMMARY FOR ISLAND HYDROELECTRIC GENERATION EXPANSION PROSPECTS.

| NO.          | PROSPECT NAME   | CAPACITY       | ТҮРЕ                         | NO.<br>OF<br>UNITS | UNIT<br>TYPE       | PERIOD OF<br>ANALYSIS FOR<br>ENERGY STUDY <sup>7</sup> | СО <b>S</b> Т<br>YE-2018       | COST<br>YE-2022                | M\$ / MW<br>YE-2022 | M\$ / GWh<br>YE-2022 | ANNUAL<br>FACILITY<br>USAGE <sup>8</sup> |
|--------------|---|----------------|------------------------------|--------------------|--------------------|--|--------------------------------|--------------------------------|---------------------|----------------------|--|
| <del>~</del> | BAY D'ESPOIR UNIT 8   | 150 MW         | Storage                      | ~                  | Francis            | Probably 1970-2019                                     | \$393,688,684                  | \$521,637,506                  | \$3.5               | \$23.1               | 1.7%                                     |
| 7            | CAT ARM ADDITION  | 68.2 MW        | Storage                      | +                  | Pelton             | Unspecified  | \$229,840,933                  | \$304,539,236                  | \$4.5               | \$12.2               | 4.2%                                     |
| с            | ISLAND POND   | 36 MW          | Storage                      | <b>-</b>           | Kaplan             | 1950-86  | \$405,200,154                  | \$536,890,204                  | \$14.9              | \$2.89               | 59.0%                                    |
| 4            | ROUND POND  | 18 MW          | Run-of-river                 | -                  | Bulb (Pit)         | 1950-86  | \$247,940,800                  | \$328,521,560                  | \$18.2              | \$2.36               | 88.2%                                    |
| Ð            | PORTLAND CREEK  | 23 MW          | Storage                      | 7                  | Pelton             | Probably 1984-2005                                     | \$261,813,751                  | \$346,903,220                  | \$15.1              | \$2.44               | 70.5%                                    |
| 9            | EXPLOITS RIVER <ul> <li>RED INDIAN FALLS</li> <li>BADGER CHUTE</li> </ul> | 42 MW<br>24 MW | Run-of-river<br>Run-of-river | 9 N                | Francis<br>Francis | Probably 1958-78<br>Probably 1958-78                   | \$392,632,346<br>\$248,637,520 | \$520,237,859<br>\$329.444.713 | \$12.4<br>\$13.7    | \$13.7<br>\$12.4     | 72.8%<br>73.2%                           |

<sup>7</sup> "Period of Analysis for Energy Study" refers to the years of hydrological data used for completion of the energy study(ies). Energy Studies using older data sets generally need to be updated with more recent data, perhaps also including climate change considerations. <sup>8</sup> "Annual Facility Usage" (sometimes also known as Capacity Factor) is the ratio of actual electrical energy output over a given period of time to the theoretical maximum electrical energy output over that same period (typically annually).

TABL



Page 17

|  | ID              | pansion - Project V2<br>Activity Name   | Original Duration Start | Finish     | Classic Schedule Layout Classic Schedule Layout VEAD 3 VEA | 04-061-22 20:41<br>DE VEADE VEADE 7 VEAD            |
|--|-----------------|---|-------------------------|------------|--|---|
|  | 2               | The second se |                         |            | 1 02 03 04 01 02 03 04 01 02 03 04 01 02 03 04 01 02 0   | 03 04 01 02 03 04 01 02 03 04 01 0                  |
|  | HydroV2 NL      | Hydro Generation Expansion - Project \  | 2722 01-Jan-23          | 14-Jun-30  |  |   |
| • 0.000         · 0.000 </td <td>HydroV2.1</td> <td>Bay d'Espoir</td> <td>2112 03-Sep-23</td> <td>14-Jun-29</td> <td></td> <td></td>   | HydroV2.1       | Bay d'Espoir  | 2112 03-Sep-23          | 14-Jun-29  |  |   |
| 0.000       Homenandian       000       Homenandian       Hom  | HydroV2.1.1     | Planning Timeline   | 832 03-Sep-23           | 12-Dec/25  |  |   |
|  | A1000           | Environmental Approval  | 365 03-Sep-23"          | 01-Sep-24  | EtwicoInteental Approval   |   |
| • 0.000         Example for the former fo                      | A1010           | Field Investigation Program including Analysis & Reports  | 90 03-Sep-23            | 01-Deo-23  | Field Investigation Brogram Inducting Analysis & Reports   |   |
| • AND         Control (Control Control Contro Control Contro Control Control Contro Control Control Control C          | A1020           | Complete Front-End Execution Planning Stage   | 182 03-Sep-23           | 02-Mar-24  | Complete Front-End Execution Planning Stage  |   |
| • No. Note: (Contract, Contract, Con                 | A1030           | Detailed Execution Planning Stage   | 650 03-Mar-24           | 12-Deo-25  | Detailed Execution   |   |
| 4         Control         Con  | HydroV2.1.2     | Execution (Construction) Timeline   | 1645 13-Deo/24          | 14-Jun-29  |  |   |
| Image: 100 bit | A1050           | Management Contingency  | 180 17-Deo-28           | 14-Jun-29  |  |   |
| 4.000         Checky Look Look         Council   | HydroV2.1       | 2.1 Turbine Generator   | 1465 13-Deo-24          | 16-Deo-28  |  |   |
| 0.000       undata teles       0000       00000       00000       00000         0.0000       0.0000       00000       00000       00000       00000       00000         0.0000       0.0000       00000       00000       00000       00000       00000       00000         0.0000       0.0000       0.0000       000000       00000       000000   | A1060           | T/G - Design & Model Test   | 365 13-Deo-24           | 12-Deo-25  |  |   |
| All         Inst in contract   | A1070           | Manufacture & Deliver   | 730 13-Deo-25           | 12-Deo-27  |  | Manufacture & Deliver                               |
| Ubbolic         Consider   | A1080           | Install & Commission  | 550 18-Jun-27           | 16-Deo-28  |  |   |
| Human Line  |                 |   |                         |            |  |   |
|  | HydroV2.2       | Cat Am  | 1695 01-Jan-23          | 22-Aug-27  |  |   |
| Immon 1         Immon 1 <t< td=""><td>HydroV2.2.1</td><td>Planning Timeline</td><td>725 01-Jan-23</td><td>26-Dec-24</td><td>Planing</td><td></td></t<>   | HydroV2.2.1     | Planning Timeline   | 725 01-Jan-23           | 26-Dec-24  | Planing  |   |
| 4100         Product Final Unidade         00 (Laboral Section 1)         00   | HydroV2.2       | 1.1 Project Definition Stage  | 240 01-Jan-23           | 28-Aug-23  | Project Definition Stage   |   |
| • 1100 <ul> <li>Undrata Field Interaction</li> <li>(2) Mayor</li> <li>(</li></ul>   | A1170           | Hydrotechnical Update   | 60 01-Jan-23            | 01-Mar-23  | Hydrotechnical Updrate   |   |
| ATIO         Device Strems /           | A1180           | Undertake Field Investigations  | 90 02-Mar-23            | 30-May-23  | Undertate Fleid Investigations   |   |
| <ul> <li>A 100</li> <li>Develop Finder</li> <li>A 100</li> <li>Develop Finder</li> <li>A 100</li> <li>Ferrer Finder</li> <li>A 100</li> <li>Ferrer Finder</li> <li>A 100</li> <li>Ferrer Finder</li> <li>A 100</li> <li>Entermental Manual Share</li> <li>A 100</li> <li>A 100</li></ul>   | A1190           | Review Scheme / Prefiminary Design / Schedule & Cost  | 80 31-May-23            | 28-Aug-23  | Réview Scheme / Preiminary Design/Schedule & Cost Estimate   |   |
| Altill         Automatical Decision         Automatical Decision <td>A1200</td> <td>Develop Environmental Momt Strateory</td> <td>45 n2 Mar 24</td> <td>15.Anc.22</td> <td></td> <td></td>  | A1200           | Develop Environmental Momt Strateory  | 45 n2 Mar 24            | 15.Anc.22  |  |   |
| <ul> <li>(1) (1) (1) (1) (1) (1) (1) (1) (1) (1)</li></ul>   | A1210           | Prenare Project Charter   | 90 18-Anr-23            | 14-hil-23  |  |   |
| • A123<br>• A123<br>• A123<br>• A124<br>• A1   | HudraM2 2       | 1.2 FrontEnd Evention Planning Stars  | 385 01-1ac-23           | 34.Dec.23  |  |   |
| <ul> <li>A120</li> <li>Underster Pril Chergen, WTO, Pain ef Cont., Coat (2)</li> <li>A120</li> <li>En Mandel Stepening</li> <li>En Mandel Stepening</li> <li>En Mandel Stepening</li> <li>A120</li> <li>En Mandel Stepening</li> <li>A120</li> <li>En Mandel Stepening</li> <li>A120</li> <li>In Mandel Stepening</li> <li>En Mandel Stepening</li> <li>En Mandel Stepening</li> <li>En Mandel Stepening</li> <li>A120</li> <li>In Mandel Resonance and Faming Stepening</li> <li>A120</li> <li>In Mandel Resonance and Faming Stepening</li> <li>In Mandel Resonance and Faming Stepening</li> <li>A120</li> <li>In Mandel Resonance and Faming Stepening</li> <li>In Mandel Resonance and Faming Stepening</li> <li>A120</li> <li>In Mandel Resonance and Faming Stepening</li> <li>In Mandel Resonance and Resonance and Resonance and Resonand Resonance</li></ul>   | = A1220         | Environmental Approval Process  | 365 01-Jan-23           | 31-Deo23   |  |   |
| Interlor         Control Francis Radio         200 </td <td>A1230</td> <td>Undertake Prel. Design, MTOs, Path of Const., Cost / St</td> <td>120 29-Aug-23</td> <td>26-Dec-23</td> <td>Undertake-Prel. Design, MTds, Path pr.Consti, Cost / Edhedule, PEP</td> <td></td>  | A1230           | Undertake Prel. Design, MTOs, Path of Const., Cost / St   | 120 29-Aug-23           | 26-Dec-23  | Undertake-Prel. Design, MTds, Path pr.Consti, Cost / Edhedule, PEP   |   |
| A 1300         Exercise Transie         Biolization France         Biolization France <td>HydroV2.2</td> <td>1.3 Detailed Execution Planning Stage</td> <td>365 27-Deo-23</td> <td>25-Deo-24</td> <td>Detailed Execution Planning Stage Execution</td> <td></td>  | HydroV2.2       | 1.3 Detailed Execution Planning Stage   | 365 27-Deo-23           | 25-Deo-24  | Detailed Execution Planning Stage Execution  |   |
| <ul></ul>  | A1240           | Execution Planning & Detailed Engineering   | 185 27-Dec-23           | 28-Jun-24  | Plaming & Detaited Engineering   |   |
| Hotory 2.5         Execution (Construction)         100         Scung27         Execution (Construction)         Feloritie (Constr   | A1650           | Bid / Evaluate / Award Recommendation   | 180 29-Jun-24           | 25-Deo-24  | Bid // Evaluate // Avard Recommendation  |   |
| A1200         TG Mundtatura. Deleney Instaltion & Commissioning         100         23-Jun-24         3-Aph/27         2-Aug/27         3-Aug/27         3   | HydroV2.23      | Execution (Construction) Timeline   | 1150 29-Jun-24          | 22-Aug-27  |  | Expedition (Construction) Timeline T/G Manufacture. |
| ■ A1200       Management Contigency       120       24-kpc/21       22-kpc/21       22-kpc/21<   | A1250           | T/G Manufacture, Delivery, Installation & Commissioning   | 1030 29-Jun-24          | 24-Apr-27  |  | Very, Installation & Commissioning                  |
| HydroV2.3     Sland Pond     2180     Ordans3     18-Dec38     10-cold       I MydroV2.3     Faming Tineline     1100     01-dans3     00-dans3     10-dans3       I MydroV2.3     Faming Tineline     1100     01-dans3     00-dans3     10-dans3       I MydroV2.3     Faming Tineline     1100     01-dans3     00-dans3     00-dans3       I MydroV2.3     Faming Tineline     1100     01-dans3     01-dans3     01-dans3       I MydroV2.3     Faming Tineline     1100     01-dans3     01-dans3     01-dans3       I Marcan     100     01-dans3     01-dans3     01-dans3     01-dans3       I Marcan     200     10-dans3     01-dans3     01-dans3     01-dans3       I Marcan     200     10-dans3     01-dans3     01-dans3     01-dans3       I Marcan     200     10-dans4     200     10-dans4     200       I Marcan     200     10-dans3     10-dans4     200     10-dans4       I Marcan     200     10-dans3     10-dans4     200     10-dans4       I Marcan     200     10-dans3     10-dans4     200     10-dans4       I Marcan     200     10-dans3     10-dans4     20-dans4     10-dans4       I Marcan<  | A1260           | Management Contingency  | 120 25-Apr-27           | 22-Aug-27  |  | Management Contrigency                              |
| <ul> <li>Mydrol/2.3.1 Fluring Timeline             </li> <li>Hydrol/2.3.1 Fluring Stage Update             </li> <li>Hydrol/2.3.1.1 Floring Stage Update             </li> <li>Hydrol/2.3.1.1 Floring Hydrol             </li> <li>Hydrol/2.3.1.1 Elevinininininini 4 Signa</li></ul>  | HvdroV2.3       | sland Pond  | 2180 01-Jan-23          | 19-Deo-28  |  |   |
| <ul> <li>Marcos St. 1 Frankung Stepe Update         </li> <li>             A1200             Environmental Approval Process         </li> <li>             A1200             Environmental Approval Process         </li> <li>             A1200             Environmental Approval Process         </li> <li>             A1300             Hydrox St. 1 Frankung Stepe Update         </li> <li>             A1300             Hydrox St. 3         </li> <li>             A1300             Hydrox A11         </li> <li>             A1300             Hydrox Process         </li> <li>             A1300             Hydrox Process         </li> </ul> <li>             A1300             Hydrox Process         <ul>             A1300             Hydrox Process             A1300             Hydrox Process         </ul></li> Hydrox Process <li>             A1300             Hydrox Process         <ul>             A1300             Hydrox Process         </ul></li> Hydrox Process <li>             A1300             Hydrox Process         <ul>             A130             Hydrox Process         </ul></li> Hydrox Process <li>             A1300             Hydrox Process         <ul>             A130             Hydrox Process         </ul></li> Hydrox Process              Hydrox Process <li>             Hydrox Process         <ul>             Hydrox Process         </ul></li> Hydrox Process              Hydrox Process <li>             Hydrox Process         <ul>             Life Hydrox Process         </ul></li> Hydrox Process              Hydrox Process <li>             Hydrox Process         <ul>             Life Hydrox Process             Hydrox Process             Hydrox Proces</ul></li>  | - Holovia       | Distantion Transferen   | tinn nt-lan-23          | 04. Ion.28 |  |   |
| • A1200 <ul> <li>• A1200             </li> <li>• A1200             </li></ul>  |                 | rianning linteinte  |                         | M ha 26    |  |   |
| <ul> <li>A1200</li> <li>Hydrotechnical Update</li> <li>A1320</li> <li>Update Pet Designs / MTOs / Schedule / Cost Estimate</li> <li>A1330</li> <li>Prepare Vendor Packages for Long-Lead Items</li> <li>A1300</li> <li>Betwork A11 Faid Work</li> <li>A1300</li> <li>Geotechnical Update</li> <li>A1300</li> <li>Geotechnical Update</li> <li>A1300</li> <li>Geotechnical Valor</li> <li>A1200</li> <li>HydroV.2.3.1 1 Faid Work</li> <li>HydroV.2.3.2 Execution Planning &amp; Detailed Exploreering</li> <li>A1000 10.01.01.01.01.01.05/Stape</li> <li>HydroV.2.3.2 Execution (Construction) Timeline</li> <li>MotoV.2.3.2 Execution (Construction) Timeline</li> <li>MotoV.2.3.2 Execution (Construction) Timeline</li> </ul> <ul> <li>Adual Level of Effort</li> <li>Peter Park Park Park Park Park Park Park Par</li></ul>  | A1270           | Environmental Approval Process  | 1100 01-Jan-23          | 04-Jan-26  | Environment Production Production  |   |
| <ul> <li>A1300</li> <li>Update Prel. Designs / MTOs / Schedule / Cost Estimate</li> <li>200</li> <li>FAgera Vendor Fackages for Long-Lead flems</li> <li>A1300</li> <li>Prepare Vendor Fackages for Long-Lead flems</li> <li>A1300</li> <li>Geotechnical / Doo / Environmental - Summer</li> <li>A1300</li> <li>Geotechnical / Doo / Environmental - Summer</li> <li>A1300</li> <li>Geotechnical / Doo / Environmental - Summer</li> <li>A1000</li> <li>Bist / Evelopible / Evelopi</li></ul>  | A1280           | Hvdrotechnical Update   | 60 01-Jan-23            | 01-Mar-23  | D Hudiosethnical Ubidate   |   |
| <ul> <li>A1330</li> <li>Prepare Vendor Pakages for Long-Lead Items</li> <li>A5</li> <li>17 Aug-23</li> <li>30.5ep.23</li> <li>11.5ep.23</li> <li>11.5ep.24</li> <li>11.5ep.23</li> <li>11.5ep.24</li> <li>11.5ep.24</li></ul>  | A1320           | Update Prel. Designs / MTOs / Schedule / Cost Estimate  | 200 15-Mar-23           | 30-Sep-23  | Ubdate Prel. [Designs/ MTOs / Schedule/ Cost Estimate  |   |
| Image: Hydrol/2.3.1.1. Field Work       211       13-Feb-23       11.5ep-23       <  | A1330           | Prepare Vendor Packages for Long-Lead Items   | 45 17-Aug-23            | 30-Sep-23  |  |   |
| <ul> <li>A1290 Island Pond Channel Bathymetry - Winter             </li> <li>A1200 Island Pond Channel Bathymetry - Winter             </li> <li>A1300 Geotechnical / Dop / Environmental - Summer             </li> <li>A1300 Geotechnical / Dop / Environmental - Summer             </li> <li>A1300 Geotechnical / Dop / Environmental - Summer             </li> <li>A1310 Execution Planning Stage             </li> <li>A1310 Execution Planning &amp; Detailed Execution Planning Stage             </li> <li>A1310 Execution Planning &amp; Detailed Execution Planning Stage             </li> <li>A1310 Execution Planning &amp; Detailed Execution Planning &amp; Detailed Execution Planning Stage             </li> <li>A1310 Execution Planning &amp; Detailed Engineering             </li> <li>A1310 Execution Flanning &amp; Detailed Engineering             </li> <li>A1310 Execution Flanning &amp; Detailed Engineering             </li> <li>A1310 Execution (Construction) Timeline             </li> <li>AndroX232 Execution (Construction) Timeline             </li> <li>AndroX332 Execution (Construction) Timeline             </li> <li>AndroX = Anaud Recommendation             </li> <li>Anaud Recommendation             </li> <li>Anaud Recommendation             </li> <li>Anaud Recommendatin             </li>             &lt;</ul>   | HydroV          | 2.3.1.1.1 Field Work  | 211 13Feb-23            | 11-Sep-23  | Field Work   |   |
| Image: State of Effection Planning Stage       120       15 May-23*       11-Sep-23       15-May-23*       11-Sep-23       11-Sep-13*       11   | 🚍 A126          | 0 Island Pond Channel Bathymetry - Winter   | 30 13.Feb-23"           | 14-Mar-23  | 🗎 island Poind Ghannel Bathymetry-Winter   |   |
| HydroV2.3.1.2 Detailed Execution Planning Stage       430       01.04-23       03.Deo24       140 ming Stage   | A130            | 0 Geotechnical / Topo / Environmental - Summer  | 120 15-May-23"          | 11-Sep-23  | Gebtechnical / Topo / Environmental -Summer  |   |
| ■ A1310       Execution Planning & Detailed Engineering       250       01-0ct-23       06-un-24       Image: Streight Planning & Detailed Engineering       Image: Streight Planning & Detailed Engineering         ■ A1800       Bid / Evaluate / Award Recommendation       180       07-un-24       03-0eo24       Image: Streight Planning & Detailed Engineering       Image: Streight Planning   | HydroV2.3       | 1.2 Detailed Execution Planning Stage   | 430 01-Oct-23           | 03-Deo-24  | Detailed Execution Planning/Stage  |   |
| ■ A1860 Bid / Evaluate / Award Recommendation       180 07-Jun-24 03-Dec24   | A1310           | Execution Planning & Detailed Engineering   | 250 01-Oct-23           | 06-Jun-24  | Execution Planning & Detailed  |   |
| Actual Level of Effort Remaining Work + Miestone Remaining Work + Miestone Page 1 of 2 TASK filter. All Activities   | A1660           | Bid / Evaluate / Award Recommendation   | 180 07-Jun-24           | 03-Deo-24  | Bid / Evaluate / Award Recommendation  |   |
| Actual Level of Effort Remaining Work + Miestone Page 1 of 2 TASK filter: All Activities   | HydroV2.3.2     | Execution (Construction) Timeline   | 1080 05-Jan-26          | 19-Deo-28  |  |   |
|  | Actual Level of | Effort Remaining Work   | ectone                  |            | Deve 4 of 9<br>TACV filter All Anti-Alie   |   |
| Advint Made Campanian Made Camman  | Actual Work     | CIION Critical Demaining Work Control Control   | estone                  |            | Page 1 of 2  | 🕲 Arada Domorațio                                   |

FIGURE 5.1 ISLAND HYDROELECTRIC GENERATION EXPANSION ALTERNATIVES PROJECT SCHEDULES SUMMARY (page 1 of 2)

### PUB-NLH-288, Attachment 4 **Reliability and Resource Adequacy Study Review** Page 17 of 158

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |
|-------------|--------------------------------------|-----|-------------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        |
| SNC+LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 |

Page <del>0</del>

| A1400     Execution Stage       A1410     Execution Stage       A1410     Management Contriger       HydroV2.4.1     Panning Timeline       HydroV2.4.1     Project Definition St       HydroV2.4.1     Project Definition St       A1350     Hydroval       A1350     Hydrotechnical Update       A1370     Planning & Execution of       A1370     Planning & Execution of       A1370     Prepare Project Charter       A1300     Prepare Project Charter       HydroV2.4.1.2     Front End Execution       A1420     Freque Project Charter       HydroV2.4.2     Execution Plannin       A1430     Execution Plannin       A1430     Bid / Evaluate / Award F       HydroV2.4.2     Execution Riannin   | ency<br>Lage<br>al Phocess<br>al Phocess<br>for a Field Phogram<br>and update Cost & Schedule<br>fing Class 5 Cost and Schedule<br>and update Cost & Schedule<br>fing Stage<br>ing Stage<br>ing Stage<br>Planning Stage<br>Detailed Engineering<br>Recommendation<br>for 1 inneline<br>for 1 inneline<br>for 1 inneline<br>for 1 inneline<br>for 1 inneline  | 800         65-Jan-26         22-Jun-28           180         23-Jun-28         19-Deo-21           180         23-Jun-28         19-Deo-21           2210         01-Jan-23         18-Jan-26           1100         01-Jan-23         04-Jan-23           1100         01-Jan-23         04-Jan-26           1100         01-Jan-23         04-Jan-23           120         01-Jan-23         28-Jun-23           130         20-Jun-23         27-Sep-23           130         29-Jun-23         28-Jun-23           200         28-Sep-23         28-Jun-23           201         28-Sep-23         14-Apr-24           202         28-Sep-23         14-Apr-24           210         21-Deo-24         18-Jun-21           2136         05-Apr-255         18-Jun-21           2136         05-Apr-255         18-Jun-21           2136         05-Apr-255         18-Jun-21           210         05-Apr-255 <th>01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       03       03       04       01       03       03       04       01       03       03       04       01       03       03       04       01       03       03       04       01       03       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       03       03       03       03       03       03       <td< th=""></td<></th> | 01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       02       03       04       01       03       03       04       01       03       03       04       01       03       03       04       01       03       03       04       01       03       03       04       01       03       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       04       01       03       03       03       03       03       03       03 <td< th=""></td<>  |
|--|--|---|--|
| <ul> <li>A1400 Execution Stage</li> <li>A1410 Management Contriger</li> <li>HydroV2.4 Round Pond</li> <li>HydroV2.4.1 Project Definition Stage</li> <li>A1340 Environmental Approval</li> <li>A1350 Hydrotechnical Update</li> <li>A1350 Apdrotechnical Update</li> <li>A1300 Review Scheme a</li> <li>A1300 Prepare Project Charter</li> <li>A1300 Optimize the Scheme a</li> <li>A1300 Prepare Project Charter</li> <li>A1300 Prepare Project Charter</li> <li>A1420 Front End Execution 6</li> <li>A1420 Free Execution Flanning &amp; I</li> <li>A1430 Bid / Evaluate / Award F</li> <li>A1470 V2.4.2 Execution (Constructs</li> </ul>   | Lige<br>Lage<br>al Process<br>al Process<br>and process<br>and update Cost & Schedule<br>and update Cost & Schedule<br>francing Stage<br>Detailed Engineering<br>Recommendation<br>for Timeline<br>for Timeline<br>for Stage   | 900         05-Jan-26         22-Jun-28           180         23-Jun-28         19-Deo21           2210         01-Jan-23         18-Jan-26           1100         01-Jan-23         04-Jan-23           120         01-Jan-23         28-Jun-23           20         01-Jan-23         28-Jun-23           20         01-Jan-23         28-Jun-23           210         01-Jan-23         28-Jun-23           210         01-Jan-23         28-Jun-23           210         28-Sep-23         14-Ap-24           210         28-Sep-23         14-Ap-24           210         16-Jan-25         18-Jan-25           210         18-Jan-26         18-Jan-26           1305         05-Apr-25         18-Jan-27           1306         05-Apr-25         18-Jan-26           1305         05-Apr-26   | E Production de la contraction   |
| A 1410 Management Contriger<br>HydroV2.41 Planning Timeline<br>HydroV2.4.1 Planning Timeline<br>A 1340 Environmental Approval<br>A 1350 Hydrotechnical Update<br>A 1350 Planning & Execution of<br>A 1370 Planning & Execution of<br>A 1380 Optimize the Scheme a<br>A 1380 Optimize the Scheme a<br>A 1300 Prepare Project Charter<br>HydroV2.4.1.3 Detailed Execution<br>A 1430 Execution Planning & I<br>A 1430 Execution Planning & I<br>A 1430 Execution Flanding & I<br>A 1430 Execution Planning & I<br>A 1430 Execution Flanding & I<br>A 1430 Execution Flanding & I  | ency<br>Lage<br>al Process<br>al Process<br>fing Class 5 Cost and Schedule<br>of a Field Program<br>and update Cost & Schedule<br>and update Cost & Schedule<br>rand FEEP Scope of Work<br>rand FEEP Scope of Work<br>and Planning Stage<br>ing Stage<br>Detailed Engineering<br>Recommendation<br>for 1 Timeline<br>for 1 Timeline<br>for 1 Timeline  | 180         23-Jun-28         18-Deo/2           2210         01-Jan-23         18-Jan-26           2210         01-Jan-23         04-Jan-26           1100         01-Jan-23         28-Jun-26           20         01-Jan-23         28-Jun-26           20         01-Jan-23         28-Jun-26           30         01-Jun-23         28-Jun-23           30         01-Jun-23         28-Jun-23           30         30-Jun-23         28-Jun-23           30         30-Jun-23         28-Jun-23           200         28-Sep-23         14-Ap-24           210         28-Sep-23         14-Ap-24           210         28-Sep-23         14-Ap-24           210         28-Sep-23         14-Ap-24           210         28-Sep-23         18-Jun-26           13086         06-Apr-24         18-Jun-26           1308         06-Apr-26         18-Jun-26           1308         06-Apr-26         1   | Environde la service de la ser   |
| HydroV2.4.     Round Pond       HydroV2.4.1     Planning Timeline       HydroV2.4.1     Planning Timeline       A 1340     Ervironmental Approval       A 1350     Hydrotechnical Update       A 1370     Planning & Execution of       A 1380     Optimize the Scheme a       A 1390     Prepare Project Charter       A 1300     Prepare Project Charter       A 1300     Prepare Project Charter       A 1420     Front End Execution       A 1420     Frequention faunning & I       A 1430     Execution Planning & I       A 1430     Execution Planning & I       A 1430     Execution Faunning & I  | Lage<br>Lage<br>al Process<br>of a Field Program<br>and update Cost and Schedule<br>of a Field Program<br>and update Cost & Schedule<br>and update Cost & Schedule<br>ing Stage<br>ing Stage<br>Planning Stage<br>Detailed Engineering<br>Recommendation<br>Planning Stage<br>Detailed Engineering<br>Recommendation<br>ion) Timeline<br>ion) Timeline<br>mental Construction  | 2210 01-Jan-23 18-Jan-26<br>1100 01-Jan-23 04-Jan-26<br>1100 01-Jan-23 04-Jan-26<br>0 01-Jan-23 04-Jan-26<br>0 01-Jan-23 21-Mar-22<br>20 01-May-23 28-Aug-2<br>3 00-Jun-23 20-Jun-23<br>20-Jun-23 20-Jun-23<br>20-Jun-23 14-Apr-24<br>20 02-8-Sep-23 14-Apr-24<br>20 02-8-Sep-23 14-Apr-24<br>250 15-Apr-24 18-Jun-23<br>180 02-10-co-24 18-Jun-23<br>180 02-10-co-24 18-Jun-23<br>180 02-10-co-24 18-Jun-23<br>1205 05-Apr-25 18-Jun-23<br>180 01-Jun-25 08-Feb-2<br>180 19-Jun-25 08-Feb-2<br>180 19-Jun-25 08-Feb-2  | Plaaning Tree from the free from the from the free from the free from the from the free from the free from the free from the from the free from the free from the from the free from the   |
| HydroV2.4.1       Planning Timeline         HydroV2.4.1       Project Definition state         A1340       Environmental Approval         A1350       Hydrobechnical Update         A1350       Hydrobechnical Update         A1370       Planning & Execution of         A1370       Planning & Execution of         A1300       Prepare Project Charter         A1300       Prepare Project Charter         A1300       Prepare Project Charter         A1420       FrontEnd Execution         A1420       FEEP Execution Planning & I         A1430       Execution Planning & I         A1430       Execution Planning & I         A1430       Execution Planning & I  | tage<br>tage<br>al Process<br>and update Cost and Schedule<br>of a Field Program<br>and update Cost & Schedule<br>and update Cost & Schedule<br>and update Cost & Schedule<br>and update Cost & Schedule<br>faming Stage<br>Planning Stage<br>Detailed Engineering<br>Planning Stage<br>Detailed Engineering<br>Recommendation<br>ion) Timeline<br>ion) Timeline<br>matuction<br>mental Construction   | 1100         01-Jan-28         04-Jan-26           1100         01-Jan-23         04-Jan-26           1100         01-Jan-23         04-Jan-26           1100         01-Jan-23         04-Jan-26           80         01-Jan-23         04-Jan-26           80         01-Jan-23         31-Marc23           80         01-Jan-23         28-Aug-23           80         01-Jan-23         27-Sep-23           80         28-Gun-23         14-Apr-24           80         28-Gun-23         14-Apr-24           810         28-Gun-25         18-Jan-23           810         18-Jan-25         18-Jan-26           810         19-Jun-26         08-Feb-23           810         19-Jun-26         08-Feb-23           810         19-Jun-26         08-Feb-23           810         19-Jun-26         08-Feb-23           810         19-Jun-26         08-Feb-2   | Planning Interine<br>Planning Inte |
| HydroVZ.4.1.1. Project Definition State         A1340       Environmental Approval         A1350       Hydrotechnical Update         A1350       Review Scheme, includi         A1350       Planning & Execution of         A1300       Planning & Execution of         A1300       Optimize the Scheme at         A1300       Prepare Project Charter         A1300       Prepare Project Charter         A1300       Prepare Project Charter         A1420       FEEP Execution for anning & 1         A1420       FEEP Execution for anning & 1         A1430       Execution Planning & 1         A1430       Execution Flanning & 1         A1470       Execution Flanning & 1  | Lage<br>al Process<br>fing Class 5 Cost and Schedule<br>of a Field Program<br>and update Cost & Schedule<br>and refer Scope of Work<br>and FEEF Scope of Work<br>and | 1100         01-Jan-23         04-Jan-26           1100         01-Jan-23         04-Jan-26           90         01-Jan-23         04-Jan-26           90         01-Jan-23         31-Mar-27           90         01-Jan-23         31-Mar-27           90         01-Jan-23         28-Jun-23           100         01-May-23         28-Aug-23           100         01-May-23         28-Aug-23           101         01-May-23         28-Aug-23           102         01-May-23         28-Aug-23           103         30-Jun-23         28-Aug-23           200         28-Sep-23         14-Apr-24           201         28-Sep-23         14-Apr-24           450         15-Apr-24         18-Jun-22           1386         05-Apr-25         18-Jun-26           1386         05-Apr-26         20-De-05           1386         05-Apr-26         21-Jun-26           1386         05-Apr-26         32-Jul-28           1386         05-Apr-26         32-Jul-28           050         16-Jun-26         06-Feb-2           080         19-Jun-26         06-Feb-2           180         23-Jul-28         1   | Properts Definition Stage  |
| <ul> <li>A1340 Environmental Approval</li> <li>A1350 Hydrotechnical Update</li> <li>A1360 Review Scheme, includie</li> <li>A1370 Planning &amp; Execution of</li> <li>A1370 Optimize the Scheme at</li> <li>A1380 Optimize the Scheme at</li> <li>A1300 Prepare Project Charter</li> <li>A1420 FEEP Execution Flanning &amp;</li> <li>A1430 Execution Planning &amp;</li> <li>A1430 Bid / Evaluate / Award F</li> <li>A1470 Bid / Evaluate / Award F</li> </ul>  | al Process<br>fing Class 5 Cost and Schedule<br>of a Field Program<br>and update Cost & Schedule<br>and update Cost & Schedule<br>and FEEP Scope of Work<br>r and FEEP Scope of Work<br>and FEEP Scope of Work<br>of Planning Stage<br>ing Stage<br>Detailed Engineering<br>Planning Stage<br>Detailed Engineering<br>Recommendation<br>ion) Timeline<br>instruction<br>mental Construction  | 1100         01-Jan-23         04-Jan-26           90         01-Jan-23         31-Mar-27           90         01-Jan-23         31-Mar-27           90         01-Jan-23         26-Jun-23           90         01-May-23         28-Aug-23           90         01-May-23         27-Sep-23           90         26-Mug-23         27-Sep-23           90         28-Sep-23         14-Apr-24           200         28-Sep-23         14-Apr-24           450         15-Apr-24         18-Jun-23           210         15-Apr-24         18-Jun-23           210         15-Apr-24         18-Jun-23           1385         05-Apr-26         18-Jun-23           1385         05-Apr-26         18-Jun-23           1385         05-Apr-26         18-Jun-23           1205         05-Apr-26         20-Deco-24           1386         05-Apr-26         18-Jun-23           050         19-Jun-25         06-Apr-26           060         19-Jun-26         06-Apr-26           180         23-Jul-28         18-Jan-2           180         23-Jul-28         18-Jan-2           180         19-Jun-26         06-   | Envirgence in the second secon   |
| <ul> <li>A1350 Hydrotechnical Update</li> <li>A1360 Review Scheme, includi</li> <li>A1370 Planning &amp; Execution of</li> <li>A1370 Optimize the Scheme at</li> <li>A1380 Optimize the Scheme at</li> <li>A1380 Prepare Project Charter</li> <li>A1420 Prepare Project Charter</li> <li>A1420 FEEP Execution Planning &amp; 1</li> <li>A1430 Execution Planning &amp; 1</li> <li>A1670 Bid / Evaluate / Award F</li> <li>HydroV2.4.2 Execution (Constructs</li> </ul>   | a fing Class 5 Cost and Schedule fing Class 5 Cost and Schedule and update Cost & Schedule and refer Scope of Work for and FEEF Scope of Work for Planning Stage ing Stage for Stage Detailed Engineering Recommendation for Nimeline for her and Construction mental Construction mental Construction for Nimeline for Nimel   | 90         01-Jan-23         31-Mar-23           90         01-Apr-23         29-Jun-23           120         01-May-23         28-Aug-23           30         20-Jun-23         27-Sep-23           30         29-Jun-23         28-Jur-23           30         29-Jun-23         28-Jur-23           200         28-Sep-23         14-Apr-24           450         15-Apr-24         18-Jun-23           450         15-Apr-24         18-Jun-23           1385         06-Apr-25         18-Jun-23           1205         06-Apr-25         18-Jun-23           1206         06-Apr-25         32-Jul-28           050         19-Jun-25         08-Feb-2           080         19-Jun-25         08-Feb-2           180         23-Jul-28         18-Jan-2           180         23-Jul-28         18-Jan-2   | Prepare       Prepare       Prepare  |
| <ul> <li>A1360 Review Scheme, including a Scheme and a A1370 Planning &amp; Execution of a A1380 Optimize the Scheme are a A1380 Prepare Project Charter in A1380 Prepare Project Charter in A1420 Prepare Project Charter in A1420 FEEP Execution Planning &amp; A1430 Exec</li></ul> | ding Class 5 Cost and Schedule of a Field Program and update Cost & Schedule and update Cost & Schedule and FEEP Scope of Work and Planning Stage ing Stage Planning Stage Detailed Engineering Recommendation for Nimeline ing Stage metal Construction mental Construction mental Construction metal Construction metal Construction   | 90         01.4pr.23         29.4mr.23           120         01.4my.23         28.4mg.23           30         29.4mg.23         27.5ep.2           30         29.4mg.23         27.5ep.2           30         30.4mr.23         28.4mg.23           200         28.5ep.23         14.4mr.23           200         28.5ep.23         14.4mr.23           200         28.5ep.23         14.4mr.23           201         15.4mr.24         18.4mr.23           202         15.4mr.24         20.0be.2           210         15.4mr.24         20.0be.2           210         15.4mr.24         18.4mr.23           210         15.4mr.24         18.4mr.23           210         15.4mr.25         18.4mr.23           21385         05.4mr.25         18.4mr.23           1386         05.4mr.26         18.4mr.23           1205         05.4mr.25         23.2mr.23           050         19.4mr.26         05.4mr.26           130         19.4mr.26         06.4mr.26           130         19.4mr.26         06.4mr.26           130         19.4mr.26         06.4mr.26           130         19.4mr.26         06.4m   | The providence in the second development of  |
| <ul> <li>A1370 Planning &amp; Execution of<br/>A1380 Optimize the Scheme at<br/>A1390 Prepare Project Charter<br/>A1420 FEEP Execution Plannin<br/>A1420 FEEP Execution Planning &amp; 1<br/>A1430 Execution Planning &amp; 1<br/>A1430 Execution Planning &amp; 1<br/>A1470 Bid / Evaluate / Award F<br/>HydroV2.4.2 Execution (Constructs)</li> </ul>  | of a Field Program<br>and update Cost & Schedule<br>r and FEEP Scope of Work<br>r and FEEP Scope of Work<br>ing Stage<br>ing Stage<br>Planning Stage<br>Detailed Engineering<br>Recommendation<br>ion Trimeline<br>ion Trimeline<br>ion Trimeline<br>mental Construction   | 120 01-May-23 28-Aug-2<br>30 29-Aug-23 27-Sep-2<br>30 30-Uun-23 29-Jul-23<br>200 28-Sep-23 14-Apr-24<br>200 28-Sep-23 14-Apr-24<br>450 15-Apr-24 18-Jur-22<br>150 15-Apr-24 18-Jur-22<br>180 21-Dec-24 18-Jur-22<br>1385 06-Apr-25 18-Jur-22<br>1306 05-Apr-25 28-Jul-28<br>650 19-Jur-25 08-Feb-2<br>180 23-Jul-28 18-Jar-2  | Planning & Elecution of a Feld Planning & Elecution of a Feld Planning & Elecution of a Feld Planning & Elecution of a Planning & Elecution of a Planning & Planning  |
| <ul> <li>A1380 Optimize the Scheme at A1380 Prepare Project Charter</li> <li>A13800 Prepare Project Charter</li> <li>A1420 FEEP Execution Planning</li> <li>A1420 Execution Planning &amp; 1</li> <li>A1430 Execution Planning &amp; 1</li> <li>A1670 Bid / Evaluate / Award F</li> <li>HydroV2.4.2 Execution (Constructs)</li> </ul>  | and update Cost & Schedule<br>r'and FEEP Scope of Work<br>I Planning Stage<br>ing Stage<br>Planning Stage<br>Detailed Engineering<br>Recommendation<br>ion) Timeline<br>ion) Timeline<br>metal Construction  | 30         29.4ug-23         27.5ep.2           30         30un-23         29ur-23           200         28.5ep.23         14.4pr-24           200         28.5ep.23         14.4pr-24           450         15.4pr-24         18ur-23           260         15.4pr-24         18ur-23           260         15.4pr-24         20-0eo-2           180         21-0eo-24         18ur-23           1385         06.4pr-25         18ur-23           1385         06.4pr-25         21ur-23           1385         06.4pr-25         18ur-23           1386         06.4pr-25         18ur-23           1385         06.4pr-25         21ur-23           050         19ur-25         08ur-23           060         19ur-25         08ur-23           180         23ur-26         08-feb-2           180         23ur-26         08-feb-2           180         23ur-26         08-feb-2   | Determine the Scherker and update Foot % Scherker % Sche  |
| <ul> <li>A1390 Prepare Project Charter</li> <li>HydroV2.4.1.2 Front.End Execution</li> <li>A1420 FEEP Execution Planning</li> <li>A1430 Execution Planning &amp; I</li> <li>A1430 Execution Planning &amp; I</li> <li>A1670 Bid / Evaluate / Award F</li> <li>HydroV2.4.2 Execution (Constructs)</li> </ul>  | r and FEEP Scope of Work<br>I Planning Stage<br>ing Stage<br>Planning Stage<br>Detailed Engineering<br>Recommendation<br>ion) Timeline<br>ion) Timeline<br>metal Construction  | 30         30-Jun-23         28-Jur-23           200         28-Sep-23         14-Apr-24           200         28-Sep-23         14-Apr-24           450         15-Apr-24         18-Jur-23           260         15-Apr-24         18-Jur-23           260         15-Apr-24         18-Jur-26           180         21-Dec-24         18-Jur-23           1385         06-Apr-25         18-Jur-26           1385         06-Apr-25         22-Jur-28           1205         05-Apr-25         23-Jur-26           1206         05-Apr-25         23-Jur-26           1300         19-Jur-25         30-Mar-2           050         19-Jur-26         08-Feb-2           180         23-Jur-26         08-Feb-2           180         23-Jur-26         18-Jar-26           180         23-Jur-26         18-Jar-26           180         23-Jur-26         18-Jar-26  | FEEP Sector of Work<br>FEEP Execution Planning Stage<br>FEEP Execution Planning Stage<br>Fee Control Planning Stage<br>Fee   |
| HydroVZ.4.1.2 Front End Execution<br>A1420 FEEP Execution Plannin<br>HydroVZ.4.1.3 Detailed Execution F<br>A1430 Execution Planning & I<br>A1670 Bid / Evaluate / Award F<br>HydroVZ.4.2 Execution (Constructs   | n Planning Stage<br>ing Stage<br>Planning Stage<br>Detailed Engineering<br>Recommedation<br>ion) Trimeline<br>Instruction<br>mental Construction   | 200 28.5ep-23 14.4pr-24<br>200 28.5ep-23 14.4pr-24<br>430 15.4pr-24 18.4ur-22<br>250 15.4pr-24 18.4ur-22<br>180 21.9eo-24 18.4ur-22<br>1385 06.4pr-25 18.4ur-22<br>1385 06.4pr-25 18.4ur-22<br>1305 05.4pr-25 28.4ur-28<br>650 19.4ur-25 08.Feb-2<br>180 23.4ur-25 08.Feb-2<br>180 23.4ur-25 08.Feb-2   | FEEP Frequencies Provide Planting Stage  |
| <ul> <li>A1420 FEEP Execution Plannir</li> <li>HydroV2.4.1.3 Detailed Execution Flanning &amp; I</li> <li>A1430 Execution Planning &amp; I</li> <li>A1670 Bid / Evaluate / Award F</li> <li>HydroV2.4.2 Execution (Constructs)</li> </ul>  | ing Stage<br>Planning Stage<br>Detailed Engineering<br>Recommendation<br>ion) Timeline<br>Instruction<br>mental Construction   | 200 28.5ep-23 14.4pr-24<br>430 15.4pr-24 18.Jun-22<br>250 15.4pr-24 20.Deo-2<br>180 21-Deo-24 18.Jun-22<br>1385 06.4pr-25 18.Jun-22<br>1385 05.4pr-25 28.Jun-28<br>1205 05.4pr-25 28.Jun-28<br>650 19.Jun-25 08.Feb-2<br>180 23.Jun-25 08.Feb-2   | TEEP Provide a p   |
| HydroVZ.4.1.3 Detailed Execution P<br>A1430 Execution Planning & I<br>A1670 Bid / Evaluate / Award F<br>HydroVZ.4.2 Execution (Constructs  | Planning Stage<br>Detailed Engineering<br>Recommendation<br>ion) Timeline<br>Instruction<br>mental Construction  | 430         15-Apr-24         18-Jun-22           2560         15-Apr-24         20-Deo-2           180         21-Deo-24         18-Jun-26           1385         06-Apr-25         18-Jun-26           1385         05-Apr-25         18-Jun-26           1205         05-Apr-25         21-Jun-26           1205         05-Apr-25         22-Jul-28           050         19-Jun-25         30-Miar-2           060         19-Jun-25         08-Feb-2           180         23-Jul-28         18-Jan-2   |  |
| <ul> <li>A1430 Execution Planning &amp; C</li> <li>A1670 Bid / Evaluate / Award R</li> <li>HydroV2.4.2 Execution (Constructs)</li> </ul>   | Detailed Engineering<br>Recommedation<br>ion) Timeline<br>Instruction<br>mental Construction   | 250 15.4pr.24 20-Deo.2<br>180 21-Deo.24 18-Jun-25<br>1385 06.4pr.25 18-Jun-26<br>1385 06.4pr.25 18-Jun-26<br>1385 05.4pr.25 28-Jul-28<br>650 18-Jun-25 08-Feb.2<br>600 19-Jun-25 08-Feb.2<br>180 23-Jul-28 18-Jan-2   |  |
| A 1670 Bid / Evaluate / Award R<br>HydroV2.4.2 Execution (Construction   | Recommendation<br>ion) Timeline<br>Instruction<br>mental Construction  | 180         21-De-24         18-Jun-26           1385         06-Apr-25         18-Jun-26           1385         06-Apr-25         18-Jun-26           1205         05-Apr-25         21-Jun-26           050         19-Jun-25         08-Feb-2           060         19-Jun-25         08-Feb-2           180         23-Jul-28         18-Jan-2  |  |
| HydroV2.4.2 Execution (Construction  | ion) Timeline<br>Instruction<br>mental Construction  | 1385 05-4pr-25 18-Jan-27<br>1385 05-4pr-25 18-Jan-27<br>1205 05-4pr-25 22-Jul-28<br>650 19-Jun-25 30-Mar-2<br>600 19-Jun-25 08-Feb-2<br>180 23-Jul-28 18-Jan-2  |  |
|  | nstruction<br>mental Construction  | 1385         05-Apr-25         18-Jan-23           1205         05-Apr-25         22-Jul-28           050         19-Jun-25         30-Miar-2           000         19-Jun-25         08-Feb-2           180         23-Jul-28         18-Jan-2   |  |
| HvdroV2.4.2.1 Execution Stane  | nstruction<br>mental Construction  | 1205 05-Apr-25 22-Jul-28<br>050 19-Jun-25 30-Mar-2<br>000 19-Jun-25 08-Feb-2<br>180 23-Jul-28 18-Jan-2  |  |
| A1440 Turbine Generator  | nstruction<br>mental Construction  | 650 19-Jun-25 30-Mar-27<br>600 19-Jun-25 08-Feb-2<br>180 23-Jul-28 18-Jan-2   |  |
| A1450 Civil / Powerhouse Cons  | mental Construction  | 600 19-Jun-25 08-Feb-2<br>180 23-Jul-28 18-Jan-2  |  |
| A 1480 Transmission / Environme  |  | 180 23-Jul-28 18-Jan-2  |  |
|  |  | 180 23-Jul-28 18-Jan-28   |  |
| A1470 Management Continge.   | ency   |   |  |
| lydroV2.5 Portland Creek   |  | 2291 01-Jan-23 09-Apr-28  |  |
| HydroV2.5.1 Project Timelines  |  | 1100 01-Jan-23 04-Jan-20  |  |
| HydroV2.5.1.1 Project Definition St  | tatement Update  | 1100 01-Jan-23 04-Jan-20  |  |
| A1480 Hydrotechnical Update.   | e / Scheme Update  | 60 01-Jan-23 01-Mar-2.  | 3 Privitatubidatev Scheme Update   |
| A1490 EAP Strategy Developn  | ment & Implementation  | 1100 01-Jan-23 04-Jan-2(  |  |
| HydroV2.5.1.1.1 Plan&Execute F   | Field Program  | 168 02-Mar-23 16-Aug-2  | Plankt telefold Protogram  |
| 🕳 A1510 Planning and Preparatio  | ion  | 90 02-Mar-23 30-May-2   | 2 Planning and Preparation   |
| A1520 Late Winter Driling  |  | 60 26-Mar-23" 24-May-2  | 3 Cale Winter Children Childre   |
| A1530 Summer Topographical   | Suneys   | 45 03-Jul-23* 16-Aug-2.   | 3 Summer Topographical Surveys   |
| HydroV2.5.1.6 FrontEnd Execution   | n Planning Stage   | 210 25-May-23 20-Deo-2  | a front-End Execution Planning Stage Complete Ney  |
| A1540 Complete Key Enginee   | ering Activities   | 180 25-May-23 20-Nov-2  |  |
| A1550 Prepare Path of Constru-   | ruction / Sequencing / Revised So  | 150 24-Jul-23 20-Deo-2  | 3 III + COMPAND Prepare Pathiot Construction (Sequencing) Revises Sociedule  |
| A1560 Prepare Class 3 Cost E.  | Estimate   | 30 21-Nov-23 20-Deo-2   |  |
| A1570 Support the Environmer   | ental Field Work   | 200 04-Jun-23 20-Deo-2  | 3  |
| 📄 HydroV2.5.1.3 Detailed Execution P   | Planning Stage   | 430 21-Deo-23 22-Feb-2  | Détailéd Execution Planning Stage  |
| A1580 Execution Planning & D   | Detailed Engineering   | 250 21-Deo-23 26-Aug-2  | Electricity of Desired Erligible efficients  |
| A1590 Bid / Evaluate / Award   |  | 180 27-Aug-24 22-Feb-2  | Big / Eladuate / Watarti   |
| HydroV2.5.2 Execution (Construction  | ion) Timeline  | 1044 01-Jun-26 09-Apr-20  |  |
| HydroV2.5.2.1 Execution Stage  |  | 1044 01-Jun-26 09-Apr-2   |  |
| A1600 Summer 1 - Access / Se   | ietup / Facility Site Prep.  | 190 01-Jun-26" 07-Deo-2   |  |
| A1610 Summer 2 - Const. Faci   | clities  | 190 01-May-27* 06-Nov-2   | Summer 2-Const: Padlifes   |
| 🚍 A1620 Winter 2 - Transmission  | I Line Construct to Peters Barrens   | 250 07-Nov-27 13-Jul-28   |  |
| A1630 Summer 3 - Complete F  | Powerhouse / Switchyard and Trai   | 160 05-May-28" 11-Oct-28  | Surhmer 3 -: Compete Powerhouse/   |
| A1640 Management Continger   | ency   | 180 12-Oct-28 09-Apr-26   |  |

FIGURE 5.1 ISLAND HYDROELECTRIC GENERATION EXPANSION ALTERNATIVES PROJECT SCHEDULES SUMMARY (page 2 of 2)

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 19   |

### 6. TASK 3: SCREENING AND RANKING OF PROSPECTS

### 6.1. PROJECT PORTFOLIO MANAGEMENT

Screening and ranking were conducted using the principles of Project Portfolio Management (PPfM) as a guide, and these principles align with Hydro's System Planning strategy. According to the Project Management Institute (PMI)<sup>9</sup>, "*PPfM is fundamentally different from project and program management. Project and program management are about execution and delivery – doing projects right. In contrast, PPfM focuses on doing the right projects at the right time by selecting and managing projects as a portfolio of investments.*"

PPfM aligns project execution with corporate strategy to maximize the value of the entire portfolio, to balance the portfolio to ensure that risks are properly considered, and to ensure that short-term results do not become the focus. There are five (5) steps to be considered, as follows.

- 1. Determine business objectives.
- 2. Compile a list of potential projects and research them.
- 3. Assess the list of projects against relevant criteria (i.e., the main subject of this study).
- 4. Validate feasibility against available resources, prioritize and move forward on selected projects.
- 5. Manage and monitor the portfolio, including, as necessary, re-scoping, reallocating resources, etc.

Deciding which projects move forward is not always straightforward and it is often difficult to leave projects off the table. Screening and ranking processes ultimately involve people forming personal opinions based on data and value propositions. It is a subjective process, but it can be approached in a structured way, especially when project decisions will be under scrutiny by stakeholders and third parties.

### 6.2. ASSESSMENT MODELS

### "Traffic Light" Assessment Model

Traffic Light Assessment is a rating system for evaluating performance against a predefined standard or set of criteria. For a study like this one, the model has the advantage of being easy to facilitate and completed quickly (see sample in **FIGURE 6.1**). With Hydro's approval, the **Traffic Light model was adopted for this Study**.





<sup>&</sup>lt;sup>9</sup> Oltmann, J. (2008). Project portfolio management: how to do the right projects at the right time. Paper presented at PMI® Global Congress 2008—North America, Denver, CO. Newtown Square, PA: Project Management Institute.

|               | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|---------------|--------------------------------------|-----|-------------|------|
|               | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC · LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 20   |

### **Qualitative Assessment Models**

### For information only (not in scope of this Study)

A qualitative "risk rating" model, similar to Hydro's *Capital Risk Rating Matrix*, was another model considered for this study but requires more information than is available at this stage of the study. In such a model, ranking criteria are less general (i.e., more prescriptive) and are focused on outcomes/impacts that could affect project metrics like cost, schedule, quality, safety, environment, reputational impact, etc. Numerical rankings are determined by multiplying a numerical rating of the probability of the outcome with a numerical rating of the severity of the outcome (**Figure 6.2**). This type of model could be of value to Hydro prior to a major stage gate, such as Project Sanction (Gate 3).

| Probability | of outcon | ne    |   |
|-------------|-----------|-------|---|
|             | Level     | Score | Description   |
|             | Very High | 5     | It is expected that the event will occur. If it does not occurs it will be a<br>surprise. |
|             | High      | 4     | The event has a great chance of occurring.  |
|             | Medium    | 3     | The event can occur.  |
|             | Low       | 2     | It will be a surprise if the event occurs.  |
|             | Very Low  | 1     | Very remote chance of the event to happen. Practically impossible.                        |

### Schedule impact

| Level     | Score | Description  |
|-----------|-------|--|
| Very High | 5     | Delays/Anticipation above 180 days or 6 months.        |
| High      | 4     | Delays/Anticipation between 120 and 180 calendar days. |
| Medium    | 3     | Delays/Anticipation between 60 and 120 calendar days.  |
| Low       | 2     | Delays/Anticipation between 15 and 60 calendar days.   |
| Very Low  | 1     | Less than 15 calendar days of delays/anticipation.     |

### Cost impact

| Level     | Score | Description   |
|-----------|-------|---|
| Very High | 5     | Variation (positive or negative) above \$1,000,000.                 |
| High      | 4     | Variation (positive or negative) between \$500,000 and \$1,000,000. |
| Medium    | 3     | Variation (positive or negative) between \$250,000 and \$500,000.   |
| Low       | 2     | Variation (positive or negative) between \$100,000 and \$250,000.   |
| Very Low  | 1     | Variation (positive or negative) lower than \$100,000.              |

### Environmental / reputational impact

| Level     | Score | Description  |
|-----------|-------|--|
| Very High | 5     | Crisis. Impact is so evident and public that the project could not proceed |
|           |       | as planned.  |
| High      | 4     | Evident impact on environment/reputation.                                  |
| Medium    | 3     | Impact is perceived and raises concerns.                                   |
| Low       | 2     | Perceived impact on environment/reputation but without relevance.          |
| Very Low  | 1     | No impact on environment and reputation.                                   |

FIGURE 6.2 Example Qualitative Assessment Model

(Source: Project Management Institute - PMI)

|               | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|---------------|--------------------------------------|-----|-------------|------|
|               | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC · LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 21   |

### **Quantitative Assessment Models**

For information only (not in scope of this Study)

More detailed models such as quantitative risk analysis use techniques like Monte Carlo simulation to assess many combinations of probabilities and outcomes, and these techniques are usually reserved for detailed cost estimates with many hundreds or thousands (or more) quantities and unit costs. An example of a Monte Carlo simulation for a Class 3 cost estimate for a major civil project is shown in **FIGURE 6.3**.





|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 22   |

### 6.3. KEY RANKING CRITERIA

Defining the Ranking Criteria is an important part of portfolio management and is done in collaboration with senior management, project managers, and, in some cases, with stakeholders and customers. In consultation with Hydro, the Ranking Criteria shown in **TABLE 6-1** were developed and used in the Traffic Light Model screening and ranking process for this study. Feedback from projects executed in the past by (and for) Hydro was important in selecting these criteria. More criteria can be added later, based on study feedback.

### **CAPACITY Criteria**

The project team confirmed CAPACITY criteria as follows.

### 1. As per APPENDIX A: DOCUMENT REVIEW

• From previous studies and reports provided by Hydro, record and confirm relevant technical information, e.g., total expected installed capacity in megawatts (MW) of each prospect.

### 2. As per APPENDIX C: PROSPECT OVERVIEWS, GAP ANALYSIS & RISKS

- From 2018 cost estimates for each prospect provided by Hydro, review and escalate costs from YE-2018 to YE-2022.
- Based on the above, calculate \$ / MW for each prospect.
- Review and expand schedules/timelines to incorporate the full project development process.

### WATER RIGHTS Criteria

A Water Right is the authorized use of surface water or groundwater by the governing authority(ies). At Hydro's request, WATER RIGHTS criteria were added to the screening and ranking process to capture issues related to water use for the prospects. For example, some prospects are already owned by Hydro, others are strictly on government (Crown) land, but others may have more complex ownership and approval issues. This study only addresses the perceived degree of effort required to secure the Water Rights for the prospect.



TABLE 6-1 KEY RANKING CRITERIA

(including Traffic Light Model examples)

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 23   |

### **RISK CONSIDERATIONS Criteria**

Project development issues that, historically, have had a measurable impact on cost, schedule, quality, safety and reputation of past projects are addressed in as Item 3. RISK CONSIDERATIONS.

- ENVIRONMENTAL considerations included technical issues, timelines and whether the project is Brownfield (a modification or addition to an existing facility) or Greenfield (a new facility).
- All energy projects must consider SOCIOECONOMIC INFLUENCES, and, for hydropower projects, these include impacts and benefits to land and resource use (e.g., First Nations traditional practice, recreation, tourism), economic resources (e.g., employment, sustainability), and community dynamics (e.g., education and training, community stability, infrastructure).
- RELIABILITY CONSIDERATIONS broadly include operations and maintenance complexity and efficiency and longevity of equipment.
- MARKET CONDITIONS are demographic and supply chain issues that may positively or negatively impact cost, schedule, quality, safety and reputation.

For this Study, Subject Matter Experts (SMEs) provided commentary on provincial Environmental Assessment (EA) approvals and permitting requirements, the provincial Project Registration documentation requirements, the federal Impact Assessment Act requirements, and the impacts of climate change on precipitation and temperature. This commentary is included in **APPENDIX D: ENVIRONMENTAL APPROVALS AND PERMITTING** and was referenced in the Screening and Ranking process.

### 6.4. SCREENING AND RANKING PROCESS

The Screening and Ranking process was completed by Hydro in a workshop held on September 28, 2022. Participants in the workshop were as follows.

5. Greg Snyder - SNC-Lavalin

- 1. Brian Sparkes NL Hydro
- 2. Brad Chaulk SNC-Lavalin 6. Marc Cullen NL Hydro
- 3. Evan Broderick NL Hydro 7. Stephen Parsons NL Hydro
- 4. Forhad Ahmad NL Hydro
- For each prospect, a Traffic Light Assessment was performed on each metric in the Key Ranking Criteria matrix. Each metric was assigned either a RED, YELLOW or GREEN ranking status based on qualitative and quantitative assessments of the metric, using the experience and judgement of the workshop attendees. While there is subjectivity in this approach, the method is considered practical for this level of study.

### 6.5. SCREENING AND RANKING BASIS

A description of the rationale used by workshop participants to rank each metric is included below.

### Prospect 1: Bay d'Espoir Hydro Generating Unit 8

- 1. <u>MW / Cost per MW Installed</u>. This project has the highest capacity (150 MW) and the lowest project development cost (\$3.48 per MW Installed) among the prospects and these metrics are, therefore, classified as GREEN.
- 2. <u>Development / Construction Timelines</u>. These timelines are classified YELLOW due to the uncertainty around the Turbine Generator design, testing, manufacture, and delivery time.
- 3. <u>Water Rights</u>. Water Rights are owned by Hydro and are classified as GREEN.

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC+LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 24   |

- 4. <u>Environmental</u>. As this is a Brownfield site and the environment impacts are considered manageable, these metrics are classified GREEN.
- 5. <u>Socioeconomic</u>. Again, as this is Brownfield site, the socioeconomic impact is considered manageable and the metric is classified as GREEN.
- 6. <u>Reliability</u>. The project is adjacent to an existing powerhouse and will have good access, make use of existing transmission routes, and use equipment similar to existing. Reliability is classified as GREEN.
- 7. <u>Market (Construction) Conditions</u>. The Green Energy construction market is already showing signs of becoming extremely busy over the next two (2) to four (4) years and will impact this project if Hydro decides to proceed within the next twelve (12) months. Therefore, the supply of Long-Lead equipment and Contractor Availability are classified as RED. Due to the considerable experience gained by contractors in eastern Canada because of muskrat Falls, the contractor capability metric has been classified as YELLOW.

### Prospect 2: Addition of a Third Generating Unit Cat Arm

- <u>MW / Cost per MW Installed</u>. This prospect has the second-highest capacity (68 MW) and the second-lowest project development cost (\$4.47 per MW Installed) of the prospects. The project documentation is 1985-vintage and it is very likely that updated hydrology will result in an increased capacity, therefore the capacity is classified as GREEN. However, the cost per MW has been assigned YELLOW due to the age of the project documentation (1985) and whether or not a new transmission line is required.
- <u>Development</u> / <u>Construction Timelines</u>. These timelines are classified YELLOW due to scope uncertainly because of the age of the project documentation (1985). An update to the Project Definition Statement is necessary and changes in the scheme could impact timelines.
- 3. <u>Water Rights</u>. Water Rights are owned by Hydro and are classified as GREEN.
- 4. <u>Environmental</u>. As this is a Brownfield site, and the environmental impacts considered manageable, these metrics are classified GREEN.
- 5. <u>Socioeconomic</u>. The socioeconomic impact is considered manageable for this Brownfield site and this metric is classified as GREEN.
- 6. <u>Reliability</u>. The project is adjacent to an existing powerhouse and will have good access, make use of existing transmission routes, and use equipment similar to existing. Reliability is classified as GREEN.
- 7. <u>Market (Construction) Conditions</u>. Assuming the Cat Arm project would start four-to-seven (4-7) years after Bay d'Espoir, market conditions are difficult to predict. Therefore, the availability of major equipment and contractor availability has been classified as YELLOW. Due to the considerable experience gained by contractors in eastern Canada from the Muskrat Falls Project and given that this project is smaller and (slightly) less complex than Bay d'Espoir, the contractor capability metric has been classified as GREEN.

### Prospect 3: Island Pond Hydroelectric Development

- <u>MW / Cost per MW Installed</u>. The project would mainly be an energy producer and its project documentation (2006) close to FEEP-Stage completion, but the hydrology has to be updated. It is ranked as third priority and is classified as GREEN in terms of MW installed. After redoing the hydrology, the scheme could be revisited and, with increased storage, could produce more capacity.
- <u>Development / Construction Timelines</u>. The development timeline is driven by the forecasted three (3)year environmental assessment and approval period. There is some uncertainty around this timeline due to the lack of component environmental studies which could have a positive or negative impact

|               | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|---------------|--------------------------------------|-----|-------------|------|
|               | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC · LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 25   |

on the timeline. Therefore, this metric is classified as YELLOW. The construction of the Works is within the bounds of normal heavy civil work and there is a reasonable degree of certainty of a three (3)-year construction timeline, therefore this metric is classified as GREEN.

- 3. <u>Water Rights</u>. Water Rights are owned by Hydro and are classified as GREEN
- 4. <u>Environmental</u>. Due to the minimum flooding of the reservoirs and the remoteness of the site, environmental impacts are considered as manageable. However, given that this is a Greenfield site, the metric has been classified as YELLOW.
- 5. <u>Socioeconomic</u>. Due to the remoteness of the site, socioeconomic impacts are considered as manageable and have been classified as GREEN.
- 6. <u>Reliability</u>. The project is within the watershed of the Bay d'Espoir system, will have good access and is close to existing transmission routes. Reliability is classified as GREEN.
- 7. <u>Market (Construction) Conditions</u>. For this metric, it has been assumed that construction may begin within the next ten (10) years and could be affected by the forecasted boom in the green energy industry. Therefore, the long-lead items and contractor availability metrics have been classified as YELLOW. Due to the relative technical simplicity of this project, the contractor capability metric has been classified as GREEN.

### Prospect 4: Round Pond Hydroelectric Development

- <u>MW / Cost per MW Installed</u>. The project is mainly an energy producer and its project documentation (1987-89) was pre-feasibility level, but it must be updated in terms of hydrology. It is ranked as fourth in priority and is classified as YELLOW in terms of MWs installed, due to uncertainty with the key project parameters. By redoing the hydrology, the scheme could be revisited and with increased storage, could add more capacity. A redefined project with all environmental impacts addressed will likely affect the cost and, therefore, the Cost per MW is classified as RED.
- 2. <u>Development / Construction Timelines</u>. The development timeline is driven by the forecasted three (3)-year period for environmental assessment and approval. There is some uncertainty around this timeline due to the lack of component environmental studies which could have a positive or negative impact on the timeline. Therefore, this metric is classified as YELLOW. The construction of the Works is within the bounds of normal heavy civil work and there is a reasonable degree of certainty around a three (3)-year construction timeline, therefore this metric is classified as GREEN.
- 3. <u>Water Rights</u>. Water Rights are owned by Hydro and are classified as GREEN.
- 4. <u>Environmental</u>. Due to the minimum flooding of the reservoirs and the remoteness of the site, environmental impacts are considered as manageable. However, given that this is a Greenfield site, the metric has been classified as YELLOW.
- 5. <u>Socioeconomic</u>. Due to the remoteness of the site, socioeconomic impacts are considered as manageable and have been classified as GREEN.
- <u>Reliability</u>. The project is within the watershed of the Bay d'Espoir system and will have good access. It is also reasonably close to existing facilities for maintenance and repair resources. Reliability is classified as GREEN.
- 7. <u>Market (Construction) Conditions</u>. Due to the type and relatively small size of the Turbine Generator, the procurement of long-lead items is not anticipated to be difficult and this metric has been classified as GREEN. Contractor Availability has been classified as YELLOW due to the uncertainty related to the project development timeline. Due to the relative simplicity of this project, the contractor capability metric has been classified as GREEN.

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 26   |

### **Prospect 5: Portland Creek Hydroelectric Development**

- <u>MW / Cost per MW Installed</u>. The project is mainly an energy producer and its project documentation (2007) is close to FEEP-Stage completion, but the hydrology must be updated. It is ranked as fifth in priority and is classified as GREEN in terms of MWs installed. By redoing the hydrology, the scheme could be revisited and with increased storage, could produce more capacity. In 2007, access to the site was proposed from Daniel's Harbour, but with access now available via the LIL access road, which pass directly through the watershed, there is potentially a significant change in access cost. Therefore, the Cost per MW has been classified as YELLOW.
- 2. <u>Development / Construction Timelines</u>. The development timeline is driven by the forecasted three (3)-year period for environmental assessment and approval. However, due to the remoteness of the site, and the potential to change the access location, this timeline could be notably shorter. Therefore, the Development Timeline metric has been classified as RED. The project is relatively small and not difficult in terms of civil construction, but the construction season is limited to summer and fall months and, therefore, the construction timeline has been classified as YELLOW.
- 3. <u>Water Rights</u>. Water Rights are owned by the Crown and are classified as YELLOW.
- 4. <u>Environmental</u>. Due to the minimum flooding of the reservoirs and the remoteness of the site, environmental impacts are considered as manageable. However, given that this is a Greenfield site, the metric has been classified as YELLOW.
- 5. <u>Socioeconomic</u>. Due to the remoteness of the site, the socioeconomic impacts are considered manageable and have been classified as GREEN.
- <u>Reliability</u>. The project site is remote and currently without access and may make access for maintenance and repair difficult. Concerns about reliability will need to be addressed in the design. Reliability is therefore classified as YELLOW.
- 7. <u>Market (Construction) Conditions</u>. Due to the type and relatively small size of the Turbine Generator(s), the procurement of long-lead items is not anticipated to be difficult and this metric has been classified as GREEN. Contractor Availability has been classified as YELLOW due to the uncertainty related to the project development timeline. Due to the relative simplicity of this project, the Contractor Capability metric has been classified as GREEN.

### **Prospect 6: Exploits River Hydroelectric Developments**

- <u>MW / Cost per MW Installed</u>. These prospects are "Run of River" projects and, as such, are energy producer. Due to the age of the project documentation (1950-60's era) and the lack of information concerning environmental impacts (which are considered high), the MW installed metric has a high probability of changing and is classified as RED. The Class 5 Cost Estimates were updated in 2005, but the environmental impacts have not been fully identified, therefore the Cost per MW is classified as YELLOW.
- 2. <u>Development / Construction Timelines</u>. Due to the unknowns pertaining to the environmental impacts and the resulting mitigations, timelines are uncertain and this metric is classified as RED.
- 3. <u>Water Rights</u>. Water Rights are owned by the Crown and are classified as YELLOW.
- 4. Environmental. For same reasons as item 2. above , this metric is classified as RED
- 5. Socioeconomic. For same reasons as item 2. above, this metric is classified as RED.
- 6. <u>Reliability</u>. The design of these sites is not sufficiently advanced to properly assess reliability issues. Reliability is therefore classified as YELLOW.

|               | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|---------------|--------------------------------------|-----|-------------|------|
|               | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC · LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 27   |

7. <u>Market (Construction) Conditions</u>. Due to the type and relatively small size of the Turbine Generator(s), the procurement of long-lead items is not expected to be difficult and this metric has been classified as GREEN. Contractor Availability has been classified as YELLOW due to the uncertainty related to the project development timeline. Due to the relative simplicity of these projects, the Contractor Capability metric has been classified as GREEN.

### 6.6. SCREENING AND RANKING RESULTS SUMMARY

The results of the Screening and Ranking process are summarized in TABLE 6-2 below.

Date Revision Rev EVALUATION OF ISLAND HYDROELECTRIC GENERATION EXPANSION ALTERNATIVES SNC · LAVALIN

# TABLE 6-2 SCREENING AND RANKING RESULTS SUMMARY

| 6    | APIT AL COST<br>ESTIMATE |                  |                | CAPACITY                |                          | WATER RIGHTS |                                  |                       |                            | RISK CONSIDE          | ERATIONS       |                    |                            |                          |
|------|--------------------------|------------------|----------------|-------------------------|--------------------------|--------------|----------------------------------|-----------------------|----------------------------|-----------------------|----------------|--------------------|----------------------------|--------------------------|
| 0.00 | \$ x 1,000<br>calated to | 1. MW / COST PER | MW INSTALLED   | 2. DEVELOPMENT / CON    | STRUCTION TIMELINES      | 3 OWNERSHIP  | 4                                | . ENVIRONMENTAL       |                            | 5. SOCIO-<br>ECONOMIC | 6. RELIABILITY | 7. MARKET (0       | ONSTRUCTION) CO            | SNDITIONS                |
|      | YE 2022)                 | MW Installed     | \$ x1,000 / MW | Development<br>Timeline | Construction<br>Timeline |              | Environmental<br>Impacts         | Approval<br>Timelines | Brownfield /<br>Greenfield | NFLUENCES             | CONSIDERATIONS | Long-Lead<br>Items | Contractor<br>Availability | Contractor<br>Capability |
|      | \$520                    | 150              | \$3.48         | 5.8 Years               | 4.5 Years                | Hydro        | Manageable                       | 1 Year                | Brownfield                 | Manageable            | Good           | Challenging        | Limited                    | Adequate                 |
|      | \$305                    | 68.2             | \$4.47         | 5.2 Years               | 3.2 Years                | Hydro        | Manageable                       | 1 Year                | Brownfield                 | Manageable            | Good           | Uncertain          | Uncertain                  | Good                     |
|      | \$<br>23<br>2            | 36               | \$14.91        | 6.0 Years               | 3 Years                  | Hydro        | Manageable                       | 3 Years               | Greenfield                 | Manageable            | Good           | Uncertain          | Uncertain                  | Good                     |
|      | \$330                    | 8                | \$18.25        | 5.6 Years               | 3.3 Years                | Hydro        | Manageable                       | 3 Years               | Greenfield                 | Manageable            | Good           | Good               | Uncertain                  | Good                     |
|      | \$345                    | 23               | \$15.08        | 6.3 Years               | 3.1 Years                | Crown        | Manageable but<br>with<br>issues | 3 years               | Greenfield                 | Manageable            | Uncertain      | Good               | Uncertain                  | Good                     |
|      | \$520                    | 42               | \$12.39        | Unknown                 | Unknown                  | Crown        | Likely high                      | >3 years              | Greenfield                 | Likely high           | Uncertain      | Good               | Uncertain                  | Good                     |
|      | \$330                    | 24               | \$13.73        | Unknown                 | Опкпомп                  | Crown        | Likely high                      | >3 Years              | Greenfield                 | Likely high           | Uncertain      | Good               | Uncertain                  | Good                     |
|      |                          | 1                |                |                         | [                        |              | [                                | 1                     |                            |                       | 1              |                    |                            |                          |

| с.     |  |
|--------|--|
| in     |  |
| aval   |  |
| ٦<br>۲ |  |
| SNC    |  |

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 29   |

### 7. TASK 4: OPTIMIZATION OPPORTUNITIES

### 7.1. PORTFOLIO MANAGEMENT

Project Portfolio Management (PPfM) is the industry standard for compiling and managing a portfolio of projects over an extended period. PPfM can help optimize project resources, lower environmental, engineering and project management costs, provide opportunities for Supply Chain optimization (and lower the cost of major equipment supply), and provide construction sequencing opportunities over the entire portfolio, thereby lowering construction cost.

Should Hydro decide to proceed with several of the projects over a 10 to 15-year period, there would be an opportunity to use a Portfolio Management approach to plan and implement these projects.

For example, Hydro's Island Hydroelectric Generation Expansion project portfolio could consist of four (4) programs, as follows.

- Program A BDE and Cat Arm
- Program C Northern Peninsula West
- Program B Island Pond and Round Pond
- Program D Exploits River

### Program A – BDE and Cat Arm

BDE and Cat Arm are Brownfield projects that are similar in scope. Therefore, concurrent execution with staggered discipline activities would result in efficient use of human, material, and equipment resources. For example, executing BDE as a distinct project followed by Cat Arm as a separate project would take around ten to twelve (10 to 12) years. Executing both projects concurrently, using one prime contractor, would likely take only six to seven (6 to 7) years.

### Program B – Island Pond and Round Pond

Island Pond and Round Pond are in proximity on the existing Bay d'Espoir watershed, are similar in scope, and environmental issues are likely the same or very similar. Therefore, treating these projects as one program with two projects will greatly reduce planning time, reduce environmental planning level of effort, and result in construction cost savings and timeline reductions, similar to that outlined for Program B.

### Program C – Northern Peninsula West

The construction of the Labrador Island Link (LIL) has provided construction access to several watersheds on the western side of the Great Northern Peninsula. Several small-scale hydro projects (15 to 30 MW range) that were previously encumbered by the cost and environmental impact of constructing access could now be viable.

### Program D – Exploits River

The hydro resources of the Exploits River (Badger Chute and Red Indian Falls) have long been recognized but come with environmental challenges. However, future development of these resources could be acceptable as part of a renewable energy strategy or as other generation options are built or economic analysis deems them unviable to develop.

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |  |
|-------------|--------------------------------------|-----|-------------|------|--|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |  |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 30   |  |

### 7.2. GENERAL OPTIMIZATIONS

A high-level review of the selected turbine generators was undertaken by an SME and the following feedback was provided.

- 1. Turbine Generator Selection
  - The type of units listed for each generation facility appears reasonable except for Badger Chute and Red Indian Falls. A Francis unit is not recommended as both head and flows are too low.
  - Model tests will be required for the larger size units, namely BDE 150 MW. For Cat Arm, a model test for a 68 MW Pelton unit might not be necessary. The other units are closer to a standard design and model testing is usually not required.
  - Previous reports and studies included quotes by North American suppliers on typical timelines for design, manufacturing, and installation of turbine generators. For this study, these quotes were reviewed by SMEs and found to be reasonable for YE-2022 except for BDE, as follows.
    - BDE 48 months (39 months used in 2018 schedule)
    - Cat Arm 34 months
      Island Pond 30 months
      Round Pond 33 months
      Portland Creek 19 months
      Red Indian Falls / Badger Chute 36 months

For this study, SMEs also confirmed that suppliers Andritz, Voith and Alstom are generally busy and are likely to be even busier due to increased demand for energy. Other manufactures in China, for example, could be considered. In addition, pricing is volatile and suppliers will not guarantee pricing very long.

- Based on the above, calculate \$ / MW for each prospect.
- Review and expand schedules/timelines to incorporate the full project development process.
- 2. Schedule Critical Items
  - Water to Wire (W2W) Equipment Packages are Long-Lead Items and the larger size turbine generator unit design, manufacturing, and installation timeline will likely form the critical path item for the construction schedule.

### 7.3. SPECIFIC OPTIMIZATIONS

Individual optimization opportunities for each prospect are presented in **APPENDIX C**: **PROSPECT OVERVIEWS, GAP ANALYSIS & RISKS**.

|                    | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|--------------------|--------------------------------------|-----|-------------|------|
|                    | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| <b>SNC+LAVALIN</b> | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 31   |

### 8. TASK 5: GO-FORWARD PLAN

### 8.1. METHODOLOGY

The main objective of this Study was to determine the current level of completeness of Project Planning for each of the generation prospects. This was done by performing a Gap Analysis to identify the differences between the current "planning maturity" and the maturity required to meet the industry standard for Pre-Sanction (Gate 3), which is the completion of Front-End Execution Planning (FEEP).

The results of the Gap Analysis were then used to prepare the Scope of Work required to complete the Front-End Execution Planning (FEEP) deliverables for each prospect ("FEEP Requirements"). The overall Project Development Timeline and Construction Timeline was also assessed for each prospect.

Details of the Gap Analysis and the FEEP Requirements for each prospect are presented in **APPENDIX C: PROSPECTS OVERVIEW, GAP ANALYSIS & RISKS**.

### 8.2. GAP ANALYSIS RESULTS

Using the list of deliverables for Stage 1 and Stage 2 of the Heavy Civil Project Execution Standard (see **SECTION 3.3**), the degree of completion ("% Complete") of each deliverable was measured by assessing the current state of each deliverable against the standard.

Results are presented in two (2) levels of detail, as follows.

- 1. **Summary Level** that uses colour-coding to quickly show the design maturity status of each prospect (see **TABLE 8-1** below).
- Detailed Level Excel spreadsheet that allows sorting of information by development stage, technical discipline, deliverable, % complete, etc. This spreadsheet is included as an attachment to this report and a hardcopy of the spreadsheet is included as an attachment to APPENDIX C.

### 8.3. WORK REQUIRED TO COMPLETE FRONT-END PLANNING STAGES

Details for each prospect are provided in **APPENDIX C**. In general, the Project Definition Statements (see **SECTION 10.5**) should be updated for all prospects (except BDE Unit 8) after Hydrotechnical reviews and, in the case of Portland Creek, a potential change in site access should be considered.

|                                    | Page                              | 32                                   |
|------------------------------------|-----------------------------------|--------------------------------------|
| Revision                           | Date                              | 21-OCT-2022                          |
|                                    | Rev                               | 01                                   |
| EVALUATION OF ISLAND HYDROELECTRIC | GENERATION EXPANSION ALTERNATIVES | SLI Doc. No. 691499-0000-40ER-1-0001 |
|                                    |                                   | SNC+LAVALIN                          |

# TABLE 8-1 GAP ANALYSIS SUMMARY

|      |     | PROSP<br>Bay d'I | ECT 1<br>Espoir |           |         | PROSP<br>Cat A | ECT 2<br>Arm |      |     | PROSPE | ECT 3<br>Pond |               |       | PROSPE | CT 4<br>ond |      | ď   | PROSPI  | ECT 5<br>Creek |         |          | Red In    | ldian Fa | PROSPI<br>alls | ECT 6<br>Ba | ldger C   | hute   | Γ    |
|------|-----|------------------|-----------------|-----------|---------|----------------|--------------|------|-----|--------|---------------|---------------|-------|--------|-------------|------|-----|---------|----------------|---------|----------|-----------|----------|----------------|-------------|-----------|--------|------|
|      | 25% | 50%              | 75%             | 100%      | 25%     | 50%            | 75%          | 100% | 25% | 50%    | 75%           | 100%<br>2FF 1 | 25%   | 50%    | 75%         | 100% | 25% | 50%     | 75%            | 100%    | 25%      | 50%       | 75%      | 100%           | 25%         | 50%       | 75%    | 100% |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      | 25% | 50%              | 75%             | 100%      | 25%     | 50%            | 75%          | 100% | 25% | 50%    | 75%           | 100%          | 25%   | 50%    | 75%         | 100% | 25% | 50%     | 75%            | %001    | 25%      | 50%       | 75%      | 100%           | 25%         | 50%       | 75%    | 100% |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      | 25% | 50%              | 75%             | 100%      | 25%     | 50%            | 75%          | 100% | 25% | 50%    | 75%           | 100%          | 25%   | 50%    | 75%         | 100% | 25% | 50%     | 75%            | 100%    | 25%      | 50%       | 75%      | 100%           | 25%         | 50%       | 75%    | 100% |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               | SEE 2 |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               | SEE 2 |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      | 25% | 50%              | 75%             | 100%      | 25%     | 50%            | 75%          | 100% | 25% | 50%    | 75%           | 100%          | 25%   | 50%    | 75%         | 100% | 25% | 50%     | 75%            | 100%    | 25%      | 50%       | 75%      | 100%           | 25%         | 50%       | 75%    | 100% |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      | 25% | 50%              | 75%             | 100%      | 25%     | 50%            | 75%          | 100% | 25% | 50%    | 75%           | 100%          | 25%   | 50%    | 75%         | 100% | 25% | 50%     | 75%            | 100%    | 25%      | 50%       | 75%      | 100%           | 25%         | 50%       | 75%    | 100% |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      | 25% | 50%              | 75%             | 100%      | 25%     | 50%            | 75%          | 100% | 25% | 50%    | 75%           | 100%          | 25%   | 50%    | 75%         | 100% | 25% | 50%     | 75%            | 100%    | 25%      | 50%       | 75%      | 100%           | 25%         | 50%       | 75%    | 100% |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
|      |     |                  |                 |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |
| GEND |     | Comple           | ete             |           |         |                |              |      |     |        |               |               |       |        | LON<br>N    | res  | -   | sland P | ond may        | require | a reviev | v of hyd  | trology. |                |             |           |        |      |
|      |     | Some             | ork co          | molotod   | 7       | 75% hi         | + <100       | ×    |     |        |               |               |       |        |             |      | c   | Drining |                | and Env | nemacri  | dial Sub- | miseion  | totae hot      | provide     | ק איז באי | dro    |      |
|      |     |                  |                 | najaidiii | . e.g., |                | 2007 / 11    | ۹    |     |        |               |               |       |        |             |      | 4   |         |                |         |          |           |          |                | biooid      |           | j<br>D |      |
|      |     | Incom            | olete           |           |         |                |              |      |     |        |               |               |       |        |             |      |     |         |                |         |          |           |          |                |             |           |        |      |

PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 32 of 158

| STAGE 1: PROJECT DEFINITION | Project Definition Statement | Project Charter | Hydrology / Power & Energy Update | STAGE 2: FRONT FEND EXECUTION PLANNING (FEEP) | PROJECT MANAGEMENT | Project Execution Plan | Project Controls - Cost Estimate | Project Controls - Schedule | ENVIRONMENTAL MANAGEMENT | Prepare Project Registration | Preparation of EPR or EIS | ENGINEERING | Facility Scope of Work | Preliminary Engineering | Field Investigations | Design Optimizations | Updated Preliminary Engineering | Material Take-Off (MTO) | SUPPLY CHAIN | Contracting Strategy | Bid and Evaluation Plan | Vendor Packages for Long-Lead Items | CONSTRUCTION | Field Investigations | Construction Management (CM) Strategy | Development of Path of Construction | Construction Schedule | רפ |
|-----------------------------|------------------------------|-----------------|-----------------------------------|---|--------------------|------------------------|----------------------------------|-----------------------------|--------------------------|------------------------------|---------------------------|-------------|------------------------|-------------------------|----------------------|----------------------|---------------------------------|-------------------------|--------------|----------------------|-------------------------|-------------------------------------|--------------|----------------------|---------------------------------------|-------------------------------------|-----------------------|----|
|-----------------------------|------------------------------|-----------------|-----------------------------------|---|--------------------|------------------------|----------------------------------|-----------------------------|--------------------------|------------------------------|---------------------------|-------------|------------------------|-------------------------|----------------------|----------------------|---------------------------------|-------------------------|--------------|----------------------|-------------------------|-------------------------------------|--------------|----------------------|---------------------------------------|-------------------------------------|-----------------------|----|

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 33   |

### 9. CONCLUSIONS

### 9.1. PROSPECTS SUMMARY

The six (6) Island Hydroelectric Generation Expansion Alternatives can be grouped into the following two (2) technical categories.

**Brownfield Projects** (expansion of generating capacity of existing facilities)

- 1. Bay d'Espoir (BDE) Unit 8
- 2. Cat Arm Addition of a Third Generating Unit

<u>Greenfield Projects</u> (development and construction of new facilities)

- 3. Island Pond
- 4. Round Pond
- 5. Portland Creek (plus the potential for adjacent watersheds, referred to as Northern Peninsula West)
- 6. Exploits River
  - Red Indian Falls
  - Badger Chute

From an Environmental Approvals perspective, Brownfield projects are generally less demanding than Greenfield Projects.

For the Brownfield projects, the development timelines are driven by the time to design, manufacture, deliver, install and commission the turbine generators. For (smaller) Greenfield projects, development timelines are driven by the estimated three (3) year timeline for the Environmental Approval Process.

### 9.2. SANCTIONING CRITERIA

The standard industry approach to pre-sanctioning activities is to balance financial risk against the front-end planning level of effort, which effectively translates into "cost estimate accuracy". This balance is a matter of overall financial risk of a cost overrun during construction that can be absorbed by the project versus the Owner's ability to absorb the pre-investment financial cost should the project not proceed.

The optimal cost estimate level of accuracy at the Project Sanction Gate is achieved by completing the engineering design, tendering the work and receiving firm contractor pricing. However, this requires additional pre-sanction spending.

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 34   |

### **10. RECOMMENDATIONS**

### 10.1. PROPOSED PROSPECT RANKING

As detailed in **SECTION 6** herein, the following ranking of Island Hydroelectric Generation Expansion Alternatives is recommended.

- 1. Bay d'Espoir
- 2. Cat Arm
- 3. Island Pond
- 4. Round Pond

- 5. Portland Creek
- 6. Exploits River
  - Red Indian Falls
  - Badger Chute

### **10.2. DECISION GATE PROCESS**

It is recommended that Hydro continue to follow its "best in class" Decision Gate Process and align the Heavy Civil Project Execution Standard used in this Study (see **SECTION 3.3**) with the phases of that process. Recommended additions to that Standard are detailed in **SECTION 10.4** below. Hydro should also ensure that recommended deliverables / activities in the Standard be addressed prior to the relevant Decision Gate.

### 10.3. GATE 3 (PRE-SANCTION) COST ESTIMATING REQUIREMENTS

It is recommended that Hydro align its cost estimating procedures and its expectations of contractor(s) estimates with the Association for Advancement of Cost Engineering (AACE) Best Practices. This is considered an important step in addressing the following Key Recommendation in the report of the Commission of Inquiry Respecting the Muskrat Falls Project (March 5, 2020).

5. The Government of Newfoundland and Labrador should proceed to fund large projects using a probability value of not less than P85. As well, recognizing the

### Volume 1 Page 61

likelihood of bias in any cost and schedule estimate, government should require the project proponent to provide a range of cost estimates in order to establish the project's budget, so that government can determine its own risk appetite. Amounts for tactical and strategic risks should be included in the overall budget but should not be specifically identified or quantified when disclosure is made to the public. Government should authorize the release of dollar amounts for tactical and strategic risks only on pre-determined, structured and well-defined terms.

The level of detail and quality of cost estimate to meet Gate 3 (Pre-Sanction) industry requirements should be at least AACE Class 3 and, in cases where market conditions or technical uncertainty is high, Class 2. This will require completion of 40% to 70% of Project Definition deliverables prior to Gate 3 (see **APPENDIX B**). It must be acknowledged that this front-end work may be a "sunk cost" should the P85 estimate be uneconomic.

In order to determine the P85-level cost estimate, a Monte Carlo simulation (risk analysis) will be required to generate a cumulative probability curve. The simulation demands a robust and transparent cost estimate, with

|               | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|---------------|--------------------------------------|-----|-------------|------|
|               | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| 5NU · LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 35   |

ranges for unit costs and quantities endorsed by Cost Engineering and Risk Management SMEs. Independent external experts will also likely review and challenge aspects of the estimate and the risk analysis.

### 10.4. CONTRACTING STRATEGY BEST PRACTICE

It is recommended that Hydro review and adopt, in whole or modified accordingly for its business, the COAA Best Practice *DEVELOPING A CONTRACTING STRATEGY*.<sup>10</sup> The purpose of this Best Practice is to ensure that Project Owners have comprehensively considered Project specifics (goals/objectives, work environment, scopes of work, Project and contract risk allocation), weighed the pros and cons in consultation with all of the key Parties and clearly articulated the appropriate Contracting Strategy for the Project.

### 10.5. HEAVY CIVIL PROJECT EXECUTION STANDARD MODIFICATIONS

It is recommended that Stages 1 and 2 of the Heavy Civil Project Execution Standard used in this Study be modified to optimize the Standard for the Island Hydroelectric Generation Expansion Alternatives. This is due primarily to the need to revisit the hydrology for the prospects (except BDE Unit 8).

### STAGE 1: Project Definition Stage Update

It is recommended that Stage 1: Project Definition deliverables / activities be modified to include the following.

- Hydrotechnical Update and resulting Scheme Update, including hydrology and power/energy calculations which include recent data and climate change projections.
- Development of an Environmental Management Strategy and filing of Project Registration documentation with the Regulatory Authority.
- Preliminary Field Investigation work to firm up Project Definition assumptions and contribute to the Environmental Management Strategy.

### STAGE 2: Front-End Execution Planning (FEEP)

It is recommended that Stage 2: Front-End Execution Planning (FEEP) deliverables / activities be modified to include the following.

• Due to the length of the Environmental Approval process, it is recommended to combine Stage 2: FEEP and Stage 3: Detailed Execution Planning (DEP) to shorten overall development timelines for the prospects. While this will result in lower overall project planning costs, it will increase the presanction financial exposure for Hydro should a project not proceed.

Note: Concurrent planning of two similar projects (e.g., BDE and Cat Arm) by one project team will contribute to mitigating the "time gaps" in the planning process due to the lengthy environmental approval timelines.

### **10.6. ISLAND GENERATION POTENTIAL**

To fully understand the power / energy potential of the island, it is recommended that watersheds and potential hydro resources of the Exploits River and the western side of the Great Northern Peninsula be identified, followed by Project Definition work for the most viable resources.

<sup>&</sup>lt;sup>10</sup> COAA (March 2018).

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 36   |

### **10.7. PORTFOLIO MANAGEMENT CONSIDERATIONS**

Should Hydro decide to proceed with two (2) or more of these projects, it is recommended that Hydro adopt a Project Portfolio Management (PPfM) approach for planning and execution of the Island Hydroelectric Generation Expansion Alternatives. For example, if the first four (4) Alternatives were considered, two (2) programs could evolve.

Program A – BDE and Cat Arm

Program B – Island Pond and Round Pond

### **10.8. SANCTION PARAMETERS**

It is recommended that Hydro carefully consider its sanction parameters for this portfolio of projects. This should take into consideration the need for power / energy and the importance of project cost estimate accuracy. These considerations should be balanced against pre-investment expenditures and pre-sanction commitments for the purchase of long-lead items, compared to the potential "lost value" of power / energy should first power be delayed by minimizing pre-sanction expenditures.

### **10.9. RELIABILITY CONSIDERATIONS**

Reliability of hydroelectric facilities covers a broad range of topics and is an important design consideration for facility Owners. It will often mean selecting a more robust design and using equipment with a proven track record of reliability, including data on mean time to failure of equipment. Consideration should also be given to equipment and material source and quality control of manufacturing.

The experience of the Owner and maintenance crews is also an important consideration in reliability. Using the same or similar systems will make maintenance easier and improve overall reliability, and the use of equipment and systems that are tried-and-proven is important to ensure reliability.

The Owner should provide designers with information on its existing systems and equipment preferences so these can be considered in the design. Some systems may be outdated and better alternatives are usually available, although overly complex systems may be difficult and expensive to maintain.

Redundancy of equipment and of power supplies and critical operations equipment should also be considered. This can also include routing of cabling, telecommunications systems and ensuring access alternatives so that the plant can continue to operate at all times.

The Owner's reliability expectations need to be clear and expressly communicated to the designer. These expectations come through in specifications as direction to the contractor for material and equipment selection and for construction approaches. For Muskrat Falls, for example, the Owner provided a series of "Design Philosophy" documents that provided direction on the design approach.

Improving of reliability can be more costly at the design and construction stage – sometimes called the "gold plated solution" – but it generally proves its worth in the long term through increased time in operation, reduced maintenance and longer service life for the facility.

### **10.10. RISK CONSIDERATIONS**

Project-specific risks for each of the Island Hydroelectric Generation Expansion prospects are outlined in **APPENDIX C**. However, there is an overarching risk consideration that will apply to the entire portfolio.

The key risk to planning and executing any heavy civil project over the next five-to-ten (5-10) years will be post-pandemic global supply chain challenges and the retirement of many the "baby boomer" generation from

|             | EVALUATION OF ISLAND HYDROELECTRIC   |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | GENERATION EXPANSION ALTERNATIVES    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-1-0001 | 01  | 21-OCT-2022 | 37   |

the workforce. For renewable energy projects, this situation is further aggravated by the predictions of a construction boom. For hydroelectric projects, timelines for major equipment, i.e., water-to-wire (W2W) packages, will be lengthy, fuel cost will be volatile, and there will be technical and craft labour shortages.

The are several ways to mitigate this risk.

- 1. Owner clarity around cost and schedule objectives, including which has priority and what are the limitations of that priority.
- 2. Innovative approaches to project contracting strategies will be necessary.
- 3. The single biggest variable to schedule can be Project Sanction criteria. Early financial commitments on environmental, engineering, and major equipment purchase can reduce the time to first power by 12-to-18 months.

Therefore, it is recommended that Hydro carefully consider its cost and schedule objectives for the proposed Island Hydroelectric Generation Expansion Alternatives and ensure these objectives are reflected in its Project Charter, Project Contracting Strategy and Sanction Parameters.

|             | APPENDIX A                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | DOCUMENT REVIEW                      | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | A-1  |

# **APPENDIX A**

### DOCUMENT REVIEW

| Prospect 1         Prospect By d'Espoir Hydro Generating Unit 8         Matri 22, 2018         Dis         Noc.Lavani           By d'Espoir Hydro Generating Unit 8         Proposed By d'Espoir Hydro Generating Unit 8         Matri 22, 2018         Dis         Noc.Lavani           Proposed By d'Espoir Hydro Generating Unit 8         Proposed By d'Espoir Hydro Generating Unit 8         Matri 22, 2018         Dis         Noc.Lavani           Proposed By d'Espoir Hydro Gone attenting Unit 8         Proposed By d'Espoir Hydro Generating Unit 8         Disender 11, 2020         Di         Hard           Proposed By d'Espoir Hydro Gone attenting Unit 8         Bay d'Espoir Hydro Generating Unit 8         Disender 11, 2020         Di         Hard           Proposed By d'Espoir Hydro Generating Unit 8         Bay d'Espoir Hydro Generating Unit 8         Disender 11, 2020         Di         Hard           Proposed By d'Espoir Hydro Generating Unit 8         Matri 23, 2018         January 144, 1997         Di         Disender           Proposed By d'Espoir Hydro Generating Unit 8         Matri 23, 2018         January 144, 1997         Di         Disender           Proposed By d'Espoir Hydro Benetic Cavaul         Matri 23, 2018         January 144, 1997         Di         Disender           Proposed By d'Espoir Hydro Benetic Cavaul         Matri 23, 2018         Matri 23, 2018         Di         Di   |   | DOCUMENT TITLE   | DATE               | REV. AUTHOR(S         |                           | O. TYPE  |
|---|---|--|--------------------|-----------------------|---------------------------|----------|
| Propried Bay of Esport Hydro Generating Unit, a.         Mach 22, 2015         C0         SVC-Lavalin           Propried Bay of Esport Hydro Generating Unit, a.         Ecusso 3 Cost ESTIMATE AND PROJECT EXECUTION         Mach 22, 2015         C0         Hadro           Propried Bay of Esport Hydrology and Feasibility Study for Potential         Bepennen 11, 2020         C0         Hadro           Propried Bay of Esport Hydrology and Feasibility Study for Potential         Bepennen 11, 2020         C0         Hadro           Propried Bay of Export Mydrology and Feasibility Study for Potential         August 34, 2018         C0         Hadro           Propried Bay of Export Mydrology and Feasibility Study January 1988         January 14, 1997         C0         Hadro           Propried Bay of Expont Hond Potel Development Final Feasibility Study January 1988         January 14, 1997         C0         Hadro           Propried Export HydroleGento PoleCt FINAL REPORT         Branary 14, 1997         C1         Hadro           Propried Export HydroleGento PoleCt FINAL REPORT         Branary 14, 1997         C1         Hadro           Propried Export HydroleGento PoleCt FINAL         Branary 14, 1997         C1         Hadro           Propried Export HydroleGento PoleCt FINAL         Branary 14, 1997         C1         Hadro           Propried Export HydroleGento PoleCt FINAL         Branary 14, 1997 <th>PROSPECT 1<br/>BAY d'ESPOIR HYDRO GENERATING UNIT 8</th> <td>Proposed Bay d'Espoir Hydro Generating Unit 8<br/>HYDRAULIC ANALYSIS OF THE CONVEYANCE SYSTEM</td> <td>March 22, 2018</td> <td>00 SNC-Lavali</td> <td>n 647756-0000-40ER-I-0001</td> <td>00 PDF</td>  | PROSPECT 1<br>BAY d'ESPOIR HYDRO GENERATING UNIT 8  | Proposed Bay d'Espoir Hydro Generating Unit 8<br>HYDRAULIC ANALYSIS OF THE CONVEYANCE SYSTEM                       | March 22, 2018     | 00 SNC-Lavali         | n 647756-0000-40ER-I-0001 | 00 PDF   |
| Respect of mycroson of the relation of a third Generating Jurit No. 8         December 11, 2020         Del         But Mont           POSPECT 3         Bay (Esport Hydrobectric Generating Jurit No. 8         September 13, 1986         1         But Mont           POSPECT 3         Addition of a third Generating Jurit No. 8         September 13, 1986         1         But Mont           POSPECT 3         Addition of a third Generating Unit. Cat Amm         August 24, 2018         1         Number 1           POSPECT 3         Cat Am Unit 3 Cost Estimate (August 24 2019)         August 24, 2018         1         Number 1           POSPECT 3         Cat Am Unit 3 Cost Estimate (August 24 2019)         August 24, 2018         1         Number 1           POSPECT 3         Cat Am Unit 3 Cost Estimate (August 24 2018)         January 14, 1897         1         Number 1           POSPECT 4         Visuan Development Final Feasibility Study January 1988         January 14, 1897         1         Number 1           POSPECT 4         Visuan Development Final Feasibility Study January 1988         January 14, 1897         1         Number 1           POSPECT 4         Visuan Development Final Feasibility Study Feasibility Study Feasibility Study         Magust 24, 2018         Number 1         Number 1           POSPECT 4         Visuan Development 2006         Post August 41 42010  |   | Proposed Bay d'Espoir Hydro Generating Unit 8<br>2 CLASS 3 COST ESTIMATE AND PROJECT EXECUTION<br>SCHEDULE         | March 22, 2018     | 00 SNC-Lavali         | n 647756-0000-40ER-I-0002 | 00 PDF   |
| ROSPECT 24Cut ARM DEVCLOPMENT ADDITION OF UNIT #3September 13, 19651BianwhortADDITION OF ATHIRD GENERATING UNIT CAT ARM2Addition of a Third Generating Unit, Cat ArmAugust 24, 20161N Li HydroADDITION OF ATHIRD GENERATING UNIT CAT ARM2Addition of a Third Generating Unit, Cat ArmAugust 24, 20181N Li HydroADDITION OF ATHIRD GENERATING UNIT ADDITION AND CAT ARM IT CAT ARMAugust 24, 20181N Li HydroPROSPECT 37Volume 1- ReportAugust 24, 20181N Li HydroPROSPECT 38N Li Hydro Edit CAT UDIVAugust 24, 2018N Li HydroPROSPECT 38N Li Hydro Edit ENUDYAugust 24, 2018N Li HydroPROSPECT 48N Li Hydro Edit ENUDYAugust 24, 2018N Li HydroPROSPECT 49N Li Hydro Edit EnudyAugust 24, 2018N Li HydroPROSPECT 49N Li Hydro Edit Enudy1Biand Hydroelectic Evoletic Project FNAL REPORTAugust 24, 2018N Li HydroPROSPECT 49N Li Hydro Edit Enudy1Biand Hydroelectic Evoletic Project FNAL REPORTAugust 24, 2018N Li HydroPROSPECT 491Biand Prod Hydroelectic Evoletic Project FNAL REPORTAugust 24, 2018N Li Hydro<  |   | Final Report for Hydrology and Feasibility Study for Potential<br>Bay d'Espoir Hydroelectric Generating Unit No. 8 | December 11, 2020  | 0 Hatch               | H363582-00000-228-230-(   | 001 PDF  |
| ADDITION OF A THIRD GENERATING UNIT CAT ARM         5         dedition of a Third Generating Unit, Cat Amm         August 24, 2018         -         N L. Hydro           6         Cat Arm Unit #3 Cost Estimate (August 24, 2018)         August 24, 2018         -         N L. Hydro           PROSPECT 3         7         Valume 1- Report         August 24, 2018         -         N L. Hydro           PROSPECT 3         7         Island Pond Development Final Feasibility Study January 1988         January 14, 1997         -         N Laydon           PROSPECT 3         Nume 1- Report         Bar L- Report         January 14, 1997         -         N Laydon           PROSPECT 4         Exchantic Valuation About Cost Curbon About Apdroslectric Projectis         May 2012         P N L-Lavalin           10         Public Cost Estimates         Nand And Cost Cost Cost Cost Cost Cost Cost Cost   | PROSPECT 2  | 4 CAT ARM DEVELOPMENT ADDITION OF UNIT # 3   | September 13, 1985 | - ShawMont            | Report No. SMR-30-85      | PDF      |
| Image: constant is a constant in the constant is a constant in the constant is a constant in the  | ADDITION OF A THIRD GENERATING UNIT CAT ARM         | 5 Addition of a Third Generating Unit, Cat Arm   | August 24, 2018    | - NL Hydro            |                           | MS Word  |
| ROSPECT3         7         Island Pond Development Final Feasibility Study January 1988         1   |   | 6 Cat Arm Unit #3 Cost Estimate (August 24 2018)   | August 24, 2018    | - Unspecified         | •                         | MS Excel |
| Report Number         Report         Report Number         Report Number </th <th>PROSPECT 3<br/>ISLAND POND HYDROELECTRIC DEVELOPMENT</th> <td>7 Island Pond Development Final Feasibility Study January 198<br/>Volume 1 – Report</td> <td>8 January 1988</td> <td>- ShawMont</td> <td>Report No. SMR-02-88</td> <td>PDF</td>   | PROSPECT 3<br>ISLAND POND HYDROELECTRIC DEVELOPMENT | 7 Island Pond Development Final Feasibility Study January 198<br>Volume 1 – Report                                 | 8 January 1988     | - ShawMont            | Report No. SMR-02-88      | PDF      |
| Problem         Production         Productio  |   | ISLAND POND / GRANITE CANAL<br>RE-OPTIMIZATION AND COST UPDATE STUDY   | January 14, 1997   | - AGRA Shav           | vMont SMR-05-96           | PDF      |
| Image: content of the set of the |   | 9 Studies for Island Pond Hydroelectric Project FINAL REPOR  | . December 2006    | - SNC-Lavali          | n Project No. 722720      | PDF      |
| 12Island Pond Hydroelectric DevelopmentAugust 29, 2018cNL Hydro12Island Pond CADD PictureUnspecifiedcUnspecifiedc13Reasibility Study13Reasibility StudyEebruary 1989cDepcified14Round Pond Hydroelectric Development Undate of the 1988May 7, 2012cHatch15Round Pond Cost Estimate (letter report)2018cUnspecified16Interconnection Requirements - Supply Adequacy HydroEebruary 26, 2018cNL Hydro17Prod Dond Hydroelectric DevelopmentMay 14, 2018may 14, 2018cNu Hydro  |   | Portland Creek and Island Pond Hydroelectric Projects<br>Update Cost Estimates                                     | May 2012           | PA SNC-Lavali         | n 501325-40ER-0001-PA     | PDF      |
| 12       Island Pond CADD Picture       Unspecified       -       Unspecified       -       Unspecified         PROSPECT 4       13       Feasibility Study       13       Feasibility Study       Eebruary 1989       -       Dispecified         Round Pond Pond Pond Development Summary Report       14       Round Pond Hydroelectric Development – Update of the 1988       May 7, 2012       -       Hatch         15       Round Pond Cost Estimate (letter report)       2018       -       2018       -       Unspecified         16       Interconnection Requirements - Supply Adequacy Hydro       February 26, 2018       -       NL Hydro         17       Proud Pond Pond Hydroelectric Development       May 14, 2018       -       N L Hydro         17       Proud Pond Hydroelectric Development       May 14, 2018       -       N L Hydro         17       Proud Pond Hydroelectric Development       May 14, 2018       -       N L Hydro  |   | 1 Island Pond Hydroelectric Development  | August 29, 2018    | - NL Hydro            | 1                         | MS Word  |
| PROSPECT 4         13         Feasibility Study         NL Hydro Endination         14         Protein February 1989         1         NL Hydro Endination         NL Hydro           17         Interconnection Requirements - Supply Adequacy Hydro         February 26, 2018         -         NL Hydro           17         Pround Doud Hydroelectric Develorment         May 14, 2018         -         Nator Energy   |   | 2 Island Pond CADD Picture   | Unspecified        | - Unspecified         |                           | MS Word  |
| 14Round Pond Hydroelectric Development – Update of the 1988<br>Cost Estimate (letter report)May 7, 2012-Hatch15Round Pond Cost Estimate<br>Interconnection Requirements - Supply Adequacy Hydro2018Unspecified16Interconnection Requirements - Supply Adequacy HydroFebruary 26, 2018-NL Hydro17PROJECT PROPOSAL SUMMARYMay 14, 2018-Nalcor Energy  | PROSPECT 4<br>ROUND POND HYDROELECTRIC DEVELOPMENT  | Beasibility Study<br>Round Pond Development Summary Report   | February 1989      | - NL Hydro E<br>Dept. | ngineering                | PDF      |
| 15     Round Pond Cost Estimate     2018     -     Unspecified       16     Interconnection Requirements - Supply Adequacy Hydro     February 26, 2018     -     NL Hydro       17     PROJECT PROPOSAL SUMMARY     May 14, 2018     -     Nalcor Energy  | -   | Round Pond Hydroelectric Development – Update of the 198<br>Cost Estimate (letter report)                          | 3 May 7, 2012      | - Hatch               | H341357-0000-00-218-000   | 1 PDF    |
| 16     Interconnection Requirements - Supply Adequacy Hydro     February 26, 2018     -     NL Hydro       17     PROJECT PROPOSAL SUMMARY     May 14, 2018     -     Nalcor Energy   |   | 5 Round Pond Cost Estimate   | 2018               | - Unspecified         |                           | MS Excel |
| PROJECT PROPOSAL SUMMARY         May 14, 2018         -         Nalcor Energy   |   | 6 Interconnection Requirements - Supply Adequacy Hydro<br>Alternatives (pp. 19-27)                                 | February 26, 2018  | - NL Hydro            | Doc #: TP-TN-023          | PDF      |
|   | -   | PROJECT PROPOSAL SUMMARY<br>Round Pond Hydroelectric Development   | May 14, 2018       | - Nalcor Ene          |                           | MS Excel |
| 18 Round Pond Hydroelectric Development August 30, 2018 - NL Hydro  | -   | 8 Round Pond Hydroelectric Development   | August 30, 2018    | - NL Hydro            |                           | MS Word  |
| 19 Round Pond Transmission Estimate Unspecified - Unspecified   |   | 9 Round Pond Transmission Estimate   | Unspecified        | - Unspecified         | 1                         | PDF      |

PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 39 of 158

 APPENDIX A
 Revision

 SNC+LAVALIN
 BOCUMENT REVIEW
 Rev
 Date
 Page

 SNC+LAVALIN
 SLI Doc. No. 691499-0000-40ER-I-0001
 00
 10-OCT-2022
 A-2

|    |   |                   | 0)   | LI Doc. No. 691499-0000-40 | DER-I-0001 00                   | 10-OCT-2022 | A-3 |
|----|---|-------------------|------|----------------------------|---------------------------------|-------------|-----|
|    |   |                   |      |                            |                                 |             | 1   |
|    |   |                   |      |                            |                                 |             |     |
|    | DOCUMENT TITLE  | DATE              | REV. | AUTHOR(S)                  | DOCUMENT / PROJECT NC           | ). TYPE     |     |
| 20 | Feasibility Study for Portland Creek Hydroelectric Project  | January 2007      | ı    | SNC-Lavalin                | Project No. 722736              | PDF         |     |
| 21 | See item 10 for Prospect 3 above  |                   | -    |                            |                                 | -           |     |
| 22 | Portland Creek Cost Estimate  | 2018              | •    | Unspecified                | I                               | MS Excel    |     |
| 23 | Interconnection Requirements - Supply Adequacy (pp. 28-37)  | February 26, 2018 | •    | NL Hydro                   | Doc #: TP-TN-023                | PDF         |     |
| 24 | PORTLAND CREEK INTERCONNECTION  | April 12, 2018    | A    | NL Hydro                   | (drawing PCKTS Rev A.skf)       | PDF         |     |
| 25 | PROJECT PROPOSAL SUMMARY Portland Creek   | May 14, 2018      | I    | Nalcor                     | ı                               | MS Excel    |     |
| 26 | Portland Creek Hydroelectric Development  | August 29, 2018   | T    | NL Hydro                   | I                               | MS Word     |     |
| 27 | DRAWING Plan of Damsite Badger Chute (1 p.)   | 7-12-1933         | 1    | Anglo-Newfoundland         | 1571 D                          | PDF         |     |
|    | PROPOSED 20,000 H.P. HYDRO-ELECTRIC POWER PLANT<br>AT RED INDIAN FALLS PRELIMINARY ESTIMATE (2 pp.)                         | October 31, 1957  | I    | Anglo-Newfoundland         | ı                               | PDF         |     |
| 28 | MEMO Notes on Completion of Construction and Operation of Surge Tank (5 pp.)  | August 12, 1958   | I    | E.R. Davis                 | File 1904                       | PDF         |     |
| 29 | PRELIMINARY EVALUATION OF POWER REQUIREMENTS<br>AND SOURCES (9 pp.)   | January 14, 1959  | I    | E.R. Davis                 | Report No. 1915                 | PDF         |     |
| 30 | EXPLOITS RIVER HYDRO INVENTORY STUDY (88 pp.)   | February 29, 1980 | I    | ShawMont                   | SMR-11-79                       | PDF         |     |
| 31 | LETTER Badger Chute Hydroelectric Development (5 pp.)   | February 15, 2002 | ı    | AMEC                       | I                               | PDF         |     |
| 32 | LETTER Badger Chute   | February 20, 2002 | T    | American Hydro Corp        | Inquiry Number 2491             | PDF         |     |
| 33 | Exploits River Hydro Potential (Red Indian Falls, Badger Chute<br>& Four Mile Pond) Preliminary Project Assessment (12 pp.) | January 28, 2005  | I    | NL Hydro                   |                                 | PDF         |     |
| 34 | Exploits River Projects Preliminary Results (1 p.)  | February 14, 2005 | 1    | NL Hydro                   | ı                               | PDF         |     |
| 35 | Minutes of Meeting Exploits River Hydro Potential (18 pp.)  | February 23, 2005 | I    | SGE Acres                  | I                               | PDF         |     |
| 36 | Badger Chute Hydro Development Capital Cost Estimate  | April 18, 2018    | 1    | NL Hydro                   | ı                               | MS Excel    |     |
| 37 | Badger Chute Hydro Development Capital Cost Estimate  | August 24, 2018   | I    | NL Hydro                   | Revision to April 18, 2018 file | MS Excel    |     |
| 38 | Transmission Planning Direction for Supply Adequacy Study   | July 25, 2018     | 1    | NL Hydro                   | E-mail by Robert Collett        | PDF         |     |
| 39 | Exploits River Hydroelectric Generation Expansion   | September 5, 2018 | I    | NL Hydro                   | I                               | MS Word     |     |
| 40 | System Adequacy Study Data Request – Hydro Expansion  | 2018              | ı    | NL Hydro                   |                                 | MS Excel    |     |
| 41 | EXPLOITS RIVER HYDRO INVENTORY (1 p.)   | Unspecified       | I    | Unspecified                | I                               | PDF         |     |
| 42 | EXPLOITS RIVER POTENTIAL GENERATION SITES REVIEW  | Unspecified       |      | Unspecified                |                                 | PDF         |     |

Page

Date Revision

Rev

APPENDIX A DOCUMENT REVIEW

 $\widehat{\mathbf{A}}$ 

## PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review

Page 40 of 158

| PROSPECT 5<br>PORTLAND CREEK HYDROELECTRIC DEVELOPMENT<br>PROSPECT 6<br>EXPLOITS RIVER HYDROELECTRIC DEVELOPMENTS<br>• RED INDIAN FALLS<br>• BADGER CHUTE |  |
|---|--|
|---|--|

|                    | APPENDIX B                           |     | Revision    |      |
|--------------------|--------------------------------------|-----|-------------|------|
|                    | COST AND SCHEDULE CLASSIFICATIONS    | Rev | Date        | Page |
| <b>SNU·LAVALIN</b> | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | B-1  |

# **APPENDIX B**

### COST AND SCHEDULE CLASSIFICATIONS

SNC-Lavalin Inc.

| •))                |
|--------------------|
| <b>SNC·LAVALIN</b> |

 APPENDIX B
 Revision

 COST AND SCHEDULE CLASSIFICATIONS
 Rev
 Date
 Page

 SLI Doc. No. 691499-0000-40ER-I-0001
 01
 21-OCT-2022
 B-2

### **TABLE OF CONTENTS**

| 1. OVERVIEW                | B-3 |
|----------------------------|-----|
| 2. COST ESTIMATING CLASSES | B-3 |
| 3. SCHEDULE LEVELS         | B-8 |

|             | APPENDIX B                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | COST AND SCHEDULE CLASSIFICATIONS    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | B-3  |

### 1. OVERVIEW

As part of the Generation Expansion Screening Study, cost estimates from 2018 were escalated to year-end 2022 for each of the prospects and overall project development timelines and construction schedules prepared. Classifications can be helpful in describing the level of accuracy and detail of cost and schedule estimates.

Cost estimates are typically classified using the AACE system (see below), with Class 5 being the lowest accuracy and preparation effort) and Class 1 being the highest accuracy and preparation effort.

Schedules, however, are typically classified by levels, starting with Level 1 (highest-level rollup of information) through to Level 5 or higher (very detailed information). Unlike the AACE system for cost estimates, schedule classifications are more subjective (see **SECTION 3.** below).

### 2. COST ESTIMATING CLASSES

Cost estimate classification is based on the Association for Advancement of Cost Engineering (AACE) *Cost Estimate Classification System.* In **TABLE B-1** below, the "Maturity Level of Project Definition Deliverables" aligns with the "% Complete" attribute used in the Gap Analysis.

Note that a Class 3 estimate has an End Usage of "Budget authorization or control", and is the minimum class usually required for Project Sanction (Gate 3) in the Decision Gate process (see **Main Report SECTION 3.2**).

|                | Primary<br>Characteristic  |   | Secondary Characteristic                                |   |  |  |  |  |  |
|----------------|--|---|---|---|--|--|--|--|--|
| ESTIMATE CLASS | MATURITY LEVEL<br>OF PROJECT<br>DEFINITION<br>DELIVERABLES<br>Expressed as % of<br>complete definition | END USAGE<br>Typical purpose of<br>estimate | <b>METHODOLOGY</b><br>Typical estimating<br>method      | EXPECTED<br>ACCURACY<br>RANGE<br>Typical +/- range<br>relative to index of 1<br>(i.e. Class 1 estimate) | PREPARATION<br>EFFORT<br>Typical degree of<br>effort relative to least<br>cost index of 1 <sup>[0]</sup> |  |  |  |  |
| Class 5        | 0% to 2%   | Screening or<br>feasibility                 | Stochastic<br>(factors and/or<br>models) or<br>judgment | 4 to 20   | 1  |  |  |  |  |
| Class 4        | 1% to 15%  | Concept study or<br>feasibility             | Primarily<br>stochastic                                 | 3 to 12   | 2 to 4   |  |  |  |  |
| Class 3        | 10% to 40%   | Budget<br>authorization or<br>control       | Mixed but<br>primarily<br>stochastic                    | 2 to 6  | 3 to 10  |  |  |  |  |
| Class 2        | 30% to 75%   | Control or<br>bid/tender                    | Primarily<br>deterministic                              | 1 to 3  | 5 to 20  |  |  |  |  |
| Class 1        | 65% to 100%  | Check estimate<br>or bid/tender             | Deterministic   | 1   | 10 to 100  |  |  |  |  |

### TABLE B-1 AACE COST ESTIMATE CLASSIFICATION SYSTEM

(Recommended Practice No. 18R-97 Rev. August 7, 2020)

Notes: [a] If the range index value of "1" represents +10/-5%, then an index value of 10 represents +100/-50%.

[b] If the cost index value of "1" represents 0.005% of project costs, then an index value of 100 represents 0.5%.

|             | APPENDIX B                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | COST AND SCHEDULE CLASSIFICATIONS    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | B-4  |

As per AACE, "Maturity Level of Project Definition Deliverables" is roughly indicated in Table B-1 by an approximate percentage of complete definition. However, it is the actual maturity of each deliverable that determines the overall maturity level of the estimate, not the percentage. This is best explained by AACE's summary checklist of basic deliverables typically found in the energy industry, reproduced in **TABLE B-2** below. The "Maturity Level" is the approximate completion status of the deliverable expected in each Cost Estimate Class according to the following descriptors.

### General Project Data

*Not Required (NR)* May not be required for all estimates of the specified class, but specific project estimates may require at least preliminary development.

- *Preliminary (P)* Project definition has begun and progressed to at least an intermediate level of completion. Review and approvals for its current status has occurred.
- *Defined (D)* Project definition is advanced, and reviews have been conducted. Development may be near completion with the exception of final approvals.

### **Technical Deliverables**

- Not Required (NR) Deliverable may not be required for all estimates of the specified class, but specific project estimates may require at least preliminary development.
- *Started (S)* Work on the deliverable has begun. Development is typically limited to sketches, rough outlines, or similar levels of early completion.
- *Preliminary (P)* Work on the deliverable is advanced. Interim, cross-functional reviews have usually been conducted. Development may be near completion except for final reviews and approvals.
- Complete (C) The deliverable has been reviewed and approved as appropriate.

There will, of course, be other deliverables specific to the individual scopes of work for projects in Hydro's portfolio. However, the list shown in Table B-2 is considered a good summary for the purposes of defining the level of Project Definition Maturity required to meet industry-standard "Pre-Sanction" requirements, i.e., at least a Class 3 estimate prior to Gate 3.

In situations where market conditions or technical uncertainty is high, it may be necessary to advance some deliverables to Class 2 standards. For example, it may be necessary to obtain bid pricing in order to reduce construction cost risk. This will require some deliverables, like earthworks, civil/structural, mechanical and/or electrical discipline drawings, to be near completion (i.e., Class 2 standard). The resulting "Maturity Level of Project Definition Deliverables" will, therefore, be approximately between Class 2 and Class 3 and the "% of complete definition" between Class 3: 10 to 40% and Class 2: 30 to 75%.

|             | APPENDIX B                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | COST AND SCHEDULE CLASSIFICATIONS    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | B-5  |

### TABLE B-2 AACE MATURITY LEVEL OF PROJECT DEFINITION DELIVERABLES

(after AACE International Technical Paper TCM-3747, 2021)

|  |          | EST           | IMATE CLASSIFIC | ATION      |             |
|--|----------|---------------|-----------------|------------|-------------|
| MATURITY LEVEL OF PROJECT<br>DEFINITION DELIVERABLES                 | CLASS 5  | CLASS 4       | CLASS 3         | CLASS 2    | CLASS 1     |
|  | 0% to 2% | 1% to 15%     | 10% to 40%      | 30% to 75% | 65% to 100% |
|  | GENERAL  | PROJECT DATA: |                 |            |             |
| A. SCOPE:  |          |               |                 |            |             |
| Project Scope of Work Description                                    | Р        | Р             | D               | D          | D           |
| Site Infrastructure (Access, Construction Power, Camp etc.)          | NR       | Р             | D               | D          | D           |
| B. CAPACITY:   |          |               |                 |            |             |
| Facility Output / Production Profile                                 | Р        | Р             | D               | D          | D           |
| Electrical Power Requirements (when not the primary capacity driver) | NR       | Р             | D               | D          | D           |
| C. PROJECT LOCATION:   |          | 8             | 0               |            | 0           |
| Plant and Associated Facilities                                      | Р        | Р             | D               | D          | D           |
| D. REQUIREMENTS:   |          |               |                 |            |             |
| Codes and/or Standards   | NR       | Р             | D               | D          | D           |
| Communication Systems  | NR       | Р             | D               | D          | D           |
| Fire Protection and Life Safety                                      | NR       | Р             | D               | D          | D           |
| Environmental Monitoring   | NR       | NR            | Р               | Р          | D           |
| E. TECHNOLOGY SELECTION:   |          |               |                 |            |             |
| N/A  |          |               |                 |            |             |
| F. STRATEGY:   |          | _             | _               |            |             |
| Contracting / Sourcing   | NR       | Р             | D               | D          | D           |
| Escalation   | NR       | Р             | D               | D          | D           |
| G. PLANNING:   | _        | _             | _               | _          | _           |
| Regulatory Approval & Permitting                                     | Р        | Р             | D               | D          | D           |
| Material Utilization (Borrow Sources)                                | Р        | Р             | P/D             | D          | D           |
| Logistics Plan   | Р        | Р             | Р               | D          | D           |
| Work Breakdown Structure   | NR/P     | Р             | P/D             | D          | D           |
| Decommissioning Plan   | NR       | Р             | D               | D          | D           |
| Integrated Project Plan <sup>1</sup>                                 | NR       | Р             | D               | D          | D           |
| Project Code of Accounts   | NR       | Р             | D               | D          | D           |
| Project Master Schedule  | NR       | Р             | D               | D          | D           |
| Risk Register  | NR       | Р             | D               | D          | D           |
| Stakeholder Consultation / Engagement /<br>Management Plan           | NR       | Р             | D               | D          | D           |
| Startup and Commissioning Plan                                       | NR       | P             | P/D             | D          | D           |

Continued...

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 46 of 158

|             | APPENDIX B                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | COST AND SCHEDULE CLASSIFICATIONS    | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | B-6  |

|   | ESTIMATE CLASSIFICATION |           |            |            |             |  |  |  |  |  |
|---|-------------------------|-----------|------------|------------|-------------|--|--|--|--|--|
| MATURITY LEVEL OF PROJECT<br>DEFINITION DELIVERABLES                          | CLASS 5                 | CLASS 4   | CLASS 3    | CLASS 2    | CLASS 1     |  |  |  |  |  |
|   | 0% to 2%                | 1% to 15% | 10% to 40% | 30% to 75% | 65% to 100% |  |  |  |  |  |
| H. STUDIES:   |                         |           |            |            |             |  |  |  |  |  |
| Hydraulics  | Р                       | Р         | D          | D          | D           |  |  |  |  |  |
| Topography and/or Bathymetry  | Р                       | Р         | P/D        | D          | D           |  |  |  |  |  |
| Environmental Impact / Sustainability<br>Assessment                           | NR                      | Р         | D          | D          | D           |  |  |  |  |  |
| Environmental / Existing Conditions   | NR                      | Р         | D          | D          | D           |  |  |  |  |  |
| Soils and Hydrology   | NR                      | Р         | D          | D          | D           |  |  |  |  |  |
| Geotechnical Investigation  | NR                      | Р         | P/D        | D          | D           |  |  |  |  |  |
| TECHNICAL DELIVERABLES:   |                         |           |            |            |             |  |  |  |  |  |
| Block Flow Diagrams   | S/P                     | С         | С          | С          | С           |  |  |  |  |  |
| Hydraulic Design and Probable Maximum<br>Flood (PMF)                          | s                       | Р         | с          | с          | с           |  |  |  |  |  |
| Equipment Datasheets  | NR/S                    | P         | С          | С          | С           |  |  |  |  |  |
| Equipment Lists: Electrical   | NR/S                    | P         | С          | С          | С           |  |  |  |  |  |
| Equipment Lists: Process / Utility /<br>Mechanical                            | NR/S                    | Р         | с          | c          | с           |  |  |  |  |  |
| Design Specifications   | NR                      | S/P       | С          | С          | С           |  |  |  |  |  |
| Electrical One-Line Drawings  | NR                      | S/P       | С          | С          | С           |  |  |  |  |  |
| General Equipment Arrangement<br>Drawings                                     | NR                      | S/P       | с          | с          | с           |  |  |  |  |  |
| Instrument List   | NR                      | S/P       | С          | С          | с           |  |  |  |  |  |
| Construction Permits  | NR                      | S/P       | P/C        | С          | С           |  |  |  |  |  |
| Civil / Site / Structural / Architectural<br>Discipline Drawings              | NR                      | S/P       | Р          | с          | с           |  |  |  |  |  |
| Demolition Plan and Drawings  | NR                      | S/P       | P          | С          | с           |  |  |  |  |  |
| Erosion Control Plan and Drawings   | NR                      | S/P       | P          | С          | С           |  |  |  |  |  |
| Fire Protection and Life Safety Drawings<br>and Details                       | NR                      | S/P       | Р          | с          | с           |  |  |  |  |  |
| Mitigation Measures (Aquatic, Terrestrial,<br>Avian, Clearing, Heritage etc.) | NR                      | s         | Р          | с          | с           |  |  |  |  |  |
| Dam Design & Drawings   | NR                      | S         | Р          | P/C        | C           |  |  |  |  |  |
| De-Silting Basins   | NR                      | S         | P          | P/C        | c           |  |  |  |  |  |
| Gates and Cranes Design & Drawings  | NR                      | S         | P          | P/C        | C           |  |  |  |  |  |
| Intake Design & Drawings  | NR                      | S         | P          | P/C        | С           |  |  |  |  |  |

\*The integrated project plan (IPP), project execution plan (PEP), project management plan (PMP), or more broadly the project plan, is a high-level management guide to the means, methods and tools that will be used by the team to manage the project. The term integration emphasizes a project life cycle view (the term execution implying post-sanction) and the need for alignment. The IPP covers all functions (or phases) including engineering, procurement, contracting strategy, fabrication, construction, commissioning and start-up within the scope of work. However, it also includes stakeholder management, safety, quality, project controls, risk, information, communication and other supporting functions. In respect to estimate classification, to be rated as defined, the IPP must cover all the relevant phases/functions in an integrated manner aligned with the project charter (i.e., objectives and strategies); anything less is preliminary. The overall IPP cannot be rated as defined unless all individual elements are defined and integrated.

Continued...

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 47 of 158

|               | APPENDIX B                           |     | Revision    |      |
|---------------|--------------------------------------|-----|-------------|------|
| SNC·LAVALIN - | COST AND SCHEDULE CLASSIFICATIONS    | Rev | Date        | Page |
|               | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | B-7  |

|   | ESTIMATE CLASSIFICATION |           |            |            |             |  |
|---|-------------------------|-----------|------------|------------|-------------|--|
| MATURITY LEVEL OF PROJECT<br>DEFINITION DELIVERABLES    | CLASS 5                 | CLASS 4   | CLASS 3    | CLASS 2    | CLASS 1     |  |
|   | 0% to 2%                | 1% to 15% | 10% to 40% | 30% to 75% | 65% to 100% |  |
| Penstock Design & Drawings                              | NR                      | S         | P          | P/C        | C           |  |
| Power House Design and Drawings                         | NR                      | S         | P          | P/C        | С           |  |
| Power Tunnel / Canal Design and<br>Drawings             | NR                      | s         | P          | P/C        | с           |  |
| Spillway Design & Drawings                              | NR                      | S         | P          | P/C        | С           |  |
| Turbine and Generator Design and<br>Drawings            | NR                      | s         | Р          | P/C        | с           |  |
| Electrical Schedules                                    | NR                      | NR/S      | P          | P/C        | С           |  |
| Instrument and Control Schedules                        | NR                      | NR/S      | P          | P/C        | С           |  |
| Instrument Datasheets                                   | NR                      | NR/S      | P          | P/C        | С           |  |
| Spare Parts Listings                                    | NR                      | NR        | P          | P/C        | С           |  |
| Electrical Discipline Drawings                          | NR                      | NR        | S/P        | P/C        | C           |  |
| Facility Emergency Communication Plan<br>and Drawings   | NR                      | NR        | S/P        | P/C        | с           |  |
| Information Systems /<br>Telecommunication Drawings     | NR                      | NR        | S/P        | P/C        | с           |  |
| Instrumentation / Control System<br>Discipline Drawings | NR                      | NR        | S/P        | P/C        | с           |  |
| Mechanical Discipline Drawings                          | NR                      | NR        | S/P        | P/C        | С           |  |
| Auxiliary Electrical Design & Drawings                  | NR                      | NR        | S          | P          | С           |  |
| Auxiliary Mechanical Design & Drawings                  | NR                      | NR        | S          | P          | С           |  |
| Protection & Controls System Design &<br>Drawings       | NR                      | NR        | S          | Р          | c           |  |
|               | APPENDIX B                           | Revision |             |      |
|---------------|--------------------------------------|----------|-------------|------|
| SNC · LAVALIN | COST AND SCHEDULE CLASSIFICATIONS    | Rev      | Date        | Page |
|               | SLI Doc. No. 691499-0000-40ER-I-0001 | 01       | 21-OCT-2022 | B-8  |

### 3. SCHEDULE LEVELS

Terms like "Level 2 Schedule" and "L4 Schedule" are sometimes used as a general description of project planning maturity, but this can be misleading. Schedule levels have evolved as a description of (1) the audience for whom the schedule is intended and (2) the level of detail within the schedule structure itself (**TABLE B-3**).

- Level 1 and Level 2 schedules are usually developed as part of conceptual or pre-feasibility studies for Program Management and financial decision-making purposes.
- A Level 3 schedule is usually first developed as a high-level critical path overview of a project and, if the project is relatively small, a Level 3 schedule can be expanded into a Level 4 schedule for coordinating the execution of the works. On larger or more complex projects with multiple Level 4 schedules, the Level 3 schedule is maintained as the project's overall integrated schedule.
- Every project that moves into the execution stage (i.e., past Gate 3) should have a Level 4 schedule for day-to-day coordination of activities that supports the Path of Construction (construction sequencing), complete with a Critical Path. It is good practice to keep Level 4 schedules to a manageable size, focused on the work in one management area.
- Level 5 schedules are generally for short-term activities and are the end-product of Workface Planning (WFP), used at the field level to plan and execute work shifts for construction crews and for review at tailgate meetings.

Given the project planning maturity of the Generation Expansion prospects considered in this study, the overall project development timelines and schedules are generally Level 1 (L1) or Level 2 (L2).

| LEVEL | NAME                          | DESCRIPTION   | MAIN AUDIENCE / USERS  |
|-------|-------------------------------|---|--|
| L1    | Milestone or Master Schedule  | Typically one page and highlights major activities and key deliverables.  | Owners, senior management,<br>stakeholders, bidders  |
| L2    | Management Summary            | Higher level summary of L3 activities<br>according to the WBS (Work<br>Breakdown Structure)   | Project and program<br>managers, project sponsors  |
| L3    | Project Coordination Schedule | Milestones and design, engineering,<br>procurement, construction,<br>commissioning and start-up   | Project or program managers,<br>construction managers,<br>Owners   |
| L4    | Working Level Schedule        | An expansion of L3, the key working<br>level schedule by Work Package,<br>usually developed by the contractor<br>and with Critical Path established | Functional managers,<br>discipline leads, project<br>engineers, construction<br>superintendents, foremen |
| L5    | Detailed Schedule             | An expansion of L4, used to plan<br>day-to-day work for crews based on a<br>1- to 2-week look-ahead   | Construction superintendents,<br>general foremen, foremen,<br>team members                               |

### TABLE B-3 SCHEDULE LEVEL DESCRIPTIONS

| •))            | F |
|----------------|---|
| SNC . LAVA LIN |   |
| SIL            |   |

| APPENDIX C                               |  |             |     |  |
|--|--|-------------|-----|--|
| PROSPECT OVERVIEWS, GAP ANALYSIS & RISKS | OVERVIEWS, GAP ANALYSIS & RISKS Rev Date |             |     |  |
| SLI Doc. No. 691499-0000-40ER-I-0001     | 01                                       | 21-OCT-2022 | C-1 |  |

# **APPENDIX C**

### PROSPECT OVERVIEWS, GAP ANALYSIS & RISKS

|                    | APPENDIX C                               | C Revision |             |      |
|--------------------|--|------------|-------------|------|
| <b>SNC·LAVALIN</b> | PROSPECT OVERVIEWS, GAP ANALYSIS & RISKS | Rev        | Date        | Page |
|                    | SLI Doc. No. 691499-0000-40ER-I-0001     | 01         | 21-OCT-2022 | C-2  |

### TABLE OF CONTENTS

| APPENDIX C-1 | PROSPECT 1 | Bay d'Espoir Hydro Generating Unit 8 C-3         |
|--------------|------------|--|
| APPENDIX C-2 | PROSPECT 2 | Addition of a Third Generating Unit Cat Arm C-22 |
| APPENDIX C-3 | PROSPECT 3 | Island Pond Hydroelectric Development C-36       |
| APPENDIX C-4 | PROSPECT 4 | Round Pond Hydroelectric DevelopmentC-53         |
| APPENDIX C-5 | PROSPECT 5 | Portland Creek Hydroelectric Development C-66    |
| APPENDIX C-6 | PROSPECT 6 | Exploits River Hydroelectric Developments C-81   |

# **APPENDIX C**

# **PROSPECT 1**

### **BAY d'ESPOIR HYDRO GENERATING UNIT 8**

PROSPECT OVERVIEW, GAP ANALYSIS & RISKS

|               | APPENDIX C – PROSPECT 1              | Revision |             |      |
|---------------|--------------------------------------|----------|-------------|------|
| SNC · LAVALIN | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev      | Date        | Page |
|               | SLI Doc. No 691499-0000-40ER-1-0001  | 01       | 21-OCT-2022 | C-4  |

### **TABLE OF CONTENTS**

| 1. | PROSPECT 1 OVERVIEW: BDE UNIT 8                            | C-6  |
|----|--|------|
|    | 1.1. LOCATION AND BACKGROUND                               | 6    |
|    | 1.2. PROJECT DESCRIPTION                                   | 7    |
|    | 1.3. PROPOSED LAYOUT                                       | 7    |
|    | 1.4. PROJECT EXECUTION TIMELINE                            | 7    |
|    | 1.5. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022) | 9    |
|    | 1.6. KEY TECHNICAL METRICS                                 | 9    |
| 2. | EXISTING PROJECT INFORMATION DATA GAP                      | C-10 |
|    | 2.1. OVERVIEW  | 10   |
|    | 2.2. DATA GAP  | 10   |
| 3. | SCOPE OF WORK TO COMPLETE FEEP STAGE                       | C-13 |
|    | 3.1. PURPOSE   | 13   |
|    | 3.2. OWNER'S FEEP-STAGE SCOPE OF WORK                      | 13   |
|    | 3.3. PROJECT TEAM FEEP-STAGE SCOPE OF WORK                 | 13   |
|    | 3.3.1. Project Management Discipline                       | 13   |
|    | 3.3.2. Environmental Discipline                            | 14   |
|    | 3.3.3. Engineering Discipline                              | 14   |
|    | 3.3.4. Procurement Discipline                              | 15   |
|    | 3.3.5. Construction Discipline                             | 15   |
| 4. | PROJECT-SPECIFIC RISKS                                     | C-17 |
|    | 4.1. ENVIRONMENTAL RISK                                    | 17   |
|    | 4.2. SOCIOECONOMIC INFLUENCES                              | 17   |
|    | 4.3. MARKET CONDITIONS                                     | 17   |
|    | 4.4. LONG-LEAD ITEMS RISK                                  | 17   |
|    | 4.5. TECHNICAL RISK  | 17   |
|    | 4.5.1. Hydrotechnical                                      | 17   |
|    | 4.5.2. Geotechnical  | 17   |
|    | 4.5.3. Technical Complexity                                | 18   |
|    | 4.6. PROJECT COST RISK                                     | 19   |
|    | 4.7. PROJECT SCHEDULE RISK                                 | 19   |

|               | APPENDIX C – PROSPECT 1              | Revision |             |      |
|---------------|--------------------------------------|----------|-------------|------|
| SNC · LAVALIN | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev      | Date        | Page |
|               | SLI Doc. No 691499-0000-40ER-1-0001  | 01       | 21-OCT-2022 | C-5  |

### 5. MINIMUM WORK REQUIRED TO UPDATE COST AND SCHEDULE C-20

| 5.1. PURPOSE AND OBJECTIVE                                      | 20 |
|---|----|
| 5.2. KEY OWNER DECISIONS REQUIRED                               | 20 |
| 5.3. REQUIREMENTS FOR UPDATING / COMPLETING THE 2018 FEEP STUDY | 20 |
| 5.4. TIMING CONSIDERATIONS                                      | 21 |

|                    | APPENDIX C – PROSPECT 1              | Revision |             |      |
|--------------------|--------------------------------------|----------|-------------|------|
| <b>SNC·LAVALIN</b> | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev      | Date        | Page |
|                    | SLI Doc. No 691499-0000-40ER-1-0001  | 01       | 21-OCT-2022 | C-6  |

### 1. PROSPECT 1 OVERVIEW: BDE UNIT 8

### 1.1. LOCATION AND BACKGROUND

Located in South Central Newfoundland (**FIGURE C1.1**), Bay d'Espoir Phase 1 consisted of six (6) x 75 MW turbine generating units in one (1) powerhouse completed in 1967.

Phase 2 consisted of a second powerhouse built to house one (1) x 150 MW generating unit ("Unit 7"), completed in 1977. The structure and tailrace were built to facilitate the extension of the powerhouse to accommodate Unit 8.

In 2018, Newfoundland and Labrador Hydro ("Hydro") commissioned SNC-Lavalin ("SLI") to study the addition of an eighth (8<sup>th</sup>) 150 MW generating unit ("Unit 8") by expanding the second powerhouse ("2018 SLI study").<sup>1</sup>



FIGURE C1.1 LOCATION AND EXISTING FACILITIES BAY D'ESPOIR

<sup>&</sup>lt;sup>1</sup> Bay d'Espoir Hydro Generating Unit 8 CLASS 3 COST ESTIMATE AND PROJECT EXECUTION SCHEDULE. SNC-Lavalin Doc. 647756-0000-40ER-I-0002-00, March 22, 2018.

|                    | APPENDIX C – PROSPECT 1              | APPENDIX C – PROSPECT 1 Revision |             |      |
|--------------------|--------------------------------------|----------------------------------|-------------|------|
| <b>SNC·LAVALIN</b> | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev                              | Date        | Page |
|                    | SLI Doc. No 691499-0000-40ER-1-0001  | 01                               | 21-OCT-2022 | C-7  |

### 1.2. PROJECT DESCRIPTION

The proposed project consists of the following major facilities.

- Generation Facility
- Water Conveyance System
- Transmission Facilities

The Generation Facility consists of a new Powerhouse adjoined to existing Powerhouse 2, with a 150 MW Francis Turbine Generator, main transformer, isolated phase bus, auxiliary mechanical/electrical equipment, control and protection equipment, fire protection system, hydro-mechanical equipment, etc. The new unit will be built in the existing excavation, upstream of the Unit 8 Draft Tube Outlet, built as a part of the original Powerhouse No. 2.

The Water Conveyance System consists of an enlarged headrace channel, a new water intake resembling the Unit 7 intake, a new buried steel penstock, widening of the tailrace, and installation of further erosion protection in the tailrace channel.

Transmission Facilities consist of a 1.9 km high-voltage 230 kV line from Unit 8 step-up transformer to Terminal Station No. 2, plus modifications to Terminal Station No. 2 and a new sub-station. The new facility will utilize the existing powerhouse forebay and does not require the construction of any dams.

### 1.3. PROPOSED LAYOUT

The proposed layout for Unit 8 is reproduced in **FIGURE C1.2** below.

### 1.4. PROJECT EXECUTION TIMELINE

The Overall Development Timeline is based on a typical Brownfield project schedule basis and incorporates the project schedule provided in the 2018 SLI study and allowance of an additional 11 months for Long-Lead delivery times. One (1) year has been assumed for the Environmental Approval Process and total estimated project duration is 5.8 years.

A more detailed analysis of project timelines for Unit 8 was provided separately in the report *Bay d'Espoir Hydro Generating Unit 8 COMPARATIVE PROJECT SCHEDULES FOR ASSESSMENT OF CONTRACTING STRATEGY ALTERNATIVES*. SLI Document No. 691499-0000-40ER-I-0002 Rev PA, September 2022.

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 56 of 158

|             | APPENDIX C – PROSPECT 1              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No 691499-0000-40ER-1-0001  | 01  | 21-OCT-2022 | C-8  |



Powerhouse Extension & Penstock



Headrace, Intake & Penstock

### FIGURE C1.2 PROPOSED LAYOUT FOR BAY D'ESPOIR UNIT 8

(from Bay d'Espoir Hydro Generating Unit 8 CLASS 3 COST ESTIMATE AND PROJECT EXECUTION SCHEDULE. SNC-Lavalin Doc. 647756-0000-40ER-I-0002-00, March 22, 2018.)

|             | APPENDIX C – PROSPECT 1              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No 691499-0000-40ER-1-0001  | 01  | 21-OCT-2022 | C-9  |

### 1.5. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022)

The 2018 cost estimate for Unit 8 was escalated to YE-2022 as shown in TABLE C1-1.

### TABLE C1-1: UNIT 8 COST ESTIMATE ESCALATED TO YE-2022

| COST ITEM   | AMOUNT        | NOTES  |
|---|---------------|--|
| Direct Cost   | \$180,345,823 | Material, labour, equipment, salaries, benefits, rentals, subcontractors, travel, etc.   |
| Indirect Cost                                       | \$94,764,963  | 52% of Direct Cost   |
| Contingency   | \$59,446,527  | P- 80: 22.5% of Construction Cost  |
| Escalation during Construction                      | \$20,304,583  | Average of 2.8% per year   |
| Total Base Budget (2018)                            | \$354,861,896 |  |
| Capitalized Interest                                | \$30,806,789  | @ 6.41% per year   |
| Total Cost (2018)                                   | \$393,668,684 |  |
| Escalation calculation (2018-2022)                  | 132.5%        | 2019: 2.2% 2020: 1.2% 2021: 11.4%<br>Statistics Canada Construction Cost Index<br>(CCPI) |
|   |               | 2022: 15%<br>Projection by SLI Cost Estimating Department                                |
| 2022 TOTAL ESCALATED COST                           | \$521,637,506 |  |
| AACE Estimate Accuracy<br>(Index of 1 = +10% / -5%) | +40% / -20%   | Class 3 accuracy index range = 2 to 6<br>Index for this estimate assumed = 4             |

### 1.6. KEY TECHNICAL METRICS

The following metrics were developed from the above information for the Screening and Ranking Process.

- Power (MW Installed): One (1) x 150 MW Francis Turbine Generator
- Cost per MW of Power (escalated to YE-2022): \$3.5 million / MW
- Overall Project Duration : 5.8 Years

| Planning Timeline:                 | 2.3 Years  |
|------------------------------------|--|
| Execution (Construction) Timeline: | 4.5 Years  |
| Less Overlap Planning/Execution:   | <u>-1.0 Year</u>   |
|                                    | Planning Timeline:<br>Execution (Construction) Timeline:<br>Less Overlap Planning/Execution: |

Overall Development Timeline: 5.8 Years

|             | APPENDIX C – PROSPECT 1              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No 691499-0000-40ER-1-0001  | 01  | 21-OCT-2022 | C-10 |

### 2. EXISTING PROJECT INFORMATION DATA GAP

### 2.1. OVERVIEW

By definition, a "Gap Analysis" is the comparison of a "current state" against a "future state" or "desired state". For this study, a Gap Analysis was performed to identify differences between the "current state" of Project Planning maturity against the "desired state" of Project Planning maturity required to meet industry standard.

Two (2) key deliverables from the SLI study were used as a basis for this Gap Analysis, as follows.

- Hydraulic Analysis of Water Conveyance System
- Class 3 Cost Estimate and Project Execution Schedule

Also considered was the Hydrology and Feasibility Study for Potential Bay d 'Espoir Hydroelectric Generating Unit No. 8 (Hatch, 2020). All relevant documents are listed in **APPENDIX A** to the main report.

**SECTION 3.3** of the Main Report summarizes the deliverables, by discipline, necessary to complete *Front-End Execution Planning (FEEP)* for a project of this nature. This level of planning is considered the industry standard for investment decision making. This section compares the existing project documentation to that of a FEEP-level requirement and identifies the data gaps. Data Gap

### 2.2. DATA GAP

The 2018 work by SLI was to define the project and estimate the costs and timeline to execute. To advance this work to a *Front-End Execution Planning (FEEP) standard*, the following gaps remain (see **TABLE C1-2**).

|                         | Page                                 | C-11                                |
|-------------------------|--------------------------------------|-------------------------------------|
| Revision                | Date                                 | 21-OCT-2022                         |
|                         | Rev                                  | 01                                  |
| APPENDIX C – PROSPECT 1 | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | SLI Doc. No 691499-0000-40ER-1-0001 |
|                         |                                      | SNC+LAVALIN                         |

# TABLE C1-2: GAP ANALYSIS FOR PROSPECT 1: BDE UNIT 8

| STAGE 1: PROJECT<br>DEFINITION |                                   |  |
|--------------------------------|-----------------------------------|--|
| RESPONSIBLE GROUP              | DELIVERABLE                       | REQUIREMENTS TO ADDRESS GAP  |
|                                | PROJECT DEFINITION STATEMENT      | Complete   |
| Owner / Corporate              | PROJECT CHARTER                   | Develop Project Charter as per standard for internal approval and sign-off, including recommended Contracting Strategy.<br>Develop the Environmental Management Strategy.<br>Approve FEEP-Stage Budget, Deliverables List, and Milestone Schedule. |
| STAGE 2: FEEP                  |                                   |  |
| RESPONSIBLE GROUP              | DELIVERABLE                       | REQUIREMENTS TO ADDRESS GAP  |
|                                | PROJECT EXECUTION PLAN (PEP)      |  |
|                                | Scope of Work                     | Based on the Scope of Work outlined in existing documentation, and the design optimizations to be prepared, prepare an updated Project Scope of Work Document (SOW) and Work Breakdown Structure (WBS).  |
|                                | Project Management Strategy       | Key elements of the execution strategy will need to be reviewed and updated based on the selected Project Delivery Model.  |
|                                | Project Controls Strategy         | Determine how cost estimating and schedule development activities are going to be coordinated.   |
| Project Management             | Health & Safety Strategy          | Prepare HS&S Project Strategy.   |
|                                | QA / QC Strategy                  | Prepare Quality Management Strategy.   |
|                                | PROJECT CONTROLS DOCUMENTATION    |  |
|                                | Cost Estimate (Class 4 / Class 3) | Update Cost Estimate based on updated Contracting Strategy, Schedule, Design Optimizations, updated Unit Costs and costs for Long-Lead Items, and the cost of implementing the Environmental Protection Plan. Prepare Monte Carlo Simulation.      |
|                                | Schedule                          | Prepare Level 2 (L2) Schedule based on Updated MTOs, Timelines for Long-Lead Items, Environmental Timelines, Construction Sequencing, and Contracting Strategy.  |

| nc.      |  |
|----------|--|
| -Lavalin |  |
| SNC.     |  |

|                         | Page  | C-12                                |
|-------------------------|---|-------------------------------------|
| Revision                | Date  | 21-OCT-2022                         |
|                         | Rev   | 01                                  |
| APPENDIX C – PROSPECT 1 | <b>BAY d'ESPOIR HYDRO GENERATING UNIT 8</b> | SLI Doc. No 691499-0000-40ER-1-0001 |
|                         |   | SNC+LAVALIN                         |

|                         | ENVIRONMENTAL MANAGEMENT PLAN    | Based on the Environmental Management Strategy, develop a detailed Management Plan.   |
|-------------------------|----------------------------------|---|
| спулоплена манаделнен.  | PROJECT REGISTRATION / EIS       | Identify key concerns, conduct Field Investigations, identify impacts and mitigations, prepare and submit Project Registration.   |
|                         | FACILITY SCOPE OF WORK           | Based on the Design Optimizations (Line 18), and revised MTOs, update the Scope of Work for each Facility.  |
|                         | PRELIMINARY ENGINEERING          | Review the 2018 preliminary designs and finalize the scope of work for the field program.   |
|                         | FIELD INVESTIGATIONS SOW         | Define a detailed Scope of Work for the Field Investigation Program.  |
| Engineering             | DESIGN OPTIMIZATIONS             | Optimize the 2018 preliminary designs based on results of the Field Investigation Program.  |
|                         | UPDATED PRELIMINARY ENGINEERING  | Complete preliminary design based on the optimizations.   |
|                         | MTOS                             | Update the Facility MTOs and the quantities in the cost estimate and schedule duration calculations, based on updated Preliminary Engineering.                                      |
|                         | CONTRACTING STRATEGY             | Based on Hydro's selected Contracting Strategy, prepare a Project Contracting Strategy document, identify standard contract documentation and procurement processes.                |
| Supply Chain Management | <b>BID &amp; EVALUATION PLAN</b> | Prepare a plan which documents standard contract documentation and the bid management process, including bid evaluation plans, approval authorities, etc.                           |
|                         | LONG-LEAD ITEMS VENDOR PACKAGES  | Co-ordinate Vendor Packages based on Engineering input.   |
|                         | FIELD INVESTIGATIONS PLAN        | Authorize the Field Investigation Program.  |
|                         | CM STRATEGY                      | Prepare a Field Investigation Program Execution Plan based on the Scope of Work prepared by engineering. Prepare Construction Management<br>Plan based on the Contracting Strategy. |
| Construction            | PATH OF CONSTRUCTION             | Undertake Construction Planning activities necessary to develop the Path of Construction (sequencing).  |
|                         | CONSTRUCTION SCHEDULE            | Based on the Path of Construction, update construction schedule.  |
|                         |                                  |   |

|             | APPENDIX C – PROSPECT 1              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No 691499-0000-40ER-1-0001  | 01  | 21-OCT-2022 | C-13 |

### 3. SCOPE OF WORK TO COMPLETE FEEP STAGE

### 3.1. PURPOSE

This section outlines the scope of work ("SOW") necessary to advance the 2018 SLI study to meet industrystandard FEEP-level documentation requirements for this prospect, including updates to cost and schedule.

### 3.2. OWNER'S KEY INPUTS

At the start of the FEEP stage, it is recommended that the Owner provide the Project Team(s) with a Project Charter, approved Environmental Management Strategy, and approved FEEP Stage Budget, Deliverables List and Milestone Schedule.

In addition, if time is of the essence, both the Owner and Project Team(s) could, during the standard Public Utilities Board ("PUB") review, jointly undertake the risk mitigation proposals in **SECTION 5**.

### 3.3. PROJECT DEFINITION STATEMENT UPDATE SCOPE OF WORK

The BDE Unit 8 prospect will not require an update to the Project Definition Statement. (All other prospects will require an update.)

### 3.4. PROJECT TEAM FEEP-STAGE SCOPE OF WORK

### 3.4.1. Project Management Discipline

The key Project Management Team deliverable is a *<u>Front-end Execution Plan (FEEP)</u>*, which incorporates the following key documentation.

- Based on the scope of work outlined in existing documentation, and the design optimizations to be prepared (see 3.3.3. Engineering below), prepare an updated <u>Project Scope of Work Document</u> (SOW) and <u>Work Breakdown Structure</u> (WBS).
- Based on the updated scope of work, prepare a Front-End Execution Plan (FEEP). Key aspect of the FEEP is the contracting strategy which details the project delivery model, compensation model, and sourcing strategy.
- Based on the SOW and WBS, develop the following key sections of the FEEP:
  - Project Management Approach
  - Project Controls Strategy
  - Health, Safety and Security
  - Quality Management Strategy
- Coordinate the preparation of the following by other disciplines.
  - Environmental Management Plan
  - Engineering Management Plan
    - Procurement Management Strategy
    - Contracting Strategy
    - Construction Management Strategy
    - Construction Sequencing Plan

|             | APPENDIX C – PROSPECT 1              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No 691499-0000-40ER-1-0001  | 01  | 21-OCT-2022 | C-14 |

- Work Packaging Plan

- Coordinate the preparation of the following Project Controls Documentation.
- Using the existing schedule data, revised WBS and Work Packaging Plan, develop and optimize a <u>L3 Project Schedule and Schedule Basis</u>, incorporating EIA and Long-Lead timelines provided by vendors. The <u>Level 3 (L3) Project Schedule should include</u>:
  - L4 Project Management Schedule and Schedule Basis
  - L4 Environmental Management Schedule and Schedule Basis
  - L4 Engineering Management Schedule and Schedule Basis
  - L3 Bid Stage Schedule and Schedule Basis
  - L3 Construction Schedule and Schedule Basis with Monte Carlo Simulation which incorporates updated Long-Lead Items delivery timelines
  - L4 Field Investigation Plan and Schedule Basis
- <u>Class 3 Cost Estimate, Estimate Basis, and Risk Analysis</u>, e.g., Monte Carlo Simulation. Update the existing Cost Estimate based on updated WBS / Work Package Plan, the facility optimizations, and revisions to the indirect scope of work, plus updated unit, and material / equipment cost.

Note: At the present stage of planning, the following key timelines and impacts remain unknown.

- Environmental Approval Process and relates impacts on cost and schedule.
- Owner's Planning and Approval Process.
- Detailed Engineering Resource availability.
- Major Equipment availability and cost.

### 3.4.2. Environmental Discipline

The Environmental discipline shall:

- Prepare an Environmental Management Plan.
- Prepare a robust Environmental Registration Document.

### 3.4.3. Engineering Discipline

The engineering discipline shall:

- Prepare a <u>Scope of Work for Field Investigation Program</u> for immediate execution by Construction, including the preparation and submission of applications for permits to carry out the field work.
- Prepare and implement an <u>Engineering Management Plan</u>, including <u>L4 Engineering Schedule and</u> <u>Schedule Basis</u>.

Key Engineering activities to be undertaken are:

- Interpretation and reporting of the field investigation results.
- Preparation (review and update) of vendor packages for the Long-Lead Items.
- Undertake Design Optimizations as recommended in the SLI 2018 Class 3 Cost Estimate and Project Execution Schedule report, which include:

|             | APPENDIX C – PROSPECT 1              | Revision |             |      |
|-------------|--------------------------------------|----------|-------------|------|
|             | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev      | Date        | Page |
| SNC·LAVALIN | SLI Doc. No 691499-0000-40ER-1-0001  | 01       | 21-OCT-2022 | C-15 |

- Hydraulic design of the headrace and tailrace canals and finalize the preliminary designs, including cost and schedule updates.
- Selection of:
  - Intake location.
  - Penstock route and excavation quantities.
- Finalize design of the Vent shaft and Gate shaft.
- Determine site access during construction.
- Determine temporary relocation of underground cables.
- Update existing scope of work information and prepare a Facility Scope of Work document.
- Update existing preliminary designs and develop into preliminary engineering work packages, by discipline, including updated MTOs. The EWPs shall support the Work Packaging Plan.
- Assess the impacts of the construction activities on operations and work with the Owner's operations team to develop mitigations.

### 3.4.4. Procurement Discipline

The Procurement discipline shall prepare and implement a *Procurement Management Plan*, Key procurement activities are:

- Working with the Owner to finalize standard contract documentation and procurement processes.
- Working with Project Management and Construction disciplines to document Contracting Strategy.
- Preparation of a L3 Bid Schedule and Schedule Basis.
- Issue vendor packages and obtain quotations / delivery timelines for Long-Lead Items.
- Prepare and issue POs for Field Program.

### **3.4.5.** Construction Discipline

The construction discipline shall prepare a Field Investigation Program Execution Plan, based on the scope of work provided by engineering. The plan shall include:

- L4 Field Investigation Schedule and Basis
- Class 2 Field Investigation Cost Estimate and Basis
- Upon approval, execute the field investigation program, with function management from engineering.

The Construction team shall prepare and implement a <u>*Construction Management Plan*</u>. Key aspects of the plan shall include:

- Define the Path of Construction<sup>2</sup> and optimize the construction sequencing.
- Prepare the L3 Construction Schedule and Basis.

<sup>&</sup>lt;sup>2</sup> The Path of Construction is defined as the optimal sequencing of the building of a facility, developed by Construction, Engineering and Project Management Subject Matter Experts (SMEs), typically working backwards from the "end state".

|             | APPENDIX C – PROSPECT 1              | Revision |             |      |
|-------------|--------------------------------------|----------|-------------|------|
|             | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev      | Date        | Page |
| SNC·LAVALIN | SLI Doc. No 691499-0000-40ER-1-0001  | 01       | 21-OCT-2022 | C-16 |

- Prepare a plan for monitoring and control of construction contractor activities.
- Review and update the indirect direct scope of work to reflect current market conditions and the selected project delivery model.
- Work with the Owner to develop mitigations to minimize the impact of construction activities on existing operations.

|                    | APPENDIX C – PROSPECT 1              |     |             |      |
|--------------------|--------------------------------------|-----|-------------|------|
| <b>SNC·LAVALIN</b> | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev | Date        | Page |
|                    | SLI Doc. No 691499-0000-40ER-1-0001  | 01  | 21-OCT-2022 | C-17 |

### 4. PROJECT-SPECIFIC RISKS

### 4.1. ENVIRONMENTAL RISK

A review of the federal and provincial Environmental Regulatory and Approval context for the proposed NL Hydro Generation Expansion Prospects is included in **APPENDIX D**.

### 4.2. SOCIOECONOMIC INFLUENCES

Socioeconomic influences for the proposed Prospects are also discussed in APPENDIX D.

### 4.3. MARKET CONDITIONS

As this could be the province's first major (hydro) project since Muskrat Falls, interest from local bidders and local labour group will be high, which is a positive factor. However, the project will also be a test case for the post-pandemic cost environment in the province, costs may be challenging to forecast.

### 4.4. LONG-LEAD ITEMS RISK

The turbine generator and related major equipment are considered Long-Lead items. Current market conditions and other supply chain management challenges are anticipated to add eleven (11) months to the schedule that was developed in the 2018 SLI study.

### 4.5. TECHNICAL RISK

This section presents risks that have been identified in previous reports and from SLI experience with similar hydroelectric developments.

### 4.5.1. Hydrotechnical

The hydrology was studied in 2020 by Hatch and is considered up to date. However, the study did not investigate the potential long-term impact from climate change. Since Unit 8 will be mainly used to add capacity to the existing facility, the design may not be affected by climate change issues but should be considered.

Optimization of the operating pattern of Units 7 and 8 should be undertaken. A risk of vortexes at the intake, with possible air entrainment, was identified in previous studies.

CFD modeling (Flow-3D) of the intake is required to optimize the geometry and operational parameters. This was not previously undertaken because it requires updated topographical and bathymetric information.

Previous studies identified the costs and benefits of widening of tailrace to minimize head losses when the new unit is added. If not done, there will be an increase in head losses and loss of revenue for the facility.

A risk of overpressure in the penstock was also identified. This can be mitigated through design of the penstock and installation of a pressure relief valve, rather than installation of a surge tank. Previous studies recommended that studies be undertaken to optimize the design and wicket gate closing time, which could lead to cost savings by eliminating the need for a pressure relief valve.

### 4.5.2. Geotechnical

Previous studies identified that there is risk from geotechnical uncertainty. In particular, this applies to the penstock route and intake siting. The need for a geotechnical Field Investigation Program was identified and should be undertaken to mitigate this risk and to allow optimization of intake location and penstock profile, and to provide a better estimate of excavation quantities that will be required. The Field Investigation Program would also include bathymetry and topography.

|               | APPENDIX C – PROSPECT 1              |     | Revision    |      |
|---------------|--------------------------------------|-----|-------------|------|
| SNC · LAVALIN | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev | Date        | Page |
|               | SLI Doc. No 691499-0000-40ER-1-0001  | 01  | 21-OCT-2022 | C-18 |

The rock excavation for the new powerhouse was undertaken during the construction of the powerhouse for Unit 7. There is a risk that additional excavation may be required, but optimization of the powerhouse design should take the existing geometry into account to minimize that risk. Currently, only a relatively small amount of excavation would be required for the oil separator sump and a new service bay. If significant additional excavation is required, blast vibrations that could interfere with Unit 7 operation. This would have to be monitored and duly mitigated.

A source of aggregate materials for construction (e.g., penstock backfill, etc.) was identified at a location approximately 35 km from the site. This source should be confirmed for availability and its ability to provide suitable materials.

A rock plug will be used as part of the intake construction and the Field Investigation Program should verify that rock quality is acceptable for this purpose. The program will also help finalize the location of the plug.

### 4.5.3. Technical Complexity

Generally, from a design and construction perspective, the project is not technically complex. However, there are a few issues worth noting, as follows.

When the Powerhouse for Unit 7 was built in 1977, rock excavation for Unit 8 was undertaken, as well as the concrete work for the Draft Tube outlet such that the adjacent tailrace area could be excavated. Based on the limited as-built information available, additional scope may be the result once the excavation is completed. If additional rock excavation is required, the operation of Unit 7 will be affected. Blast vibrations will also need to be mitigated (see **Section 4.5.2**).

For a turbine generator of this size, model testing will be required. Due to the preconstruction of the Draft Tube of Unit 8, outlet geometry has been established, which may limit optimization of the turbine design.

Site access will be limited by the Unit 8 addition and further complicated by cable trays and other electrical component adjacent to the proposed powerhouse.

Even though the project is not technically complex, management of the interfaces will be key to schedule and cost control should multiple contractors be used.

All construction traffic will need to go over the Powerhouse 1 tailrace deck (single lane, load limit 15 t) and this will present clearance constraints and logistics difficulties. To help with clearances, relocation of the cable trays at P/H 1 should be studied.

Venting of the penstock during filling is a risk at many powerhouses. Limiting air velocities will be required to prevent damage, especially during emergency de-watering. This was previously identified in the study with comments about combining air vent and gate shaft to be reviewed at design.

The study included a reference to higher grade steel available today that could allow for reduction in thickness of penstock steel for the design. However, availability may be affected by supply chain issues and market conditions may drive costs higher.

A concrete wall is required between Unit 7 penstock and the new penstock to prevent destabilization of Unit 7. This wall will be important to maintaining Unit 7 in operation during construction and care should be taken in its location and installation. The Field Investigation Program should verify that there is sufficient information available to design this wall.

The original plan during Unit 7 construction was that Unit 8 would use the same service bay. The study identified/recommends an additional service bay to advance the schedule by provision of adequate space for assembly and erection of Unit 8. This approach also mitigates interference with Unit 7 maintenance, if required.

New stoplogs will be required for Unit 8 to allow for maintenance on Unit 7 if required during construction.

|             | APPENDIX C – PROSPECT 1              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No 691499-0000-40ER-1-0001  | 01  | 21-OCT-2022 | C-19 |

Overhead travelling crane rails will be extended from Unit 7 so the existing crane can be used. It needs to be verified that the crane is fully operational, is in good condition and has sufficient capacity for this purpose. Usually, heaviest lifts are seen during construction and cranes see limited service thereafter.

It should be verified that any systems that will make use of equipment or space in Unit 7 will be workable, e.g., jockey pump for fire water pressure and drainage into Unit 7 sump pit. Other construction logistics considerations include the provision of potable water, wastewater treatment, 24 kV emergency power, and telecommunication provided from Unit 7 P/H without interrupting that operation.

Existing embedded parts for draft tube gates will need to be verified that they are in good condition.

Electrical grounding of the new system needs to be reviewed. Previous reports contain reference to an ungrounded station service system and recommend that it be upgraded to current Hydro standards.

The selected transmission line route appears to cross multiple other existing facilities, but this could be examined further to see if the route could be made more efficient (e.g., can existing cut lines be used?).

Owner's Costs were provided by NL Hydro for the cost estimate in the 2018 SLI study. There is a list of assumed items included that should be verified and Hydro costs revisited for update.

### 4.6. PROJECT COST RISK

Given the global supply chain challenges, the largest risk factors to schedule and cost will be the variable cost of fuel and contractor capacity limitations (availability of human resources, both technical and trades).

### 4.7. PROJECT SCHEDULE RISK

Using a Modified EPCM schedule, the critical path for the planning stage is Cost and Schedule Update (schedule line-item BDE L2.1), specifically the Field Investigation Program, which is a prerequisite to design optimizations and MTO revisions (and, thus, cost and schedule). This assumes that the Owner has completed the activities in schedule line-item BDE L2.02 and assumes that the Detailed Execution Planning (DEP) Stage starts immediately following BDE L2.1.

|                    | APPENDIX C – PROSPECT 1              |     |             |      |
|--------------------|--------------------------------------|-----|-------------|------|
| •))                | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev | Date        | Page |
| <b>SNC+LAVALIN</b> | SLI Doc. No 691499-0000-40ER-1-0001  | 01  | 21-OCT-2022 | C-20 |

### 5. MINIMUM WORK REQUIRED TO UPDATE COST AND SCHEDULE

### 5.1. PURPOSE AND OBJECTIVE

The SOW required to complete Front-End Execution Planning (FEEP) is outlined in **SECTION 3** above. It should be noted that the most accurate cost and schedule estimate would be attained by completed the full FEEP scope. However, for the BDE Unit 8 Prospect, Hydro requested that the study estimate the minimum level of work required to update cost and schedule and still meet Gate 3 (Project Sanction) requirements.

The FEEP stage was not fully completed in the 2018 SLI study and the information it was based on is now four (4) years old. This increases the schedule and financial risk associated with the accuracy of the escalated cost estimate. These risks can be mitigated by finalizing certain key decisions by the Owner and updating/completing the schedule and cost estimate from the previous 2018 SLI study.

### 5.2. KEY OWNER DECISIONS REQUIRED

The following key decisions by the Owner are required to advance the work to Gate 3.

- 1. Specification of Hydro's key objectives (in the Project Charter) related to:
  - 1.1. Cost
  - 1.2. Schedule
  - 1.3. Sanction Parameters

1.3.1. What conditions must be meet before significant contractual commitments are made?

- 2. Selection of a Contracting Strategy<sup>3</sup>, which consists of making recommendations on:
  - 2.1. Project Delivery Method
  - 2.2. Compensation Method(s)
  - 2.3. Sourcing Strategy
- 3. Turbine Generator
  - 3.1. Timing of the selection of a supplier and authorization to proceed with model testing.
- 4. Environmental Management
  - 4.1. Preparation of an Environmental Management Strategy including milestone date for Registration of the Project.

### 5.3. REQUIREMENTS FOR UPDATING / COMPLETING THE 2018 FEEP STUDY

- 1. Undertake Field Investigation Program
  - 1.1. Topographic and Bathymetric Surveys
  - 1.2. Geotechnical Investigations
- 2. Optimize Preliminary Designs based on the Field Data
- 3. Obtain Quotations and Delivery Timelines for W2W Packages

<sup>&</sup>lt;sup>3</sup> See COAA Best Practice *Developing a Contracting Strategy* (March 2018).

|                    | APPENDIX C – PROSPECT 1              |     | Revision    |      |
|--------------------|--------------------------------------|-----|-------------|------|
|                    | BAY d'ESPOIR HYDRO GENERATING UNIT 8 | Rev | Date        | Page |
| <b>SNC·LAVALIN</b> | SLI Doc. No 691499-0000-40ER-1-0001  | 01  | 21-OCT-2022 | C-21 |

- 4. Prepare Construction Sequencing Plan, a precursor to the full Path of Construction to be prepared in Detailed Execution Planning (DEP) Stage
- 5. Update Cost and Schedule

### 5.4. TIMING CONSIDERATIONS

Updating/completing the schedule and cost estimate would take approximately six (6) months, which includes three (3) months for a Field Investigation Program. (*Note: the Field Program should be executed between the months of April and November.*) Carrying out this work during the PUB review period, for example, would result in a six (6) month reduction in project schedule, allowing the Detailed Execution Planning (DEP) Stage to begin immediately after PUB approval.

| APPENDIX C – PROSPECT 2                     | Revision |             |      |
|---|----------|-------------|------|
| ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev      | Date        | Page |
| SLI Doc. No. 691499-0000-40ER-I-0001        | 01       | 21-OCT-2022 | C-22 |

# **APPENDIX C**

# **PROSPECT 2**

### ADDITION OF A THIRD GENERATING UNIT CAT ARM

PROSPECT OVERVIEW, GAP ANALYSIS & RISKS

# APPENDIX C - PROSPECT 2 Revision ADDITION OF A THIRD GENERATING UNIT CAT ARM Rev Date Page SLI Doc. No. 691499-0000-40ER-I-0001 01 21-OCT-2022 C-23

### **TABLE OF CONTENTS**

| 1. | PROSPECT 2 OVERVIEW: CAT ARM ADDITION                      | C-24 |
|----|--|------|
|    | 1.1. LOCATION AND BACKGROUND                               | 24   |
|    | 1.2. PROJECT DESCRIPTION                                   | 25   |
|    | 1.3. PROPOSED LAYOUT                                       | 25   |
|    | 1.4. KEY TECHNICAL METRICS                                 | 25   |
|    | 1.5. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022) | 27   |
| 2. | EXISTING PROJECT INFORMATION DATA GAP                      | C-28 |
|    | 2.1. OVERVIEW  | 28   |
|    | 2.2. DATA GAP  | 28   |
| 3. | SCOPE OF WORK TO COMPLETE FEEP STAGE                       | C-31 |
|    | 3.1. PURPOSE   | 31   |
|    | 3.2. OWNER'S KEY INPUTS                                    | 31   |
|    | 3.3. PROJECT DEFINITION STATEMENT UPDATE SCOPE OF WORK     | 31   |
|    | 3.4. PROJECT TEAM FEEP-STAGE SCOPE OF WORK                 | 31   |
|    | 3.4.1. Project Management Discipline                       | 31   |
|    | 3.4.2. Environmental Discipline                            | 32   |
|    | 3.4.3. Engineering Discipline                              | 32   |
|    | 3.4.4. Procurement Discipline                              | 33   |
|    | 3.4.5. Construction Discipline                             | 33   |
| 4. | PROJECT-SPECIFIC RISKS                                     | C-34 |
|    | 4.1. ENVIRONMENTAL RISK                                    | 34   |
|    | 4.2. SOCIOECONOMIC INFLUENCES                              | 34   |
|    | 4.3. MARKET CONDITIONS                                     | 34   |
|    | 4.4. LONG-LEAD ITEMS RISK                                  | 34   |
|    | 4.5. TECHNICAL RISK  | 34   |
|    | 4.5.1. Hydrotechnical                                      | 34   |
|    | 4.5.2. Geotechnical  | 34   |
|    | 4.5.3. Technical Complexity                                | 35   |
|    | 4.6. PROJECT COST RISK                                     | 35   |
|    | 4.7. PROJECT SCHEDULE RISK                                 | 35   |

|             | APPENDIX C – PROSPECT 2 Revision            |     | Revision    |      |
|-------------|---|-----|-------------|------|
|             | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001        | 01  | 21-OCT-2022 | C-24 |

### 1. PROSPECT 2 OVERVIEW: CAT ARM ADDITION

### 1.1. LOCATION AND BACKGROUND

Located in the southeastern section of the Great Northern Peninsula, north of Jacksons Arm, the existing Cat Arm Generation Facility consist of a Powerhouse with two (2) x 68.2 MW hydroelectric generating units. In 1985, ShawMont Newfoundland Limited was commissioned by NL Hydro to prepare a cost estimate for a third unit as an extension to the existing powerhouse in Cat Arm ("Cat Arm Addition")<sup>1</sup>. The scope of the study included the following.

- Review of the adequacy existing canals and tunnel system to support a third unit.
- Review of electrical and mechanical systems to ascertain the extent of modifications and extensions.
- Prepare conceptual layouts.
- Prepare project schedule and cost estimate.
- Identify the need for further studies and field investigations.
- Estimate the benefits that would be realized by reduction of spill.



FIGURE C2.1 LOCATION MAP CAT ARM

<sup>&</sup>lt;sup>1</sup> CAT ARM DEVELOPMENT ADDITION OF UNIT # 3. Shawmont Report No. SMR-30-85, September 13, 1985

|             | APPENDIX C – PROSPECT 2                     | Revision |             |      |
|-------------|---|----------|-------------|------|
|             | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev      | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001        | 01       | 21-OCT-2022 | C-25 |

### 1.2. PROJECT DESCRIPTION

Provision of a third unit with all major equipment similar to existing Units 1 and 2. Major equipment includes a new Pelton Turbine, Generator and Power Transformer.

Additional Facilities include:

- 2.1 m diameter Steel Penstock x 459 m long
- 30 m of new tunnel
- Extension to powerhouse
- Mechanical and Electrical Services including control system, and 230 kV switchgear
- New channel to Tailrace

### 1.3. PROPOSED LAYOUT

The proposed layout for the Cat Arm addition is reproduced in FIGURE C2.2 below.

An alternate layout based on having a separate powerhouse in front of the high-pressure Adit Portal was considered. This alternative would simplify foundation excavation and eliminate tunnel construction. However, it would require complete duplication of mechanical and electrical auxiliaries, a larger powerhouse, a longer penstock, and a new tailrace and was not recommended in the 1985 study. A key selection parameter was the assumption that equipment, controls, and layout for Unit 3 would be identical to units 1 and 2. Today, this assumption may not be applicable and as such the two options should be reassessed.

### 1.4. KEY TECHNICAL METRICS

The following metrics were determined and used in the Screening and Ranking Process.

- Power (MW Installed): One (1) x 62.2 MW Pelton Turbine
- Cost per MW of Power (escalated to YE-2022): \$4.5 million / MW
- Overall Project Duration : 5.2 Years

| • | Planning Timeline:                 | 2 Years   |
|---|------------------------------------|-----------|
| • | Execution (Construction) Timeline: | 3.2 Years |

- Less Overlap Planning/Execution: <u>0 Years</u>
- Overall Development Timeline: 5.2 Years

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 74 of 158

|             | APPENDIX C – PROSPECT 2                     |     | Revision    |      |
|-------------|---|-----|-------------|------|
|             | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001        | 01  | 21-OCT-2022 | C-26 |



FIGURE C2.2 PROPOSED LAYOUT FOR CAT ARM ADDITION (from CAT ARM DEVELOPMENT ADDITION OF UNIT # 3.

ShawMont Report No. SMR-30-85, September 13, 1985)

|             | APPENDIX C – PROSPECT 2                     |     | Revision    |      |
|-------------|---|-----|-------------|------|
|             | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001        | 01  | 21-OCT-2022 | C-27 |

### 1.5. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022)

The 1985 cost estimate for the Cat Arm Addition was updated for Hydro in 2018 and was escalated to YE-2022 as shown in **TABLE C2-1**.

### TABLE C2-1: CAT ARM ADDITION COST ESTIMATE ESCALATED TO YE-2022

| COST ITEM   | AMOUNT           | NOTES   |
|---|------------------|---|
| Direct Costs  | \$119,789,380.00 | Tunnel excavation, penstock, powerhouse & tailrace, Pelton turbine, generator, switchyard and supporting equipment/infrastructure |
| Contractor's Indirects and General                  | \$23,957,876.00  | Overhead (staff and supervisory), mob/demob,<br>temporary site facilities, site services,<br>construction camp and subsistence.   |
| Project Management / Engineering                    | \$21,562,088.40  |   |
| Owner's Cost  | \$5,749,890.24   |   |
| Environmental & Regulatory                          | \$750,000.00     |   |
| Interest  | \$16,550,263.14  |   |
| Contingency   | \$34,361,853.45  |   |
| Subtotal Cost (2018)                                | \$222,721,351.23 |   |
| Other   | \$7,119,581.77   | Unspecified (delta added to reconcile Subtotal with Total Cost below)   |
| Total Cost (2018)                                   | \$229,840,933    |   |
| Escalation calculation (2018-22)                    | 132.5%           | 2019: 2.2% 2020: 1.2% 2021: 11.4%<br>Statistics Canada Construction Cost Index<br>(CCPI)  |
|   |                  | 2022: 15%<br>Projection by SLI Cost Estimating Department   |
| 2022 TOTAL ESCALATED COST                           | \$ 304,539,236   |   |
| AACE Estimate Accuracy<br>(Index of 1 = +10% / -5%) | +50% / -25%      | Class 4 accuracy index range = 3 to 12<br>Index for this estimate assumed = 5   |

|             | APPENDIX C – PROSPECT 2                     |     | Revision    |      |
|-------------|---|-----|-------------|------|
|             | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001        | 01  | 21-OCT-2022 | C-28 |

### 2. EXISTING PROJECT INFORMATION DATA GAP

### 2.1. OVERVIEW

While the 1985 report was called a "Feasibility Study", it was essentially a cost and schedule determinization. Given this fact, and the age of the report (35+ years), it is recommended that the report be considered a Project Definition document.

### 2.2. DATA GAP

A complete review and update of the Project Definition document, followed by FEEP-level documentation, is recommended. The updated project definition should be based on updated hydrological data and recalculated power and energy availability, including selection of the Turbine Generator unit and related equipment. Included in this stage should be the Project Registration for the Environmental Assessment process plus the planning and execution of the Field Investigation Program.

During the FEEP, the two (2) options for the location of the powerhouse should be revisited.

To advance this work to a *Front-End Execution Planning (FEEP) standard*, the following gaps remain (see **TABLE C2-2**).

|             | APPENDIX C – PROSPECT 2                     |     | Revision    |      |
|-------------|---|-----|-------------|------|
|             | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev | Date        | Page |
| SNC+LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001        | 01  | 21-OCT-2022 | C-29 |

Ī

# TABLE C2-2: GAP ANALYSIS FOR PROSPECT 2: CAT ARM ADDITION

| STAGE 1: PROJECT DE | FINITION                       |  |
|---------------------|--------------------------------|--|
| RESPONSIBLE GROUP   | DELIVERABLE                    | REQUIREMENTS TO ADDRESS GAP  |
| Owner / Corporate   | PROJECT DEFINITION STATEMENT   | Update Hydrology, then identify Power / Energy options, select preferred option, identify benefits if there is a reduction in Spill.<br>Gather as-built information and original design information. Assess if upgrades are required.<br>Desktop study to document environmental impacts (no field studies required).<br>Plan and implement a Field Investigation Program.<br>Update Project Scheme, prepare Class 5 schedule and cost estimate. |
|                     | PROJECT CHARTER                | Develop Project Charter as per standard for internal approval and sign-off, including recommended Contracting Strategy.<br>Develop the Environmental Management Strategy.<br>Approve FEEP Stage Budget, Deliverables List, and Milestone Schedule.   |
| STAGE 2: FEEP       |                                |  |
| RESPONSIBLE GROUP   | DELIVERABLE                    | REQUIREMENTS TO ADDRESS GAP  |
|                     | PROJECT EXECUTION PLAN (PEP)   |  |
|                     | Scope of Work                  | Update based on optimized preliminary designs.   |
|                     | Project Management Strategy    | Key elements of the execution strategy will need to be reviewed and updated based on the selected Project Delivery Model.  |
| Project Management  | Project Controls Strategy      | Determine how cost estimating and schedule development activities are going to be coordinated.   |
|                     | Health & Safety Strategy       | Prepare HS&S Project Strategy.   |
|                     | QA / QC Strategy               | Prepare Quality Management Strategy.   |
|                     | PROJECT CONTROLS DOCUMENTATION |  |
|                     |                                |  |

| ON OF A THIRD (   |
|-------------------|
| SLI Doc. No. 6914 |

|                          | Cont Entimote (Close 1 / Close 3) | I hadet Cest keest on undeted contractions stated a decide adviser cationizations unit and and for land items and the  |
|--------------------------|-----------------------------------|--|
|                          |                                   | opdate Cost based on updated contracting strategy, scredule, design optimizations, updated unit costs and costs for Long-Lead items, and the cost of implementing the Environmental Protection Plan. |
|                          | Schedule                          | Prepare L2 Schedule based on Updated MTOs, Timelines for Long Lead Item, Environmental Timelines, Construction Sequencing, and Contracting Strategy.   |
|                          | ENVIRONMENTAL MANAGEMENT PLAN     | Based on the Environmental Management Strategy, develop a detailed Management Plan.  |
| Environmental management | PROJECT REGISTRATION / EIS        | Prepare Robust Environmental Registration Document   |
|                          | FACILITY SCOPE OF WORK            | Update Scope of Work documentation based on optimized preliminary designs  |
|                          | PRELIMINARY ENGINEERING           | Prepare Vendor Packages for the Long-Lead Items. Undertake Preliminary Engineering.  |
|                          | FIELD INVESTIGATIONS SOW          | Completed in the Project definition Stage.   |
| Engineering              | DESIGN OPTIMIZATIONS              | Based on the field data, optimize the preliminary designs, including assessment of both powerhouse location options.   |
|                          | UPDATED PRELIMINARY ENGINEERING   | Develop the optimized design into preliminary EWPs, including updated MTOs.  |
|                          | MTOS                              | Update the MTOs based on the optimized design.   |
|                          | CONTRACTING STRATEGY              | Work with PM and Construction discipline to document the Contracting Plan.   |
| Supply Chain Management  | BID & EVALUATION PLAN             | Prepare a plan which documents standard contract documentation, the bid management process, including bid evaluation plans, approval authorities, etc  |
|                          | LONG-LEAD ITEMS VENDOR PACKAGES   | Issue vendor packages and obtain quotations / delivery timelines for Long Lead Items.  |
|                          | FIELD INVESTIGATIONS PLAN         | Issue PO for Field Investigation Activities.   |
|                          | CM STRATEGY                       | Prepare Construction Management Plan based on the Contracting Strategy.  |
| Construction             | PATH OF CONSTRUCTION              | Undertake Construction Planning activities necessary to develop the Path of Construction (sequencing).   |
|                          | CONSTRUCTION SCHEDULE             | Based on the Path of Construction, update construction schedule.   |
|                          |                                   |  |

|             | APPENDIX C – PROSPECT 2                     |     | Revision    |      |
|-------------|---|-----|-------------|------|
|             | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001        | 01  | 21-OCT-2022 | C-31 |

### 3. SCOPE OF WORK TO COMPLETE FEEP STAGE

### 3.1. PURPOSE

This section outlines the scope of work necessary update the Project Definition documentation for this project and to prepare FEEP-Stage documentation.

### 3.2. OWNER'S KEY INPUTS

At the start of the FEEP stage, it is recommended that the Owner provide the Project Team(s) with a Project Charter, approved Environmental Management Strategy, and approved FEEP Stage Budget, Deliverables List and Milestone Schedule.

### 3.3. PROJECT DEFINITION STATEMENT UPDATE SCOPE OF WORK

The scope of work for the Project Definition Statement Update consists of the following.

- A detailed review of hydrology taking into consideration potential climate change impacts.
- A calculation of the options for Power and Energy scenarios, culminating in Hydro's selection of the preferred combination.
- Estimate of the benefits if there is a reduction in spill.
- Gather and review all original design data and construction data, including has built information.
- Determine if existing switchyard equipment can be used or if upgrades are required.
- Development of a project scheme, including the selection of the location of the new powerhouse and type / size of a turbine generator or other major equipment, including review of possible modifications to existing equipment, canals and tunnel system to support a third unit.
- Planning and implementation of a Field Investigation Program.
- Development of an Environmental Management Strategy, including registration of the Project for the Environmental Assessment Process.
- Preparation of a Project Charter, including the selection of the Contracting Strategy.
- Updated Project Scope of Work, Class 5 Cost Estimate and Schedule, include current timelines for supply and delivery of long lead items.

### 3.4. PROJECT TEAM FEEP-STAGE SCOPE OF WORK

### 3.4.1. Project Management Discipline

The key Project Management Team deliverable is a *Front-end Execution Plan (FEEP)*, which incorporates the following key documentation.

- Based on the project definition documentation, prepare an updated <u>Project Scope of Work Document</u> (SOW) and <u>Work Breakdown Structure</u> (WBS).
- Based on the updated scope of work, prepare a Front-End Execution Plan (FEEP). Key aspect of the FEEP is the contracting strategy which details the project delivery model, compensation model, and sourcing strategy.
- Based on the SOW and WBS, develop the following key sections of the FEEP:
  - Project Management Approach, based on the Project Delivery Model.
  - Project Controls Strategy

|             | APPENDIX C – PROSPECT 2                     |     | Revision    |      |
|-------------|---|-----|-------------|------|
|             | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001        | 01  | 21-OCT-2022 | C-32 |

- Health, Safety and Security
- Quality Management Strategy
- Coordinate the preparation of the following by other disciplines.
  - Environmental Management Plan
  - Engineering Management Plan
  - Procurement Management Strategy
  - Contracting Strategy
  - Construction Management Strategy
  - Construction Sequencing Plan
  - Work Packaging Plan
- Coordinate the preparation of the following Project Controls Documentation.
  - Using the existing schedule data, revised WBS and Work Packaging Plan, develop and optimize a <u>L3 Project Schedule and Schedule Basis</u>, incorporating EIA and Long Lead timelines provided by vendors. The <u>Level 3 (L3) Project Schedule should include</u>:
    - L4 Project Management Schedule and Schedule Basis
    - L4 Environmental Management Schedule and Schedule Basis
    - L4 Engineering Management Schedule and Schedule Basis
    - L3 Bid Stage Schedule and Schedule Basis
    - L3 Construction Schedule and Schedule Basis with Monte Carlo Simulation which incorporates updated long lead item delivery timelines
  - <u>Class 3 Cost Estimate, Estimate Basis, and Risk Analysis</u>, e.g., Monte Carlo Simulation. Update the existing Cost Estimate based on updated WBS / Work Package Plan, the facility optimizations, and revisions to the indirect scope of work, plus updated unit, and material / equipment cost.

### 3.4.2. Environmental Discipline

The Environmental discipline shall:

- Prepare an Environmental Management Plan.
- Prepare a robust Environmental Registration Document.

### 3.4.3. Engineering Discipline

The engineering discipline shall:

• Prepare and implement an Engineering Management Plan, including L4 Engineering Schedule and Schedule Basis.

Key Engineering activities to be undertaken are:

• Preparation (review and update) of vendor packages for the Long-Lead Items.

|             | APPENDIX C – PROSPECT 2                     |     | Revision    |      |
|-------------|---|-----|-------------|------|
|             | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001        | 01  | 21-OCT-2022 | C-33 |

- Based on the project scheme, prepare the preliminary designs develop the information into preliminary engineering work packages, by discipline, including updated MTOs. The EWPs shall support the Work Packaging Plan.
- Update existing scope of work information and prepare a Facility Scope of Work document.
- Assess the impacts of the construction activities on existing operations and work with the Owner's operations team to develop mitigations.

### 3.4.4. Procurement Discipline

The Procurement discipline shall prepare and implement a <u>Procurement Management Plan</u>, Key procurement activities are:

- Working with the Owner to finalize standard contract documentation and procurement processes.
- Working with PM and Construction discipline to document the Contracting Plan.
- Preparation of a L3 Bid Schedule and Schedule basis.
- Issue vendor packages and obtain quotations / delivery timelines for Long Lead Items.

### 3.4.5. Construction Discipline

The Construction team shall prepare and implement a <u>Construction Management Plan</u>. Key aspects of the plan are:

- Define the Path of Construction<sup>2</sup> and optimize the construction sequencing.
- Prepare the L3 Construction Schedule and Basis.
- Prepare a plan for monitoring and control of construction contractor activities.
- Review and update the indirect direct scope of work to reflect current market conditions and the selected project delivery model.
- Work with the Owner to develop mitigations to minimize the impact of construction activities on existing operations.

<sup>&</sup>lt;sup>2</sup> The Path of Construction is defined as the optimal sequencing of the building of a facility, developed by Construction, Engineering and Project Management Subject Matter Experts (SMEs), typically working backwards from the "end state".

|             | APPENDIX C – PROSPECT 2                     |     | Revision    |      |
|-------------|---|-----|-------------|------|
|             | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev | Date        | Page |
| SNC+LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001        | 01  | 21-OCT-2022 | C-34 |

### 4. PROJECT-SPECIFIC RISKS

### 4.1. ENVIRONMENTAL RISK

A review of the federal and provincial Environmental Regulatory and Approval context for the proposed NL Hydro Generation Expansion prospects is included in **APPENDIX D**.

### 4.2. SOCIOECONOMIC INFLUENCES

Socioeconomic influences for the proposed prospects are discussed in **APPENDIX D**. Since this brownfield project is remote, socioeconomic influences will likely be positive.

### 4.3. MARKET CONDITIONS

The project start date is assumed to be some years away, so it is difficult to comment on market conditions.

### 4.4. LONG-LEAD ITEMS RISK

The schedule for this prospect outlined in the Main Report assumes a T/G generator is the critical path item for construction and uses today's market conditions timeline for Long-Lead Items.

### 4.5. TECHNICAL RISK

### 4.5.1. Hydrotechnical

The hydrology for Cat Arm is out of date and should be updated to a common timeframe with other projects under review so that a valid comparison can be made between the projects. This should then be used to update the Power and Energy study, which will also allow confirmation of the main project characteristics (dam height and type, spillway capacity, installed capacity, etc.).

The report *CAT ARM DEVELOPMENT ADDITION OF UNIT # 3* (Shawmont Report No. SMR-30-85, September 13, 1985) identified that the capacity of the upstream water convenance system was not sized for three (3) units, although the penstock capacity is adequate. That report identified the need for a study to review the adequacy of existing canals and tunnel system to support a third unit. This should be done in conjunction with planned operating methodology to verify that the system will be capable of meeting planned needs.

The potential geometry for the tailrace proposed in the 1985 report should be reviewed with Flow-3D to optimize the geometry and validate the previous assumptions. This should be included in a reassessment of the two (2) options proposed for the location of the new powerhouse.

At the time of the 1985 report, the facility had only been in operation for a short time. New studies should include the latest information on bathymetry to adequately assess the hydraulics. Information should also be provided on the behaviour of the breakwater, which should then be studied to determine if changes are required to accommodate the additional flow.

Since Cat Arm has been in operation since 1985, there should be considerable operational information. This information would be useful for the hydrotechnical studies and should be reviewed as part of the Power and Energy study.

### 4.5.2. Geotechnical

The 1985 report identified the potential that blasting operations for the excavations for the new tunnel section could cause vibrations that could interrupt power production at the existing plant.

The report also based excavation requirements and quantities on information available from the newly completed facility. Any information from previous investigations should be collected and reviewed to determine

| <b>&gt;))</b><br>SNC·LAVALIN | APPENDIX C – PROSPECT 2                     | Revision |             |      |
|------------------------------|---|----------|-------------|------|
|                              | ADDITION OF A THIRD GENERATING UNIT CAT ARM | Rev      | Date        | Page |
|                              | SLI Doc. No. 691499-0000-40ER-I-0001        | 01       | 21-OCT-2022 | C-35 |

the extent of additional field information required to validate the existing information. If the information cannot be found, a more extensive field investigation program may be required.

There could be issues identified in dam safety reviews that need to be taken into consideration for the additional unit. This could include existing tailrace behaviour (riprap protection) and breakwater performance.

### 4.5.3. Technical Complexity

A cost estimate update in 2010 identified that NL Hydro had purchased a spare runner for the existing turbines that could be used as the runner for the proposed third unit. This assumption should be validated. The Power and Energy study and final design review should consider the optimal selection for the unit to meet current needs and planned operation. There may also be concerns about the preservation of the runner (how long ago was it purchase? Has there been an overhaul since the 2010 report that already put this runner into service?). Use of an existing runner may also limit the suppliers who would be interested in bidding on the work.

The 1985 plan for the third unit considered an expansion to the existing powerhouse and assumed tie-in to existing systems (service water, air, telecommunications, etc.) and that all electrical and mechanical equipment would be identical to that in the existing plant. With changes to technologies since 1985, and possible changes within the plant, this is unlikely to be a valid approach.

The changes required to the switchyard and transmission (that will allow the facility to be expanded with the addition of another 230 kV line) should be reviewed and documented so there is no risk that the requirements could be changed in future.

There is a risk that documentation from the initial installation could be difficult to locate. Hydro should verify what information can be located and that information should be made available for FEEP. This includes asbuilt drawings, previous topographic and bathymetric information, geotechnical studies and reports, etc.

Any changes made to the facility since initial construction need to be identified and fully documented. There may be changes which impact the assumptions made in previous studies and these changes can affect the current layout or approach.

### 4.6. PROJECT COST RISK

This project is not technically complex nor difficult to construct. Sound planning and engineering, with a sanction estimate based on bid prices, should address the risks of cost or schedule overruns.

### 4.7. PROJECT SCHEDULE RISK

See above.
# **APPENDIX C**

# **PROSPECT 3**

# ISLAND POND HYDROELECTRIC DEVELOPMENT

PROSPECT OVERVIEW, GAP ANALYSIS & RISKS

|             | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|-------------|---------------------------------------|-----|-------------|------|
| •           | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-37 |

## **TABLE OF CONTENTS**

| PROSPECT 3 OVERVIEW: ISLAND POND HYDROELECTRIC             |   |
|--|---|
| DEVELOPMENT  | C-38  |
| 1.1. LOCATION AND BACKGROUND                               | 38  |
| 1.2. PROJECT DESCRIPTION                                   | 39  |
| 1.3. PROPOSED LAYOUT                                       | 39  |
| 1.4. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022) | 42  |
| 1.5. KEY TECHNICAL METRICS                                 | 43  |
| EXISTING PROJECT INFORMATION DATA GAP                      | C-44  |
| 2.1. OVERVIEW  | 44  |
| 2.2. DATA GAP  | 44  |
| SCOPE OF WORK TO COMPLETE FEEP STAGE                       | C-47  |
| 3.1. PURPOSE   | 47  |
| 3.2. OWNER'S FEEP-STAGE SCOPE OF WORK                      | 47  |
| 3.3. PROJECT TEAM FEEP-STAGE SCOPE OF WORK                 | 47  |
| 3.3.1. Project Management Discipline                       | 47  |
| 3.3.2. Environmental Discipline                            | 48  |
| 3.3.3. Engineering Discipline                              | 48  |
| 3.3.4. Procurement Discipline                              | 49  |
| 3.3.5. Construction Discipline                             | 49  |
| PROJECT-SPECIFIC RISKS                                     | C-51  |
| 4.1. ENVIRONMENTAL RISK                                    | 51  |
| 4.2. SOCIOECONOMIC INFLUENCES                              | 51  |
| 4.3. MARKET CONDITIONS                                     | 51  |
| 4.4. LONG-LEAD ITEMS RISK                                  | 51  |
| 4.5. TECHNICAL RISK  | 51  |
| 4.5.1. Hydrotechnical                                      | 51  |
| 4.5.2. Geotechnical  | 52  |
| 4.5.3. Technical Complexity                                | 52  |
| 4.6. PROJECT COST RISK                                     | 52  |
| 4.7. PROJECT SCHEDULE RISK                                 | 52  |
|  | PROSPECT 3 OVERVIEW: ISLAND POND HYDROELECTRIC         DEVELOPMENT         1.1. LOCATION AND BACKGROUND         1.2. PROJECT DESCRIPTION         1.3. PROPOSED LAYOUT         1.4. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022)         1.5. KEY TECHNICAL METRICS         EXISTING PROJECT INFORMATION DATA GAP         2.1. OVERVIEW         2.2. DATA GAP         SCOPE OF WORK TO COMPLETE FEEP STAGE         3.1. PURPOSE         3.2. OWNER'S FEEP-STAGE SCOPE OF WORK         3.3. PROJECT TEAM FEEP-STAGE SCOPE OF WORK         3.3.1. Project Management Discipline         3.3.2. Environmental Discipline         3.3.3. Engineering Discipline         3.3.4. Procurement Discipline         3.3.5. Construction Discipline         3.3.6. Construction Discipline         3.3.7. MORENTAL RISK         4.1. ENVIRONMENTAL RISK         4.2. SOCIOECONOMIC INFLUENCES         4.3. MARKET CONDITIONS         4.4. LONG-LEAD ITEMS RISK         4.5. TECHNICAL RISK         4.5.1. Hydrotechnical         4.5.2. Geotechnical         4.5.2. Geotechnical         4.5.3. Technical Complexity         4.6. PROJECT COST RISK         4.7. PROJECT SCHEDULE RISK |

|             | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|-------------|---------------------------------------|-----|-------------|------|
| •))         | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-38 |

### 1. PROSPECT 3 OVERVIEW: ISLAND POND HYDROELECTRIC DEVELOPMENT

### 1.1. LOCATION AND BACKGROUND

Situated in South Central Newfoundland within the existing watershed of the Bay d 'Espoir development, the Island Pond Hydroelectric Development is located on the North Salmon River (see **FIGURE C3.1**). In 1988, ShawMont Newfoundland Limited was commissioned by Hydro to prepare a Final Feasibility Study for the Island Pond Development.<sup>1</sup> The scope of the study included the following.

- Hydrological studies of the watershed
- Geotechnical field investigations
- Topographical surveys of all construction work areas
- Confirmation of selected scheme
- Mitigative measure to eliminate icing in the diversion canal
- Preparation of a detailed schedule and cost estimate

Transmission line considerations and EIA studies were excluded.



FIGURE C3.1 LOCATION OF ISLAND POND HYDROELECTRIC DEVELOPMENT

<sup>&</sup>lt;sup>1</sup> Island Pond Development Final Feasibility Study Volume 1 – Report. Shawmont Report No. SMR-30-85, January 1988.

|             | APPENDIX C – PROSPECT 3               | Revision |             |      |
|-------------|---------------------------------------|----------|-------------|------|
| •))         | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev      | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01       | 21-OCT-2022 | C-39 |

In preparation for the construction of the Granite Canal Generation Facility, re-optimization and cost update studies were carried out in 1996-7 for both Granite Canal and Island Pond Generation Facilities.<sup>2</sup> Recommended were two (2)x 18 MW vertical-axis Francis units, although the report acknowledged that Kaplan units would be suitable.

In July 2006, Hydro commissioned SNC-Lavalin ("SLI") to do a further Island Pond study based on the following goals and objectives.<sup>3</sup>

- Optimize the Generation facility, utilizing Kaplan Unit(s).
- Gather field data as required (scope was later reduced due to budget constraints).
- In support of environmental studies, provide:
  - Recommendations related to HADD mitigation measures.
  - Engineering support data.
- Prepare a Capital Cost Estimate and Construction Schedule.

Hydro was to provide the layout of the switchyard and its direct cost of construction while SLI was to determine the site preparation cost. The following section outlines the results of that study.

### 1.2. PROJECT DESCRIPTION

The proposed generation facility would utilize the available head of approximately 25 m between the Meelpaeg Reservoir and Crooked Lake. The facility would consist of a Roller Compacted Concrete (RCC) dam and a close-coupled powerhouse with one (1) 36 MW Kaplan Turbine, a switchyard, a 0.75 km long Forebay, and a 0.55 km Tailrace. Additional facilities include:

- 3 km long diversion canal between Meelpaeg Reservoir and Island Pond.
- 3.4 km of channel improvements in Meelpaeg Reservoir and Island Pond Reservoir.

Other related Infrastructure included:

- New roadway to connect Ebbegunbaeg and the Upper Salmon / Bay d 'Espoir areas.
- Main Access Road updates including a new bridge at Noel Paul's Brook and access from the existing main road to the project site

### 1.3. PROPOSED LAYOUT

The layout proposed for the Island Pond development in 2006 is reproduced in **FIGURE C3.2** below. Additional drawings from the 2006 SLI report are reproduced in **FIGURE C3.3**.

Note: it was assumed that, in Year One (1), Hydro would construct a 25 kV distribution line from Ebbegunbaeg control structure to the campsite and powerhouse in order to provide construction power to the site.

<sup>&</sup>lt;sup>2</sup> ISLAND POND / GRANITE CANAL RE-OPTIMIZATION AND COST UPDATE STUDY. AGRA Shawmont Report SMR-05-96, January 14, 1997.

<sup>&</sup>lt;sup>3</sup> Studies for Island Pond Hydroelectric Project FINAL REPORT. SNC-Lavalin Project No. 722720, December 2006.

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 88 of 158

|             | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|-------------|---------------------------------------|-----|-------------|------|
| <b>&gt;</b> | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-40 |



FIGURE C3.2 ISLAND POND HYDROELECTRIC DEVELOPMENT LAYOUT

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 89 of 158

|               | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|---------------|---------------------------------------|-----|-------------|------|
| SNC · LAVALIN | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
|               | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-41 |



### FIGURE C3.3 ISLAND POND DEVELOPMENT DRAWINGS FROM 2006 SLI report

|             | APPENDIX C – PROSPECT 3               | Revision |             |      |
|-------------|---------------------------------------|----------|-------------|------|
| •))         | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev      | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01       | 21-OCT-2022 | C-42 |

### 1.4. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022)

The 2006 cost estimate was based on a traditional EPCM approach with numerous contract packages, e.g.:

- Construction of temporary and permanent access roads.
- The construction of the powerhouse, dam, intake, tailrace and the HADD in the tailrace.
- The construction of a diversion canal, including the channel improvements in island pond, reservoir clearing and construction of HADD facilities.
- Hydro contracts for transmission lines, distribution lines, switchyard, protection and control, or telecommunications.

The estimate was updated in 2012<sup>4</sup>, again in 2018<sup>5</sup>, and escalated to YE-2022 as shown in **TABLE C3-1**.

### TABLE C3-1: ISLAND POND COST ESTIMATE ESCALATED TO YE-2022

| COST ITEM   | AMOUNT        | NOTES   |  |  |
|---|---------------|---|--|--|
| Material Supply                                     | \$5,300,000   | From 2012 estimate escalated to 2018 by Hydro.  |  |  |
| Labour  | \$28,266,700  | ""  |  |  |
| Consultant  | \$35,333,400  | "   |  |  |
| Contract Work                                       | \$244,247,900 | "   |  |  |
| Other Direct Costs                                  | \$1,766,700   | ""  |  |  |
| Interest  | \$27,302,400  | "   |  |  |
| Contingency   | \$62,983,154  | "   |  |  |
| Total Cost (2018)                                   | \$405,200,154 | "   |  |  |
| Escalation calculation (2018-2022)                  | 122.5%        | 2019: 2.2% 2020: 1.2% 2021: 11.4%<br>Statistics Canada Construction Cost Index (CCPI) |  |  |
|   | 102.070       | 2022: 15%<br>Projection by SLI Cost Estimating Department                             |  |  |
| 2022 TOTAL ESCALATED COST                           | \$536,890,204 |   |  |  |
| AACE Estimate Accuracy<br>(Index of 1 = +10% / -5%) | +50% / -25%   | Class 5 accuracy index range = 4 to 20<br>Index for this estimate assumed = 5         |  |  |

<sup>&</sup>lt;sup>4</sup> Portland Creek and Island Pond Hydroelectric Projects Update Cost Estimates. SNC-Lavalin 501325-40ER-0001-PA, May 2012.

<sup>&</sup>lt;sup>5</sup> Island Pond Hydroelectric Development. NL Hydro, August 29, 2018.

|             | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|-------------|---------------------------------------|-----|-------------|------|
| •))         | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-43 |

### 1.5. KEY TECHNICAL METRICS

The following key technical metrics were developed from the above information and used in the Screening and Ranking Process.

- Power (MW Installed): One (1) x 36 MW Kaplan Turbine Generator
- Cost per MW of Power (escalated to YE-2022): \$14.9 million / MW
- Overall Project Duration : 6 Years

| Planning Timeline:                 | 3 Years  |
|------------------------------------|--|
| Execution (Construction) Timeline: | 3 Years  |
| Less Overlap Planning/Execution:   | <u>0 Years</u>   |
|                                    | Planning Timeline:<br>Execution (Construction) Timeline:<br>Less Overlap Planning/Execution: |

Overall Development Timeline: 6 Years

|             | APPENDIX C – PROSPECT 3               | Revision |             |      |
|-------------|---------------------------------------|----------|-------------|------|
| •//         | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev      | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01       | 21-OCT-2022 | C-44 |

### 2. EXISTING PROJECT INFORMATION DATA GAP

### 2.1. OVERVIEW

The 2006 report was considered at the feasibility level at the time of preparation. In terms of the standard recommended in the Main Report of this study, the 2006 report is lacking in execution planning and some elements of construction planning, an Environmental Management plan is required, as well as updated Hydrology / Power and Energy Calculations. Further field investigation work is also required

### 2.2. DATA GAP

To advance this prospect to a Front-End Execution Planning (FEEP) standard, the following gaps remain (see **TABLE C3-2**).

|                         | Page                                  | C-45                                 |
|-------------------------|---------------------------------------|--------------------------------------|
| Revision                | Date                                  | 21-OCT-2022                          |
|                         | Rev                                   | 01                                   |
| APPENDIX C – PROSPECT 3 | ISLAND POND HYDROELECTRIC DEVELOPMENT | SLI Doc. No. 691499-0000-40ER-I-0001 |
|                         |                                       | SNC+LAVALIN                          |

# TABLE C3-2: GAP ANALYSIS FOR PROSPECT 3: ISLAND POND

| STAGE 1: PROJECT DE | FINITION                          |  |
|---------------------|-----------------------------------|--|
| RESPONSIBLE GROUP   | DELIVERABLE                       | REQUIREMENTS TO ADDRESS GAP  |
|                     | PROJECT DEFINITION STATEMENT      | Update Hydrology, then Update Power / Energy Calculations  |
| Owner / Corporate   | PROJECT CHARTER                   | Develop Project Charter as per standard for internal approval and sign-off, including recommended Contracting Strategy.<br>Develop the Environmental Management Strategy.<br>Approve FEEP Stage Budget, Deliverables List, and Milestone Schedule. |
| STAGE 2: FEEP       |                                   |  |
| RESPONSIBLE GROUP   | DELIVERABLE                       | REQUIREMENTS TO ADDRESS GAP  |
|                     | PROJECT EXECUTION PLAN (PEP)      |  |
|                     | Scope of Work                     | Update Scope Work document based on completed field data and update preliminary design / MTOs  |
|                     | Project Management Strategy       | Key elements of the execution strategy will need to be reviewed and updated based on the selected Project Delivery Model.  |
|                     | Project Controls Strategy         | Determine how cost estimating and schedule development activities are going to be coordinated.   |
| Project Management  | Health & Safety Strategy          | Prepare HS&S Project Strategy.   |
|                     | QA / QC Strategy                  | Prepare Quality Management Strategy.   |
|                     | PROJECT CONTROLS DOCUMENTATION    |  |
|                     | Cost Estimate (Class 4 / Class 3) | Update based on updated contracting strategy, schedule, design optimizations, updated unit costs and costs for Long-Lead items and the cost of implementing the Environmental Protection Plan.   |
|                     | Schedule                          | Prepare L2 based on updated MTOs, Timelines for long-lead items, Environmental timelines, Construction Sequencing, and Contracting Strategy.   |
|                     | ENVIRONMENTAL MANAGEMENT PLAN     | Based on the Environmental Management Strategy, develop a detailed Management Plan.  |
|                     | PROJECT REGISTRATION / EIS        | Prepare Robust Environmental Registration Document.  |
|                     | FACILITY SCOPE OF WORK            | Based on the Design Optimizations, and revised MTO's, update the Scope of Work for each Facility.  |
|                     |                                   |  |

|                         | Page                                  | C-46                                 |
|-------------------------|---------------------------------------|--------------------------------------|
| Revision                | Date                                  | 21-OCT-2022                          |
|                         | Rev                                   | 01                                   |
| APPENDIX C – PROSPECT 3 | ISLAND POND HYDROELECTRIC DEVELOPMENT | SLI Doc. No. 691499-0000-40ER-I-0001 |
|                         |                                       | SNC+LAVALIN                          |

|                         | PRELIMINARY ENGINEERING          | Review the 2006 preliminary designs and finalize the scope of work for the field program.   |
|-------------------------|----------------------------------|---|
|                         | FIELD INVESTIGATIONS SOW         | Define a detailed Field Investigation Plan.   |
| Engineering             | DESIGN OPTIMIZATIONS             | Optimize the 2006 preliminary designs based on results of the field program.  |
|                         | UPDATED PRELIMINARY ENGINEERING  | Complete preliminary design based on the optimizations.   |
|                         | MTOs                             | Update the Facility MTO's and the quantities in the cost estimate and schedule duration calculations, based on the update Preliminary Engineering.  |
|                         | CONTRACTING STRATEGY             | Based on Hydro's selected Contracting Strategy, prepare a Project Contracting Strategy document, identify standard contract documentation and procurement processes.                          |
| Supply Chain Management | <b>BID &amp; EVALUATION PLAN</b> | Prepare a plan which documents standard contract documentation, the bid management process, including bid evaluation plans, approval authorities, etc   |
|                         | LONG-LEAD ITEMS VENDOR PACKAGES  | Issue vendor packages and obtain quotations / delivery timelines for Long Lead Items.   |
|                         | FIELD INVESTIGATIONS PLAN        | Issue PO for Field Investigation Activities.  |
|                         | CM STRATEGY                      | Prepare and implement a Field Investigation Program Execution Plan based on the scope of work prepared by engineering. Prepare Construction Management Plan based on the Contracting Strategy |
| Construction            | PATH OF CONSTRUCTION             | Undertake Construction Planning activities necessary to develop the Path of Construction (sequencing).  |
|                         | CONSTRUCTION SCHEDULE            | Based on the Path of Construction, update construction schedule.  |

|             | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|-------------|---------------------------------------|-----|-------------|------|
|             | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC+LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-47 |

### 3. SCOPE OF WORK TO COMPLETE FEEP STAGE

### 3.1. PURPOSE

This section outlines the scope of work ("SOW") necessary to advance the 2006 SLI Feasibility Study to meet industry-standard FEEP-level documentation requirements for this prospect, including updates to cost and schedule.

### 3.2. OWNER'S KEY INPUTS

At the start of the FEEP stage, it is recommended that the Owner provide the Project Team(s) with a Project Charter, approved Environmental Management Strategy, and approved FEEP Stage Budget, Deliverables List and Milestone Schedule.

### 3.3. PROJECT DEFINITION STATEMENT UPDATE SCOPE OF WORK

The scope of work for the Project Definition stage consists of the following.

- A detailed review of hydrology taking into consideration potential climate change impacts.
- A calculation of the options for Power and Energy scenarios, culminating in Hydro's selection of the preferred combination.

### 3.4. PROJECT TEAM FEEP-STAGE SCOPE OF WORK

### 3.4.1. Project Management Discipline

The key Project Management Team deliverable is a *Front-end Execution Plan (FEEP)*, which incorporates the following key documentation.

- Based on the scope of work outlined in existing documentation, and the design optimizations to be
  prepared (see 3.3.3. Engineering below), prepare an updated <u>Project Scope of Work Document</u>
  (SOW) and <u>Work Breakdown Structure</u> (WBS).
- Based on the updated SOW, prepare a Front-End Execution Plan (FEEP). A key part of the plan is the Contracting Strategy, which includes a Project Delivery Model, Compensation Model, and Sourcing Strategy.
- Based on the SOW and WBS, develop the following key sections of the FEEP:
  - Project Management Approach
  - Project Controls Strategy
  - Health, Safety and Security
  - Quality Management Strategy
- Coordinate the preparation of the following by other disciplines.
  - Environmental Management Plan
  - Engineering Management Plan
  - Procurement Management Strategy
  - Contracting Strategy
  - Construction Management Strategy
  - Construction Sequencing Plan

|             | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|-------------|---------------------------------------|-----|-------------|------|
|             | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-48 |

- Work Packaging Plan
- Coordinate the preparation of the following Project Controls Documentation.
  - Using the existing schedule data, revised WBS and Work Packaging Plan, develop and optimize a <u>L3 Project Schedule and Schedule Basis</u>, incorporating EIA and Long Lead timelines provided by vendors. The <u>Level 3 (L3) Project Schedule should include</u>:
    - L4 Project Management Schedule and Schedule Basis.
    - L4 Environmental Management Schedule and Schedule Basis.
    - L4 Engineering Management Schedule and Schedule Basis.
    - L3 Bid Stage Schedule and Schedule Basis.
    - L3 Construction Schedule and Schedule Basis with Monte Carlo Simulation which incorporates updated long lead item delivery timelines.
  - <u>Class 3 Cost Estimate, Estimate Basis, and Risk Analysis</u>, e.g., Monte Carlo Simulation. Update the existing Cost Estimate based on updated WBS / Work Package Plan, the facility optimizations, and revisions to the indirect scope of work, plus updated unit, and material / equipment cost.

Note: At the present stage of planning, the following key timelines and impacts remain unknown:

- Environmental Approval Process and relates impacts on cost and schedule.
- Owner's Planning and Approval Process.
- Detailed Engineering Resource availability.
- Major Equipment availability and cost.

### 3.4.2. Environmental Discipline

The Environmental discipline shall:

- Prepare an Environmental Management Plan.
- Prepare a robust Environmental Registration Document.

### 3.4.3. Engineering Discipline

The Engineering discipline shall:

- Prepare a <u>Scope of Work for Field Investigation Program</u> for immediate execution by Construction, including the preparation and submission of applications for permits to carry out the field work.
- Prepare and implement an Engineering Management Plan, including L4 Engineering Schedule and Schedule Basis.
- Key Engineering activities to be undertaken are:
  - Interpretation and reporting of the field investigation results.
  - Update vendor packages for the Long-Lead Items.
  - Based on the updated Project Definition Statement and data gathered during the winter and summer field programs, undertake design optimizations / preliminary reviews as recommended in the SLI 2006 report, which include:
    - Update the forebay and tailrace preliminary design and MTO, based on the bedrock profile.

|             | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|-------------|---------------------------------------|-----|-------------|------|
|             | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-49 |

- Review the Dam, Powerhouse and Dyke preliminary designs based on the geotechnical data.
- Preliminary Design of the 3.4 km of Channel Improvements in Meelpaeg Reservoir and Island Pond Reservoir based on the bathymetric and geotechnical data including detailed quantity calculations for an MTO.
- Preliminary Designs the HADD Facilities and prepare an MTO.
- Quantify Aggregate sources, including HADD grave, and prepare quantities for Pit development.
- Identify areas of Acid Generating Rock (AGR) and develop the necessary mitigation measures.
- Update existing scope of work information and prepare a Facility Scope of Work document.
- Update existing preliminary designs and develop into preliminary engineering work packages, by discipline, including updated MTOs. The EWPs shall support the Work Packaging Plan.
- Assess the impacts of the construction activities on operations and work with the Owner's operations team to develop mitigations.

### 3.4.4. Procurement Discipline

The Procurement discipline shall prepare and implement a *Procurement Management Plan*, Key procurement activities are:

- Working with the Owner to finalize standard contract documentation and procurement processes.
- Working with PM and Construction discipline to develop a Contracting Plan.
- Preparation of a L3 Bid Schedule and Schedule basis.
- Issue vendor packages and obtain quotations / delivery timelines for Long Lead Items.
- Prepare and issue POs for Field Program.

### 3.4.5. Construction Discipline

In the Project Definition Statement update, the construction discipline shall prepare and implement a Field Investigation Program Execution Plan, based on the scope of work provided by Engineering. The plan shall include:

- L4 Field Investigation Schedule and Basis
- Class 2 Field Investigation Cost Estimate and Basis
- Upon approval, execute the field investigation program, with functional management from engineering.

The Construction team shall prepare and implement a <u>Construction Management Plan</u>. Key aspects of the plan are:

• Define the Path of Construction<sup>6</sup> and optimize the construction sequencing.

<sup>&</sup>lt;sup>6</sup> The Path of Construction is defined as the optimal sequencing of the building of a facility, developed by Construction, Engineering and Project Management Subject Matter Experts (SMEs), typically working backwards from the "end state".

|             | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|-------------|---------------------------------------|-----|-------------|------|
|             | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-50 |

- Prepare the L3 Construction Schedule and Basis.
- Prepare a plan for monitoring and control of construction contractor activities.
- Review and update the indirect direct scope of work to reflect current market conditions and the selected project delivery model.
- Work with the Owner to develop mitigations to minimize the impact of construction activities on existing operations.

|             | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|-------------|---------------------------------------|-----|-------------|------|
|             | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC+LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-51 |

### 4. PROJECT-SPECIFIC RISKS

The 2006 SLI report "Studies for Island Pond Hydroelectrical Project" has a detailed review of technical risk for the project. This section identifies similar risks and concerns.

### 4.1. ENVIRONMENTAL RISK

A review of the federal and provincial Environmental Regulatory and Approval context for the proposed NL Hydro Generation Expansion prospects is included in **APPENDIX D**.

The 2006 report indicates that the key environmental concern is the disruption to fish habitat. Fish habitat studies were undertaken in 2006, but extensive discussion between all parties is required before the level of effort to complete this assessment can be determined.

A high-level assessment of the environmental management strategy undertaken as a part of this study suggests that up to three (3) years will be required to obtain environmental approval, placing this process on the schedule critical path.

Regarding reservoir clearing, there may be technical limitations on being able to clear the full area required. More recent imagery may help refine area to be cleared and help understand the accessibility of those areas.

The 2006 SLI report identifies the need for a more rigid evaluation of potential spoil areas to understand potential impacts. There are five (5) spoil areas currently identified for potential use.

### 4.2. SOCIOECONOMIC INFLUENCES

Socioeconomic influences for the proposed prospects are also discussed in APPENDIX D.

### 4.3. MARKET CONDITIONS

As the project is relatively small by hydro standards, Contractor Capability / Availability should not be an issue (there are several local contractors who could undertake this work).

### 4.4. LONG-LEAD ITEMS RISK

Due to the small size of the Turbine / Generator, Supply Chain issues should be manageable and are unlikely to seriously impact the schedule. However, the design, manufacturing, and installation timeline being quoted in 2022 by North American suppliers for the Turbine / Generator is 30 months for this type of T / G. In the 2006 SLI report, this lead time was only 18 months and was still considered a schedule risk.

### 4.5. TECHNICAL RISK

### 4.5.1. Hydrotechnical

The hydrology for Island Pond is out of date. The hydrology should be updated to a common time base with other projects under review so that a valid comparison can be made between projects. This should be used to update the power and energy study, which will also allow confirmation of the main project characteristics (dam height and type, spillway capacity, installed capacity, etc.).

The review of hydrology should consider the potential impact of climate change over the life of the project, and this should be taken into consideration in finalizing designs.

Previous studies identified the need to improve flow characteristics (channel improvements) in the reservoirs and approach channels. The diversion canal was optimized in a study in 1988 but has not been updated since. Updated bathymetry will be required to set up flow models to revisit the previous design and determine if the improvements are possible. This should also consider the risk of ice effects and methods to mitigate this risk.

|              | APPENDIX C – PROSPECT 3               |     | Revision    |      |
|--------------|---------------------------------------|-----|-------------|------|
|              | ISLAND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SINC+LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001  | 01  | 21-OCT-2022 | C-52 |

### 4.5.2. Geotechnical

A geotechnical Field Investigation Program was identified in the 2006 SLI report to address the risk of unknown geotechnical conditions for the facilities. This program should be reviewed prior to implementation to ensure it addresses all concerns.

The issue of potential for the rock to be acid-generating needs to be addressed (the extent of the problem and a plan to address). This can be a complex issue to deal with, as described in the 2006 SLI study.

The field investigations carried out in 2006 stated that excavated rock from the forebay canal and intake/powerhouse and other excavations would not be suitable for concrete. Suitable sources of concrete aggregate were identified but it should be verified that they are close, assessable and have sufficient quantities of material available. Similarly, sources for other construction materials should be confirmed.

During the 2006 field work, rock samples were identified as having acid generating properties. This can be quantified during the next field program and mitigation measures can be incorporated into the earthwork's specifications. A \$1.0 million allowance was added to the 2006 cost estimate.

### 4.5.3. Technical Complexity

A Roller Compacted Concrete (RCC) dam was suggested for consideration in the previous study. This should be assessed in light of recent Muskrat Falls experience. The commentary on RCC vs. Conventional Mass Concrete (CVC) should be updated to consider recent advancements in RCC construction. Alternative dam types should be considered to ensure most cost-effective solution.

The Turbine SME concurs that the 36 MW turbine would not require a model test to optimize efficiency.

Transmission line requirements are different from the 2006 SLI report assumptions (see the 2018 Transmission System Review document. These should be reviewed to verify technical requirements and costs.

Ground resistivity measurements must be performed to allow design of the earthing grid. This should be performed in conjunction with the Field Investigation Program in order to finalize the design.

The dewatering scheme for the diversion canal construction should be revisited to understand risks related to cofferdam sizing and location and to finalize optimum routing and configuration. The Forebay Canal should also be reviewed. These reviews should consider environmental concerns, as identified in previous reports.

The powerhouse cofferdam is the only critical dewatering facility that may be at risk of an unforeseen flood event. Construction during the summer is the least cost mitigation.

### 4.6. PROJECT COST RISK

The 2006 SLI report reviewed aspects of "commercial risk" that included significant wage increase trends in the labour market. At this time, the largest risk factors to cost (and, in some respects, to schedule) will be volatility in fuel costs, contractor capacity (availability of human resources, both technical and construction), and the potential for excessive cost escalation due to local market conditions and global factors.

### 4.7. PROJECT SCHEDULE RISK

The 2006 SLI report identified "scheduling considerations" as a key risk, with specific factors including the need to expedite the Environmental Approval Process and Project Registration, pre-ordering of construction camp units, and T / G delivery time slippage (see **SECTION 4.4** above).

# **APPENDIX C**

# **PROSPECT 4**

# ROUND POND HYDROELECTRIC DEVELOPMENT

PROSPECT OVERVIEW, GAP ANALYSIS & RISKS

|             | APPENDIX C – PROSPECT 4              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ROUND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC+LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | C-54 |

## **TABLE OF CONTENTS**

| 1. | PROSPECT 4 OVERVIEW: ROUND POND HYDROELECTRIC              |             |
|----|--|-------------|
|    | DEVELOPMENT  | C-55        |
|    | 1.1. LOCATION AND BACKGROUND                               | 55          |
|    | 1.2. PROJECT DESCRIPTION                                   | 56          |
|    | 1.3. PROPOSED LAYOUT                                       | 56          |
|    | 1.4. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022) | 58          |
|    | 1.5. KEY TECHNICAL METRICS                                 | 58          |
| 2. | EXISTING PROJECT INFORMATION DATA GAP                      | C-59        |
|    | 2.1. OVERVIEW  | 59          |
|    | 2.2. DATA GAP  | 59          |
| 3. | SCOPE OF WORK TO COMPLETE FEEP STAGE                       | C-62        |
|    | 3.1. PURPOSE   | 62          |
|    | 3.2. OWNER'S FEEP-STAGE SCOPE OF WORK                      | 62          |
|    | 3.3. PROJECT DEFINITION STATEMENT UPDATE                   | 62          |
|    | 3.4. PROJECT TEAM FEEP-STAGE SCOPE OF WORK                 | 62          |
|    | 3.4.1. Project Management Discipline                       | 62          |
|    | 3.4.2. Environmental Discipline                            | 63          |
|    | 3.4.3. Engineering Discipline                              | 63          |
|    | 3.4.4. Procurement Discipline                              | 64          |
|    |  | 64<br>C C C |
| 4. |  | C-05        |
|    | 4.1. ENVIRONMENTAL RISK                                    | 65          |
|    | 4.2. SOCIOECONOMIC INFLUENCES                              | 65          |
|    | 4.3. MARKET CONDITIONS                                     | 65          |
|    | 4.4. LONG-LEAD ITEMS RISK                                  | 65          |
|    | 4.5. TECHNICAL RISK  | 65          |
|    | 4.5.1. Hydrotechnical                                      | 65          |
|    | 4.5.2. Geotechnical  | 65          |
|    | 4.5.3. Technical Complexity                                | 65          |
|    | 4.6. PROJECT COST RISK                                     | 65          |
|    | 4.7. PROJECT SCHEDULE RISK                                 | 65          |

|                    | APPENDIX C – PROSPECT 4              |     | Revision    |      |
|--------------------|--------------------------------------|-----|-------------|------|
|                    | ROUND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| <b>SNC+LAVALIN</b> | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | C-55 |

### 1. PROSPECT 4 OVERVIEW: ROUND POND HYDROELECTRIC DEVELOPMENT

### 1.1. LOCATION AND BACKGROUND

In 1988, Shawinigan Newfoundland Limited carried out a final feasibility study of the Round Pond Development (see **FIGURE C4.1**) with the key objective of establishing an accurate cost estimate. Shawinigan's scope of work included the following.

- Hydrological Studies
- Site Surveys and Geotechnical investigations
- Preliminary designs and optimizations
- Cost Estimate and Schedule Timelines

Conceptual layouts

Concurrent with Shawinigan's work, Hydro carried out a review of terminals, transmission, telecontrol and equipment requirements.<sup>1</sup> In 2012, Hatch was retained to update the cost estimate and schedule from 1988.<sup>2</sup>



FIGURE C4.1 PROJECT LOCATION – ROUND POND

<sup>&</sup>lt;sup>1</sup> Feasibility Study – Round Pond Development Summary Report. NL Hydro Engineering Dept., February 1989.

<sup>&</sup>lt;sup>2</sup> Round Pond Hydroelectric Development – Update of the 1988 Cost Estimate. Hatch Report H341357-0000-00-218-0001, May 7, 2012.

|                    | APPENDIX C – PROSPECT 4              |     | Revision    |      |
|--------------------|--------------------------------------|-----|-------------|------|
|                    | ROUND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| <b>SNC·LAVALIN</b> | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | C-56 |

### 1.2. PROJECT DESCRIPTION

The proposed generation facility would utilize the available head of approximately 12 m between the Godaleich Pond and Long Pond Reservoir. The development would consist of the following.

- Generation Facilities
  - Close-Coupled Powerhouse / Intake 18 MW Bulb (Pit) Turbine Generator
  - Power Canal
  - Tailrace
- Reservoir
  - Main Dam
  - Gated Spillway
  - Saddle Dams 1, 2 & 3
- Access
  - Main Access Road
  - Access to Saddle Dam 3
- Temporary Facilities
  - Access / Bridges
  - Cofferdams
  - Laydowns
  - Camp Site
  - Camp Facilities
  - Construction Power
  - Fuel Storage
- Transmission
  - 66 kV Switchyard
  - 44 km of 69 kV Transmission Line
  - Telecontrol
- Environmental Infrastructure
  - Fish Passageway

### 1.3. PROPOSED LAYOUT

The layout proposed for the Round Pond development is reproduced in FIGURE C.3.2 below.

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 105 of 158

|               | APPENDIX C – PROSPECT 4              | Revision |             |      |
|---------------|--------------------------------------|----------|-------------|------|
|               | ROUND POND HYDROELECTRIC DEVELOPMENT | Rev      | Date        | Page |
| SNC · LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01       | 21-OCT-2022 | C-57 |



FIGURE C4.2: ROUND POND PROPOSED LAYOUT

|             | APPENDIX C – PROSPECT 4              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ROUND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | C-58 |

### 1.4. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022)

The 2012 cost update by Hatch was further updated in 2018 by Hydro and escalated to YE-2022 as shown in **TABLE C4-1**. (Note that Environmental Mitigation costs were not addressed in the reports.)

### TABLE C4-1: ROUND POND COST ESTIMATE ESCALATED TO YE-2022

| COST ITEM   | AMOUNT        | NOTES   |  |
|---|---------------|---|--|
| Material Supply                                     | \$3,115,000   | From Hydro's 2018 update of Hatch 2012 update   |  |
| Labour  | \$16,613,200  | ""  |  |
| Consultant  | \$20,766,500  | " "   |  |
| Contract Work                                       | \$145,215,800 | ""  |  |
| Other Direct Costs                                  | \$1,038,300   | " "   |  |
| Interest  | \$23,842,400  | " "   |  |
| Contingency   | \$37,349,700  | ""  |  |
| Total Cost (2018)                                   | \$247,940,800 | " "   |  |
| Escalation calculation (2018-2022)                  | 132 5%        | 2019: 2.2% 2020: 1.2% 2021: 11.4%<br>Statistics Canada Construction Cost Index (CCPI) |  |
|   | 132.370       | 2022: 15%<br>Projection by SLI Cost Estimating Department                             |  |
| 2022 TOTAL ESCALATED COST                           | \$328,541,560 |   |  |
| AACE Estimate Accuracy<br>(Index of 1 = +10% / -5%) | +50% / -25%   | Class 4 accuracy index range = 3 to 12<br>Index for this estimate assumed = 5         |  |

### 1.5. KEY TECHNICAL METRICS

The following key technical metrics were used in the Screening and Ranking Process.

- Power (MW Installed): One (1) Bulb (Pit) Turbine Generators with Installed Capacity 18 MW
- Cost per MW of Power (escalated to YE-2022): \$18.3 million / MW
- Overall Project Duration : 5.6 Years

|   |      | ~     |      |        |      |       |     |       |  |     |       |     |
|---|------|-------|------|--------|------|-------|-----|-------|--|-----|-------|-----|
| • | Exe  | cutio | n (C | onstr  | ucti | on) T | ime | line: |  | 3.3 | 8 Yea | irs |
| • | Plar | nning | Tim  | neline | :    |       |     |       |  | 3.0 | ) Yea | irs |

- Less Overlap Planning/Execution: <u>-0.7 Year</u>
- Overall Development Timeline: 5.6 Years

|             | APPENDIX C – PROSPECT 4              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ROUND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | C-59 |

### 2. EXISTING PROJECT INFORMATION DATA GAP

### 2.1. OVERVIEW

While the 1989 study was considered a Feasibility Study, it is suggested the existing project documentation be considered Project Definition level, given it is thirty-seven (37) years old.

### 2.2. DATA GAP

A complete review and update of the project definition, followed by a FEEP study is recommended. The updated project definition should be based on updated Hydrological data and recalculated power and energy availability, including selection of the Turbine Generator unit and related equipment. Included in this stage should be the project registration for the environmental assessment process and a preliminary field investigation program.

The 1989 study, Section 7, indicates that the project was registered with the department of environment in 1987 and environmental concerns were fish habitat, waterfowl breeding habitat, caribou, raptors and moose and the minster required that an EIS be prepared. The environmental registration information is missing from the project data provided for this study.

To advance this work to a *Front-End Execution Planning (FEEP) standard*, the following gaps remain (see **TABLE C4-2**).

|                         | Page                                 | C-60                                 |
|-------------------------|--------------------------------------|--------------------------------------|
| Revision                | Date                                 | 21-OCT-2022                          |
|                         | Rev                                  | 01                                   |
| APPENDIX C – PROSPECT 4 | ROUND POND HYDROELECTRIC DEVELOPMENT | SLI Doc. No. 691499-0000-40ER-I-0001 |
|                         |                                      | SNC+LAVALIN                          |

# TABLE C4-2: GAP ANALYSIS FOR PROSPECT 3: ROUND POND

| STAGE 1: PROJECT DE   | FINITION                          |   |
|-----------------------|-----------------------------------|---|
| RESPONSIBLE GROUP     | DELIVERABLE                       | REQUIREMENTS TO ADDRESS GAP   |
|                       | PROJECT DEFINITION STATEMENT      | Undertake the Hydrotechnical Review.<br>Plan and Execute the Field Investigation Program, including environmental field work.<br>Optimize the Scheme and Prepare a new Class 5 Cost estimate and L2 Schedule. |
| Owner / Corporate     | PROJECT CHARTER                   | Prepare a Project Charter including selection of a Contracting Strategy.<br>Develop the Environmental Management Strategy.<br>Approve FEEP Stage Budget, Deliverables List and Milestone Schedule.            |
| STAGE 2: FEEP         |                                   |   |
| RESPONSIBLE GROUP     | DELIVERABLE                       | REQUIREMENTS TO ADDRESS GAP   |
|                       | PROJECT EXECUTION PLAN (PEP)      |   |
|                       | Scope of Work                     | Update Scope Work document based on completed field data and update preliminary design / MTOs.  |
|                       | Project Management Strategy       | Key elements of the execution strategy will need to be reviewed and updated based on the selected Project Delivery Model.   |
|                       | Project Controls Strategy         | Determine how cost estimating and schedule development activities are going to be coordinated.  |
| Project Management    | Health & Safety Strategy          | Prepare HS&S Project Strategy.  |
|                       | QA / QC Strategy                  | Prepare Quality Management Strategy.  |
|                       | PROJECT CONTROLS DOCUMENTATION    |   |
|                       | Cost Estimate (Class 4 / Class 3) | Update based on updated contracting strategy, schedule, design optimizations, updated unit costs and costs for Long-Lead items and the cost of implementing the Environmental Protection Plan.                |
|                       | Schedule                          | Prepare L2 based on updated MTOs, Timelines for long-lead items, Environmental timelines, Construction Sequencing, and Contracting Strategy.  |
| Twitten montel Mennes | ENVIRONMENTAL MANAGEMENT PLAN     | Based on the Environmental Management Strategy, develop a detailed Management Plan.   |
| спугоптела маладетел  | <b>PROJECT REGISTRATION / EIS</b> | Prepare a robust Project Registration Document.   |
|                       |                                   |   |

|                         | Page                                 | C-61                                 |
|-------------------------|--------------------------------------|--------------------------------------|
| Revision                | Date                                 | 21-OCT-2022                          |
|                         | Rev                                  | 10                                   |
| APPENDIX C – PROSPECT 4 | ROUND POND HYDROELECTRIC DEVELOPMENT | SLI Doc. No. 691499-0000-40ER-I-0001 |
|                         |                                      | SNC+LAVALIN                          |

ſ

|                         | FACILITY SCOPE OF WORK          | Prepare a Facility Scope of Work.  |
|-------------------------|---------------------------------|--|
|                         | PRELIMINARY ENGINEERING         | Prepare and optimize Preliminary Designs.  |
|                         | FIELD INVESTIGATIONS SOW        | Included in Project Definition Update.   |
| Engineering             | DESIGN OPTIMIZATIONS            | Included in Preliminary Engineering above.   |
|                         | UPDATED PRELIMINARY ENGINEERING | Included in Preliminary Engineering above.   |
|                         | MTOs                            | Prepare MTOs.  |
|                         | CONTRACTING STRATEGY            | Work with PM and Construction discipline to document the Contracting Plan.   |
| Supply Chain Management | BID & EVALUATION PLAN           | Prepare Plan and work with the Owner to finalize standard contract documentation and procurement processes.<br>Prepare Bid Plan. |
|                         | LONG-LEAD ITEMS VENDOR PACKAGES | Issue Vendor Packages and obtain quotations / delivery times for Long-Lead Items.  |
|                         | FIELD INVESTIGATIONS PLAN       | Included in Project Definition Update.   |
|                         | CM STRATEGY                     | Based on the Project Delivery Method, and Project Execution Plan, prepare a Construction Management Strategy.                    |
|                         | PATH OF CONSTRUCTION            | Define the Path of Construction and optimize the construction sequencing.  |
|                         | CONSTRUCTION SCHEDULE           | Prepare a L3 construction Schedule and Basis.  |
|                         |                                 |  |

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 109 of 158

| с.     |  |
|--------|--|
| valin  |  |
| SNC-La |  |

|                         | Page                                 | C-60                                 |
|-------------------------|--------------------------------------|--------------------------------------|
| Revision                | Date                                 | 21-OCT-2022                          |
|                         | Rev                                  | 01                                   |
| APPENDIX C – PROSPECT 4 | ROUND POND HYDROELECTRIC DEVELOPMENT | SLI Doc. No. 691499-0000-40ER-I-0001 |
|                         |                                      | SNC+LAVALIN                          |

# TABLE C4-2: GAP ANALYSIS FOR PROSPECT 3: ROUND POND

| STAGE 1: PROJECT DE   | FINITION                          |   |
|-----------------------|-----------------------------------|---|
| RESPONSIBLE GROUP     | DELIVERABLE                       | REQUIREMENTS TO ADDRESS GAP   |
|                       | PROJECT DEFINITION STATEMENT      | Undertake the Hydrotechnical Review.<br>Plan and Execute the Field Investigation Program, including environmental field work.<br>Optimize the Scheme and Prepare a new Class 5 Cost estimate and L2 Schedule. |
| Owner / Corporate     | PROJECT CHARTER                   | Prepare a Project Charter including selection of a Contracting Strategy.<br>Develop the Environmental Management Strategy.<br>Approve FEEP Stage Budget, Deliverables List and Milestone Schedule.            |
| STAGE 2: FEEP         |                                   |   |
| RESPONSIBLE GROUP     | DELIVERABLE                       | REQUIREMENTS TO ADDRESS GAP   |
|                       | PROJECT EXECUTION PLAN (PEP)      |   |
|                       | Scope of Work                     | Update Scope Work document based on completed field data and update preliminary design / MTOs.  |
|                       | Project Management Strategy       | Key elements of the execution strategy will need to be reviewed and updated based on the selected Project Delivery Model.   |
|                       | Project Controls Strategy         | Determine how cost estimating and schedule development activities are going to be coordinated.  |
| Project Management    | Health & Safety Strategy          | Prepare HS&S Project Strategy.  |
|                       | QA / QC Strategy                  | Prepare Quality Management Strategy.  |
|                       | PROJECT CONTROLS DOCUMENTATION    |   |
|                       | Cost Estimate (Class 4 / Class 3) | Update based on updated contracting strategy, schedule, design optimizations, updated unit costs and costs for Long-Lead items and the cost of implementing the Environmental Protection Plan.                |
|                       | Schedule                          | Prepare L2 based on updated MTOs, Timelines for long-lead items, Environmental timelines, Construction Sequencing, and Contracting Strategy.  |
| Twitten montel Mennes | ENVIRONMENTAL MANAGEMENT PLAN     | Based on the Environmental Management Strategy, develop a detailed Management Plan.   |
| спугоптела маладетел  | <b>PROJECT REGISTRATION / EIS</b> | Prepare a robust Project Registration Document.   |
|                       |                                   |   |

|                         | Page                                 | C-61                                 |
|-------------------------|--------------------------------------|--------------------------------------|
| Revision                | Date                                 | 21-OCT-2022                          |
|                         | Rev                                  | 10                                   |
| APPENDIX C – PROSPECT 4 | ROUND POND HYDROELECTRIC DEVELOPMENT | SLI Doc. No. 691499-0000-40ER-I-0001 |
|                         |                                      | SNC+LAVALIN                          |

ſ

| Engineering       PRELIMINARY ENGINEERING         Engineering       FIELD INVESTIGATIONS SOW         DESIGN OPTIMIZATIONS       DESIGN OPTIMIZATIONS         MTOS       UPDATED PRELIMINARY ENGINE         MTOS       MTOS         Supply Chain Management       BID & EVALUATION PLAN | IRINGPrepare and optimize Preliminary Designs.Image: SowIncluded in Project Definition Update.Image: SowIncluded in Preliminary Engineering above.Image: SomIncluded in Preliminary Engineering above.Image: Prepare MTOs.Prepare MTOs.Image: SomWork with PM and Construction discipline to document the Contracting Plan. |
|--|---|
| Engineering       FIELD INVESTIGATIONS SOW         Engineering       DESIGN OPTIMIZATIONS         DESIGN OPTIMIZATIONS       UPDATED PRELIMINARY ENGINE         MTOS       MTOS         Supply Chain Management       BID & EVALUATION PLAN  | SOWIncluded in Project Definition Update.SIncluded in Preliminary Engineering above.Y ENGINEERINGIncluded in Preliminary Engineering above.Prepare MTOs.Mork with PM and Construction discipline to document the Contracting Plan.  |
| Engineering     DESIGN OPTIMIZATIONS       UPDATED PRELIMINARY ENGINE       MTOS       MTOS       CONTRACTING STRATEGY       Supply Chain Management       BID & EVALUATION PLAN   | S     Included in Preliminary Engineering above.       Y ENGINEERING     Included in Preliminary Engineering above.       Prepare MTOs.     Work with PM and Construction discipline to document the Contracting Plan.  |
| UPDATED PRELIMINARY ENGINE         MTOS         MTOS         CONTRACTING STRATEGY         Supply Chain Management         BID & EVALUATION PLAN  | Y ENGINEERING       Included in Preliminary Engineering above.         Prepare MTOs.       Prepare MTOs.         Cork with PM and Construction discipline to document the Contracting Plan.   |
| MTOS<br>CONTRACTING STRATEGY<br>Supply Chain Management BID & EVALUATION PLAN  | Prepare MTOs.         Work with PM and Construction discipline to document the Contracting Plan.  |
| CONTRACTING STRATEGY<br>Supply Chain Management BID & EVALUATION PLAN  | GY Work with PM and Construction discipline to document the Contracting Plan.   |
| Supply Chain Management BID & EVALUATION PLAN  |   |
|  | Prepare Plan and work with the Owner to finalize standard contract documentation and procurement processes.<br>Prepare Bid Plan.  |
| LONG-LEAD ITEMS VENDOR PA(   | DOR PACKAGES Issue Vendor Packages and obtain quotations / delivery times for Long-Lead Items.  |
| FIELD INVESTIGATIONS PLAN  | PLAN Included in Project Definition Update.   |
| Construction<br>Construction   | Based on the Project Delivery Method, and Project Execution Plan, prepare a Construction Management Strategy.   |
|  | <b>Define the Path of Construction and optimize the construction sequencing.</b>  |
| CONSTRUCTION SCHEDULE  | <b>DULE</b> Prepare a L3 construction Schedule and Basis.   |

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 111 of 158

| с.     |  |
|--------|--|
| valin  |  |
| SNC-La |  |

| •)          | APPENDIX C – PROSPECT 4              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ROUND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | C-62 |

### 3. SCOPE OF WORK TO COMPLETE FEEP STAGE

### 3.1. PURPOSE

This section outlines the scope of work necessary to update Project Definition Stage and then prepare the FEEP-stage scope of work. This assumes that the Hydrotechnical review will redefine the Power and Energy configuration and, therefore, reopen a Project Scheme review. A Field Investigation is proposed to be undertaken during Project Definition such that the FEEP stage can be executed in an uninterrupted workflow.

### 3.2. OWNER'S KEY INPUTS

The key input required here is Hydro's internal assessment of its projected power and energy needs, followed by the preparation of a Project Charter, approved Environmental Management Strategy, and approved FEEP Stage Budget, Deliverables List, and Milestone Schedule.

### 3.3. PROJECT DEFINITION STATEMENT UPDATE SCOPE OF WORK

The scope of work consists of the following.

- Development of an Environmental Management Strategy. Note: Section 7 of the 1989 Feasibility Study indicates that the project was registered in 1987 resulting in the need for an Environmental Impact Statement. Like Island Pond, Fish Habit is the key environmental concern. Other noted concerns were waterfowl breeding habitat, caribou, raptors, and moose.
- A detailed review of hydrology taking into consideration potential climate change impacts.
- A calculation of the options for Power and Energy scenarios, cumulating in Hydro's selection of the preferred combination.
- Review and Optimization of the project scheme.
- Planning and execution of Field Investigation Program, including key field work to support component studies which are likely to be required to address potential environmental concerns.
- Prepare new Class 5 Cost Estimate and L2 Schedule based on the optimized scheme.
- Preparation of a Project Charter, including the selection of a Contracting Strategy.
- Approved FEEP Stage Scope of Work and Cost Estimate and Schedule.

### 3.4. PROJECT TEAM FEEP-STAGE SCOPE OF WORK

### 3.4.1. Project Management Discipline

The key Project Management Team deliverable is a *Front-end Execution Plan (FEEP)*, which incorporates the following key documentation.

- Based on the project definition documentation, prepare an updated <u>Project Scope of Work Document</u> (SOW) and <u>Work Breakdown Structure</u> (WBS).
- Based on the updated scope of work, prepare a Front-End Execution Plan (FEEP). Key aspect of the FEEP is the contracting strategy which details the project delivery model, compensation model, and sourcing strategy.
- Based on the SOW and WBS, develop the following key sections of the FEEP:
  - Project Management Approach, based on the project delivery model.
  - Project Controls Strategy

|             | APPENDIX C – PROSPECT 4              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ROUND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | C-63 |

- Health, Safety and Security
- Quality Management Strategy
- Coordinate the preparation of the following by other disciplines.
  - Environmental Management Plan
  - Engineering Management Plan
  - Procurement Management Strategy
  - Contracting Strategy
  - Construction Management Strategy
  - Construction Sequencing Plan
  - Work Packaging Plan
- Coordinate the preparation of the following Project Controls Documentation.
  - Using the existing schedule data, revised WBS and Work Packaging Plan, develop and optimize a <u>L3 Project Schedule and Schedule Basis</u>, incorporating EIA and Long Lead timelines provided by vendors. The <u>Level 3 (L3) Project Schedule should include</u>:
    - L4 Project Management Schedule and Schedule Basis
    - L4 Environmental Management Schedule and Schedule Basis
    - L4 Engineering Management Schedule and Schedule Basis
    - L3 Bid Stage Schedule and Schedule Basis
    - L3 Construction Schedule and Schedule Basis with Monte Carlo Simulation which incorporates updated long lead item delivery timelines
  - <u>Class 3 Cost Estimate, Estimate Basis, and Risk Analysis</u>, e.g., Monte Carlo Simulation. Update the existing Cost Estimate based on updated WBS / Work Package Plan, the facility optimizations, and revisions to the indirect scope of work, plus updated unit, and material / equipment cost.

### 3.4.2. Environmental Discipline

The Environmental discipline shall:

- Prepare an Environmental Management Plan.
- Prepare a robust Environmental Registration Document.

### 3.4.3. Engineering Discipline

The engineering discipline shall:

• Prepare and implement an Engineering Management Plan, including L4 Engineering Schedule and Schedule Basis.

Key Engineering activities to be undertaken are:

- Prepare facility Scope of Work
- Preliminary Engineering and Design Optimizations
- Preparation of MTOs

|             | APPENDIX C – PROSPECT 4              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ROUND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | C-64 |

• Update the Facility Scope of Work

### 3.4.4. Procurement Discipline

The Procurement discipline shall prepare and implement a <u>Procurement Management Plan</u>, Key procurement activities are:

- Issue vendor packages and obtain quotations / delivery timelines for Long Lead Items.
- Work with PM and Construction discipline to document the contracting strategy.
- Work with the Owner to finalize standard contract documentation and procurement processes.
- Preparation of a L3 Bid Schedule and Schedule basis.

### 3.4.5. Construction Discipline

The Construction team shall prepare and implement a <u>Construction Management Plan</u>. Key aspects of the plan are:

- Define the Path of Construction<sup>3</sup> and optimize the construction sequencing.
- Prepare the L3 Construction Schedule and Basis.
- Review and update the indirect direct scope of work to reflect current market conditions and the selected project delivery model.
- Develop a Work Packaging Plan.

<sup>&</sup>lt;sup>3</sup> The Path of Construction is defined as the optimal sequencing of the building of a facility, developed by Construction, Engineering and Project Management Subject Matter Experts (SMEs), typically working backwards from the "end state".

|             | APPENDIX C – PROSPECT 4              |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ROUND POND HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC+LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | C-65 |

### 4. PROJECT-SPECIFIC RISKS

### 4.1. ENVIRONMENTAL RISK

A review of the federal and provincial Environmental Regulatory and Approval context for the proposed NL Hydro Generation Expansion prospects is included in **APPENDIX D**.

### 4.2. SOCIOECONOMIC INFLUENCES

Socioeconomic influences for the proposed prospects are also discussed in **APPENDIX D**.

### 4.3. MARKET CONDITIONS

As the project is relatively small by hydro standards, Contractor Capability / Availability should not be an issue (there are several local contractors who could undertake this work).

### 4.4. LONG-LEAD ITEMS RISK

Due to the small size of the Turbine / Generator, Supply Chain issues should be manageable and are unlikely to seriously impact the schedule.

### 4.5. TECHNICAL RISK

### 4.5.1. Hydrotechnical

It is recommended that the hydrology be updated to reflect current data and forecasted climate considerations.

### 4.5.2. Geotechnical

Should the Hydrotechnical review result in a change to the project Power and Energy configuration, then updates to the scheme will likely necessitate a detailed geotechnical investigation. The existing geotechnical information was not available for this screening & ranking assessment, further comment would not be warranted, although a Google Earth review indicates the present of cut lines, access trails, etc., so it would appear that an extensive program was undertaken for the present scheme.

### 4.5.3. Technical Complexity

Generally the project is not technical complex. In-depth Environmental Mitigations will be required, however, and these will impact cost and schedule. Numerous stream crossings are required, most of which will be temporary, and other temporary diversions will be necessary for construction. While there are a large number a earthworks-related facilities, the volume of earthmoving will be small.

The North Access to the project area will probably have the least impact, as there appears to be a forestrytype road to within 3 km of the site.

### 4.6. PROJECT COST RISK

Like Prospect 3: Island Pond, the largest risk factors to cost (and, in some respects, to schedule) will be volatility in fuel costs, contractor capacity (availability of human resources, both technical and construction), and the potential for excessive cost escalation due to local market conditions and global factors.

### 4.7. PROJECT SCHEDULE RISK

The 2018 Hydro report identified environmental and regulatory approvals; detailed design and tendering of the water-to-wire (W2W) package; design, manufacturing and delivery of the W2W equipment; and W2W equipment installation and commissioning are key schedule risks. These remain valid in 2022.

# **APPENDIX C**

# **PROSPECT 5**

# PORTLAND CREEK HYDROELECTRIC DEVELOPMENT

PROSPECT OVERVIEW, GAP ANALYSIS & RISKS

## **TABLE OF CONTENTS**

| 1. | PROSPECT 5 OVERVIEW: PORTLAND CREEK HYDROELECTRIC<br>DEVELOPMENT | C-68 |
|----|--|------|
|    | 1.1. LOCATION AND BACKGROUND                                     | 68   |
|    | 1.2. PROJECT DESCRIPTION   | 69   |
|    | 1.3. PROPOSED LAYOUT   | 69   |
|    | 1.4. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022)       | 71   |
|    | 1.5. KEY TECHNICAL METRICS                                       | 72   |
| 2. | EXISTING PROJECT INFORMATION DATA GAP                            | C-73 |
|    | 2.1. OVERVIEW  | 73   |
|    | 2.2. DATA GAP  | 73   |
| 3. | SCOPE OF WORK TO COMPLETE FEEP STAGE                             | C-76 |
|    | 3.1. PURPOSE   | 76   |
|    | 3.2. OWNER'S KEY INPUTS  | 76   |
|    | 3.3. PROJECT DEFINITION STATEMENT UPDATE SCOPE OF WORK           | 76   |
|    | 3.4. PROJECT TEAM FEEP-STAGE SCOPE OF WORK                       | 76   |
|    | 3.4.1. Project Management Discipline                             | 76   |
|    | 3.4.2. Environmental Discipline                                  | 77   |
|    | 3.4.3. Engineering Discipline                                    | 77   |
|    | 3.4.4. Procurement Discipline                                    | 78   |
|    | 3.4.5. Construction Discipline                                   | 78   |
| 4. | PROJECT-SPECIFIC RISKS   | C-79 |
|    | 4.1. ENVIRONMENTAL RISK  | 79   |
|    | 4.2. SOCIOECONOMIC INFLUENCES                                    | 79   |
|    | 4.3. MARKET CONDITIONS   | 79   |
|    | 4.4. LONG-LEAD ITEMS RISK  | 79   |
|    | 4.5. TECHNICAL RISK  | 79   |
|    | 4.5.1. Hydrotechnical  | 79   |
|    | 4.5.2. Geotechnical  | 79   |
|    | 4.5.3. Technical Complexity                                      | 80   |
|    | 4.6. PROJECT COST RISK   | 80   |
|    | 4.7. PROJECT SCHEDULE RISK                                       | 80   |

|             | APPENDIX C – PROSPECT 5                  |     | Revision    |      |
|-------------|--|-----|-------------|------|
|             | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001     | 01  | 21-OCT-2022 | C-68 |

### 1. PROSPECT 5 OVERVIEW: PORTLAND CREEK HYDROELECTRIC DEVELOPMENT

### 1.1. LOCATION AND BACKGROUND

The proposed Portland Creek Hydroelectric Development ("Portland Creek") is located near Daniel's Harbour on the west side of the Great Northern Peninsula on the island of Newfoundland, specifically on Main Port Brook, a tributary of Portland Creek (see **FIGURE C5.1**). A pre-feasibility study for the development was completed in 1987, followed by a full Feasibility study in 2007.<sup>1</sup>



FIGURE C5.1 PROJECT LOCATION – PORTLAND CREEK

<sup>&</sup>lt;sup>1</sup> Feasibility Study for Portland Creek Hydroelectric Project. SNC-Lavalin Project No. 722736, January 2007.

|             | APPENDIX C – PROSPECT 5                  |     | Revision    |      |
|-------------|--|-----|-------------|------|
|             | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001     | 01  | 21-OCT-2022 | C-69 |

### 1.2. PROJECT DESCRIPTION

Several drawings from the 2007 Feasibility Study are reproduced in **FIGURE C5.3** on the following page. The proposed project consists of the following key components.

Generation Facility

• Water Conveyance System

Control Structures

• Transmission Facilities

The Generation Facility consists of a 17 m x 14 m Powerhouse with a concrete substructure and steel superstructure with two (2) Pelton Turbines Generator, each with a rated output of 11.5 MW.

Control Structures include a 110 m long concrete gravity Diversion Dam and overflow spillway with a crest length of 70 m and maximum height of 12 m; a 320 m long Diversion Canal that transfers flows from a Diversion Pond into the main storage reservoir; a 45 m long concrete gravity Storage Dam including a flow regulating structure fitted with a trash rack; and a 143 m long Headpond Dam with maximum height of 15 m, including a power intake structure fitted with a trash rack and an overflow spillway.

The Water Conveyance System consists of a 2900 m long, 1.52 m diameter penstock to convey water from the Headpond Dam to the Powerhouse.

Transmission Facilities in the original concept consist of a 27 km long 66 kV transmission line connecting a 66 kV switchyard to the existing substation at Peter's Barren.

### 1.3. PROPOSED LAYOUT

In the 2007 Feasibility Study, site access was planned from the Daniel's Harbour Mine Road, approximately 18 km from the proposed Powerhouse. An additional 12 km of access road would have been required through the watershed, but, today, the access road built for the new Labrador Island Link (LIL) eliminates the need to build access to Daniel's Harbour. The revised layout is summarized in **FIGURE C5.2** below.



FIGURE C5.2 PORTLAND CREEK LAYOUT INCLUDING NEW LIL ACCESS ROAD
### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 120 of 158

|               | APPENDIX C – PROSPECT 5                  |     | Revision    |      |
|---------------|--|-----|-------------|------|
|               | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC · LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001     | 01  | 21-OCT-2022 | C-70 |



### FIGURE C5.3 PORTLAND CREEK DEVELOPMENT DRAWINGS FROM 2007 FEASIBILITY STUDY

|             | APPENDIX C – PROSPECT 5                  |     | Revision    |      |
|-------------|--|-----|-------------|------|
|             | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001     | 01  | 21-OCT-2022 | C-71 |

### 1.4. COST ESTIMATE TO BUILD PROJECT (ESCALATED TO YE-2022)

In 2018, Hydro updated the cost estimate<sup>2</sup> for Portland Creek by escalating a 2012 estimate update<sup>3</sup> by SLI from the 2007 Feasibility Study. Here, 2018 costs were escalated to YE-2022 as shown in **TABLE C5-1**.

### TABLE C5-1: PORTLAND CREEK COST ESTIMATE ESCALATED TO YE-2022

| COST ITEM   | AMOUNT        | NOTES   |  |  |
|---|---------------|---|--|--|
| Material Supply                                     | \$3,245,800   | From 2012 estimate escalated to 2018 by Hydro.  |  |  |
| Labour  | \$17,344,700  | ""  |  |  |
| Consultant  | \$21,674,200  | ""  |  |  |
| Contract Work                                       | \$154,770,300 | ""  |  |  |
| Other Direct Costs                                  | \$1,083,700   | ""  |  |  |
| Interest  | \$24,071,400  | ""  |  |  |
| Contingency   | \$39,623,700  | " "   |  |  |
| Total Cost (2018)                                   | \$261,813,751 | " "   |  |  |
| Escalation calculation (2018 2022)                  | 132 5%        | 2019: 2.2% 2020: 1.2% 2021: 11.4%<br>Statistics Canada Construction Cost Index (CCPI) |  |  |
|   | 132.370       | 2022: 15%<br>Projection by SLI Cost Estimating Department                             |  |  |
| 2022 TOTAL ESCALATED COST                           | \$346,903,220 |   |  |  |
| AACE Estimate Accuracy<br>(Index of 1 = +10% / -5%) | +50% / -25%   | Class 5 accuracy index range = 4 to 20<br>Index for this estimate assumed = 5         |  |  |

<sup>&</sup>lt;sup>2</sup> *Island Pond Hydroelectric Development*. NL Hydro, August 29, 2018.

<sup>&</sup>lt;sup>3</sup> Portland Creek and Island Pond Hydroelectric Projects Update Cost Estimates. SNC-Lavalin 501325-40ER-0001-PA, May 2012.

|             | APPENDIX C – PROSPECT 5                  |     | Revision    |      |
|-------------|--|-----|-------------|------|
|             | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001     | 01  | 21-OCT-2022 | C-72 |

### 1.5. KEY TECHNICAL METRICS

The following key technical metrics were developed from the above information and used in the Screening and Ranking Process.

- Power (MW Installed): Two (2) Pelton Turbine Generators with Installed Capacity 23 MW
- Cost per MW of Power (escalated to YE-2022): \$15.1 million / MW
- Overall Project Duration : 6.3 Years

| • | Planning Timeline:                 | 3.2 Years      |
|---|------------------------------------|----------------|
| • | Execution (Construction) Timeline: | 3.1 Years      |
| • | Less Overlap Planning/Execution:   | <u>0 Years</u> |
| • | Overall Development Timeline:      | 6.3 Years      |

|             | APPENDIX C – PROSPECT 5                  |     | Revision    |      |
|-------------|--|-----|-------------|------|
|             | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001     | 01  | 21-OCT-2022 | C-73 |

### 2. EXISTING PROJECT INFORMATION DATA GAP

### 2.1. OVERVIEW

To prepare the 2007 Feasibility Study, an initial Field Program was undertaken and access options were assessed. The key recommendation pertaining to this Gap Analysis (from Appendix D of that study) is that further Field Investigation work is required, estimated to cost in the range of \$400,000 (2007 dollars) and including the following tasks.

Assessment of the HADD requirements and solutions.

Additional geotechnical work in the Powerhouse area.

Further confirmation of Borrow Pit and Aggregate sources.

The initial access resulted in the upgrading and new construction of approximately 40 km of roadway. Today, the Labrador-Island Link (LIL) Access Road passes within 0.5 km of the division structure and only access to the remaining structure plus the powerhouse is required, saving considerable capital expenditure.

Therefore, in terms of the preparing a Scope of Work for a FEEP study, the above-noted information has been accounted for in updating to the cost estimate and schedule.

In addition, a hydrological review undertaken as a part of this study indicates that a new review should be undertaken to account for the potential impact of climate change. Therefore, an update to the Project Definition statement is also included.

### 2.2. DATA GAP

To advance this work to a *Front-End Execution Planning (FEEP) standard*, the following gaps remain (see **TABLE C5-2**).

|                         | Page                                     | C-74                                 |  |
|-------------------------|--|--------------------------------------|--|
| Revision                | Date                                     | 21-OCT-2022                          |  |
|                         | Rev                                      | 10                                   |  |
| APPENDIX C – PROSPECT 5 | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | SLI Doc. No. 691499-0000-40ER-I-0001 |  |
| SNC • LAVALIN           |  |                                      |  |

# TABLE C5-2: GAP ANALYSIS FOR PROSPECT 5: PORTLAND CREEK

| STAGE 1: PROJECT DE      | FINITION                          |  |
|--------------------------|-----------------------------------|--|
| <b>RESPONSIBLE GROUP</b> | DELIVERABLE                       | REQUIREMENTS TO ADDRESS GAP  |
| Owner / Corporate        | PROJECT DEFINITION STATEMENT      | Update Hydrology, then identify Power / Energy options<br>Selection of preferred Power / Energy Option.<br>Identify preferred option for site access and transmission line routing.<br>Update Project Scheme.                                      |
|                          | PROJECT CHARTER                   | Develop Project Charter as per standard for internal approval and sign-off, including recommended Contracting Strategy.<br>Develop the Environmental Management Strategy.<br>Approve FEEP-Stage Budget, Deliverables List, and Milestone Schedule. |
| STAGE 2: FEEP            |                                   |  |
| <b>RESPONSIBLE GROUP</b> | DELIVERABLE                       | REQUIREMENTS TO ADDRESS GAP  |
|                          | PROJECT EXECUTION PLAN (PEP)      |  |
|                          | Scope of Work                     | Update based on optimized preliminary designs.   |
|                          | Project Management Strategy       | Key elements of the execution strategy will need to be reviewed and updated based on the selected Project Delivery Model.  |
|                          | Project Controls Strategy         | Determine how cost estimating and schedule development activities are going to be coordinated.   |
| Project Management       | Health & Safety Strategy          | Prepare HS&S Project Strategy.   |
|                          | QA / QC Strategy                  | Prepare Quality Management Strategy.   |
|                          | PROJECT CONTROLS DOCUMENTATION    |  |
|                          | Cost Estimate (Class 4 / Class 3) | Update based on updated contracting strategy, schedule, design optimizations, updated unit costs and costs for Long-Lead items and the cost of implementing the Environmental Protection Plan.   |
|                          | Schedule                          | Prepare L2 based on updated MTOs, Timelines for long-lead items, Environmental timelines, Construction Sequencing, and Contracting Strategy.   |
|                          | ENVIRONMENTAL MANAGEMENT PLAN     | Based on the Environmental Management Strategy, develop a detailed Management Plan.  |

SNC-Lavalin Inc.

|                         | Page                                     | C-75                                 |
|-------------------------|--|--------------------------------------|
| Revision                | Date                                     | 21-OCT-2022                          |
|                         | Rev                                      | 01                                   |
| APPENDIX C – PROSPECT 5 | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | SLI Doc. No. 691499-0000-40ER-I-0001 |
|                         |  | SNC+LAVALIN                          |

| Environmental Management | <b>PROJECT REGISTRATION / EIS</b> | Prepare Robust Environmental Registration Document  |
|--------------------------|-----------------------------------|---|
|                          | FACILITY SCOPE OF WORK            | Update the Facility Scope of Work document based revised project scheme and the optimized design.   |
|                          | PRELIMINARY ENGINEERING           | Update / optimize the preliminary engineering based on the revised scheme, including a review of the penstock access road to determine its suitabil for use a main access road to the powerhouse Prepare Vendor Packages for the Long Lead Items. |
| Engineering              | FIELD INVESTIGATIONS SOW          | Prepare Field Program Scope of Work.  |
| )                        | DESIGN OPTIMIZATIONS              | Based on the results of the field investigations, optimize the preliminary designs. Prepare Preliminary EWPs.   |
|                          | UPDATED PRELIMINARY ENGINEERING   | Develop the optimized designs into preliminary EWPs.  |
|                          | MTOS                              | Update the MTOs and incorporate quantities into the cost estimate and schedule duration calculations.   |
|                          | CONTRACTING STRATEGY              | Work with PM and Construction discipline to document the Contracting Plan.  |
| Supply Chain Management  | BID & EVALUATION PLAN             | Prepare a plan which documents standard contract documentation, the bid management process, including bid evaluation plans, approval authorities, etc   |
| )                        | LONG-LEAD ITEMS VENDOR PACKAGES   | Issue vendor packages and obtain quotations / delivery timelines for Long Lead Items.   |
|                          | FIELD INVESTIGATIONS PLAN         | Issue PO for Field Investigation Activities.  |
|                          | CM STRATEGY                       | Prepare and Implement a Field Investigation Program Execution Plan based on the scope of work prepared by engineering. Prepare Construction Management Plan based on the Contracting Strategy   |
| Construction             | PATH OF CONSTRUCTION              | Undertake Construction Planning activities necessary to develop the Path of Construction (sequencing).  |
|                          | CONSTRUCTION SCHEDULE             | Based on the Path of Construction, update construction schedule.  |
|                          |                                   |   |

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 125 of 158

|             | APPENDIX C – PROSPECT 5                  |     | Revision    |      |
|-------------|--|-----|-------------|------|
|             | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001     | 01  | 21-OCT-2022 | C-76 |

### 3. SCOPE OF WORK TO COMPLETE FEEP STAGE

### 3.1. PURPOSE

This section outlines the scope of work necessary to update Project Definition Stage and then prepare the FEEP-stage scope of work. This assumes that the Hydrotechnical review will redefine the Power and Energy configuration and, therefore, reopen a Project Scheme review. A Field Investigation is proposed to be undertaken during Project Definition such that the FEEP stage can be executed in an uninterrupted workflow.

### 3.2. OWNER'S KEY INPUTS

The key input required here is Hydro's internal assessment of its projected power and energy needs, followed by the preparation of a Project Charter, approved Environmental Management Strategy, and approved FEEP Stage Budget, Deliverables List, and Milestone Schedule.

### 3.3. PROJECT DEFINITION STATEMENT UPDATE SCOPE OF WORK

The following key activities are included.

- 1. Development of a revised access plan.
- Review / update of existing preliminary designs, based on the revised hydrology and Power / Energy requirements, including a review of the access road along the Penstock to determine if it can serve as the main access to the Powerhouse.
- 3. Plan and implement a Field Investigation Program.
- 4. Revise activities 1. and 2.
- 5. Prepare a Class 5 Cost Estimate.
- 6. Preparation of documentation to support the Environmental Management Strategy.

### 3.4. PROJECT TEAM FEEP-STAGE SCOPE OF WORK

### 3.4.1. Project Management Discipline

The key Project Management Team deliverable is a *Front-end Execution Plan (FEEP)*, which incorporates the following key documentation.

- Based on the scope of work outlined in existing documentation, and the design optimizations to be
  prepared (see 3.3.3. Engineering below), prepare an updated <u>Project Scope of Work Document</u>
  (SOW) and <u>Work Breakdown Structure</u> (WBS).
- Based on the updated SOW, prepare a Front-End Execution Plan (FEEP). A key part of the plan is the Contracting Strategy, which includes a Project Delivery Model, Compensation Model, and Sourcing Strategy.
- Based on the SOW and WBS, develop the following key sections of the FEEP:
  - Project Management Approach
  - Project Controls Strategy
  - Health, Safety and Security
  - Quality Management Strategy
- Coordinate the preparation of the following by other disciplines.

|                    | APPENDIX C – PROSPECT 5                  | Revision |             |      |
|--------------------|--|----------|-------------|------|
| <b>SNC·LAVALIN</b> | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev      | Date        | Page |
|                    | SLI Doc. No. 691499-0000-40ER-I-0001     | 01       | 21-OCT-2022 | C-77 |

- Environmental Management Plan
- Engineering Management Plan
- Procurement Management Strategy
- Contracting Strategy
- Construction Management Strategy
- Construction Sequencing Plan
- Work Packaging Plan
- Coordinate the preparation of the following Project Controls Documentation.
  - Using the existing schedule data, revised WBS and Work Packaging Plan, develop and optimize a <u>L3 Project Schedule and Schedule Basis</u>, incorporating EIA and Long Lead timelines provided by vendors. The <u>Level 3 (L3) Project Schedule should include</u>:
    - L4 Project Management Schedule and Schedule Basis.
    - L4 Environmental Management Schedule and Schedule Basis.
    - L4 Engineering Management Schedule and Schedule Basis.
    - L3 Bid Stage Schedule and Schedule Basis.
    - L3 Construction Schedule and Schedule Basis with Monte Carlo Simulation which incorporates updated long lead item delivery timelines.
  - <u>Class 3 Cost Estimate, Estimate Basis, and Risk Analysis</u>, e.g., Monte Carlo Simulation. Update the existing Cost Estimate based on updated WBS / Work Package Plan, the facility optimizations, and revisions to the indirect scope of work, plus updated unit, and material / equipment cost.

### 3.4.2. Environmental Discipline

The Environmental discipline shall:

- Prepare an Environmental Management Plan.
- Prepare a robust Environmental Registration Document.

### 3.4.3. Engineering Discipline

The engineering discipline shall:

• Prepare and implement an Engineering Management Plan, including L4 Engineering Schedule and Schedule Basis.

Key Engineering activities to be undertaken are:

- Prepare Facility Scope of Work.
- Preliminary Engineering and Design Optimizations.
- Preparation of MTOs
- Update the Facility Scope of Work.

|                    | APPENDIX C – PROSPECT 5                  |     | Revision    |      |
|--------------------|--|-----|-------------|------|
| ♥))<br>SNC+LAVALIN | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
|                    | SLI Doc. No. 691499-0000-40ER-I-0001     | 01  | 21-OCT-2022 | C-78 |

### **3.4.4. Procurement Discipline**

The Procurement discipline shall prepare and implement a Procurement Management Plan, Key procurement activities are:

- Issue vendor packages and obtain quotations / delivery timelines for Long Lead Items.
- Work with PM and Construction discipline to document the contracting strategy.
- Work with the Owner to finalize standard contract documentation and procurement processes.
- Preparation of a L3 Bid Schedule and Schedule basis.

### **3.4.5.** Construction Discipline

The Construction team shall prepare and implement a Construction Management Plan. Key aspects of the plan include:

- Define the Path of Construction<sup>4</sup> and optimize the construction sequencing.
- Prepare the L3 Construction Schedule and Basis.
- Review and update the indirect direct scope of work to reflect current market conditions and the selected project delivery model.
- Develop a Work Packaging Plan.

<sup>&</sup>lt;sup>4</sup> The Path of Construction is defined as the optimal sequencing of the building of a facility, developed by Construction, Engineering and Project Management Subject Matter Experts (SMEs), typically working backwards from the "end state".

| <b>NC · LAVALIN</b> | APPENDIX C – PROSPECT 5                  | Revision |             |      |
|---------------------|--|----------|-------------|------|
|                     | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev      | Date        | Page |
|                     | SLI Doc. No. 691499-0000-40ER-I-0001     | 01       | 21-OCT-2022 | C-79 |

### 4. PROJECT-SPECIFIC RISKS

### 4.1. ENVIRONMENTAL RISK

A review of the federal and provincial Environmental Regulatory and Approval context for the proposed NL Hydro Generation Expansion prospects is included in **APPENDIX D**.

### 4.2. SOCIOECONOMIC INFLUENCES

Socioeconomic influences for the proposed prospects are discussed in **APPENDIX D**. This Brownfield project is remote and socioeconomic influences will likely be positive.

### 4.3. MARKET CONDITIONS

The project start date is assumed to be some years away, so it is difficult to comment on market conditions.

### 4.4. LONG-LEAD ITEMS RISK

The selected T/G selection is not difficult to procure and will not be the critical path for construction.

### 4.5. TECHNICAL RISK

### 4.5.1. Hydrotechnical

The hydrology for Portland Creek is out of date. The hydrology should be updated to a common time base with other projects under review so that a valid comparison can be made between projects. This should be used to update the power and energy study, which will also allow confirmation of the main project characteristics (dam height and type, spillway capacity, installed capacity, etc.).

The potential for sudden torrents on rivers and streams in the area should be investigated to understand risk.

### 4.5.2. Geotechnical

The 2007 feasibility study had proposed an extensive geotechnical program that was significantly reduced and that study was to make use of previous information. There is a risk that the assumptions made were based on information that was not valid. It is important that adequate geotechnical field investigations be undertaken to determine if changes are required to the assumptions and designs from the 2007 study.

The 2007 study stated that the material excavated from the diversion canal should be suitable for concrete aggregate, but testing has not been done to validate this assumption, nor the suitability of other potential aggregate sources identified. The study did state that there are abundant materials, should they be suitable.

The previous study commented that the area is well-suited for a concrete gravity dam, but that foundation grouting will be required. Additional information is required to help assess the extent of grouting that might be required to adequately seal the foundations in the required locations.

The 2007 study geotechnical information provided the assumption that 1H:4V for excavation in rock, but with further investigation on the strength of the rock, a steeper slope could be possible. This could result in cost savings to the project. Adequate geotechnical information is required to assess this.

The geotechnical section of the 2007 study commented on the risk of avalanches, river torrents (during extreme rainfall) and areas of Karst topography, which may affect construction access and the penstock route.

An initial review of potential acid generating rock was examined as part of the previous study, but this should be validated as part of any further geotechnical investigations.

|               | APPENDIX C – PROSPECT 5                  |     | Revision    |      |
|---------------|--|-----|-------------|------|
| SNC · LAVALIN | PORTLAND CREEK HYDROELECTRIC DEVELOPMENT | Rev | Date        | Page |
|               | SLI Doc. No. 691499-0000-40ER-I-0001     | 01  | 21-OCT-2022 | C-80 |

### 4.5.3. Technical Complexity

Siting of dams, powerhouse and penstock route should be reviewed and optimized with updated geotechnical information and information from updated power and energy study.

### 4.6. PROJECT COST RISK

This project is not technically complex nor difficult to construct. Sound planning and engineering, with a sanction estimate based on bid prices, should address the risk of cost or schedule overruns.

### 4.7. PROJECT SCHEDULE RISK

It is assumed for construction schedule purposes that no work will take place in the winter, except T/L construction to Peter's Barrens. If this must change, considerable cost and schedule risk will result.

### APPENDIX C

### **PROSPECT 6**

### **EXPLOITS RIVER HYDROELECTRIC DEVELOPMENTS**

**PROSPECT OVERVIEW, GAP ANALYSIS & RISKS** 

|               | APPENDIX C – PROSPECT 6                   | Revision |             |      |
|---------------|---|----------|-------------|------|
| SNC · LAVALIN | EXPLOITS RIVER HYDROELECTRIC DEVELOPMENTS | Rev      | Date        | Page |
|               | SLI Doc. No. 691499-0000-40ER-I-0001      | 01       | 21-OCT-2022 | C-82 |

### **TABLE OF CONTENTS**

| 1. | PROSPECT 6 OVERVIEW: EXPLOITS RIVER HYDROELECTRIC |      |
|----|---|------|
|    | DEVELOPMENTS                                      | C-83 |
|    | 1.1. LOCATION AND BACKGROUND                      | 83   |
|    | 1.2. REDUCED STUDY SCOPE FOR PROSPECT 6           | 84   |
|    | 1.3. PROJECT DESCRIPTION                          | 84   |
|    | 1.4. KEY TECHNICAL METRICS                        | 84   |
| 2. | EXISTING PROJECT INFORMATION DATA GAP             | C-85 |

|               | APPENDIX C – PROSPECT 6                   | Revision |             |      |
|---------------|---|----------|-------------|------|
| SNC · LAVALIN | EXPLOITS RIVER HYDROELECTRIC DEVELOPMENTS | Rev      | Date        | Page |
|               | SLI Doc. No. 691499-0000-40ER-I-0001      | 01       | 21-OCT-2022 | C-83 |

### 1. PROSPECT 6 OVERVIEW: EXPLOITS RIVER HYDROELECTRIC DEVELOPMENTS

### 1.1. LOCATION AND BACKGROUND

Prospect 6 includes two (2) subprojects on the Exploits River at the locations of Red Indian Falls and Badger Chute (see **FIGURE C6.1**), which have long been recognized as potential hydro resources. Both subprojects have been studied at a high level, with the most recent reviews dating from 2018<sup>1</sup> and 2005.<sup>2</sup> The 2018 report suggests that both projects are "reasonably viable", but with the following caveat.

"(T)here are significant concerns surrounding the potential environmental, socioeconomic and archeological impacts associated with these developments. The full extent of these impacts and their associated mitigation costs will need to be understood prior to the completion of an accurate assessment. It is uncertain at this time as to whether or not either of these alternatives would receive approval as part of the Environmental Assessment Process."



FIGURE C6.1 PROJECT LOCATION – EXPLOITS RIVER PROSPECTS

<sup>&</sup>lt;sup>1</sup> *Exploits River Hydroelectric Generation Expansion*. NL Hydro, September 5, 2018.

<sup>&</sup>lt;sup>2</sup> Exploits River Hydro Potential (Red Indian Falls, Badger Chute & Four Mile Pond) Preliminary Project Assessment. NL Hydro, January 28, 2005.

|               | APPENDIX C – PROSPECT 6                   | Revision |             |      |
|---------------|---|----------|-------------|------|
| SNC · LAVALIN | EXPLOITS RIVER HYDROELECTRIC DEVELOPMENTS | Rev      | Date        | Page |
|               | SLI Doc. No. 691499-0000-40ER-I-0001      | 01       | 21-OCT-2022 | C-84 |

### 1.2. REDUCED STUDY SCOPE FOR PROSPECT 6

Based on Hydro's 2018 assessment of the Exploits River subprojects and the Project Team's review of available information, it was determined that Prospect 6 did not warrant the same level of investigation as the other prospects. Considerable technical and environmental work (at high cost) will be required before the economic viability can be properly assessed. There also appears to be considerable risk in obtaining social licence for the subprojects, given the concerns surrounding the environmental, socioeconomic and archeological impacts associated with the developments.

This level of study will require considerable upfront expenditure. While it is likely that many of the issues can be mitigated, it is more likely that other alternatives on the island, particularity on the southwestern side of the Great Northern Peninsula, present viable alternatives with considerably less environmental impact and an improved opportunity of obtaining social licence.

### 1.3. PROJECT DESCRIPTION

Red Indian Falls would see the construction of a 42 MW hydroelectric generating facility 20 km upstream of the Town of Badger. Generation would be achieved through the use of two (2) vertical Francis turbines.

Badger Chute consists of the construction of a 24 MW hydroelectric generating facility 7 km downstream of the Town of Badger. Generation would be achieved with three (3) vertical Francis turbines.

It was noted in the 2018 study that the development of Badger Chute has the potential to increase ice formation and elevate the risk of flooding for the Town of Badger. However, the construction of Red Indian Falls would, conversely, reduce (if not eliminate) the flooding problem. For this reason, Badger Chute would need to be completed in conjunction with (or closely following on the completion of) Red Indian Falls. This condition would likely further complicate obtaining social licence for the developments.

### 1.4. KEY TECHNICAL METRICS

The following key technical metrics were developed from the available information on the subprojects and used in the Screening and Ranking Process.

### Red Indian Falls

- Power (MW Installed): Two (2) x Francis Turbines delivering 42 MW
- Cost (escalated to YE-2022): \$329,444,713
- Cost per MW of Power (escalated to YE-2022): \$13.7 million / MW

### **Badger Chute**

- Power (MW Installed): One (1) x 62.2 MW Pelton Turbine
- Cost (escalated to YE-2022):: \$520,237,859
- Cost per MW of Power (escalated to YE-2022): \$12.4 million / MW

|                    | APPENDIX C – PROSPECT 6                   |     | Revision    |      |
|--------------------|---|-----|-------------|------|
| <b>SNC·LAVALIN</b> | EXPLOITS RIVER HYDROELECTRIC DEVELOPMENTS | Rev | Date        | Page |
|                    | SLI Doc. No. 691499-0000-40ER-I-0001      | 01  | 21-OCT-2022 | C-85 |

### 2. EXISTING PROJECT INFORMATION DATA GAP

For the Exploits River prospects (Red Indian Falls and Badger Chute), the normal planning and engineering activities for Project Definition and Front-End Execution Planning (FEEP), as detailed for the other prospects, would also be applicable.

However, the level of planning and engineering required to support the Environmental Assessment Process for these prospects will likely be very significant in terms of definition and scoping, but also very challenging in determining the cost and schedule implications. This is beyond the scope of the current study. Therefore, the scope of work to undertake the Project Definition and FEEP stages cannot be estimated at this time.

It is suggested that a Project Definition Statement be prepared for each Exploits River prospect by a joint team of planners, engineers and environmental SMEs. A full understanding of the potential impacts is necessary to assess the FEEP scope of work.



| APPENDIX D                           |     |             |      |
|--------------------------------------|-----|-------------|------|
| ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-1  |

### **APPENDIX D**

### ENVIRONMENTAL APPROVALS AND PERMITTING

|               | APPENDIX D                           | Revision |             |      |
|---------------|--------------------------------------|----------|-------------|------|
| SNC · LAVALIN | ENVIRONMENTAL APPROVALS & PERMITTING | Rev      | Date        | Page |
|               | SLI Doc. No. 691499-0000-40ER-I-0001 | 01       | 21-OCT-2022 | D-2  |

### **TABLE OF CONTENTS**

| 1. OVERVIEW   | D-3  |
|---|------|
| 2. PROVINCIAL ENVIRONMENTAL ASSESSMENT (EA)                       | D-4  |
| 2.1. OVERVIEW   | 4    |
| 2.2. ROBUST REGISTRATION DOCUMENT                                 | 6    |
| 2.3. ALTERNATIVE APPROACH: CLASS EA                               | 6    |
| 3. FEDERAL IMPACT ASSESSMENT ACT                                  | D-7  |
| 4. PERMIT REQUIREMENTS  | D-10 |
| 4.1. FISHERIES ACT (FEDERAL)                                      | 10   |
| 4.2. CERTIFICATE OF APPROVAL FOR ALTERATIONS TO A BODY OF WATER   | 10   |
| 4.3. WATER USE LICENCE  | 11   |
| 4.4. WASTE MANAGEMENT   | 11   |
| 4.5. WILDERNESS AND ECOLOGICAL RESERVES REGULATIONS               | 12   |
| 4.6. SPECIES AT RISK ACT AND MIGRATORY BIRDS CONVENTION (FEDERAL) | 12   |
| 4.7. CANADIAN NAVIGABLE WATERS ACT (FEDERAL)                      | 12   |
| 4.8. ADDITIONAL PERMITS AND LICENCES – OPERATIONAL PHASE          | 12   |
| 5. SOCIOECONOMIC INFLUENCES                                       | D-14 |
| 6. TIMELINES  | D-15 |
| 7. CLIMATE CHANGE   | D-16 |

|             | APPENDIX D                           |     | Revision    | 1    |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-3  |

### 1. OVERVIEW

**APPENDIX D** is a review of the federal and provincial Environmental Regulatory and Approval context for the proposed NL Hydro Generation Expansion Prospects. For the purposes of the regulatory approval process, the prospects under consideration have been grouped into two (2) broad categories.

Brownfield Projects (expansion of generating capacity of existing facilities)

- 1. Bay d 'Espoir (BDE) Unit 8
- 2. Cat Arm Addition

Greenfield Projects (development and construction of new facilities)

- 3. Island Pond
- 4. Round Pond
- 5. Portland Creek (plus the potential for adjacent watersheds, referred to as Northern Peninsula West)
- 6. Exploits River
  - Red Indian Falls
  - Badger Chute

Each project would have to undergo a provincial Environmental Assessment ("EA") under the Newfoundland and Labrador *Environmental Assessment Regulations* (NLR 54/03) issued under the *Environmental Protection Act* (SNL 2002, c. E-14.2). In addition, various federal and provincial environmental permits will be required for each project, as discussed below.

|             | APPENDIX D                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-4  |

### 2. PROVINCIAL ENVIRONMENTAL ASSESSMENT (EA)

### 2.1. OVERVIEW

Development of a hydroelectric generating plant or expansion of an existing plant both constitute "designated undertakings" listed in Part III of the *Environmental Assessment Regulations*. As such, both brownfield and greenfield projects must be registered for environmental assessment because they include multiple activities listed under "Utilities" (clause 34) of the Regulations.

- 34.(1) An undertaking that will be engaged in electric power generation and the provision of structures related to that power generation, including
  - (a) the construction of dams and associated reservoirs where the area to be flooded is more than 50 hectares;
  - (b) the excavation of reservoirs where the area to be flooded is more than 50 hectares;
  - (c) inter-basin or intra-basin water transfers;
  - (d) the construction of hydroelectric power developments with a capacity of more than one megawatt shall be registered.

### [portions deleted]

(2) An undertaking that will be engaged in the construction of new electric power transmission lines or the relocation or realignment of existing lines where a portion of a new line will be located more than 500 metres from an existing right of way shall be registered.

Any hydroelectric project currently under consideration, whether brownfield or greenfield, will "trigger" various aspects of the EA process and permitting requirements based on reservoir size, generating capacity, and other characteristics unique to each project. Trigger factors are summarized in **TABLE D-1**.

Within 45 days of receiving a registration, the Minister will advise the proponent of the decision on the undertaking. The following are possible decisions.

- Undertaking released (45 days from registration).
- Environmental Preview Report (EPR) (estimated 1.5 years from registration).
- Environmental Impact Statement (EIS) (estimated 3-3.5 years from registration).
- Undertaking rejected

Based on conversations with Rod Healey, Manager Environment Operations with NL Hydro, the requirements for the proposed "brownfield" projects are likely to consist primarily of permit applications and approvals. These projects are likely to be "released" from further assessment under the provincial EA process. The anticipated length from registration to approval, including required permit approvals, is approximately six (6) months.

The "greenfield" projects may be assessed under either an EPR or EIS process. However, instead of submitting a basic registration document and awaiting the Minister's decision regarding whether to proceed with an EPR or EPS, NL Hydro's approach in recent years has been to submit a "robust" registration document. This approach may lead to a more rapid approval, as detailed below.

|            | Page                                 | D-5                                  |
|------------|--------------------------------------|--------------------------------------|
| Revision   | Date                                 | 21-0CT-2022                          |
|            | Rev                                  | 01                                   |
| APPENDIX D | ENVIRONMENTAL APPROVALS & PERMITTING | SLI Doc. No. 691499-0000-40ER-I-0001 |
|            |                                      | SNC+LAVALIN                          |

TABLE D-1 SUMMARY OF ENVIRONMENTAL ASSESSMENT TRIGGER ACTIVITIES

| TRIGGER ACTIVITY  | PROSPECT 1  | PROSPECT 2  | PROSPECT 3                         | PROSPECT 4                         | PROSPECT 5                              | PROSPECT 6: E                      | XPLOITS RIVER                      |
|---|---|---|------------------------------------|------------------------------------|---|------------------------------------|------------------------------------|
|   | BDE UNIT 8  | CAT ARM   | ROUND POND                         | ISLAND POND                        |   | BADGEK<br>CHUTE                    | KEU INDIAN<br>FALLS                |
| Construction of dams and reservoirs > 50 ha (0.5 km²)   | No new construction   | No  | Yes (800 ha)                       | Yes                                | Yes                                     | Yes                                | Yes                                |
| Excavation of reservoirs > 50 ha (0.5 km²)  | No  | No  | No                                 | No                                 | No                                      | No                                 | Q                                  |
| Inter-basin or intra-basin water transfers  | No (existing)   | No  | No                                 | No                                 | No                                      | No                                 | No                                 |
| Construction of hydroelectric power<br>developments > 1 MW  | Yes<br>150 MW increase  | Yes<br>68.2 MW increase   | New construction<br>18 MW          | New construction<br>36 MW          | New construction<br>23 MW               | New construction<br>24 MW          | New construction<br>42 MW          |
| Construction of new electric power lines or<br>relocation<br>of existing lines where a portion of a new line<br>will be<br>> 500 m from an existing ROW | Possible (to be determined<br>based on design of line<br>from existing powerhouse<br>to switchyard; Anticipated<br>distance < 2 km) | 120 km transmission<br>line possibly planned,<br>but no trigger if within<br>500 m of existing right-<br>of-way | 44 km transmission line<br>planned | 18 km transmission line<br>planned | 25.5 km<br>transmission line<br>planned | 20 km transmission<br>line planned | 50 km transmission<br>line planned |

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 140 of 158

|             | APPENDIX D                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-6  |

### 2.2. ROBUST REGISTRATION DOCUMENT

Based on a review of projects currently listed in the Newfoundland and Labrador Environmental Assessment Registry (<u>https://www.gov.nl.ca/ecc/env-assessment/projects-list/</u>) and conversations with Rod Healey, NL Hydro's approach to environmental assessment for its projects in recent years has been to submit a robust registration document in lieu of a basic registration followed by a ministerial decision and issuance of Terms of Reference for an EPR or EIS process.

Under this approach, the Registration document itself includes much of the content that would be included in the Terms of Reference for either an EPR or EIS, including results of ecological field studies where applicable (e.g., fish presence and fish habitat surveys, avian nesting and migration studies, species at risk and wildlife use studies). Proposed standard operating procedures, mitigation measures to reduce environmental impact, and compensation measures where impacts are unavoidable are also submitted as part of the registration document.

Because content of this nature is anticipated to be required for an EPR or EIS of any major utility project, submitting this material in advance increases the likelihood that the projects will be "released" from further assessment (i.e., approved to proceed) following the 45-day ministerial review period.

### 2.3. ALTERNATIVE APPROACH: CLASS EA

Under section 18 of the Newfoundland and Labrador *Environmental Assessment Regulations*, the minister may establish requirements for a class environmental assessment. This approach has been implemented in Ontario, where the Ontario Waterpower Association has obtained a Class Environmental Assessment for Waterpower Projects (currently 9<sup>th</sup> edition, 2022) which covers all hydroelectric developments in Ontario. Similarly, a class EA has been implemented for Minor Transmission Facilities in Ontario.

Pursuing this approach may be beneficial for the NL Hydro, as it would provide blanket EA approval for all NL Hydro Generation Expansion projects currently under consideration, as well as all future projects of a similar nature. Ecological surveys of individual development sites would still need to be conducted but known impacts and mitigation measures associated with the projects would be documented and approved in advance.

|             | APPENDIX D                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-7  |

### 3. FEDERAL IMPACT ASSESSMENT ACT

The proposed project does not trigger application of the federal *Impact Assessment Act* (S.C. 2019, c. 28). The federal act generally applies to larger-scale hydroelectric projects and transmission lines that cross provincial or international boundaries, as designated in the *Physical Activities Regulations* (SOR/2019-285) under the Act. A summary of the requirements in the *Physical Activities Regulations*, by section, and why they do not apply to the project under consideration is presented in **TABLE D-2**.

NOTE: For Prospect 2, the planned addition of a 68.2 MW generator to the existing Cat Arm hydroelectric facility represents a 50% expansion of generating capacity relative to its current capacity (136.4 MW), and the planned 204.6 MW capacity exceeds the 200 MW threshold. As such, the planned configuration would trigger application of the Impact Assessment Act through section 43 (a) of the Physical Activities Regulations, as summarized in **TABLE D-2** below. The proponent is advised to consider reducing the planned capacity increase if it wishes to remain below the section 43 (a) criteria.

|             | APPENDIX D                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC+LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-8  |

TABLE D-2 SUMMARY OF FEDERAL ENVIRONMENTAL ASSESSMENT PHYSICAL ACTIVITIES REGULATIONS

| RIVER             | IDIAN<br>LS            |
|-------------------|------------------------|
| EXPLOITS I        | RED IN<br>FAL          |
| <b>PROSPECT 6</b> | <b>BADGER</b><br>CHUTE |
| <b>PROSPECT 5</b> | PORTLAND<br>CREEK      |
| PROSPECT 4        | ISLAND POND            |
| PROSPECT 3        | ROUND POND             |
| PROSPECT 2        | CAT ARM                |
| PROSPECT 1        | DE UNIT 8              |

ing and abandonment of either of the following. 39 The construction, operation, decommissioni (a): a new international electrical transmission line with a voltage of 345 kV or more that requires a total of 75 km or more of new right of way;

| No.<br>Not international.     | No.<br>Not international.    | No.<br>Not international.   | No.<br>Not international.   | No.<br>Not international.   | No.<br>Not international.   | No.<br>Not international.   |
|-------------------------------|------------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|
| d by an order under section 2 | 61 of the Canadian Energy Re | gulator Act.                |                             |                             |                             |                             |
| No.<br>Not interprovincial.   | No.<br>Not interprovincial.  | No.<br>Not interprovincial. | No.<br>Not interprovincial. | No.<br>Not interprovincial. | No.<br>Not interprovincial. | No.<br>Not interprovincial. |
|                               |                              |                             |                             |                             |                             |                             |
| •                             |                              |                             |                             |                             |                             |                             |

production capacity of 200 MW or more; (a) a new hydroelectric generating facility with a

| Not a new facility.           | Not a new facility.              | Planned capacity<br>18 MW < 200 MW | Planned capacity<br>36 MW < 200 MW | Planned capacity<br>23 MW < 200 MW | Planned capacity<br>24 MW < 200 MW | Planned capacity<br>42 MW < 200 MW |  |
|-------------------------------|----------------------------------|------------------------------------|------------------------------------|------------------------------------|------------------------------------|------------------------------------|--|
| if the expansion would result | t in an increase in production c | apacity of 50% or mo               | ore and a total produc             | ction capacity of 200 l            | MW or more;                        |                                    |  |

. No

. No

No.

. No

°. No

. No

. No

No. Not an expansion. Current capacity 136.4 MW Proposed increase 68.2 MW Increase = 50% (< 50%) Yes. Proposed increase 154 MW Increase = 34.2% (< 50%) Total 604 MW Current capacity 450 MW . N

Total 204.6 MW

Continued



### TRIGGER ACTIVITY AND SECTION NUMBER

## ELECTRICAL TRANSMISSION LINES AND PIPELINES

(b): a new interprovincial power line designated

**RENEWABLE ENERGY** 

42 The construction, operation, decommissioning and abandonment of one of the following.

43 The expansion of one of the following.

(a) an existing hydroelectric generating facility

|            | Page                                 | 0-0                                  |
|------------|--------------------------------------|--------------------------------------|
| Revision   | Date                                 | 21-OCT-2022                          |
|            | Rev                                  | 10                                   |
| APPENDIX D | ENVIRONMENTAL APPROVALS & PERMITTING | SLI Doc. No. 691499-0000-40ER-I-0001 |
|            |                                      | SNC+LAVALIN                          |

| PROSPECT 1  | PROSPECT 2  | PROSPECT 3  | PROSPECT 4  | PROSPECT 5  | PROSPECT 6:                 | EXPLOITS RIVER              |
|---|---|---|---|---|-----------------------------|-----------------------------|
| BDE UNIT 8  | CAT ARM   | ROUND POND  | ISLAND POND   | PORTLAND<br>CREEK   | BADGER<br>CHUTE             | RED INDIAN<br>FALLS         |
| ing and abandonment of a ne<br>tural water body by 1 500 ha                                 | w dam or dyke on a natural w  | ater body, if the new c   | dam or dyke would re  | sult in the creation o  | of a reservoir with a su    | urface area that would      |
| No.<br>No new dam or dyke.  | No.<br>No new dam or dyke.  | No. Reservoir size<br>criterion not met.<br>To be confirmed<br>during design. | No. Reservoir size<br>criterion not met.<br>To be confirmed<br>during design. | No. Reservoir size<br>criterion not met.<br>To be confirmed<br>during design. | No.<br>Run-of-river design. | No.<br>Run-of-river design. |
| n a natural water body, if the  | expansion would result in an i  | increase in the surfac  | e area of the existing  | reservoir of 50% or   | more and an increase        | of 1 500 ha or more in      |
| No. Expansion size criteria<br>not anticipated to be met. To<br>be confirmed during design. | No. Expansion size criteria<br>not anticipated to be met. To<br>be confirmed during design. | No.<br>Not an expansion.  | No.<br>Not an expansion.  | No.<br>Not an expansion.  | No.<br>Not an expansion.    | No.<br>Not an expansion.    |
| ne diversion of water from a r<br>or more.  | natural water body into anothe  | r natural water body,   | if the expansion woul   | ld result in an increa  | se in diversion capac       | ity of 50% or more and      |
| No.   | No.   | No.   | No.   | No.   | No.                         | No.                         |
| le diversion of water from a r<br>or more.  | natural water body into anothe  | r natural water body,   | if the expansion woul   | ld result in an increa  | se in diversion capac       | ity of 50% or more and      |
| No. Expansion size criteria<br>not anticipated to be met. To<br>be confirmed during design. | No. Expansion size criteria<br>not anticipated to be met. To<br>be confirmed during design. | No.<br>Not an expansion.  | No.<br>Not an expansion.  | No.<br>Not an expansion.  | No.<br>Not an expansion.    | No.<br>Not an expansion.    |
|   |   |   |   |   |                             |                             |

SNC-Lavalin Inc.

### TRIGGER ACTIVITY AND SECTION NUMBER

WATER PROJECTS

58 The construction, operation, decommissionir exceed the annual mean surface area of the natu 59 The expansion of an existing dam or dyke on the annual mean surface area of that reservoir. 60 The expansion of an existing structure for the a total diversion capacity of 10 000 000 m³/year o

61 The expansion of an existing structure for the a total diversion capacity of 10 000 000 m³/year

|             | APPENDIX D                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-10 |

### 4. PERMIT REQUIREMENTS

Federal and provincial permit requirements for the proposed NL Hydro Expansion projects are summarized below. Requirements may vary based on the final configuration of the project to be confirmed during the design phase. Permit requirements are summarized in **TABLE D-3** at the end of this Appendix (starting page D-17).

### 4.1. FISHERIES ACT (FEDERAL)

The project will require several authorizations under the Fisheries Act (R.S.C., 1985, c. F-14), as follows.

• Habitat alteration, disturbance, destruction (HADD) Authorization

In accordance with the *Authorizations Concerning Fish and Fish Habitat Protection Regulations* (SOR/2019-286), an authorization is Required for activities in or near water containing fish or fish habitat. The proponent must submit details of fish and fish habitat protection / mitigation / compensation or replacement measures.

• Compliance with Fisheries Act section 34(1), "Deleterious Substances"

Discharge from the project, both during construction and operation, must not be deleterious or lethal to fish. Runoff from site(s) must comply with applicable standards (Canadian Environmental Quality Guidelines). The proponent will need to prepare and submit a Water Sampling and Monitoring Plan, and an Erosion and Sedimentation Control Plan.

One "environmental risk" consideration is noteworthy here. Flooding of reservoirs during development of hydroelectric generating facilities is known to release naturally occurring mercury and arsenic from rock, soil, felled trees and other vegetation exposed to reservoir waters. Concentrations of mercury cannot be predicted in advance. Monitoring of mercury concentrations in the reservoirs and receiving waters will likely be required under both the federal *Fisheries Act* and provincial *Water Resources Act*.

The Exploits River is a scheduled salmon river under the *Fisheries Act*, and this will impact the Exploits River prospects (Badger Chute and Red Indian Falls). Temporary and permanent fish passage structures and scheduling of construction work to avoid impacts to fish during migration periods will likely be included in the terms and conditions of the authorizations for these projects. These measures should be incorporated in the project design and planning process and included in the Fisheries Act authorization documents.

### 4.2. CERTIFICATE OF APPROVAL FOR ALTERATIONS TO A BODY OF WATER

A Certificate of Approval for Alterations to a Body of Water issued under the *Water Resources Act* (SNL 2002, c. W-4.01, Section 48) will be required for all of the proposed developments, both brownfield and greenfield.

For brownfield developments, the scope of the permit is expected to be limited to construction of the required modifications to the head race (inlet) and tail race (outlet) sections of the existing facilities, including placement of riprap and use of coffer dams. For greenfield developments, the permit will include the overall changes to the water bodies affected by the hydroelectric development. In both cases, NL Hydro standard operating procedures for nearshore construction work, dewatering, erosion and sedimentation control, use of coffer dams and placement of riprap will be submitted with the permit application.

### Watercourse Crossing Permits

Watercourse crossing permits issued under the Act will be required for temporary and permanent watercourse crossings (i.e., bridges and culverts).

### Certificate of Approval for Instream Activity

|             | APPENDIX D                           |     |             |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-11 |

A Certificate of Approval issued under the Act is required before construction for instream work (e.g., placement of a coffer dam, channel widening or deepening).

### <u>Wetlands</u>

In addition to the Certificate of Approval for Alternations to a Body of Water, the proponent will be required to comply with the "Policy Directive for Development in Wetlands." A permit application will be required under section 48 of the *Water Resources Act* for each affected wetland to be crossed or affected by construction or permanent structures.

Work should be planned and completed to avoid adverse effects to the water quantity, water quality, hydrologic characteristics or functions, and terrestrial and aquatic habitats of the wetlands. Mitigation measures will be required where hydrological functions of wetlands are impacted, however the Newfoundland and Labrador regulations do not include a requirement for compensation or replacement of wetlands.

Two additional considerations should be retained during the project planning phase. First, it is preferable to plan rights-of-way to avoid crossing wetlands where possible. Second, creosote-containing structures in wetlands (including pilings, bridge piers and transmission poles) will not be approved for use in wetlands.

### 4.3. WATER USE LICENCE

A Water Use Licence issued under section 17 (1) of the *Water Resources Act* (SNL 2002, c. W-4.01) will be required for each project as a whole. NL Hydro and/or Newfoundland Power currently hold individual Water Use Licences for each hydroelectric facility in their portfolios.

For greenfield developments, a new Water Use Licence is required to enable water withdrawal and transfer from a headpond / reservoir to downstream receiving waters. For brownfield developments, the existing Water Use Licences will need to be amended to account for changes in flow rates or volumes associated with the planned additional turbines.

If groundwater wells are needed to supply employee facilities at the dam or powerhouse locations, these will need to be included in the Water Use Licence.

Additional Water Use Licences may be required for process / makeup water used during construction, for example in concrete mixtures or for dust control on roads.

### Environmental Control Water and Sewage Regulations (2003)

Hydroelectric dam effluent discharged into receiving waters must comply with the *Environmental Control Water and Sewage Regulations*, generally included in the terms and conditions of the Water Use Licence.

As stated in the summary of requirements under the federal Fisheries Act, elevated mercury concentrations are a known consequence of hydroelectric dam development. This may constitute "Release of a Substance" as considered by the provincial *Environmental Protection Act*. Monitoring of mercury concentrations in the reservoirs and receiving waters will likely be required under both the federal and provincial regulations.

### 4.4. WASTE MANAGEMENT

Preparation of a soil management plan in accordance with the "Guidance Document – Protocol for the Management of Excavated Soils, Concrete Rubble and Dredged Materials" (GD-PPD-054.2, 2005 rev. 2015) is anticipated to be a requirement of environmental approvals for these projects. In addition, petroleum impacted soil generated during construction, if any, must be transported to an existing licenced facility.

A Waste Certificate of Approval issued under section 16 of the *Environmental Protection Act* will not be required for the proposed hydroelectric generation expansion projects, as NL Hydro is not anticipated to operate a stand-alone facility as part of these projects.

|             | APPENDIX D                           |     |             |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-12 |

### 4.5. WILDERNESS AND ECOLOGICAL RESERVES REGULATIONS

Based on a preliminary review, none of the proposed hydroelectric developments are located within a designated provincial wilderness and ecological reserve as defined by the *Wilderness and Ecological Reserves Act* (RSNL 1990, c. W-9).

However, if subsequent review determines that portions of the infrastructure associated with the proposed projects (e.g., roads or transmission lines, or reservoir boundaries) will pass through or contact a wilderness or ecological reserve, certain provisions under clause 23. (1) of the Wilderness Reserve Regulations, 1997 (NLR 65/97) will apply. These include submission of an environmental protection plan detailing how work will be carried out to minimize environmental damage and submission of annual work plans detailing the type and timing of work to be carried out.

### 4.6. SPECIES AT RISK ACT AND MIGRATORY BIRDS CONVENTION (FEDERAL)

Evaluation of potential presence of species at risk listed under the *Species at Risk Act* (S.C. 2002, c. 29) and the *Migratory Birds Convention Act, 1994* (S.C. 1994, c. 22) will need to be conducted for the prospects.

For brownfield developments, this will be a desktop review of available species population and habitat data. For greenfield developments, this will include both a desktop review and field surveys. A permit or agreement under section 73(1) of the *Species at Risk Act* may be required if project activities affect a listed wildlife species, any part of its critical habitat or the residences of individuals.

The *Migratory Birds Convention Act* applies to activities that could cause disturbance to or mortality of federally listed migratory birds. The Act also applies to discharge of harmful substances in waters or areas frequented by migratory birds. Compliance requirements are anticipated to be similar to the *Fisheries Act* "Deleterious Substances" requirements.

The proponent will need to submit plans to avoid disturbance or destruction of nests and eggs through timing of work or design considerations / mitigation measures in the project EA registration and permit applications.

### 4.7. CANADIAN NAVIGABLE WATERS ACT (FEDERAL)

Some of the watercourses under consideration for development under the NL Hydro Generation Expansion projects may be designated as "navigable waters" under the *Canadian Navigable Waters Act* (R.S.C. 1985, c. N-22). This includes use of rivers for recreational boating.

Permits under the *Navigable Waters Works Regulations* (C.R.C., c. 1232) will be required for activities in or across navigable water as defined by the Act, including works located below the high-water mark, or works passing over, under or through navigable waters. In addition, publication of notifications in accordance with the *Minor Works Order* (SOR/ 2021-170) will be required for erosion protection works, aerial cables, submarine cables, buried pipelines, outfalls and water intakes, dredging and watercourse crossings.

### 4.8. ADDITIONAL PERMITS AND LICENCES – OPERATIONAL PHASE

Additional permits will be required for the operational phase of the project for items such as auxiliary generators required to operate dam lift gates or other infrastructure in the event of power failures; associated fuel storage tanks; and onsite new and used lubricant storage. These permits can be obtained after the primary EA approval and construction permits have been obtained. Applicable regulations for issuance of these permits include:

- Air Pollution Control Regulations, 2004;
- Storage and Handling of Gasoline and Associated Products Regulations, 2003;
- Used Oil Control Regulations.

### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 148 of 158

|                | APPENDIX D                           |     |             |      |
|----------------|--------------------------------------|-----|-------------|------|
|                | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SINC + LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-13 |

NL Hydro (Licence no. 14-043) is currently a Licenced Pesticide Operator for industrial vegetation control under the *Environmental Protection Act* (SNL 2002, c. E-14.2) and the *Pesticides Control Regulations, 2012*. In addition, NL Hydro currently holds two Water Use Licences (WUL-22-12516 and WUL-21-11929) for withdrawal and use of water from water bodies along its transmission line rights-of-way for vegetation management. It is the anticipated that vegetation control for the proposed hydroelectric generation expansion projects will be covered under the existing licences or their renewals.

|             | APPENDIX D                           |     |             |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-14 |

### 5. SOCIOECONOMIC INFLUENCES

Socioeconomic considerations must be documented fully in whatever form of EA process is followed for the NL Hydro Generation Projects (i.e., EPR, EIS, Robust Registration or Class EA). These are anticipated to include, at a minimum:

- Anticipated labour requirements during the construction and operational phases of the project;
- Economic impacts of the project (consumer electricity rates, wages, government revenue and taxation, indirect impacts to the local and regional economy);
- Local, regional and national labour market impacts, including availability and skills development for trained positions and labour equity considerations;
- Safety and security considerations related to extra-regional transient labour during construction, if planned;
- Aboriginal stakeholder engagement.

Aboriginal stakeholders must be engaged early in the planning process. Aboriginal traditional ecological knowledge, historical and current land use, and ceremonial uses of the land and resources must be considered throughout the planning and development process. Opportunities for direct Aboriginal participation in construction and operation of the project through training and employment should be identified.

|             | APPENDIX D                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
| •))         | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-15 |

### 6. TIMELINES

The anticipated timelines for completion of the EA and permitting process will vary by project. Based on experience with projects of a similar nature, the following timelines are anticipated:

### Brownfield (Bay d'Espoir Unit 8, Cat Arm Unit 3)

Approximately 6 months from registration to EA release under the provincial *Environmental Assessment Regulations*, based on:

- Primarily a permit application process. Timelines for issuance of permits varies and is not specified in the relevant regulations;
- Desktop study to document environmental impacts (no field studies required);
- Application of standard operating procedures and mitigation measures;
- Limited federal government involvement (no migratory fish impacts, limited potential impacts to fish or fish habitat);
- Limited public comment on environmental registration document, once published in the provincial EA register;
- Release from further EA anticipated without further documentation.

### Greenfield

Approximately 2.5 years from registration for EA approval under the Environmental Assessment Regulations, based on:

- Ecological field studies required (fish presence and habitat surveys, avian, terrestrial wildlife and species at risk surveys);
- Field studies must be planned in the autumn of the prior year to start late March/early April of the following year, and continue for 12 consecutive months;
- · Field studies to be completed in advance to support submission of a robust EA registration document;
- Application of standard operating procedures and mitigation measures;
- Federal Fisheries Act authorizations (HADD and others) will be required. Timelines for authorizations are not specified in the regulations; anticipate 2.5 years, coincident with provincial EA process;
- Level of public engagement cannot be predicted in advance; may extend approval process by 1 year;
- Release from further EA is feasible with submission of a robust registration document that fulfils all content requirements.

|             | APPENDIX D                           |     |             |      |
|-------------|--------------------------------------|-----|-------------|------|
| •))         | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-16 |

### 7. CLIMATE CHANGE

The potential implications of climate change were not addressed in this study. However, information from the Climate Atlas of Canada is provided in **FIGURE D.1** below for Hydro's consideration.



|                  |           | Chang   | es in comp  | arison witl | h 1976-2005 | (référence p | eriod)    |           |             |         |
|------------------|-----------|---------|-------------|-------------|-------------|--------------|-----------|-----------|-------------|---------|
|                  |           | Annual  | Precipitati | on (mm)     |             |              | Annual Me | ean Tempe | rature (°C) |         |
| Climate Change   | Base      | Le      | ss          | М           | ore         | Base         | Le        | ss        | М           | ore     |
|                  | 1976-2005 | 2021-50 | 2051-80     | 2021-50     | 2051-80     | 1976-2005    | 2021-50   | 2051-80   | 2021-50     | 2051-80 |
| Blanc -Sablon    | 1042      | +7%     | +10%        | +8%         | +13%        | 0.9          | 2.5       | 3.5       | 2.8         | 4.9     |
| St-Anthony       | 1022      | +6%     | +9%         | +7%         | +12%        | 1.3          | 2.8       | 3.7       | 3.1         | 5.0     |
| Port Saunders    | 1062      | +7%     | +10%        | +8%         | +13%        | 2.2          | 3.8       | 4.8       | 4.1         | 6.1     |
| Bay of Island    | 1169      | +6%     | +9%         | +7%         | +12%        | 3.9          | 5.6       | 6.6       | 5.9         | 7.9     |
| Sandy Lake       | 1073      | +6%     | +9%         | +7%         | +13%        | 3.1          | 4.8       | 5.7       | 5.0         | 7.0     |
| Botwood          | 1040      | +6%     | +8%         | +7%         | +12%        | 4.4          | 5.9       | 6.8       | 6.1         | 8.0     |
| Stephenville     | 1274      | +6%     | +8%         | +6%         | +11%        | 3.9          | 5.6       | 6.6       | 5.8         | 7.9     |
| Red Indian Lake  | 1243      | +6%     | +8%         | +7%         | +12%        | 3.4          | 5.1       | 6.0       | 5.3         | 7.2     |
| Gander Lake      | 1176      | +6%     | +8%         | +6%         | +11%        | 4.5          | 6.1       | 6.9       | 6.3         | 8.2     |
| Bonavista        | 1166      | +5%     | +7%         | +6%         | +10%        | 5.1          | 6.5       | 7.3       | 6.7         | 8.5     |
| Port-aux Basques | 1408      | +5%     | +8%         | +6%         | +11%        | 4.0          | 5.7       | 6.6       | 5.8         | 7.9     |
| Burgeo           | 1430      | +6%     | +8%         | +6%         | +11%        | 4.2          | 5.8       | 6.7       | 6.0         | 7.9     |
| Belleoram        | 1352      | +6%     | +8%         | +6%         | +10%        | 5.0          | 6.5       | 7.4       | 6.7         | 8.6     |
| St. John's       | 1341      | +5%     | +7%         | +5%         | +9%         | 5.3          | 6.7       | 7.5       | 6.8         | 8.6     |
| St Lawrence      | 1402      | +5%     | +7%         | +5%         | +9%         | 5.3          | 6.8       | 7.6       | 6.9         | 8.8     |
| Trepassey        | 1439      | +5%     | +7%         | +5%         | +8%         | 5.1          | 6.5       | 7.3       | 6.6         | 8.4     |
| Average          |           | +5.8%   | +8.2%       | +6.4%       | +11.1%      | 3.9          | 5.4       | 6.3       | 5.6         | 7.6     |

FIGURE D.1 FORECASTED PRECIPITATION CHANGES (source: Climate Atlas of Canada)

### APPENDIX DRevisionENVIRONMENTAL APPROVALS & PERMITTINGRevDatePageSLI Doc. No. 691499-0000-40ER-I-00010121-OCT-2022D-17

### TABLE D-3 APPLICABLE STATUTES AND REGULATIONS

| PART 1 OF 4: F  | PROVINCIAL STAT   | UTES AND REC  | GULATIONS  |
|---|---|---|--|
| Statute /<br>Regulation   | Responsible<br>Department   | Permit /<br>Approval  | Details  |
| Environmental<br>Protection Act<br>(SNL 2002, c.<br>E-14.2)<br>Environmental<br>Assessment<br>Regulations,<br>2003 (NLR<br>54/03) | Dept. of<br>Environment<br>and Climate<br>Change-<br>EA Division                    | EA<br>Registration<br>(proponent<br>submittal)<br>EA Release<br>(ministerial<br>approval) | Environmental Assessment Registration<br>and Release are required for each<br>project as a whole. Multiple triggers for<br>Registration under Section 34(1), Section<br>34(2) for power lines and 35(1) for<br>associated roads.<br>Considerations: Robust registration<br>document may streamline approval – see<br>text. Class EA for hydroelectric<br>developments may accelerate approval<br>of future projects. |
| Environmental<br>Protection Act<br>(SNL 2002, c.<br>E-14.2)<br>Guidance<br>Document GD-<br>PPD-054.2<br>(2005, rev.<br>2015)      | Dept. of<br>Environment<br>and Climate<br>Change                                    | Compliance<br>Approved Soil<br>Management<br>Plan   | Comply with Guidance Document –<br>Protocol for the Management of<br>Excavated Soils, Concrete Rubble and<br>Dredged Materials.  |
| Water<br>Resources Act<br>(SNL 2002, c. W-<br>4.01)   | Dept. of<br>Environment<br>and Climate<br>Change-<br>Water<br>Resources<br>Division | Certificate of<br>Approval for<br>Alteration to a<br>Body of<br>Water                     | Required for construction within 15 m of<br>high-water mark (e.g., placement of<br>riprap, berms, lateral roads).<br>Separate permit application required for<br>each alteration.  |
| Water<br>Resources Act<br>(SNL 2002, c. W-<br>4.01)   | Dept. of<br>Environment<br>and Climate<br>Change-<br>Water<br>Resources<br>Division | Permit for<br>Development<br>in Wetlands<br>under Section<br>48 of the Act                | Required for each affected wetland to be<br>crossed or affected by construction or<br>permanent structures<br>Design considerations: Plan rights-of-way<br>to avoid crossing wetlands where<br>possible. Creosote-containing structures<br>will not be approved.   |

| •))                |
|--------------------|
| <b>SNC·LAVALIN</b> |

### APPENDIX D Revision ENVIRONMENTAL APPROVALS & PERMITTING Rev Date Page SLI Doc. No. 691499-0000-40ER-I-0001 01 21-OCT-2022 D-18

| PART 1 OF 4: F                                      | ROVINCIAL STAT  | UTES AND REC  | GULATIONS   |
|---|---|---|---|
| Statute /<br>Regulation                             | Responsible<br>Department   | Permit /<br>Approval  | Details   |
| Water<br>Resources Act<br>(SNL 2002, c. W-<br>4.01) | Dept. of<br>Environment<br>and Climate<br>Change-<br>Water<br>Resources<br>Division | Watercourse<br>Crossing<br>Permits  | Required for temporary and permanent watercourse crossings (bridges, culverts)  |
| Water<br>Resources Act<br>(SNL 2002, c. W-<br>4.01) | Dept. of<br>Environment<br>and Climate<br>Change-<br>Water Resources<br>Division    | Certificate of<br>Approval for<br>Instream<br>Activity  | Required before construction for instream<br>work (e.g., coffer dam, channel widening<br>or deepening)  |
| Water<br>Resources Act<br>(SNL 2002, c. W-<br>4.01) | Dept. of<br>Environment<br>and Climate<br>Change-<br>Water<br>Resources<br>Division | Water Use<br>Licence issued<br>under Section<br>17 (1) for<br>hydroelectric<br>use<br>Additional<br>licences (see<br>Details<br>column) | <ul> <li>Required for each project as a whole. A new Water Use Licence is required to enable water withdrawal and transfer from a headpond / reservoir to downstream receiving waters.</li> <li>Existing licences for Bay d'Espoir and Cat Arm may need to be amended for changes in flow rate or volume.</li> <li>Additional licence may be required for an onsite potable water source (either intake from the reservoir or well).</li> <li>Additional licence may also be required for process / makeup water during construction (e.g., for use in concrete, dust control on roads, etc.).</li> </ul> |
| Water<br>Resources Act<br>(SNL 2002, c.<br>W-4.01)  | Dept. of<br>Environment<br>and Climate<br>Change-<br>Water<br>Resources<br>Division | Certificate of<br>Approval for<br>Construction<br>Site Drainage   | Required for site runoff. Runoff drainage<br>plans to be submitted with overall<br>application.   |

| •))                |
|--------------------|
| <b>SNC·LAVALIN</b> |

### APPENDIX D Revision ENVIRONMENTAL APPROVALS & PERMITTING Rev Date Page SLI Doc. No. 691499-0000-40ER-I-0001 01 21-OCT-2022 D-19

| PART 1 OF 4: PROVINCIAL STATUTES AND REGULATIONS   |   |                        |   |  |  |
|--|---|------------------------|---|--|--|
| Statute /<br>Regulation  | Responsible<br>Department   | Permit /<br>Approval   | Details   |  |  |
| Water<br>Resources Act<br>(SNL 2002, c.<br>W-4.01)<br>Environmental<br>Control Water<br>and Sewage<br>Regulation   | Dept. of<br>Environment<br>and Climate<br>Change-<br>Water<br>Resources<br>Division | Compliance /<br>permit | Required for water or sewage<br>discharges from the project.<br>Effluent must comply with standards in<br>the regulations |  |  |
| Water<br>Resources Act<br>(SNL 2002, c.<br>W-4.01)<br>Water Power<br>Rental<br>Regulations,<br>2003<br>(NLR 64/03) | Dept. of<br>Environment<br>and Climate<br>Change-<br>Water<br>Resources<br>Division | fee payment            | Not required for construction<br>applicable during operational phase<br>only.   |  |  |



### APPENDIX DRevisionENVIRONMENTAL APPROVALS & PERMITTINGRevDatePageSLI Doc. No. 691499-0000-40ER-I-00010121-OCT-2022D-20

| PART 2 OF 4: FEDERAL STATUTES AND REGULATIONS  |   |   |   |  |  |
|--|---|---|---|--|--|
| Statute /<br>Regulation  | Responsible<br>Department   | Permit /<br>Approval  | Details   |  |  |
| Impact<br>Assessment Act<br>(S.C. 2019, c. 28,<br>s. 1)  | Environment<br>Canada   | EIA Approval  | No federal EIA triggers for currently<br>planned hydro expansion projects<br>(except Cat Arm: see accompanying<br>text).  |  |  |
| Fisheries Act<br>(R.S.C., 1985, c. F-<br>14)<br>Authorizations<br>Concerning Fish<br>and Fish Habitat<br>Protection<br>Regulations<br>(SOR/2019-286) | Fisheries and<br>Oceans Canada  | Habitat alteration,<br>disturbance,<br>destruction<br>(HADD)<br>Authorization | Required for activities in or near water<br>containing fish or fish habitat.<br>Proponent must submit details of fish<br>and fish habitat protection / mitigation /<br>compensation or replacement measures.  |  |  |
| Fisheries Act<br>(R.S.C., 1985, c. F-<br>14)<br>Section 34(1):<br>"Deleterious<br>Substances"  | Environment<br>Canada (Section<br>36(3) of Fisheries<br>Act)<br>Fisheries and<br>Oceans Canada<br>(sedimentation) | Compliance  | Discharge must not be deleterious or<br>lethal to fish.<br>Runoff from site(s) must comply with<br>applicable standards (Canadian<br>Environmental Quality Guidelines)<br>Proponent will need to prepare and<br>submit a Water Sampling and Monitoring<br>Plan, and an Erosion and Sedimentation<br>Control Plan.                     |  |  |
| Canadian<br>Navigable Waters<br>Act (R.S.C.,<br>1985, c. N-22)<br>Navigable Waters<br>Works<br>Regulations<br>(C.R.C., c. 1232)                      | Transport<br>Canada   | Permit(s)   | Required for activities in or across<br>navigable water as defined by the Act.<br>Not applicable for all planned projects –<br>applicability to be determined on a case-<br>by-case basis during project planning.<br>Permits may be required for works located<br>below the high-water mark,<br>over/under/through navigable waters. |  |  |
| Canadian<br>Navigable Waters<br>Act (R.S.C.,<br>1985, c. N-22)<br>Minor Works<br>Order<br>(SOR/ 2021-170)  | Transport<br>Canada /<br>Canadian Coast<br>Guard  | Notification of a<br>Minor Work   | Applicability to be confirmed during<br>project planning.<br>Applies to erosion protection works, aerial<br>cables, submarine cables, buried<br>pipelines, outfalls and water intakes,<br>dredging and watercourse crossings.   |  |  |
| •))                |
|--------------------|
| <b>SNC·LAVALIN</b> |

# APPENDIX D Revision ENVIRONMENTAL APPROVALS & PERMITTING Rev Date Page SLI Doc. No. 691499-0000-40ER-I-0001 01 21-OCT-2022 D-21

# PART 2 OF 4: FEDERAL STATUTES AND REGULATIONS

| Statute /<br>Regulation   | Responsible<br>Department                              | Permit /<br>Approval   | Details  |
|---|--|--|--|
| Species at Risk<br>Act<br>(S.C. 2002, c. 29)  | Canadian Wildlife<br>Service,<br>Environment<br>Canada | Permit or<br>Agreement<br>under Section<br>73(1) of the<br>Act | May be required if project activities affect<br>a listed wildlife species, any part of its<br>critical habitat or the residences of<br>individuals.  |
| Migratory Birds<br>Convention Act,<br>1994 (S.C. 1994, c.<br>22)<br>Migratory Birds<br>Regulations<br>(C.R.C., c. 1035) | Canadian Wildlife<br>Service,<br>Environment<br>Canada | Permit   | Applies to activities that could cause<br>disturbance to or mortality of federally<br>listed migratory birds.<br>Also applies to discharge of harmful<br>substances in waters or areas frequented<br>by migratory birds. Compliance<br>requirements similar to Fisheries Act<br>"Deleterious Substances" requirements.<br>Submit plans to avoid disturbance or<br>destruction of nests and eggs through<br>timing of work or design considerations /<br>mitigation measures. |

#### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 157 of 158

|             | APPENDIX D                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-22 |

# PART 3 OF 4: MUNICIPAL STATUES AND REGULATIONS

| Statute / Regulation   | Responsible Department                                    | Permit / Approval                 | Details  |
|--|---|-----------------------------------|--|
| Urban and Rural Planning Act<br>Municipal Planning Regulations | Municipal Planning Dept.                                  | Development or Building<br>Permit | Building permits required within<br>municipal boundaries |
| Urban and Rural Planning Act<br>Municipal Planning Regulations | Municipal Dept of Public<br>Works<br>or Landfill Operator | Waste disposal approval           | Approval required for waste disposal by contractors      |

#### PUB-NLH-288, Attachment 4 Reliability and Resource Adequacy Study Review Page 158 of 158

|             | APPENDIX D                           |     | Revision    |      |
|-------------|--------------------------------------|-----|-------------|------|
|             | ENVIRONMENTAL APPROVALS & PERMITTING | Rev | Date        | Page |
| SNC·LAVALIN | SLI Doc. No. 691499-0000-40ER-I-0001 | 01  | 21-OCT-2022 | D-23 |

| PART 4 OF 4: CODE COMPLIANCE (BUILDINGS / FIRE/ OH&S)       |                                 |                     |   |  |  |
|---|---------------------------------|---------------------|---|--|--|
| Statute / Regulation  | Department                      | Permit / Approval   | Details   |  |  |
| National Building Code                                      | Service NL                      | compliance / permit | Required for all onsite structures<br>(during construction and<br>permanent occupancy)<br>Prepare and submit building plans   |  |  |
| National Fire Code  | Service NL                      | compliance / permit | Required for all onsite structures<br>(during construction and<br>permanent occupancy)  |  |  |
| NL Fire Prevention Act<br>and Regulations                   | Service NL                      | compliance / permit | Required for all onsite structures (during construction and permanent occupancy)  |  |  |
| NL Occupational Health<br>and Safety Act and<br>Regulations | Service NL<br>(Dept. of Labour) | compliance / permit | Proponent must prepare HASP (for<br>construction and for facility<br>operation)<br>Notify Dept. prior to construction   |  |  |
| Occupational Health and<br>Safety Act<br>WHMIS Regulations  | Service NL<br>(Dept. of Labour) | -                   | Proponent must prepare and<br>submit a project specific WHMIS<br>document detailing HazMat's in<br>use on site, incl. handling, storage<br>and labelling instructions |  |  |

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 1 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

# Newfoundland and Labrador Hydro Combustion Turbine Screening

# **Final Study Report**

PROFESSION 10710 DEYO SC G

|            |       |        | Orda-       | K. Merhavi | K. Meihari  |
|------------|-------|--------|-------------|------------|-------------|
| 2022-10-28 | 1     | Final  | O. Owolabi  | K. Meghari | K. Meghari  |
| 2022-10-17 | 0     | Final  | O. Owolabi  | K. Meghari | K. Meghari  |
| Date       | Rev.  | Status | Prepared By | Checked By | Approved By |
|            | ΗΔΤCΗ |        |             |            |             |

#### **IMPORTANT NOTICE TO READER**

This study report has been prepared by Hatch Ltd. (Hatch) for the sole and exclusive use of Newfoundland and Labrador Hydro. (the "Client") for the purpose of assisting the Client to complete a combustion turbine screening study. Any information or deliverable provided by Hatch to the Client in connection with the Services is provided solely for Client's use and for the specific purpose for which the Services were engaged. This report shall not otherwise be provided to, used by, or relied upon by any third parties.

This report contains opinions, conclusions and recommendations made by Hatch, using its professional judgment and reasonable care. Use of, or reliance upon, this report by the Client is subject to the following conditions:

- The report being read in the context of, and subject to, the terms of the Agreement between Hatch and the Client dated 22 June 2022 (the "Agreement"), including any methodologies, procedures, techniques, assumptions and other relevant terms or conditions that were specified or agreed therein.
- The report being read as a whole, with sections or parts hereof read or relied upon in context.
- The conditions may change over time (or may have already changed) due to natural forces or human intervention, and Hatch takes no responsibility for the impact that such changes may have on the accuracy or validity, or the observations, conclusions and recommendations set out in this report.
- The report is based on information made available to Hatch by the Client or by certain third parties; and unless stated otherwise in the Agreement, Hatch has not verified the accuracy, completeness, or validity of such information, makes no representation regarding its accuracy, and hereby disclaims any liability in connection therewith.



# **Table of Contents**

| 1. | Executive Summary1             |   |                                |  |  |
|----|--------------------------------|---|--------------------------------|--|--|
|    | 1.1<br>1.2                     | Site Location<br>Combustion Turbine<br>1.2.1 Fuel Capability<br>1.2.2 Project Schedule<br>1.2.3 Capital Cost  | 1<br>2<br>2<br>2               |  |  |
|    | 1.3<br>1.4                     | Bioruei Sourcing  | 3                              |  |  |
| 2. | Intro                          | duction   | 5                              |  |  |
| 3. | Desig                          | gn Criteria   | 6                              |  |  |
|    | 3.1                            | General Plant Description3.1.1Plant Description and Configuration3.1.2Operating Requirements3.1.3Redundancy Design Philosophy   | 6<br>6<br>6<br>7               |  |  |
| 4. | Desig                          | gn Basis  | 8                              |  |  |
|    | 4.1                            | Electrical, Instrumentation and Control System  | 8                              |  |  |
|    | 4.2                            | Civil and Structural  | 8                              |  |  |
|    | 4.3                            | Mechanical4.3.1Fuel Type4.3.2Combustion Turbine Generators114.3.3Raw Water114.3.4Demineralized Water114.3.5Compressed Air114.3.6Glycol Cooling System1  | 9<br>9<br>10<br>10<br>10<br>11 |  |  |
| 5. | Site /                         | Assessment1   | 3                              |  |  |
|    | 5.1                            | Site Location       1         5.1.1       Assessment Methodology       1         5.1.2       Transmission       1         5.1.3       Noise       1         5.1.4       Fuel Supply       1         5.1.5       Water Requirement       1 | 3<br> 3<br> 3<br> 3<br> 3      |  |  |
|    | 5.2                            | Site Ranking  | 14                             |  |  |
| 6  | 5.3<br>Dosc                    | Assumptions and Limitations   | 14                             |  |  |
| 0. | 6 1                            | Compustion Turbine Overview   | 15                             |  |  |
|    | 0.1                            | 6.1.1       General Electric – LM6000   | 15<br>15<br>18<br>20           |  |  |
| 7. | Turbine Technology Selection23 |   |                                |  |  |



| 8.  | Powe  | er Plant Performance                                  | 23              |  |  |  |  |
|-----|-------|---|-----------------|--|--|--|--|
| 9.  | Preli | ninary Process Flow Diagram and Plant Layout          | 24              |  |  |  |  |
| 10. | Leve  | 1 Project Schedule                                    | roject Schedule |  |  |  |  |
| 11. | Com   | bustion Turbine Maintenance                           |                 |  |  |  |  |
| 12. | Capit | Cost Estimate   |                 |  |  |  |  |
|     | 12.1  | Basis of Estimate                                     | 26              |  |  |  |  |
|     | 12.2  | Capital Cost Estimate                                 | 27<br>27        |  |  |  |  |
|     |       | 12.2.2 Direct Costs<br>12.2.3 Permanent Equipment     | 27<br>28        |  |  |  |  |
|     |       | 12.2.4 Bulk Materials                                 | 28<br>28        |  |  |  |  |
|     |       | 12.2.6 Major and Heavy Lift Cranes.                   | 28              |  |  |  |  |
|     |       | 12.2.7 Construction Labor Rate and Productivity       | 28              |  |  |  |  |
|     |       | 12.2.8 Indirect Costs                                 | 29<br>29        |  |  |  |  |
|     |       | 12.2.10 Project Contingency.                          | 29              |  |  |  |  |
|     |       | 12.2.11 Freight, Duties and Logistics                 | 30              |  |  |  |  |
|     |       | 12.2.12 Spare Parts                                   | 30              |  |  |  |  |
|     | 12.3  | Estimate Qualifications and Assumptions               | 30              |  |  |  |  |
|     |       | 12.3.1 Indirect Cost Assumptions                      | 31              |  |  |  |  |
|     |       | 12.3.2 Owner Costs                                    | 31              |  |  |  |  |
|     | 12.4  | Capital Cost Summary                                  | 33              |  |  |  |  |
| 13. | Biofu | els – Biodiesel/Renewable Diesel/Ethanol              | 34              |  |  |  |  |
|     | 13.1  | Biofuel Facilities in Canada                          | 39              |  |  |  |  |
|     | 13.2  | Potential Biofuel Supply Chain                        | 40              |  |  |  |  |
|     | 13.3  | Storage   | 41              |  |  |  |  |
|     |       | 13.3.1 Biodiesel                                      | 41              |  |  |  |  |
|     |       | 13.3.2 Renewable Diesel                               | 4Z<br>43        |  |  |  |  |
|     | 13.4  | Economics   | 44              |  |  |  |  |
| 14  | Hydr  | ogen  | 45              |  |  |  |  |
|     |       |   |                 |  |  |  |  |
|     | 14.1  | Sourcing  | 46<br>46        |  |  |  |  |
|     |       | 14.1.2 Hydrogen Projects in Newtoundland and Labrador | 48<br>52        |  |  |  |  |
|     |       | 14.1.4 Transportation of Hvdrogen                     | 54              |  |  |  |  |
|     | 14.2  | Green Hydrogen Production                             | 56              |  |  |  |  |
|     |       | 14.2.1 CAPEX  | 57              |  |  |  |  |
|     |       | 14.2.2 OPEX   | 58              |  |  |  |  |
|     | 11 2  | 14.2.3 FIDUUCIION COSI UUIIOOK                        | 59              |  |  |  |  |
|     | 14.3  | oluraye   | 00              |  |  |  |  |



| 15. | 15. References |          |                               |    |  |
|-----|----------------|----------|-------------------------------|----|--|
|     | 14.4           | Pricing. |                               | 64 |  |
|     |                | 14.3.5   | Comparison of Storage Mediums | 63 |  |
|     |                | 14.3.4   | Other Storage Methods         |    |  |
|     |                | 14.3.3   | Geological                    | 61 |  |
|     |                | 14.3.2   | Liquid H2/Ammonia             |    |  |
|     |                | 14.3.1   | Compressed Hydrogen Storage   | 60 |  |

#### List of Tables

| Table 1-1: Capital Cost  | 3  |
|--|----|
| Table 4-1: Fuel Storage  | 10 |
| Table 5-1: Grade Descriptions for Site Assessment                              | 14 |
| Table 5-2: Site Assessment for Green Field Locations                           | 14 |
| Table 12-1: Foreign Currency Exchange Rates                                    | 25 |
| Table 12-2: Summary of Estimate Basis  | 26 |
| Table 12-3: Capital Cost Summary   | 33 |
| Table 13-1: Comparison of Conventional Diesel, Renewable Diesel, and Biodiesel | 37 |
| Table 13-2: Biofuel Facilities in Eastern Canada                               | 39 |
| Table 13-3: Biodiesel Storage Considerations                                   | 41 |
| Table 13-4: Renewable Diesel Storage Considerations                            | 42 |
| Table 13-5: Ethanol Storage Considerations                                     | 43 |
| Table 13-6: Average Fuel Price Comparison Between Canada and the US            | 44 |
| Table 14-1: Comparison of Transport of H2                                      | 56 |
| Table 14-2: Alkaline and PEM Electrolysis Comparison                           | 56 |
| Table 14-3: Budgetary CAPEX for a 200 MW Green Hydrogen Facility               | 57 |
| Table 14-4: Budgetary OPEX   | 58 |
| Table 14-5: Comparison of Tank Types [29]                                      | 60 |
| Table 14-6: Comparison of Storage Mediums                                      | 64 |
| Table 14-7: Storage Tank Volumes   | 64 |

#### List of Figures

| Figure 6-1: LM6000 Gas Turbine Engine   | 15  |
|---|-----|
| Figure 6-2: FT4000 SWIFTPAC Aero-Derivative Gas Turbine   | 19  |
| Figure 6-3: Siemens SGT – 800 Gas Turbine   | 21  |
| Figure 13-1: Feedstock and Processes for Bio Sourced Diesels  | 34  |
| Figure 13-2: Types of Biofuels  | 35  |
| Figure 13-3: Map of Biofuel Facilities in Eastern Canada  | 39  |
| Figure 13-4: Refined Petroleum Product Flow in Canada (Canadian Fuels Association <sup>2</sup> )      | 40  |
| Figure 14-1: Schematic of "4-to-1" Round Trip Efficiency of Green Hydrogen to Electricity*            | 46  |
| Figure 14-2: Map of Hydrogen Projects in Atlantic Canada and Quebec                                   | 48  |
| Figure 14-3: Map of Potential Hydrogen Projects and Major Power Generating Stations in Newfoundla     | and |
| and Labrador  | 49  |
| Figure 14-4: World Energy GH2 Project Proposed Location [22]  | 51  |
| Figure 14-5: World Energy GH2 Hydrogen Facility [22]  | 52  |
| Figure 14-6: Suiso Frontier Liquid Hydrogen Transport Vessel [25]                                     | 54  |
| Figure 14-7: Simulated Appearance of the Completed 160,000m <sup>3</sup> Liquid Hydrogen Carrier [26] | 55  |
| Figure 14-8: Levelized Production Cost of Hydrogen  | 59  |
| Figure 14-9: Atlas Salt [37]  | 63  |



#### List of Appendices

#### Appendix A : Heat and Mass Balance

#### Appendix B : Plant Layout

Appendix B1: 2 Unit Combustion Turbine – Brownfield Appendix B2: 2 Unit Combustion Turbine – Greenfield Appendix B3: 4 Unit Combustion Turbine – Brownfield Appendix B4: 4 Unit Combustion Turbine – Greenfield

#### Appendix C : Process Flow Diagrams

Appendix C1: General PFD Appendix C2: Diesel PFD Appendix C3: Biofuel PFD

#### Appendix D : Budgetary Cost

Appendix D1: GE – LM6000 Appendix D2: Mitsubishi Power Aero – FT4000 Appendix D3: Siemens – SGT-800

#### Appendix E : Project Schedule

Appendix E1: 2 Unit Combustion Turbine Schedule Appendix E2: 4 Unit Combustion Turbine Schedule

#### Appendix F : Equipment List

Appendix F1: 2 Unit Combustion Turbine – Brownfield Appendix F2: 2 Unit Combustion Turbine – Greenfield Appendix F3: 4 Unit Combustion Turbine – Brownfield Appendix F4: 4 Unit Combustion Turbine – Greenfield

#### Appendix G : Cost Estimate

Appendix G1: 2 Unit Combustion Turbine – Brownfield Appendix G2: 2 Unit Combustion Turbine – Greenfield Appendix G3: 4 Unit Combustion Turbine – Brownfield Appendix G4: 4 Unit Combustion Turbine – Greenfield

#### **Appendix H : Specification Sheet**

#### Appendix I : GTG Comparison Sheet

#### Appendix J : Experience List

Appendix J1: GE – LM6000 Appendix J2: Siemens – SGT-800

#### Appendix K : 3D Model



| Appendix K1: 2 Unit Combustion Turbine – Brownfield |
|---|
| Appendix K2: 2 Unit Combustion Turbine – Greenfield |
| Appendix K3: 4 Unit Combustion Turbine – Brownfield |
| Appendix K4: 4 Unit Combustion Turbine – Greenfield |



# Acronyms

- BXX Blended XX percent biodiesel with (1-XX) ULSD
- CCS Carbon Capture and Storage
- CRFP Carbon Fibre Reinforce Polymer
- CFS Clean Fuel Standard
- CH2 Compressed Hydrogen Gas
- CI Carbon Intensity
- FAME Fatty Acid Methyl Esters
- GE General Electric
- GHG Greenhouse Gas
- GTG Gas Turbine Generator
- HDRD Hydrogenation Derived Renewable Diesel
- LH2 Liquid Hydrogen
- MCC Motor Control Centre
- MHI Mitsubishi Power Aero
- NL Newfoundland and Labrador
- NLH Newfoundland and Labrador Hydro
- OEM Original Equipment Manufacturer
- PFD Process Flow Diagram
- RFRs Renewable Fuels Regulations
- SMR Steam-methane reforming
- TIC Total Installed Cost
- ULSD Ultra-Low Sulphur Diesel, conventional diesel, fossil diesel

# 1. Executive Summary

Newfoundland and Labrador Hydro (NLH) as part of its system planning strategy is investigating efficient, reliable, and cost reflective combustion turbine technology options that will meet the growing power demand of the province.

Hatch was engaged by NLH to carry out a combustion turbine screening study aimed at reviewing industrial gas turbines with fuel flexibility, fast start, and synchronous condenser capability. The simple cycle combustion turbine will be designed to operate at base load, part load and peaking load to accommodate the varying power demand profile of the province.

The objective of the study consists of:

- Performing a conceptual study including a preliminary process flow diagram, combustion turbine performance estimate, plant layout, site assessment, level 1 project schedule, and a class 5 cost estimate.
- Reviewing the use and sourcing of biodiesel, ethanol, and hydrogen within the provinces to generate electricity.

Two base scenarios were considered in the study, these are:

- Scenario 1: Two (2) units to achieve 100 MW nominal simple cycle power plant.
- Scenario 2: Four (4) units to achieve 200 MW nominal simple cycle power plant.

#### 1.1 Site Location

The study categorises the sites into two broad groups, namely a greenfield and brownfield site location. The greenfield location is an undeveloped land with little to no existing shared facility, while brownfield site locations have shared facilities that can be leveraged in the design of the proposed power plant. One major advantage of using a brownfield site is the exclusion of capital cost such as land acquisition from the project developmental cost. Holyrood thermal generating station was identified as a proposed brownfield site. Both greenfield and brownfield site are identified along the Avalon Peninsula in Newfoundland and Labrador.

# 1.2 Combustion Turbine

Three major original equipment manufacturers (OEM) were contacted, which were selected due to the nominal power requirement for the plant. The three OEMs are General Electric (GE), Siemens, and Mitsubishi Power Aero (MHI). A gas turbine specification sheet was developed and shared with the OEM to obtain a budgetary price, equipment general arrangement, fuel capability, estimated major equipment delivery date, turbine experience on biofuels and hydrogen, and estimated performance. The OEMs responded to the specification sheet by proposing units that closely match the defined requirements. The proposed units are:

- GE LM6000 PC Sprint.
- Siemens SGT 800.

• MHI – FT4000.

#### 1.2.1 Fuel Capability

GE with the LM6000 aeroderivative gas turbine has limited experience burning ethanol or biodiesel. The unit is designed to burn a maximum of 35% hydrogen by volume, however some balance of plant upgrade would be required.

Siemens has limited experience with biodiesel but confirms its capability. The SGT800 is currently being built in Sweden to run on biodiesel with a commercial operation date of 2023. As of the time of the report, Siemens do not have any experience burning ethanol in their gas turbine fleet. However, they claim they have the technology and are willing to partner with any developer or utility power producer to achieve this capability. The SGT800 can burn 75% hydrogen at the time of this report.

The FT4000 is designed to run on liquid fuel such as diesel and natural gas. As of the time of this report, the FT4000 does not have the capability to burn any biofuel, and its capability to burn hydrogen has not been verified.

#### 1.2.2 Project Schedule

A level 1 preliminary project schedule was developed for two (2) and four (4) unit gas turbines. The estimated timeline for budgeting approval, environmental assessment, engineering procurement, construction, and management to commercial operating is approximately 3 and 4 years for the two- and four-unit configuration respectively. This time is highly dependent on gas turbine generator availability from OEM.

#### 1.2.3 Capital Cost

The capital cost of each scenario is broken down into direct cost, indirect cost, and contingency. The equipment list with budgetary numbers received from OEM's was used to develop an AACE Class 5 Estimate with target accuracy of -20% to + 30%.

The capital cost estimate was compiled based on the following parameters:

- General Electric LM6000 PC Sprint budgetary price.
- The Hatch Thermal Power Plant Factored Estimate model was used develop the costs by area and system. The Hatch Thermal Factored Model was developed from benchmark data for completed projects and definitive estimates.

The average labour rate for all works was established by Hatch.

GE – LM6000 PC Sprint was used in developing the cost estimate as it meets the technical requirement as specified in the specification sheet. Siemens SGT 800 was also reviewed; however, the unit has not demonstrated experience burning ethanol and has a longer start up time. As for the MHI FT4000, while the unit is designed to burn diesel, natural gas, and hydrogen blend, it has no capability and experience in burning biofuels.

Table 1-1: Capital Cost

A summary of the capital cost estimate is shown in Table 1-1.

| Breakdown of  | Greenfield    |               | Brownfield    |               |
|---------------|---------------|---------------|---------------|---------------|
| Activities    | 2 x 50 MW     | 4 x 50 MW     | 2 x 50 MW     | 4 x 50 MW     |
| Direct cost   | \$159,217,000 | \$276,356,000 | \$150,523,000 | \$267,174,000 |
| Indirect cost | \$31,259,000  | \$48,854,000  | \$30,879,000  | \$47,533,000  |
| Contingency   | \$36,503,000  | \$62,278,000  | \$34,775,000  | \$60,270,000  |
| Capital Costs | \$226,979,000 | \$387,488,000 | \$216,177,000 | \$374,977,000 |

# 1.3 Biofuel Sourcing

There is currently no established biofuel supply chain in Newfoundland and Labrador (NL). The Braya Renewable Fuels production facility in Come by Chance is the only biofuel producer in NL, and they are not expected to be supplying into Canada in the near future as they are selling into more established markets in the US. Biofuel is currently being produced in other provinces such as Ontario and Quebec, but the majority of these are either being used in-province or exported to the US. Several announcements regarding biofuel production projects in Canada have been made, but none of them are set to be in NL.

Pure biodiesel and renewable diesel costs in Canada are currently 1.5 to 2 times higher than petroleum diesel. Ethanol (E85) has always been \$0.2-0.3 cheaper than gasoline per gallon, but more expensive on an energy equivalent basis. This cost difference is primarily due to the high production and supply cost, in addition to the lack of low-carbon fuel incentives and policies in place.

Storage for biofuels also requires additional considerations as it may differ from their petroleum counterparts. Pure Biodiesel (B100) needs to be stored in insulated and heated tanks during winter months as it is sensitive to cold temperatures. Long-term storage of biodiesel may cause complications due to different summer and winter blends, degradation caused by temperature fluctuations, and exposure to oxygen. Unlike biodiesel, renewable diesel does not have cold temperature concerns and is more stable for long-term storage. Ethanol is biodegradable and does not have the toxic or carcinogenic properties of gasoline. However, if blended, the harmful properties of gasoline will still apply to the ethanol blend.

# 1.4 Hydrogen Sourcing

There is currently no established hydrogen supply chain in NL. The refinery located in Come by Chance is the sole user of hydrogen on the island, which is produced and consumed onsite. The hydrogen is produced from butane feedstock, which is imported to the facility, and would be considered grey hydrogen. This is not a clean form of hydrogen production and is not an option to reduce emissions in power generation using hydrogen. Cleaner hydrogen production technologies, such as green hydrogen (via electrolysis) or blue hydrogen (steam-methane reforming with carbon capture), should be considered for emissions reduction.

NL's proximity to natural gas reservoirs (for blue or grey hydrogen production) along with its renewable energy sources in hydropower and wind (green hydrogen production), shows the large potential for hydrogen production in the province. However, the province is not currently projected to have a large domestic demand and most of the production being considered is dedicated to export markets.

Several hydrogen production projects have recently been announced in NL and other parts of Eastern Canada. Many of these projects are still in the early stages of development. This report has identified some of the key projects in the area. There may be potential to partner with some of these projects to import hydrogen for power generation.

Green hydrogen production via electrolysis is very energy-intensive and capital-intensive. Highlevel CAPEX and OPEX estimates have been produced for a nominal 200 MW facility (producing approximately 100 tonnes of hydrogen per day), to provide an order-of-magnitude indication for the level of investment required to produce green hydrogen.

A summary of the cost estimate is shown in Table 1-1.

| Budgetary CAPEX                  | Alkaline,<br>MM CAD | PEM, MM<br>CAD |
|----------------------------------|---------------------|----------------|
| Direct Cost                      | 235 – 335           | 310 – 415      |
| Utilities                        | 30                  | 35             |
| Indirect Cost @ 33.5%            | 90                  | 115            |
| TIC Total (US Gulf Coast Cost)   | 355 – 455           | 460 – 565      |
| TIC Total (NL Cost @ 1.2 factor) | 425-545             | 550 – 680      |

#### Table 1-2: Hydrogen Capex Cost

# 2. Introduction

Newfoundland and Labrador Hydro has engaged Hatch to carry out a combustion turbine screening study. The combustion turbine screening study stems of Newfoundland and Labrador Hydro's system planning strategy to continuously improve its generation capacity to meet power demands and reliability.

The study examines potential location of the powerplant on a greenfield and brownfield site. The greenfield sites are located on the Avalon Peninsula, situated on the southeastern part of the island of Newfoundland, while the brownfield site is located at Holyrood thermal power plant.

In addition to examining different potential site locations, the study included different power output scenarios. These scenarios are:

- Scenario 1: Two (2) units to achieve 100 MW nominal simple cycle power plant.
- Scenario 2: Four (4) units to achieve 200 MW nominal simple cycle power plant.

The combustion turbine was screened based on the equipment fast start capability, synchronous condenser, fuel flexibility and ability to be used as a back up generation and peaking plant. An AACE class V estimate was developed for the two scenarios for the greenfield and brownfield sites.

Technical limitations of burning hydrogen, diesel, biofuels such as ethanol and biodiesel in the combustion turbine was reviewed along aside specific upgrades required for a turbine to burn more volume of hydrogen and biofuels.

Furthermore, as part of the scope of this study, the sourcing and transportation of hydrogen, biodiesel, and ethanol within and outside the province was reviewed, and considered hydrogen storage requirements and production.

# 3. Design Criteria

#### 3.1 General Plant Description

#### 3.1.1 Plant Description and Configuration

The combustion turbine generators will be arranged in a parallel configuration with sufficient spacing for equipment maintenance, including crane access and laydown. Each combustion turbine generator (CTG) will be a stand-alone generating unit which will include all necessary support equipment including exhaust stack, air cooled lube oil coolers, power augmentation and winterization packages. A diesel generator will be required to initiate startup sequence of the combustion turbine generator in the absence of an external power source.

Each generator is connected to the switchyard through a dedicated step up transformer located to the north of each generator.

The CTG package and plant auxiliary systems include the following:

- Fuel system including filtration.
- Compressed air for the self-cleaning CTG inlet air filters and other service and instrument air users.
- Demineralized water for emission control and power augmentation.
- Water wash skid and Aerosol fire protection system.
- Balance of plant control and electrical system.
- Turbine exhaust system with exhaust silencers, expansion joints, ducts, and instrumentation.

#### 3.1.2 Operating Requirements

The CTG will be designed for cyclic, peak, part, and base load service. Each unit will be capable of frequent start-ups and shutdowns as well as occasional full load rejection trips and shall be designed suitable in all respects for cycling service operation. Although the turbine is capable of frequent cycling the initial planned service is defined as follows:

- CTG starts/year: 120
- Maximum operating hours/year: 8,000
- Normal operating hours/year: 500

#### 3.1.3 Redundancy Design Philosophy

Plant redundancy will be provided as follows:

- Each CTG system will be complete and capable of full load operation without support from the other units. Full system and component redundancy is not provided within a single CTG package. However, redundancy is provided within the CTG package for protection and control and as required to prevent equipment damage. Backup power during a turbine trip is provided by a battery powered DC system. This will power the emergency lube oil pumps for safe shut down process of the equipment. This will prevent thermal stress on the gas turbine rotor and bearings due to abrupt stoppage of the unit.
- Redundancy will be provided for all normally operating fuel system components, i.e., pressure regulating valves and filter/separators.
- Service and demineralization water pumps with independent power supplies will be provided with 100% redundancy in pump capacity.
- Redundant air compressors and air dryers with independent power supplies will be provided.

# 4. Design Basis

#### 4.1 Electrical, Instrumentation and Control System

The power plant electrical system is designed to include a high and low voltage system, generator step-up transformers, lighting poles/panels, cathodic protection for outside tanks, and exhaust stack lightning protection.

The electrical, instrumentation, and control system for the combustion turbine includes the following:

- Air-conditioned control room for turbine/generator panels.
- Electric motor driven hydraulic pump assembly.
- 600 VAC electrical power for gas turbine starting and accessories.
- Electrical power connections (power cable or duct) from the generator lineside cubicle to the plant facility electrical systems.
- Electrical control connection from the on-base terminal points to the turbine control panel, and from the generator control panel to plant facility electrical systems.
- Motor control centers (MCC) and auxiliary power transformers.
- Control cables between the turbine/generator panels and MCC.
- Power cables to and from the 24/125 VDC battery and charger systems.
- Generator protective relay panels.
- Automatic voltage regulator, power system stabilizer and vibration monitor.

#### 4.2 Civil and Structural

The structural design at all sites is based on a simple steel-frame building with concrete foundations and metal cladded exterior. Depending on the interior layout requirements, this can be accomplished using a stick-build or pre-engineered type of construction.

It is anticipated that the geotechnical conditions on site will allow for the foundations to be a spread footing type bearing on undisturbed native fill or bedrock without the need for a piled foundation. The foundations are expected to have an underside of footing that is below frost depth, which is assumed to be 1.5 metres below finished grade. The slab-on-grade will be designed to support standard occupancy load and any additional equipment may have either a thickened slab or separate foundation detail, depending on specific equipment isolation and loading requirements.

The environmental loading for the building (wind, snow, and seismic) will be based on the NBCC 2015 for St. John's, NL since all sites are near the city. The structure is anticipated to be a "normal" importance category for all environmental loads.

Other than the excavation and backfill requirements for installation of the foundations, it is assumed that none of the proposed sites require a significant amount of site grading or drainage detailing.

Overhead cranes will be installed in the powerhouse to facilitate major maintenance.

#### 4.2.1 Heating, Ventilation, and Air Conditioning (HVAC)

The ventilation system for the turbine building will provide sufficient air circulation to ensure that heat losses from the equipment do not result in an excessive and/or uneven temperature distribution. It also will maintain acceptable working conditions within buildings and structures.

The air intake and exhaust stack of the combustion turbine will be located just outside the powerhouse building allowing sufficient access for maintenance activities.

The air conditioning system will maintain comfortable working conditions in the control room, and electrical room. It will also maintain the required humidity and temperature levels in control rooms and some equipment rooms as applicable.

The system will be designed to the latest revision of the NBC and applicable ASHRAE and ASTM standards.

#### 4.3 Mechanical

#### 4.3.1 Fuel Type

The basis for the design of the simple cycle aero derivative combustion turbine is that the turbines need to have the capability of running on diesel with a possibility of converting to either biodiesel, ethanol, or hydrogen in the future.

The liquid fuel system includes the following major components:

- Manual isolation valve.
- Fuel offloading and forwarding pumps.
- Electric fuel heaters.
- Coalescing filter.
- Fire safety valve with limit switches.
- Duplex filter assembly.
- Fuel boost pump.
- Metering flow control valve.
- Automatic shut-off valves.
- Flow meter.
- Flow divider valve.

- Automatic drain valves.
- Pressure and temperature instrumentation.

#### 4.3.1.1 Fuel Storage

The tank farm is designed for continuous diesel fuel supply for seven (7) days at the maximum rated capacity of the gas turbine (GT). The tank farm also include fuel forwarding and offloading pumps.

| Combustion<br>Turbine | Number of Tanks | Tank Volume         |
|-----------------------|-----------------|---------------------|
| 2 Units               | 2               | 1400 m <sup>3</sup> |
| 4 Units               | 2               | 2800 m <sup>3</sup> |

#### Table 4-1: Fuel Storage

#### 4.3.2 Combustion Turbine Generators

The combustion turbine generators will operate in simple cycle mode with an aeroderivative technology and have a nominal capacity of 50 MW. The generators need to have synchronous condensing capabilities as well as fast start capabilities up to the rated load in 10 minutes or less.

#### 4.3.2.1 Combustor Technology

Combustion turbine generator is designed with either a single annular combustor (SAC) or dry low emission (DLE) combustor. In a single annular combustor, combustion is achieved with a diffusion flame technology where compressed air and fuel are separated before burning in the combustion chamber. This results in high flame temperatures, hence high NOx. SAC technology requires water injection for NOx abatement.

Dry low emission combustor used premix flame approach to achieve combustion. The fuel and compressed air are premixed before being injected in the combustion chamber of the gas turbine. This allows for better control of the combustion process, hereby reducing NOx formation without water injection.

DLE is a modification of the SAC combustors but is limited in application to type of fuel. For nonconventional fuels like biodiesel, ethanol, or naphtha, a single annual combustor is preferred for its robustness and hence requiring water injection for control NOx.

#### 4.3.3 Raw Water

For the greenfield sites, raw water can potentially be supplied from municipalities water main, which can be piped to site. While for the brownfield site, we have assumed the existing Holyrood Power Plant raw water system can provide raw water to the combustion turbines.

#### 4.3.4 Demineralized Water

Demineralized water will be used for the following:

- The Sprint power augmentation system at a maximum flow rate as specified in GE Contract.
- Compressor water wash.

• NOx abatement.

A demineralization plant will be built to supply demineralized water for plant use. Service water will be demineralized then pumped and stored in the demineralized water tank.

Demineralized water will be pumped from the demineralized water tank to the combustion turbine Sprint skids.

The demineralized water system will be designed to meet the water quality requirements.

The demineralized water system includes the following:

- Multimedia Inlet Filter
- Reverse Osmosis System
- Polishing demineralizer
- Demineralized water tank:
  - Demineralized Water Pumps: 2 x 100%

The demineralized tank construction will be stainless steel with interior coating.

The demineralized water tank will be provided with insulation and immersion heaters to prevent freezing.

The plant demineralized water pumps and service water pumps will be in a building.

#### 4.3.5 Compressed Air

The compressed air will provide for both "Instrument Air" and "Service Air" from common compressors. Both instrument and service air will be dried before distribution to prevent freezing/corrosion.

Compressed air will be used for the following:

- CTG inlet air self-cleaning filter (air pulse type).
- CTG lube oil shut down cooling.
- Miscellaneous Instrument Air Users.
- Miscellaneous Service Air Users.

The following equipment will be included:

- Compressors.
- Air dryers.
- Receivers.

The air receiver will be sized to provide emergency shutdown of the power plant when all power to compressors has been lost.

#### 4.3.6 Glycol Cooling System

The Glycol Cooling System for the main lube oil system consists of a fin fan air cooled heat exchanger and a single glycol circulation pump with a three-way temperature control valve. The glycol cooler is located outdoors, and the circulating pump and three-way temperature control valve are in the Auxiliary Module Building dedicated for the lube oil storage and pump facility.

# 5. Site Assessment

#### 5.1 Site Location

The potential greenfield and brownfield site are located on the Avalon Peninsula which is located on the southeastern part of the island of Newfoundland. For this study, a greenfield site was identified for referencing, while Holyrood generation thermal station was identified as the brownfield site location.

#### 5.1.1 Assessment Methodology

The potential greenfield and brownfield site are evaluated for their proximity to a transmission substation, noise considerations, diesel fuel supply, and water availability.

#### 5.1.2 Transmission

The sites are evaluated based on proximity to nearest transmission substation. The Oxen Pond transmission substation is assumed as reference for the sites. Greenfield site is located approximately 15 km to the Oxen Pond substation while Holyrood has an existing transmission line that needs to be further studied for addition transmission capacity. In the absence of this study, the Holyrood site is approximately 30 km from the Oxen Pond substation.

#### 5.1.3 Noise

The distances between the greenfield site to a residential or industrial zone is evaluated to determine the acceptable noise limits. Greenfield site is approximately 6 km, from the nearest residential area. Once a location has been identified, it is important to carry out an environmental assessment reviewing the acceptable noise level. Depending on the report, additional cost may be incurred to mitigate the power plant noise pollution.

#### 5.1.4 Fuel Supply

The greenfield site is located near a major city such as Mount Pearl, and St. John's. This makes sourcing and transporting of diesel easily accessible to the plant.

#### 5.1.5 Water Requirement

A municipality water supply review of Bay Bulls Pond water treatment plant, supplying the St. John's region, revealed a water capacity of 110,000 m<sup>3</sup>/day. In a simple cycle power plant, water is mainly used to control NOx emissions. Four (4) units of the GE LM6000 PC will require approximately 500 m<sup>3</sup>/day of water for NOx abatement. Bay Bulls water treatment plant is a potential source of raw water for the plant. Further investigation will be required to ascertain the available capacity at the water treatment plant. A license will be required to source water from the municipality. A permit will be required to take water from the ponds.

ΗΔΤΟΗ

Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

#### 5.2 Site Ranking

Table 5-1 and Table 5-2 below present the results of the site assessment for each location.

| Table 5-1: Grade Descriptions for Site | Assessment |
|--|------------|
|--|------------|

| Grade | Condition | Description  |  |
|-------|-----------|--|--|
| 2     | Excellent | <ul> <li>Transmission substation is near site</li> <li>Fuel and water resources easily accessible</li> <li>Noise within allowable limits</li> </ul>              |  |
| 1     | Good      | <ul> <li>Transmission substation is far from site</li> <li>Fuel and water resources accessible</li> <li>Noise level to be examined.</li> </ul>                   |  |
| 0     | Poor      | <ul> <li>Transmission substation must be constructed</li> <li>Fuel and water resources are not accessible</li> <li>Noise not within allowable limits.</li> </ul> |  |

#### Table 5-2: Site Assessment for Green Field Locations

| Site Criteria                  | Greenfield Site | Brownfield Site - Holyrood |
|--------------------------------|-----------------|----------------------------|
| Transmission Line Availability | 2               | 2                          |
| Fuel Supply                    | 1               | 2                          |
| Water Source                   | 2               | 2                          |
| Noise Considerations           | 2               | 2                          |

# 5.3 Assumptions and Limitations

The site assessment has been prepared subject to the following assumptions and limitations:

- Detailed field studies or surveys were not conducted as part of this study. The findings obtained from desktop studies and discussions with relevant stakeholders may not have captured all features and characteristics of the sites.
- Information was collected and sources from public sources and external parties. The accuracy of such information cannot be guaranteed. In addition, some of the data obtained may be outdated.
- This study has excluded direct contact with Network Service Providers, Water Supply Authority, Municipalities, Federal, Provincial authorities, and landowners.



#### 6. **Description of Major Equipment**

#### 6.1 **Combustion Turbine Overview**

The following combustion turbine vendors were contacted for the technology screening:

- **General Electric**
- Mitsubishi Power Aero (MHI)
- Siemens.

All three vendors have experience in the design and supply of gas turbines.

#### 6.1.1 General Electric – LM6000

The technology recommended by General Electric (GE) was the LM6000-PC Sprint gas turbine generator set. The design would involve two gas turbines installed in simple cycle mode. The LM6000 group of turbines has more operating experience than any other aeroderivative gas turbine greater than 50 MW.



Figure 6-1: LM6000 Gas Turbine Engine

The technology has the following capabilities:

- Achieves emissions standards while ramping up at 50 MW/minute starting as low as 25% of full load.
- Meets various dispatch profiles with 5-minute start and can reach max power in less than 10 minutes.
- Low emissions technology and fuel flexibility (ethane, propane, LPG) with a standard combustor.

The following sections provide further details on the systems:

#### 6.1.1.1 Combustor Technology

The LM6000 is fitted with a Single Annular Combustor (SAC) or a Dry-Low Emissions (DLE), combustor. For this project GE selected the Single Annular Combustor. Thirty nozzles supply fuel into the LM6000 annular combustor. This produces maximum output with low thermal stress. The swirl-cup dome design produces a lean thoroughly mixed mixture in the primary zone of the combustor. This provides cleaner combustion, reduces NOx, and helps to eliminate the formation of high-carbon visible smoke. Available nozzle designs allow natural gas, or dual-fuel (distillate/natural) operation. The nozzles also permit NOx reduction with Water injection for NOx (Steam injection is no longer offered). The annular combustor design provides low pressure loss, low exit temperature, low smoke, and high combustion efficiency.

#### 6.1.1.2 Water Injection

Water Injection for the NOx System is an available option to reduce emissions on LM6000 PC. The Water Injection for NOx System pumps de-mineralized water to the fuel nozzles via an engine mounted manifold. The water injection motor/pump assemblies, duplex filter assembly, and flow-control valve are located on the auxiliary skid. On natural gas, the LM6000PC can achieve 25 ppm NOx and 42 ppm NOx on diesel no 2.

#### 6.1.1.3 Fuel Capability

The LM6000 can run on the following fuels:

- Natural Gas
- Diesel
- Biodiesel
- Ethanol
- Hydrogen blend.

GE confirmed they can burn biodiesel and ethanol in the LM6000 gas turbine. The LM6000 PC package can burn biodiesel and ethanol without any system upgrade. The unit however requires an alternative fuel such as diesel or natural gas for startup operation. They however have limited experience in burning ethanol in their global fleet. Appendix J of this report shows GE reference list burning ethanol and other alternative fuels like Naphtha and Biomass.

The LM6000 can burn 35% hydrogen by volume with major upgrade in the gas turbine. Some of the required upgrades include:

- Fuel blending skid.
- H2 and NG stop/control valves.
- Flow meters, instrumentation, and controls.
- Inert purge system.



- Fuel piping material upgrade.
- Optical fire protection system.
- Gas sensor.
- Ventilation system upgrade.
- Hazardous gas detection system upgrade.
- Software changes.

When specified, the package is furnished complete with two independent fuel systems. This could include two gaseous fuels, two liquid fuels, or one gaseous and one liquid fuel.

#### 6.1.1.4 Winterization

GE provides winterization for the package modules. This consists mainly of heat tracing, which includes a variable speed ventilation fans and controlled ventilation louvers. In addition to the package module, an air inlet heating system is also provided. This is achieved by installing an inlet heating coil that sits in front of the air filters to prevent them from clogging with ice/snow.

For equipment operating in hot or cold climates, GE recommends selecting the ambient thermal condition options to mitigate the site operating conditions. GE will provide winterization of the gas turbine package to -29°C.

These options may include, but are not limited to:

- Inlet air conditioning (heating or cooling).
- Air conditioning or heaters for some equipment.
- Heat tracing and insulation of applicable unit mounted piping.
- Enclosing and heating exposed instruments and equipment.
- Winterization enclosures for auxiliary skids.
- Variable Frequency Drives for ventilation fans.
- For ambient temperatures below -20°F (-28.9°C), the above modifications plus additional special equipment may be required.

#### 6.1.1.5 Synchronous Condensing

The brush generator is a synchronous, two-pole, cylindrical rotor machine. It has open-air cooling and a brushless excitation system with permanent magnet generator. This power plant operation mode allows the generator to operate as a synchronous motor for grid voltage stabilization at a leading or lagging power factor. The Synchronous condenser mode can ne entered from normal operation or from shutdown condition. When entering this mode from a shutdown condition, the turbine will complete a normal start sequence to breaker closure, after which fuel will be shut off and with the breaker closed the electrical generator/power turbine will turn the gas generator. The

synchronous motor can be operated in voltage control to enable support of transmission system requirement.

6.1.1.6 Balance of Plant – Instrumentation and Controls

The instrumentation and controls provided will ensure safe and efficient operation of the process over the complete range of operating conditions:

- Gas Turbine Enclosure.
- Lubricating Oil and Hydraulic Oil Systems.
- Lube Oil Cooler: Shell & Tube Cooler.
- Lube Oil Piping and Reservoir.
- Multi-stage Static Air Filtration System.
- Evaporative Cooling for improved performance Exhaust.
- Exhaust Collector and Flange.
- Turbine Control Panel (TCP).
- Generator Monitoring and Integrated Generator Protection System.
- 24 V DC Battery and Charger System.
- Human Machine Interface (HMI).
- Fire Protection System.
- Vibration Monitor.
- GTG Motor Control Center (MCC).

#### 6.1.1.7 Start-Up

The GE LM6000 package has the unique ability to reach full power (simple-cycle) from a cold start within 5-minutes for special applications. The gas turbine load ramp rate would be 500 kW/sec, a total of 90 seconds to full load.

#### 6.1.2 *MHI* – *FT4000*

Mitsubishi Power Aero LLC supplies aero-derivative gas turbine packages that generate 30 to 140 MW, tailored and responsive aftermarket services, turnkey EPC expertise, and battery storage.

# PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 27 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022



Figure 6-2: FT4000 SWIFTPAC Aero-Derivative Gas Turbine

The FT4000 has the following features:

- Enables a start-up time of less than 5 minutes from cold start.
- A load change rate of 50% per minute.

#### 6.1.2.1 Combustor Technology

The FT4000® gas turbine utilizes a dry low NOx combustor and is furnished with 24 external radially mounted fuel nozzles for liquid distillate fuel, natural gas fuel, or dual fuel depending upon the fuel system specified by the customer. The combustion system can achieve 42 ppm NOx without a selective catalytic reducer (SCR) while running on diesel.

#### 6.1.2.2 Water Injection

The FT4000 comes with a dry low emission combustor technology that does not required water for NOx emission abatement to achieve a 42 ppm NOx on diesel.

#### 6.1.2.3 Fuel Capability

The FT4000 is designed to run on liquid fuel - diesel, and natural gas FT4000 currently can burn 10% hydrogen by volume with a development cycle of attaining 30% by 2025. As of the time of this report, the FT4000 does not have the capability to burn any biofuel such as ethanol and biodiesel.

#### 6.1.2.4 Winterization

The gas turbine enclosure and electric generator enclosure are designed for outdoor operation to protect the engine and related equipment from the weather and to reduce noise levels. The stated design temperature range is from -4°C min/20°C max. The enclosure is supplied with filtered ventilation air. For installation into building, the inlet and exhaust stacks will need to be ducted. Sufficient access to the enclosure is provided with man doors and equipment removal doors or panels. Sufficient space within the enclosure is provided to allow for normal maintenance and removal of major components.

In cold weather applications, Mitsubishi Power Aero provides a set of engineered systems which allows operations below -14°F / -30°C. By using heat tracing and an EG recirculation air damper, the equipment can operate at low temperatures and be resistant to icing.

#### 6.1.2.5 Synchronous Condensing Mode

This mode allows the generator to operate as a synchronous motor for grid voltage stabilization at a leading or lagging power factor selected by the operator. This mode can be entered from normal operation or from shutdown condition. The synchronous motor can be operated in Voltage control or VAR control to enable support of transmission system requirements.

#### 6.1.2.6 Start-Up

Start-up time of less than 5 minutes from cold start with outstanding system stability and a load change rate of 50% per minute.

# 6.1.2.7 Balance of Plant – Instrumentation and Controls

The following are the balance of plant systems required for the FT4000:

- Gas Fuel System.
- Liquid Fuel System.
- Water Treatment System.
- Compressed Air System.
- Wastewater System.
- Fire Protection System.
- Auxiliary Electrical Systems.
- Medium Voltage Electrical System.
- High Voltage Switchyard/Transmission.
- Civil/Structural Works.

#### 6.1.3 Siemens – SGT-800

#### 6.1.3.1 Technology Overview

The SGT-800 industrial gas turbine combines a simple robust design for high reliability and easy maintenance with high efficiency and low emissions.

# PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 29 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022



Figure 6-3: Siemens SGT – 800 Gas Turbine

The technology has the following capabilities:

- Broad flexibility in fuels, operating conditions, maintenance concepts, package solutions and ratings to satisfy different market requirements.
- World-class reported fleet reliability of >99.5%.
- Guaranteed 42 PPMV NOx.

#### 6.1.3.2 Combustor Technology

The SGT-800 gas turbine package comes with welded 15 stage compressor rotor, 3 stage variable guide vanes (VGV) with a vertically split compressor casing for ease of serviceability. The gas turbine is designed with a single shaft rotor with a rotor speed of 6600 rpm connected to a three (3) stage turbine. Siemens proposed two SGT800 packages rated at 57 MW and 62 MW. The unit price difference between these two-product offering is approximately \$1.7 million. The main improvements for higher power and efficiency includes minor changes in the combustor outlet temperature, improved turbine blades and vanes, improved turbine rotor with curvic couplings for robustness and changed heat shield design.

#### 6.1.3.3 Water Injection

The SGT800 combustion turbine comes with dry low emission (DLE) combustion system which does not require water injection. The unit us able to achieve 25 ppm NOx (Nitrogen Oxide) on natural gas and 42 ppm NOx on diesel no 2. The combustor consists of 30 DLE replaceable burners with on load fuel changeover capability.

#### 6.1.3.4 Fuel Capability

The SGT-800 offers gas only, liquid only (Diesel No.2) or dual fuel (gas/liquid) with on-load fuelchangeover capability. The engine, equipped with DLE burners, is capable to burn up to 75 vol% of hydrogen ( $H_2$ ).

Siemens has limited experience with biodiesel but confirms its capability. The SGT800 is currently being built in Sweden to run on biodiesel with a commercial operation date of 2023. As of the time of the report, Siemens do not have any experience burning ethanol in their gas turbine fleet. However, they claim they have the technology and is willing to partner with any developer or utility power producer to achieve this capability.

# 6.1.3.5 *Winterization* The turbine generator package will require an anti-icing heater for temperatures below -4 °C.

- 6.1.3.6 Synchronous Condensing The water-cooled AC generator comes with synchronizing equipment.
- 6.1.3.7 Balance of Plant Instrumentation and Controls The following are a list of the balance of plant systems:
  - Combustion Air Intake System.
  - Exhaust System.
  - Gas Fuel and Ignition System.
  - Lubricating Oil System.
  - Cooling Water System.
  - Water Cooled AC Generator.
  - Electric Start & Barring System.
  - Weatherproof Acoustic Enclosure.
  - Enclosure Ventilation System.
  - Electrical and control module.
  - Fire Extinguishing System.

# 7. Turbine Technology Selection

General Electric (GE) LM6000 PC sprint aeroderivative gas turbine was technically selected as a preferred technology as it meets all the technical requirements of the proposed plant. These technical requirements are:

- Ability to run biofuels biodiesel and ethanol.
- Synchronous condenser capability.
- Equipment fast start capability under ten minutes (good for peaking plant).
- Ability to burn hydrogen.

The GE LM6000 PC sprint with a 50 MW output on diesel fuel was used in developing a preliminary layout, general arrangement, project schedule and a class 5 cost estimate.

Siemens SGT 800 also meets the technical requirements. The SGT800 gas turbine can only runon biodiesel as a biofuel with longer start up times. However, the unit can burn more hydrogen blend by volume than LM6000 and FT4000.

MHI FT4000 is designed to burn diesel, natural gas, and hydrogen blend. The gas turbine has no capability and experience in burning biofuels.

See Appendix I for combustion turbine evaluation sheet.

# 8. Power Plant Performance

As defined in the design basis section, three different models of gas turbines from multiple OEMs were considered for the study. The combustion technology considered includes:

- GE (General Electric) LM6000.
- Siemens SGT800.
- MHI FT4000.

See Appendix A for a detailed summary of the estimated performances from the OEMs burning diesel and biodiesel.

# 9. Preliminary Process Flow Diagram and Plant Layout

Three (3) preliminary process flow diagrams (PFD) were developed for this study namely:

- 1. General plant arrangement PFD.
- 2. Biofuel (biodiesel) PFD.
- 3. Diesel Fuel PFD.

Four (4) preliminary plant layouts were developed for Scenario 1 and 2 for both greenfield and brownfield sites. The preliminary PFD and plant layout is included in Appendix C.

# 10. Level 1 Project Schedule

The proposed Level 1 schedule for project execution is included in Appendix E. The level 1 project schedule developed was for two scenarios namely:

- Scenario 1: Two (2) units of 100MW nominal simple cycle power plant.
- Scenario 2: Four (4) units of 200MW nominal simple cycle power plant.

See Appendix E for a level 1 Gantt chart project schedule.

# 11. Combustion Turbine Maintenance

Aeroderivative gas turbines maintenance services typically consists of:

• Periodic inspections.

Period inspection typically includes:

- Borescope inspection of the engine. This is typically performed approximately every 4000 hour or annually, depending on whichever occurs first.
- Annual package inspection and controls calibration
- HGPI- Hot Gas Path Inspection

Hot section and combustor rotable exchange. This is typically performed approximately at 30,000 fired hours on natural gas which could vary depending on the operation and condition of the engine. During this maintenance interval, the existing hot gas path section will be removed, refurbished, and replaced.

Major Overhaul

Major Overhaul. This is done at approximately 60,000 fired hours, during which the engine is removed and shipped to the nearest repair workshop for an overhaul. During the overhaul, there is a complete tear down and inspection of engine and rebuilding with new or refurbished components. GE has an optional lease program that provides a lease engine during the major overhaul.

# 12. Capital Cost Estimate

This section describes the basis of the preparation of the capital cost estimate for the NLH Gas Turbine Screening Study for the power plant. Section 13.2 of this report provides a cost estimate for hydrogen production for hydrogen use in the combustion turbine.

The target accuracy of the capital cost estimates is in the range -20% to + 30% which represents an AACE Class 5 Estimate.

The capital cost estimate was compiled based on the following parameters:

- General Electric LM6000 PC Sprint budgetary price.
- The Hatch Thermal Power Plant Factored estimate model was used develop the costs by area and system. The Hatch Thermal Factored Model was developed from benchmark data for completed projects and definitive estimates. Refer to Appendix F for the equipment list.
- United States Dollar currency was converted to Canadian Dollar, based on the current exchange rates tabulated below:
  - The average labour rate for all works was established by Hatch.

| Currency Code | Currency        | Conversion Rate     |
|---------------|-----------------|---------------------|
| Canada        | Canadian Dollar | 1.00 USD = 1.30 CAN |

- Use of a defined Estimate Breakdown Structure (EBS) aligned to the project Work Breakdown Structure (WBS).
- An estimate base date of September 2022.
- All other costs are exclusive of escalation, taxes, and owner's costs.
- Estimates have been produced in accordance with Hatch Global Estimating Standards.


# 12.1 Basis of Estimate

Table 12-2 identifies the Basis of Estimate in summary form.

### Table 12-2: Summary of Estimate Basis

| Commodity                                  | Estimate Basis  |
|--|---|
| Plant and Equipment                        |   |
| Major Equipment                            | Budget quotations based on specifications and data sheets. GE price used for the gas turbines 32 million CAD per gas turbine. |
| Minor Equipment                            | Factored using the Hatch Thermal Power Plant Factored Model   |
| Bulk Materials & Site Works                |   |
| Site Preparation                           | Factored using the Hatch Thermal Power Plant Factored Model   |
| Concrete                                   | Factored using the Hatch Thermal Power Plant Factored Model   |
| Structural Steelwork                       | Factored using the Hatch Thermal Power Plant Factored Model   |
| Site Services Piping, and Valves           | Factored using the Hatch Thermal Power Plant Factored Model   |
| Tanks                                      | Calculated based on volume of tank, ton of steel, fabrication cost, field erection, and internal Hatch database.              |
| Buildings                                  | Factored using building area and benchmark building costs from Hatch internal database  |
| Electrical                                 | Factored using the Hatch Thermal Power Plant Factored Model   |
| Instrumentation                            | Factored using the Hatch Thermal Power Plant Factored Model   |
| Control System                             | Factored using the Hatch Thermal Power Plant Factored Model   |
| Installation                               |   |
| Installation Labour                        | Man-hours calculated or based on historical benchmark data.   |
| Vendor<br>Representatives/Supervision      | Factored using the Hatch Thermal Power Plant Factored Model   |
| Contractor Distributable/<br>Preliminaries | Assessed and applied as a cost per man-hour to the unit labour rates by discipline.   |
| Freight                                    |   |
| Freight                                    | Factored using the Hatch Thermal Power Plant Factored Model   |
| Spare Parts                                |   |
| Commissioning Spares                       | Factored using the Hatch Thermal Power Plant Factored Model   |
| Operations Spares                          | Owner's cost. No Spares Parts have been included in this estimate.  |

# 12.2 Capital Cost Estimate

### 12.2.1 Estimating Methodology

The approach to the estimate preparation was as follows:

- Define the scope of work.
- Structure and code the project into an agreed Estimate Breakdown Structure (EBS).
- Request pricing for Major Equipment.
- Calculate labour man-hour rates for construction work.
- Calculate the labour Productivity Adjustment.
- Establish foreign currency costs and exchange rates.
- Input Major Equipment costs into the Hatch Thermal Power Plant Factored Estimating Model.
- Adjust the model inputs to reflect the specific project scope.
- Determine the costs to carry out the EPCM.
- Establish an appropriate estimate base date.
- Establish appropriate contingency inline with the Hatch Project Life Cycle Process.
- Prepare estimate reports and summaries.
- Undertake estimate reviews.

### 12.2.2 Direct Costs

Direct costs are factored based on major equipment costs and include all the permanent equipment, materials and labour associated with the physical construction of the permanent process facility, and include:

- Land costs (by others).
- Purchase and installation of permanent plant, equipment, and materials.
- Construction labour.
- Contractor's temporary construction facilities, power, and water.
- General construction plant and equipment.
- Contractor's preambles overheads and profit.

# 12.2.3 Permanent Equipment

Estimates for major equipment are based on budget quotations derived from vendors using GTG specification data sheets. For minor equipment, costs were factored based on historical benchmark data. See Appendix H for GTG specification data sheet.

# 12.2.4 Bulk Materials

Bulk materials estimates were developed using the Hatch Factored Model Approach based on the pricing for major equipment.

### 12.2.5 Installation Costs

# 12.2.5.1 Direct Field Labour Costs

Direct field labour is the skilled and unskilled labour required to install the permanent plant, equipment, and bulk materials at the project site. Direct field installation man-hours are developed using estimated the Factored Model approach and benchmarked against completed projects.

# 12.2.5.2 Contractor Indirect Costs

Contractor's indirect costs are costs which are related to the contractor's direct costs, but which cannot easily be allocated to any particular part of them or are not part of the permanent works. For the purposes of this capital cost estimate, these costs are effectively direct costs, and will include the following:

- Contractor's mobilisation and demobilisation, including establishment and later removal and making good, of site offices, storage and other construction facilities, plant, and equipment.
- Contractor's manual indirect and non-productive labour, including time spent in inductions, training, toolbox meetings, clean-ups, bus drivers, crane, and truck operators and store men.
- Scaffolding, safety equipment, personal protection equipment.
- Special construction equipment and special temporary works.

# 12.2.6 Major and Heavy Lift Cranes

Major and heavy-lift cranes, which are project-specific and outside the scope of contractors' general cranage and plant, were identified and estimated as a direct cost. All general cranage is allocated within the all-in labour man-hour rates.

# 12.2.7 Construction Labor Rate and Productivity

# 12.2.7.1 Mechanical Installation Costs

In general, the mechanical installation cost includes:

- Equipment unloading and inspection.
- Storage and storage protection.
- Removal from storage and transport to point of installation.

- Assembly and setting of equipment, leveling, grouting, installation of drive guards, preliminary and final alignments, and balancing.
- First oil fill and cleaning of lube oil piping.
- Installation of on-board equipment.
- Installed integral controls and wiring to first junction box.
- Construction (mechanical completion) testing.
- Touch up painting and clean-up.

# 12.2.8 Indirect Costs

### 12.2.8.1 Basis of Estimate for Indirect Costs

During the next phase of the project a thorough study will be undertaken to determine and document the facilities and services required during the construction and commissioning phases.

12.2.8.2 Engineering, Procurement, Construction Management (EPCM) and Pre-Commissioning The EPCM costs were calculated based on a percentage of the total installed cost (TIC) estimated for the project.

# 12.2.9 Owner Costs

The Owner's costs have not been included in the estimate.

### 12.2.10 Project Contingency

Contingency included in the capital cost estimate is an allowance for normal and expected items of work which must be performed within the defined scope of work covered by the estimate, but which could not be explicitly foreseen or described at the time the estimate was completed. The contingency amount is an integral part of the cost estimate. It does not cover potential scope changes, price escalation, currency fluctuations, allowances for force majeure, or other project risk factors or any of the other items that are excluded from the capital cost estimate.

Typical uncertainties applicable to contingency:

- Insufficient information due to incomplete engineering.
- Areas or systems with a reasonable probability of changes occurring during the detail design stage (considered "design development").
- Equipment or material costs obtained by ratio or update from historical costs or previous estimates.
- Labor productivity and costs.
- Project contingency does not cover scope changes or project exclusions. A contingency allowance of 20% is included.

# 12.2.11 Freight, Duties and Logistics

The freight budget, calculated as a percentage of total direct costs, covers the costs for the transportation of equipment and materials from the anticipated market to the plant site.

# 12.2.12 Spare Parts

Allowance to cover commissioning spares is calculated as a percentage of total direct cost.

### 12.2.13 First Fills

An allowance, calculated as a percentage of total direct costs, has been included to fill plant operating equipment and storage vessels with applicable consumables and fluids. This includes, but is not limited to, the first fills of materials listed below (i.e., materials that need to be replaced due to degradation or leakages rather than process consumption).

- Transformer oil.
- Hydraulic fluid.
- Lube oil and grease.

First fills do not include reagents and fuels.

# 12.3 Estimate Qualifications and Assumptions

The following qualifications and assumption apply to the capital cost estimate:

- The base date of the estimate is generally August 2022.
- Taxes are excluded.
- Environmental Approval Process costs are excluded.
- Owner's Cost including operations support, site representatives and management costs.
- Financing costs are excluded.
- Camp Costs are excluded.
- Site De-watering costs are not included.
- Costs associated with escalation are excluded.
- Schedule acceleration costs are excluded.
- Schedule delays and associated costs are excluded, such as those caused by:
  - Unexpected site conditions.
  - Unidentified ground conditions.
  - Labour disputes.
  - Lack of Labour Resources.
  - Weather Related conditions.

- Force majeure.
- Permit applications.
- Development fees and approval costs of Statutory Authorities are excluded.
- Foreign currency changes from project exchange rates are excluded.
- No allowance for piled foundations has been included.

### 12.3.1 Indirect Cost Assumptions

The following project indirect costs are included in capital cost estimates:

- Construction power and water.
- Heavy haul.
- Performance testing and stack emissions testing (where applicable).
- Preoperational testing, start-up, flushes, cleaning, and calibration.
- Start-up management.
- Initial fills and consumables.
- Construction/start-up technical service.
- Site surveys and studies.
- Engineering.
- Construction management.
- Construction testing.
- Operator training.
- Start-up spare parts.
- Performance and payment bond.
- Subcontractor mark-ups.

### 12.3.2 Owner Costs

Owner costs are not included in the capital cost estimates. Typical Owner's costs include, but are not limited to the following:

- Project development.
- Owner's operations personnel prior to COD.
- Owner's legal costs.

- Owner construction/project management.
- Owner start-up engineering.
- Permitting and licensing fees.
- ECA tax.
- Land.
- Fuel, water, chemicals, and power used during construction and start-up and testing.
- Initial fuel inventory.
- Site security.
- Operating spare parts.
- Permanent plant equipment and furnishings.
- Mobile Equipment (dozers, trucks, etc.).
- Builder's risk insurance and other insurances such as marine insurance, etc.
- Owner's contingency.
- Transmission lines or transmission upgrades.
- Connection fees.
- Escalation through COD.
- Interest during construction (IDC).
- Financing fees.

Access road improvements, new access roads, erection of new bridges, modifications of existing bridges, relocation of existing electrical poles or circuits, or other work not directly associated with facility operation within the site boundaries are not considered or addressed in this report.

It is assumed that the labour force is local. Therefore, camp and per diems have not been included for construction labour.

No taxes, import duties, custom clearance, or any other tax associated with the construction of the facility have been included in the cost estimate.

# 12.4 Capital Cost Summary

The capital cost of each scenario is broken down into direct cost, indirect cost, and contingency. The capital cost estimate is AACE Class 5 Estimate with target accuracy of -20% to + 30%.

Table 12-3 below is a summary of the capital cost for a greenfield and brownfield site.

| Breakdown of  | Gree          | Greenfield    |               | Brownfield    |  |  |
|---------------|---------------|---------------|---------------|---------------|--|--|
| Activities    | 2 x 50 MW     | 4 x 50 MW     | 2 x 50 MW     | 4 x 50 MW     |  |  |
| Direct cost   | \$156,311,000 | \$272,491,000 | \$148,107,000 | \$263,644,000 |  |  |
| Indirect cost | \$31,033,000  | \$48,526,000  | \$30,684,000  | \$47,225,000  |  |  |
| Contingency   | \$35,906,000  | \$61,478,000  | \$34,277,000  | \$59,537,000  |  |  |
| Capital Costs | \$223,250,000 | \$382,495,000 | \$213,068,000 | \$370,406,000 |  |  |

### Table 12-3: Capital Cost Summary

See Appendix G for detailed cost estimate summary.

# 13. Biofuels – Biodiesel/Renewable Diesel/Ethanol

Biofuels can be produced through a variety of different biological and thermo-chemical processes. In general, the terms "Renewable, Green or Drop-in Diesel" and "biodiesel" refer to diesel alternatives derived from biomass. There are two primarily sub-categories of bio-sourced diesels with important differences in their chemical composition due to the different methods of production:

- **Renewable Diesel** is produced through the thermochemical (e.g., gasification, pyrolysis, hydrothermal liquefaction), oleochemical (hydro-processing of lipid feedstock from oil crops, algae, or animal fats), and biochemical (e.g., fermentation) processes for conversion of a variety of feedstocks including lignocellulosic biomass and lipids.
- **Biodiesel** refers to diesel produced through transesterification of lipids (plant and animal oil and fats) or fermentation of crops containing starch/ sugars prior to transesterification. Biodiesel, together with ethanol, were the first biofuels on the market and are deemed first-generation biofuels produced from food-based sources.

Figure 13-1 below demonstrates the different feedstocks and processes to obtain bio-sourced diesels.



Figure 13-1: Feedstock and Processes for Bio Sourced Diesels

The feedstock and production method differentiate biofuels by generation. Figure 13-2 below demonstrates the generations of biofuels.

- 1<sup>st</sup> generation: based on "food grade" biomass (e.g., corn and sugar-based ethanol).
- **2<sup>nd</sup> generation:** a shift towards waste derived feedstock to address socio-political concerns. (e.g., food vs fuel debate).
- **3<sup>rd</sup> generation**: focus on the on-purpose cultivated feedstock such as algae.
- 4<sup>th</sup> generation: derived from specially engineered plants or biomass.





The federal Renewable Fuels Regulations (RFRs), which came into effect in 2010 in Canada, requires fuel producers and importers to have an average renewable fuel content of at least 5% by volume for gasoline and at least 2% by volume for diesel. The provinces have been specifying their own mandates that meet or exceed the minimum federal requirements. However, the RFRs will be replaced by the recently published Canadian Clean Fuels Standard (CFS). The final version of the CFS was published in the Canada Gazette on July 6, 2022. It came into force upon registration but however, with the exception of two sections repealing the pre-existing Renewable Fuels Regulations (RFRs), which will come into force on September 30, 2024, [1]. Unlike the RFRs, the CFS requires greenhouse gas (GHG) reductions on a lifecycle basis, accounting for emissions from the production to the end use of the fuel. The CFS establishes lifecycle carbon intensity (CI) limits for each fuel type (gasoline and diesel), expressed in grams of carbon dioxide equivalent per megajoule (gCO2e/MJ) [1]. Primary suppliers must lower the CI of the gasoline and diesel that they produce in Canada and/or import in accordance with these limits. Rather than requiring each primary supplier to calculate the current CI of their unique gasoline and diesel

pools, the CFS establishes a baseline CI for each fuel. Primary suppliers must lower the CI of their unique gasoline and diesel pools by an amount equal to the difference between the baseline CI for that fuel and the CI limit for the corresponding compliance period. It may be noted that the proposed CFS would have applied to kerosene, fuel oil, and jet fuel in addition to gasoline and diesel, but these fuels were removed in the final CFS.

### Biodiesel

Biodiesel is a substitute for petroleum diesel and is manufactured from plant oil (soybean, canola, corn, etc.,), cooking greases/oils, animal fats, or cellulosic feedstock. Through the chemical process of esterification, the oils are converted into chemicals called fatty acid methyl esters (FAME).

Biodiesel can be blended with petroleum diesel, which is referred to as Bn, where *n* is the percentage of biodiesel in the blend. For example, B5 is a blend of 5% pure biodiesel and 95% petroleum diesel. Biodiesels are most often blended at B2, B5 and sometimes up to B20 as the specifications at this level do not require equipment modification without risking damage.

### **Biodiesel versus Renewable Diesel**

The major difference between biodiesel and renewable (green or drop-in) diesel is the chemical structure, oxygen content, and distinct properties that impact the extent to which it can be blended in the conventional petroleum diesel. The renewable diesel and can be used in its pure form (called R100) as a direct substitute or mixed/blended with petroleum diesel in any proportion, therefore also termed as "drop-in" diesel. Biodiesel composed of FAME has a higher boiling point (close to maximum for road diesel) and poor cold flow properties (cloud point and cold-filter plugging point) that limits its blending (widely termed as a blend wall) to 5-20% max in conventional fossil fuel-derived diesel.

The point at which crystals start to form in biodiesel (cloud point) compared to petroleum diesel is typically higher. This effects the performance of biodiesel in colder temperatures. To accommodate the lower temperatures performance, low temperature flow additives, or low cloud point petroleum diesel or both are necessary. At a high level, the lower the blend the better the operability in colder weather. A comparison of the types of diesels can be seen in Table 13-1.

### Table 13-1: Comparison of Conventional Diesel, Renewable Diesel, and Biodiesel

| Parameter                                     | Conventional Diesel<br>(ASTM D975 US<br>No. 2-D S15)   | Renewable Diesel   | Biodiesel   |  |  |
|---|--|--|---|--|--|
| Chemical structure                            | -  | Oxygen free, straight-<br>chain and branched<br>paraffins (like petroleum<br>diesel) | Fatty acid methyl esters<br>(FAME)  |  |  |
| Blending suitability                          | -  | Diesel Substitute (100%)<br>or any proportion  | <20% for Fleets;<br>5-7% Std (ASTM D975<br><5%; E590 <7%)                   |  |  |
| Vehicle and refuelling equipment adaptability | -  | No changes required  | Modification required (for >5-20% blends)                                   |  |  |
| Adaptability to existing infrastructure       | -  | Suitable   | Material compatibility,<br>deposits/filtration, engine<br>durability issues |  |  |
| Long-term storage<br>stability                | -  | Stable   | Stability issues during<br>long-term storage                                |  |  |
| Properties                                    |  |  |   |  |  |
| Cetane number                                 | >40<br>(>53 in California)<br>>51 in Euro Diesel)  | 70-80  | 45-55   |  |  |
| LHV, MJ/kg                                    | ~43  | ~44  | ~37   |  |  |
| Density @ 15°C, kg/m³                         | Typically 820-840;<br>N/A in North America   | 770-790  | 880   |  |  |
| Flash point, °C                               | >52  | >59  | 100-180   |  |  |
| Cloud point, °C                               | Varies based on Ambient<br>Conditions (Beyond <-<br>12°C, Grades No. 1 and<br>No. 2 are blended) | -34 to -5  | -13 to 10.5   |  |  |
| Viscosity @ 40°C, mm²/s                       | 2-4  | 2-5  | 3-11  |  |  |
| Composition                                   |  |  |   |  |  |
| Carbon, wt%                                   | ~87  | ~85  | ~76   |  |  |
| Hydrogen, wt%                                 | ~13  | ~15  | ~13   |  |  |
| Oxygen, wt%                                   | 0  | 0  | ~11   |  |  |
| Sulfur, ppmw                                  | <15  | <5   | <5  |  |  |

### Ethanol

Ethanol or ethyl alcohol is made from sorted municipal solid waste and from agricultural and forestry crops and residues. Feedstocks for ethanol production vary by region depending on the availability of crops and/or residue. United States and Brazil are the major Ethanol producers, In North America ethanol is typically sourced from corn or wheat grain while in Brazil it is typically sugar cane, and also cellulosic feedstock in both areas.

Besides ethanol being a renewable fuel, its higher oxygen content and complete burning (lower emissions), ethanol has a higher-octane number than gasoline which contributes to its premium blending properties. Most of the gasoline in Canada contains 10% ethanol.

### Sourcing

The production capacity of biofuel has grown significantly over the last decade. As of 2022, there are 19 operational biofuel production facilities in Canada - 14 as ethanol plants and 5 as biodiesel [2] [2] [3] [3]. All facilities are currently located in Central and Western Canada.

In 2021, Canadian imports of ethanol from the U.S. increased by 8% year over year to 1.3 billion liters. This was driven by higher Canadian fuel usage as well as an increased share of domestic supply being exported - the total production of ethanol within Canada was over 1.7 billion liters with 100 million liters being exported [4]. In 2022, imports from the U.S are expected to be 1.5 billion liters to support an upward trend in the average nationwide blend level [4].

Canada's biodiesel facilities are export-oriented with only a fraction of the production focused on the domestic market. Approximately 75 to 90% of Canada's biodiesel is exported, with almost all of it being shipped to the United States driven primarily by the tax credits/incentives and margins.

Overall, the current supply in Canada is not enough to meet the demand required, therefore, there is a very low chance that there will be any availability for domestic supply to Newfoundland and Labrador in the near future. As the biofuel supply chain grows in Canada, provinces near Newfoundland and Labrador such as Ontario, Quebec, Nova Scotia, and New Brunswick may be of interest to NL Hydro to determine their ability to import.

# 13.1 Biofuel Facilities in Canada

Figure 13-3 shows the current and upcoming biofuel facilities in Eastern Canada that may be of interest to NLH.



Figure 13-3: Map of Biofuel Facilities in Eastern Canada

Table 13-2 below includes the biofuel facilities from Eastern Canada. The majority of the current production is in southern Ontario, however, there are several upcoming facilities in Ontario, Quebec, and western Canada.

| Мар | Name                       | City   | Fuel Source                             | Capacity<br>(MMly) |
|-----|----------------------------|--|---|--------------------|
| A   | World Energy               | Sombra, ON   | Biodiesel from variety of<br>feedstocks | 50                 |
| В   | Suncor Energy              | St. Clair, ON Ethanol                                |   | 400                |
| С   | Greenfield Global          | Chatham, ON Ethanol                                  |   | 200                |
| D   | IGCP Ethanol Inc.          | Aylmer, ON Ethanol                                   |   | 340                |
| E   | World Energy               | Hamilton, ON Biodiesel from variety of<br>feedstocks |   | 68                 |
| F   | Refuel YYZ                 | Toronto, ON Renewable Diesel                         |   | 174                |
| G   | Verbio North America Corp. | Welland, ON Biodiesel from vegetable oils            |   | 170                |
| Н   | Kawartha Ethanol Inc.      | Havelock, ON   | Ethanol                                 | 80                 |

|  | Table 13-2: | Biofuel | Facilities | in | Eastern | Canada |
|--|-------------|---------|------------|----|---------|--------|
|--|-------------|---------|------------|----|---------|--------|

| Мар | Name              | City               | Fuel Source      | Capacity<br>(MMly) |
|-----|-------------------|--------------------|------------------|--------------------|
| I   | Greenfield Global | Johnstown, ON      | Ethanol          | 252                |
| J   | Greenfield Global | Varennes, QC       | Ethanol          | 190                |
| K   | Braya Renewables  | Come by Chance, NL | Renewable Diesel | 81                 |

# 13.2 Potential Biofuel Supply Chain

Biofuel import to Newfoundland and Labrador can be accomplished through trucking, shipping, or piping depending on the location and amount required, in a similar manner to conventional fuels such as petroleum diesel.

The movement of refined products in Canada is largely regional due to infrastructure limitations (especially pipelines). The two broad geographic regions include:

- Western Canada: Refineries in Alberta and Saskatchewan supply the demand in the Prairies, British Columbia (BC) and the Northern Territories (Yukon, NW Territories and Nunavut). BC has a couple of small refineries as well that supply part of the provincial demand. The Western Canadian provinces are connected by a network of refined petroleum product pipelines that start near Edmonton, transporting product west to the coast (Vancouver) and east into Winnipeg where it can then be railed or trucked to as far as Thunder Bay.
- **Eastern Canada:** Refineries in Ontario and Quebec supply mainly the provincial demands while most of the production from the Atlantic refineries is exported mainly to the United States. There is a network of pipelines that carries refined products from facilities in Sarnia and Nanticoke towards the Toronto area, and another set of pipelines in Quebec that carry refined products west into the Toronto area.

Figure 13-4 below shows the current product flow system for refined products in Canada for export, import and trades. This can potentially apply to biofuels as well when the market becomes more mature.



Figure 13-4: Refined Petroleum Product Flow in Canada (Canadian Fuels Association<sup>2</sup>)

# 13.3 Storage

### 13.3.1 Biodiesel

In general, biodiesel can be stored similarly to petroleum diesel with a few additional considerations. Solutions for biodiesel storage handling include insulation, agitation, and heating systems. Fuel pumps, lines and dispensers must be protected from cold and wind with proper heating equipment. Unless B100 is stored in underground tanks, it must be stored in insulated and heated tanks, pipes, and pumping equipment during winter months. B100 must also be transported in heated tanks in winter.

Long term storage of biodiesel can pose problems due to slightly different summer and winter blends, degradation caused by temperature fluctuations, and exposure to oxygen. Oxidation of the fuel can cause organic acids, water, and methanol to form in the fuel which will cause problems for fuel consumption and delivery systems. This becomes more of a concern at more concentrated blends, around B20 or higher. Table 13-3 below summarizes storage concerns with biodiesel.

| Storage<br>Consideration  | Explanation   |
|---------------------------|---|
| Contamination<br>Concerns | The flash point of biodiesel significantly lowers if there is methanol or ethanol present in the fuel, allowing it no longer to be handled like petroleum diesel.   |
|                           | Low flash point is a safety hazard and may also lead to decreased lubricity, corroded injectors, and degraded materials in the fuel distribution system.  |
|                           | Biodiesel also has higher tendency to pick up and dissolve water than that of traditional diesel fuels, which can lead to microbiological growth and requires consideration of measures to prevent water contact.   |
| Storage Length            | Biodiesel typically has a "use before" date and should provide six months of storage capability before unacceptable degradation occurs. While Biodiesel is known to have a shorter shelf than most petroleum diesels, but additives can be used to ensure a longer storage life.                  |
| Storage Condition         | Heat and sunlight can accelerate the oxidation process to degrade biodiesel, and therefore should be avoided.   |
|                           | Also, avoiding exposing biodiesel to oxygen during the storage can also help to extend the shelf life.  |
| Storage Transition        | Fuel systems should be thoroughly cleaned and dried before using biodiesel to minimize possible corrosion and contamination. Esters have a solvent effect at higher concentrations and resulting sedimentation and deposits issue. These risks are lesser with lower blends of biodiesel (< B35). |
| Transport                 | Biodiesel can be transported like petroleum diesel fuel, through tanks or piping made of aluminum, carbon steel or stainless steel. These should be properly washed, dried, and inspected before loading to avoid contamination. [5]  |

### Table 13-3: Biodiesel Storage Considerations



| Storage<br>Consideration         | Explanation   |
|----------------------------------|---|
| Cold Temperature<br>Restrictions | Biodiesel will form crystals in cold weather which can cause issues such as plugging filters.<br>Biodiesel should be stored at temperatures at least 2.5-5 °C higher than the cloud point.<br>Biodiesel blends form crystals at temperatures higher than petroleum diesel. Solutions to<br>address this include using fuel additives and fuel filter heaters. |

### 13.3.2 Renewable Diesel

Like biodiesel, renewable diesel can also be stored similarly to petroleum diesel however, unlike biodiesel, it does not have cold temperature concerns.

Table 13-4 summarizes storage attributes regarding renewable diesel.

| Storage<br>Consideration         | Explanation   |
|----------------------------------|---|
| Storage Length                   | Renewable diesel does not have long-term storage stability issues and can be stored for up to similar length as petroleum diesel.   |
| Storage Condition                | There are no additional oxidation concerns with renewable diesel, although it should still be stored under cool and dry conditions like petroleum diesel.   |
| Storage Transition               | Fuel systems should be thoroughly cleaned and dried before using renewable diesel to minimize possible contamination.   |
| Transport                        | Renewable diesel can be transported like petroleum diesel fuel, through tanks or piping made of aluminum, carbon steel or stainless steel. These should be properly washed, dried, and inspected before loading to avoid contamination. [5] |
| Cold Temperature<br>Restrictions | Renewable diesel does not have cold temperature restrictions. It can operate in similar temperature ranges as petroleum diesel.   |

### Table 13-4: Renewable Diesel Storage Considerations

# 13.3.3 Ethanol

Ethanol is much safer than gasoline and diesel, having no toxic or carcinogenic properties, and is fully biodegradable. However, once blended, the harmful properties of the gasoline or diesel still apply to the fuel blend. Ethanol, and ethanol-blended gasoline, however, has high affinity to pick up water and therefore cannot typically be transported by pipeline.

| Storage<br>Consideration                 | Explanation   |
|--|---|
| Contaminant Concerns                     | Ethanol, and ethanol-blended gasoline, has high affinity and ability to pick up water<br>and therefore cannot typically be transported by pipeline. It is typically shipped by rail or<br>truck and blended into gasoline at the terminal.  |
| Compatibility/Material<br>Considerations | Ethanol blends may impact materials in fueling systems such as metallic and elastomer materials. Manufacturers have upgraded materials and developed products that are compatible with E25-85 blends. Fuel systems certified for E85 are known as flex fuel vehicles (FFV).   |
|  | Many elastomer products such as hoses and seals have been upgraded in fueling<br>equipment to accommodate for a range of fuels. Blends below E25 may impact<br>elastomers and contact with E85 causes some elastomers to swell. [6]   |
|  | Materials that can store ethanol include thermoset-reinforced fibreglass, thermoplastic piping, and thermoset-reinforced fibreglass tanks. Other materials have been proven to degrade with prolonger contact to ethanol.   |
| Storage Condition                        | Most existing tanks are compatible with ethanol blends above E10 [6].   |
|  | Ethanol has the tendency to absorb water from the surrounding environment. As such tanks must be cleaned to store ethanol blends. Debris and moisture can build up over time to form water bottoms in the tank which due to the solubility of ethanol in water can cause the fuel to become contaminated [6]. As such is should be stored in dry areas with low humidity. |
|  | All tanks storing E85 blends should be double walled and made of steel, fibreglass-<br>jacketed steel, or UL-listed fibreglass.   |
| Storage Transition                       | Fuel systems should be thoroughly cleaned and dried before using ethanol to minimize possible contamination.  |
| Transport                                | Like storage conditions, ethanol compatible materials should be used to transport and dispense the fuel. As stated above, pipeline transport at larger scale is typically avoided to prevent water contamination.   |

# Table 13-5: Ethanol Storage Considerations

# PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 52 of 163

Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

# 13.4 Economics

Currently, biofuel costs in Canada are higher than their petroleum or conventional counterparts, with biodiesel and renewable diesel being 1.5 and 2 times higher than petroleum diesel. E85 has always been \$0.2-0.3 cheaper than gasoline per gallon, but it is more expensive on an energy equivalent basis. This cost difference is mostly due to the high production cost as well as lack of low-carbon fuel incentives and policies in place. Since there are no policies currently in place to push the use of biofuel, there isn't a need for domestic usage, so current production in Canada is mostly shipped elsewhere where there is a market and incentives (as in the US) for biofuel. There are no incentives in place in Canada to help the biofuel producers with production cost. Since biofuel production costs are higher than petroleum products, this increase in cost is either pushed onto the buyer, or the supplier will sell it into a region that has incentives in place.

The Canada Clean Fuel Standard (CFS) is a federal regulation that is working to incentivize investment and growth in the clean fuel sector, and it is one of the pioneer regulations for Canada as a whole. As stated previously, the regulation will increase the CI reduction requirement and increase the need for alternative fuels in the country, which in return should increase production to drive down the prices.

Unlike Canada, the US, specifically the west coast region (California, Washington State and Oregon) currently has the most advanced/established regulatory environment for alternative fuels in North America. In the US, alternative fuels and their petroleum counterparts are very similar in pricing. In California specifically, biodiesel has been cheaper than petroleum diesel since 2018.

| Fuel<br>(Q2 2022)  | Average Price in US<br>(CAD/L)* [7] | Canadian Average Price<br>(CAD/L) [8] [9]<br>(Global Fuel Prices) |
|--------------------|-------------------------------------|---|
| Diesel             | \$1.66                              | \$1.80  |
| Biodiesel B20      | \$1.56                              | \$2.30  |
| Biodiesel B99-B100 | \$1.71                              | \$2.70  |
| Renewable Diesel   | \$1.67                              | \$3.60  |
| Gasoline           | \$1.40                              | \$1.89  |
| Ethanol (E85)      | \$1.20                              | \$1.67  |

Table 13-6: Average Fuel Price Comparison Between Canada and the US

Note \*: Exchange rate used is 1 USD = 1.28 CAD

# 14. Hydrogen

In recent years hydrogen has gained significant momentum globally due to the potential to help create clean energy solutions. The number of policies and projects around the globe are growing at an unprecedented rate regarding hydrogen integration and development. Today hydrogen is primarily used in the refining and chemical sectors and produced from fossil fuels.

Hydrogen is light, storable, reactive, has a high energy content per unit mass, and can be readily produced at industrial scale. The growing interest in hydrogen for clean energy systems is based on two additional attributes: it can be used without direct emissions of air pollutants or greenhouse gases (GHG); and it can be made from a diverse range of low-carbon energy sources. It offers a way to decarbonize a range of sectors, including long-haul transport, chemicals, steel, and power.

There are many technologies available today to produce, transport, and store hydrogen. Although hydrogen is a clear gas, the "colours" of hydrogen refer to the method in which it is generated. This includes the following categories of hydrogen production:

- **Grey** produced from natural gas via steam methane reforming (SMR). Steam and natural gas react at high temperatures and pressures to produce hydrogen and carbon dioxide (CO<sub>2</sub>). This is currently the dominant technology for large-scale hydrogen production.
- **Brown** produced from coal gasification to create a synthetic gas of carbon monoxide (CO) and CO<sub>2</sub>, hydrogen, and steam from which the hydrogen is extracted.
- **Blue** blue hydrogen uses the same production method of grey or brown with the difference being the resulting CO<sub>2</sub> is captured instead of being released to the atmosphere.
- **Green** produced through electrolysis using renewable energy source. Hydrogen electrolysis is the process of running an electrical current through water to separate the hydrogen from the oxygen.
- Purple/Pink- produced through electrolysis using nuclear energy source.

Hydrogen has the potential to be used for medium to long term energy storage. Several power plants around the world are being converted to use both natural gas and hydrogen with the potential to transition in the future to 100% hydrogen.

Issues with low round-trip efficiency are present with large scale hydrogen storage. This is from the process of converting electricity through electrolysis into hydrogen and then hydrogen back into electricity.

Green hydrogen is produced through the electrolysis of water and requires significant amounts of renewable electricity. When green hydrogen is used in turbines, the final output is electricity with  $\sim 25\%$  round-trip efficiency (electricity-to-electricity) as demonstrated below:



Figure 14-1: Schematic of "4-to-1" Round Trip Efficiency of Green Hydrogen to Electricity\*

\*The storage component shown here is for illustrative purposes only and can represent compressed, liquified, or ammonia-based hydrogen storage.

This 4-to-1 round trip efficiency results in substantial degradation of final electrical output compared to the original electrical input.

# 14.1 Sourcing

There is currently no established hydrogen supply chain in Newfoundland and Labrador. To maximize emission reduction when using hydrogen for power generation, the process by which hydrogen is produced, or its "colour", is a key input. For this study, only low carbon hydrogen production was considered.

The refinery located in Come by Chance is the sole user of hydrogen on the island and it is produced and consumed onsite. The hydrogen is produced from butane feedstock, which is imported to the facility, and would be considered grey hydrogen.

Newfoundland and Labrador's proximity to natural gas reservoirs (blue or grey hydrogen production) and its renewable energy sources in hydropower and wind (green hydrogen production) show the large potential for hydrogen production in the province. However, the province is not currently projected to have a large domestic demand and most of the production being considered is for export markets [10] [10].

### 14.1.1 Hydrogen Projects in Eastern Canada

There has been recent development in the hydrogen industry within Eastern Canada. Some of the more notable projects are listed below. While these projects are in their infancy there is potential to work with developers to import hydrogen to the island.

 Point Tupper, Nova Scotia- EverWind Fuels LLC is scheduled to begin production of a green hydrogen facility in 2025. [11] The company plans to convert the former NuStar transshipment terminal into a producer for hydrogen.

- 2) Bear Head, Nova Scotia- Buckeye Partners LP has completed a takeover of Bear Head LNG. They have outlined plans to remake the export project into a large-scale green hydrogen and ammonia production facility. The electrolyser capacity is expected to be over 2GW [12] [12].
- 3) Saint John, New Brunswick- Irving Oil purchased a 5MW electrolyser from Plug Power Inc. Plug Power is a leading provider of hydrogen solutions. The electrolyser is a proton exchange membrane (PEM) system and will be used at the refinery for the production and distribution of hydrogen. [13] The initial phase of the electrolyser will be powered by the local grid and generate 2 tonnes of hydrogen per day for refining and mobility applications. Irving stated the electrolyser will allow the company to produce hydrogen in a "clean" way. Irving plans to continue to work with the province of New Brunswick to decarbonize the grid and ensure the electricity being used to power the electrolyser is as clean as possible [14] [14].
- **4) Varennes, Quebec-** Hydro-Quebec awarded an engineering contract to Thyssenkrupp to oversee the construction of an 88MW water electrolysis plant. The plant is expected to produce 11,000 tonnes of green hydrogen annually [15].
- 5) Port Hawkesbury Paper- Charbone Hydrogen Corporation signed a memorandum of understanding with Port Hawkesbury Paper to which both parties are entering discussions to develop a partnership for the establishment of Charbone's first small-scale green hydrogen production facility in Atlantic Canada. It is expected that Charbone will be the facilitator of the sale and distribution of the green hydrogen within the Maritime provinces [16].
- 6) H2V Energies Quebec- the facility will use plasma gasification technology to convert raw residual biomass materials such as waste wood and paper into syngas to produce green hydrogen with electrolysis. The estimated production capacity is 49,000 tonnes. The pure compressed hydrogen will start this year at a price of CAD \$3.50/kg [17]. The facility is set to be constructed in Beacancour Industrial Park and scheduled for production in 2024 [18].

## PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 56 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022



Figure 14-2: Map of Hydrogen Projects in Atlantic Canada and Quebec

### 14.1.2 Hydrogen Projects in Newfoundland and Labrador

There has been a more pronounced interest in the hydrogen market in Newfoundland and Labrador in the last 6-12 months. As a result, the provincial government recently announced its plans to open crown land for wind development. There is also interest in developing wind-to-hydrogen projects on the Island. Recently the Government of Canada and Germany signed a "joint declaration of intent" to establish a transatlantic Canada-Germany supply corridor and start exporting hydrogen by 2025 [19]. This announcement was made in Stephenville, Newfoundland, and Labrador the proposed site for the World Energy GH2 Hydrogen project. At this moment it is anticipated that the majority of these projects would focus on export markets. Some of the more notable projects announced shown in Figure 14-3 and described below.

# PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 57 of 163

Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022



# Figure 14-3: Map of Potential Hydrogen Projects and Major Power Generating Stations in Newfoundland and Labrador

Note: Brookfield Renewables has not announced a location publicly for a proposed hydrogen development.

### **BRAYA Renewables**

The refinery in Come by Chance is currently the only hydrogen production in the province. The hydrogen is grey and produced through steam-methane reforming. The hydrogen is used in the refining process. The refinery has been converted to produce hydrogenation-derived renewable diesel and sustainable aviation fuel at 18,000 barrel a day using a variety of renewable feedstocks.

### Port of Argentia and Pattern Energy

In June 2022, the Port of Argentia announced it had signed an Option-to-Lease agreement with Pattern Energy Group to advance the development of a multi-phase renewable energy project in Argentia. The proposed project is a wind energy project to generate green hydrogen and derivative renewable fuels along with an export facility [20]. The project is expected to be 100-200 MW.

Pattern Energy operates around 6 gigawatts (GW) of renewable energy globally [21]. Pattern Energy plans on investigating the commercial feasibility of wind energy and green hydrogen production at the port through the Option-to-Lease Agreement.

### World Energy GH2 Inc. Port au Port-Stephenville Wind Power and Hydrogen Generation

World Energy GH2 Inc. has proposed to construct a maximum 1 GW, 164 turbine onshore wind farm on the Port au Port Peninsula, with associated transmission and supporting infrastructure to power a 0.5 GW hydrogen/ammonia production facility in the port of Stephenville.

The proposed project named project Nujio'Qonik GH2 registered its environmental assessment in June of 2022. On August 5<sup>th,</sup> the Minister of Climate Change ordered a full Environmental Impact Statement (EIS) to be completed. Any areas of the proposed project that overlap with protected areas, private land, mining operations, mineral licenses, and leases, as well as recreational and traditional land uses must be identified along with a potential project redesign.

Phase 1-Onshore (Current Scope of Registered Environmental Assessment):

- Up to 1 GW onshore wind Generation.
- 0.5 GW Green Hydrogen Production.
- 230 kV interconnection to electrical grid.
- 3x50 MW gas turbine generators (fueled primarily by hydrogen).
- 700 gallons/minute industrial water supply.
- Hydrogen processing facility at the port of Stephenville.
- Grid interconnections and the hydrogen-fuelled turbine generator at the Port.

Phase 2 Onshore Expansion (subject to separate regulatory requirements):

- 1.0 GW additional through onshore wind.
- 0.5 GW Green hydrogen production.
- 350 gallons per minute industrial water supply.
- Switchyard expansion.
- Concurrent expansion of the hydrogen plant.

Phase 3 Onshore Expansion (subject to separate regulatory requirements):

- Evaluate further wind resource potential in the region and potentially expand further.
- 1.0 GW additional through onshore wind.
- 0.5 GW Green hydrogen production.
- 350 gallons per minute industrial water supply.
- Switchyard expansion.

The proposed phases of the project and location can be seen in Figure 14-4 below.



Figure 14-4: World Energy GH2 Project Proposed Location [22]

The plant layout for the production facility can be seen in Figure 14-5 below:

- 1. High Voltage (HV) Transformer (230 to kV)
- Medium Voltage (MV) Transformer and rectifier
- Electrolyzer Building, Separators, Pipe Racks
- Cooling System and Oxygen Handling
- 5. Hydrogen Purification and Surge Storage
- Compression and Processing
- 7. Water Purification
- 8. Offices, Controls, and
- 9. Truck Loading Rack for Local Distribution



Figure 14-5: World Energy GH2 Hydrogen Facility [22]

### **Brookfield Renewables**

Another major player with reported interest in a hydrogen project in the province is Brookfield Renewables. While the company has been less forthcoming about its plans to develop hydrogen in the province it has recently released it plans to wind generation of 250MW to power a 240MW hydrogen facility [23]. The estimated cost is \$2 billion CAD. However, the company has not yet disclosed if they have a location in mind. The company has partnered with German energy firm Uniper and anticipated export of hydrogen by 2027.

### **Fortescue Future Industries**

Australian company Fortescue Future Industries has been investing in green energy projects around the world. They have signed numerous deals for feasibility studies in countries such as Brazil, Indonesia, and Afghanistan. As part of their global assessment, the company investigated opportunities in Newfoundland and Labrador. In 2021, the company was reviewing the 2,500 MW generating capacity in Gull Island [24].

The company has recently proposed a 2,000MW wind to green hydrogen facility on the west coast of the island of Newfoundland. The project is called Project Lynx and consists of 400 wind turbines, a hydrogen production facility, ammonia conversion and a marine export facility. An estimated 700,000 to 900,000 tonnes per year of green ammonia would be produced exclusively for export.

It was reported in July that the company is looking at Searston, Doyles, South Branch, Codroy Pond, and Gallants for the turbine location. For the hydrogen facility the company is looking at Port aux Basque, Turf Point and Stephenville. The company would expect construction to start in late 2026 and have it operational in 2029.

Fortescue Future Industries has signed a Memoranda of Understanding (MoU) with the Miawpukek First Nation to explore the feasibility of a project to produce hydrogen on the southwest coast of Newfoundland and Labrador.

### 14.1.3 Hydrogen Carriers

### 14.1.3.1 Liquid Hydrogen

Liquid Hydrogen is one of the primary options for transporting hydrogen over long distances. The primary advantage of transporting liquid hydrogen is its increased density compared to gaseous hydrogen when it comes to transporting large quantities of hydrogen.

Gaseous hydrogen is liquefied when its temperature is cooled below -253°C at atmospheric pressure. At this temperature, the density of liquid hydrogen is about 800 times that of gaseous hydrogen at standard temperature and pressure and approximately 1.7 times higher than compressed hydrogen at 800 bar.

Hydrogen liquefaction is currently very energy intensive, and it typically consumes around 30% of its energy content.

In North America there are currently liquefaction plants ranging in size from 6 to 80 tonnes per day of hydrogen, with most of these plants located in the U.S.

### 14.1.3.2 Ammonia (NH3)

Ammonia can be used to transport hydrogen long distances, but it is also currently used in different industries such as a raw material for fertilizers and chemical production.

Ammonia is currently produced industrially through the Haber-Bosch process. This process has been well-established since 1918, where it was used in the chemical industry. The process combines hydrogen and nitrogen at high pressure and temperature to produce ammonia.

For end-users that ammonia is not the feedstock it will be required to be dissociated back to hydrogen and nitrogen.

# 14.1.3.3 Liquid Organic Hydrogen Carrier (LOHC's)

Liquid organic hydrogen carriers are organic compounds that can be used as a storage media for hydrogen. This technology is relatively new compared to liquid hydrogen and ammonia.

The concept of LOHC's is to use organic compounds that can absorb and release hydrogen through chemical reactions (hydrogenation and dehydrogenation) to carry hydrogen as a liquid.

# 14.1.4 Transportation of Hydrogen

As there is currently no established hydrogen supply chain in Newfoundland and Labrador, different methods of importing hydrogen would need to be evaluated. Hydrogen has a high gravimetric energy density but a relatively low volumetric energy density. This directly relates to a higher storage and transportation cost. As a result, hydrogen is typically produced near its end user. However, as the forecasted global demand for hydrogen is expected to increase, a greater emphasis has been placed on transportation.

This section provides an overview of the main methods that could be considered for importing hydrogen in Newfoundland and Labrador.

### 14.1.4.1 Pipelines

Historically, pipelines have been the most cost-effective method of transporting hydrogen over long distances. Globally there are several pipelines dedicated to hydrogen distribution. Existing infrastructure around the globe is being investigated to be converted to hydrogen transport. The IEA has stated that for distances under 1,500 km transporting hydrogen as a gas by pipeline will likely be the cheapest delivery option.

There is no existing pipeline infrastructure in Newfoundland and Labrador. The capital cost is intensive and social impact would require further evaluation to pursue this option.

### 14.1.4.2 Shipping

Liquid Hydrogen can be transported by vessel. The Suiso Frontier, built by Kawasaki Heavy Industries, is the world's first liquid hydrogen carrier ship. In January of this year, it completed its first shipment from Australia to Japan. The vessel is capable of carrying up to 1,250 m<sup>3</sup> (90 tonnes) of compressed liquid hydrogen.



Figure 14-6: Suiso Frontier Liquid Hydrogen Transport Vessel [25]

In April of 2022, Kawaski obtained their Approval in Principle (AiP) for a large 160,000 m<sup>3</sup> (11,400 tonnes) hydrogen carrier. This carrier would be 100 times larger than the Suiso Frontier.

# PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 63 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022



Figure 14-7: Simulated Appearance of the Completed 160,000m<sup>3</sup> Liquid Hydrogen Carrier [26]

Transporting ammonia can be completed using liquefied petroleum gas (LPG) carrier ships. Unlike liquefied hydrogen ammonia has a long history in transportation and does not have the same issues with transporting cryogenic liquids and does not require high-pressure that is required for compressed hydrogen.

During transportation, ammonia is executed in refrigerated ships at low temperatures to keep the ammonia in liquid form. Current ammonia ships have capacities up to 86,700m<sup>3</sup>.

Currently LOHC's are not being transported by marine vessel. However, in theory, existing infrastructure for conventional fuel transportation can be used as saturated LOHC can be transported by ordinary oil tankers to the end user. This is advantageous over gaseous and liquid hydrogen as it removes requirements for cryogenic or compressed gases.

Many LOHC carriers such as methanol, toluene and other chemicals are widely transported by vessel around the world today. Methanol can be stored in inorganic zinc/epoxy coated tanks, although stainless steel is preferred. Toluene can be stored in mild steel or stainless-steel tanks and can be transported via vessel.

### 14.1.4.2.1 Road (Liquid)

Transport by truck on the road in liquid form can transport higher volumes than compressed gas with higher efficiency over shorter distances.

### 14.1.4.2.2 Road (Gaseous)

Hydrogen can be compressed and transported through tube trailers. The trailers can be mounted to trucks or to barges and transported short distances.

Presently hydrogen is most commonly distributed through compressed gas trailer trucks for distances less than 300km [27]. Currently, single trucks can transport up to 400 kg H2 at 200 bar, with the potential of transporting further compressed hydrogen (500 bar) of up to 1,000 kg H2 [27]. Highly insulated cryogenic tanker trucks can potentially carry up to 4,000 kg of liquid hydrogen and can be used for long distance transport [27].

Table 14-1 below compares present day hydrogen transportation methods.

| Parameter                  | Unit                 | Truck (Gaseous)<br>Low Pressure | Truck (Liquid) | Pipeline<br>(Gasous)   | Shipping<br>(Liquid) |
|----------------------------|----------------------|---------------------------------|----------------|------------------------|----------------------|
| Pressure                   | Barg                 | 200                             | 0              | 30-120                 | 0                    |
| Temperature                | °C                   | Ambient                         | -253           | Ambient                | -253                 |
| Approx. Capacity           | Kg of H <sub>2</sub> | 400 (1)                         | 4,000 (2)      | 1700/km <sup>(3)</sup> | 90,000 (4)           |
| Approx. Levelized Quantity | -                    | 225 Trucks                      | 25 Trucks      | (5)                    | 1 Ship               |

#### Table 14-1: Comparison of Transport of H2

[1] Capacity is based on a 26 m<sup>3</sup> 40-ft tube trailer at 200 barg. Note: Larger transport capacity is expected in the midterm due to lighter composite storage tanks that are being developed.

- [2] Capacity is based on a loading volume of 50m<sup>3</sup>.
- [3] Capacity is based on 1000% injection in a 36" pipeline at 100 barg and 0°C.
- [4] Capacity is based on the Suiso Frontier Ship, the first and only hydrogen transport ship in operation globally.
- [5] Dependent on distance from location.

# 14.2 Green Hydrogen Production

Green hydrogen is produced from electrolysis where water is used to split into oxygen and hydrogen. Alkaline and proton exchange membrane (PEM) electrolysis are the most widely adopted methods of green hydrogen production. Alkaline electrolysis is more mature and commercially developed, but PEM has a faster ramp rate and can be made to be more compact. Table 14-2 shows some of the major differences between the 2 technologies.

|                     | Alkaline Electrolysis   | PEM Electrolysis  |  |
|---------------------|---|---|--|
| Process Description | <ul> <li>Uses a liquid alkaline solution of sodium or potassium hydroxide</li> <li>Operates via transport of hydroxide ions (OH -) through the electrolyte from the cathode to the anode</li> <li>Hydrogen is generated on the cathode side.</li> </ul> | <ul> <li>Water oxidizes to form oxygen and<br/>hydrogen ions at the anode when<br/>voltage is applied</li> <li>Electrons flow through an external circuit<br/>and hydrogen move across the solid<br/>electrolyte membrane to the cathode</li> <li>Hydrogen combines with the electrons at<br/>the cathode to form hydrogen gas</li> </ul> |  |
| Advantages          | <ul><li>Mature technology</li><li>Lower comparative CAPEX</li><li>Better scalability</li></ul>  | <ul><li>Compact footprint</li><li>Dynamic response</li><li>High H2 purity</li></ul>   |  |
| Disadvantages       | Larger footprint  | Higher component cost   |  |

Table 14-2: Alkaline and PEM Electrolysis Comparison

|                                     | Alkaline Electrolysis      | PEM Electrolysis  |  |
|-------------------------------------|----------------------------|---|--|
|                                     | Low dynamic responsiveness | <ul> <li>Higher degradation rate</li> <li>Higher projection costs due to precious metal used</li> </ul> |  |
| Technology Readiness<br>Level (TRL) | 9                          | 9   |  |

### 14.2.1 CAPEX

A high-level cost estimate has been produced for a hydrogen production facility based on Hatch's historic costs and expertise on previous studies. A typical hydrogen production plant includes the following components:

- Hydrogen assumed at 99.99% purity.
- Oxygen is vented to safe location and not recovered.
- Cost of H2 and O2 vents included in hydrogen generation cost.
- Buildings for Alkaline technology equipped with overhead crane, fully enclosed with HVAC system, vents for hydrogen and oxygen installed on the roof.
- Average cost of compressor building included for Alkaline and PEM building cost.
- Hydrogen Production includes transformers, rectifiers, electrolyzer stacks, gas separation and scrubbing, Compression if required.
- Substation: Assumes high voltage connection is available at site, conversion into medium voltage 34.5 kV is required through a substation.
- Utilities Cost includes Water Treatment, Instrument Air and Nitrogen, Cooling System, Instrument/Process Control System.
- Indirect cost includes freight, engineering, temporary site facilities, contractor assistance during commissioning, third party services, construction camp, contractors travel and owner cost.

The CAPEX for a 200 MW green hydrogen production facility varies depending on the technology used. Table 14-3 below shows a high-level breakdown of the cost for each technology. Overall, the capex using alkaline is around \$425-545 million CAD, and the capex for PEM is between \$550-680 million CAD. This would be around \$CAD 2.5 MM/MW for alkaline and \$CAD 3.0 MM/MW for PEM. Additional Contingency is not included in the CAPEX estimate.

### Table 14-3: Budgetary CAPEX for a 200 MW Green Hydrogen Facility

| Budgetary CAPEX   | Alkaline,<br>MM CAD | PEM, MM<br>CAD |
|---|---------------------|----------------|
| Hydrogen Production (inc. Transformers, Rectifiers, Electrolysis, Scrubbing, Compression if required) | 150 – 250           | 230 – 340      |

| Budgetary CAPEX                  | Alkaline,<br>MM CAD | PEM, MM<br>CAD |
|----------------------------------|---------------------|----------------|
| Substation                       | 65                  | 65             |
| Building                         | 20                  | 15             |
| Process Units Subtotal           | 235 – 335           | 310 – 415      |
| Utilities                        | 30                  | 35             |
| Indirect Cost @ 33.5%            | 90                  | 115            |
| TIC Total (US Gulf Coast Cost)   | 355 – 455           | 460 – 565      |
| TIC Total (NL Cost @ 1.2 factor) | 425-545             | 550 - 680      |

### 14.2.2 OPEX

The OPEX for a 200 MW hydrogen facility is made up of electricity costs, maintenance costs, labor costs, and water costs. Since the electricity cost makes up over 90% of the operating cost for a green hydrogen production facility, a cheaper electricity price can drastically decrease the total OPEX required. The electricity price used for this calculation is based on the current NL Hydro Island Industrial Firm Rate. The SUSEX (sustaining capital) is also a contributing part of the total cost averaged at about \$4-6 MM CAD/annum and this is used to replace the electrolyser stacks at the end of their lifetime.

#### Table 14-4: Budgetary OPEX

| OPEX Input                         | Unit                         | Alkaline   | PEM        |
|------------------------------------|------------------------------|------------|------------|
| Variable Costs                     |                              |            |            |
| Chemicals, Catalysts & Consumables | MM CAD/year                  | negligible | negligible |
| Water                              | M3/day municipal water spec. | 2340       | 1281       |
| Water Treatment Costs              | CAD/m3                       | 0.5        | 0.5        |
| Power (Total)                      | MWh                          | 246-270    | 245-268    |
| Direct Fixed Costs                 |                              |            |            |
| Staffing                           | Number of employees          | 14         | 14         |
| Maintenance                        | % of direct costs            | 3          | 3          |
| Other Fixed Costs                  |                              |            |            |
| SUSEX                              | MM CAD/year                  | 4          | 6          |

# 14.2.3 Production Cost Outlook

According to the International Energy Agency (IEA), it currently costs up to \$10.25 CAD/kg (\$8 USD/kg) to produce green hydrogen, which is much higher than hydrogen produced from other sources [28] According to previous studies done within Hatch, the current levelized cost of hydrogen produced from alkaline is around \$5.5 CAD/kg. Hydrogen produced from PEM electrolysis are expected to be slightly higher.



# Current Levelized Production Costs, USD/kg

### Figure 14-8: Levelized Production Cost of Hydrogen

Green hydrogen production costs are influenced by many technical and economic factors, such as electrolyser scale, production capacity, conversion efficiency and electricity costs. As more commercial-scale applications and large production facilities come online, this will help decrease the capital cost and scale up supply chain. Decreasing renewable electricity cost will also decrease the operating cost since the majority of the OPEX comes from the electricity cost.

Summarized in the IEA's net zero scenario, the price of green hydrogen could decrease to under \$4 USD/kg by 2030 and less than \$3.5 USD/kg by 2050 which allows it to be more competitive with other types of hydrogen.

# 14.3 Storage

Hydrogen can be stored in different states depending on the end use and capacity requirements. Currently it is most commonly stored and delivered in either compressed gas or liquid form. The majority is either produced and consumed on-site (around 85%) or transported via trucks or pipelines (15%).

# 14.3.1 Compressed Hydrogen Storage

Compressing hydrogen to a high pressure increases its density thereby decreasing the volume required for storage. A high-pressure gas steel cylinder is the most common method to store hydrogen with at pressures greater than 200 bar.

Hydrogen gas is typically compressed to 100-825 bar for large-scale storage. The pressure vessels for hydrogen storage can be categorized by four types (I, II, III, IV). In general, the vessels have a central cylindrical section with two spherical domes and polar opening (s).

| Туре     | Material                  | Liner            | Pressure (Max) | Wt.% H2 When<br>Filled           |
|----------|---------------------------|------------------|----------------|----------------------------------|
| Туре I   | Metal (Steel)             | N/A              | 200 - 300 Bar  | 1%                               |
| Type II  | CFRP frame                | Metal            | -              | 2%                               |
| Type III | CFRP cylinder<br>and ends | Metal (Aluminum) | 450 Bar        | -                                |
| Type IV  | CFRP cylinder<br>and ends | Plastic (HDPE)   | 1000 Bar       | 5.5% (350 Bar)<br>5.2% (700 Bar) |

### Table 14-5: Comparison of Tank Types [29]

Compressed hydrogen has only 15% (at 700 bar) of the energy density of gasoline. Therefore, storing the same amount of energy would require 7 times the space.

For stationary storage, type I and type II tanks are the most cost effective, typically constructed out of stainless steel.

### 14.3.2 Liquid H2/Ammonia

Two ways of storing hydrogen, especially for transportation over long distances, are as liquid hydrogen and ammonia.

Liquid hydrogen storage is mainly considered for large production where storage space is limited, when it must be transported over long distances or for industrial applications requiring liquid hydrogen. Hydrogen liquefies at -253 °C and requires cryogenic tanks for storage. These tanks are comprised of two layers separated by a vacuum thermal insulation to avoid heat transfer by convection.

Currently, the largest cryogenic storage tank is a  $3,800m^3$  spherical tank owned by NASA with a capacity of 270 tonnes of liquid hydrogen [30]. Japan's Kobe LH<sub>2</sub> Terminal has a spherical LH<sub>2</sub> storage tank with a capacity of 178 tonnes (2,500 m<sup>3</sup>) [31].

After the hydrogen has been liquefied, it is important to minimize the amount of evaporation during storage. To avoid losses such as boil-off and heat leakage and to prevent any risks due to the physical properties of hydrogen, the boil-off effect must be continuously controlled. The boil-off rate can be reduced by minimizing the surface-to-volume ratio of the tanks by making them spherical and by adding insulation to minimize heat transfer through the tank walls. The boil-off rates for larger insulated spherical tanks are commonly below 0.1% per day [32].

Another method to store liquid hydrogen is using cryo-compressed hydrogen storage which stores hydrogen at cryogenic temperatures in a vessel that can be pressurised. This is a relatively new technology.

Since ammonia is one of the most transported chemicals worldwide each year, infrastructure and facilities for ammonia storage is well developed and efficient [33]. Tanks to store ammonia are often constructed of steel or ductile iron. Composite and aluminum tanks are also compatible with ammonia. Ammonia can react with metals which can lead to corrosion. Therefore, these storage tanks must be monitored and evaluated on a periodic basis to avoid risk of containment failure [34].

Currently, industrial atmospheric/low pressure ammonia storage tanks have capacities from 15,000 to 50,000 tonnes (~24,000 to 80,000 m<sup>3</sup>) of ammonia [35] [36].

### 14.3.3 Geological

Long-term geological storage options for hydrogen include salt caverns, depleted natural gas and oil reservoirs and aquifers. These storage mediums are currently used for natural gas storage. Geological storage has a high efficiency, high storage potential and low operational cost. The types of underground storage can be categories by the type of geology:

- Porous media (e.g., sandstone): this includes depleted oil and gas reservoirs as well as aquifers.
- Cavern Storage: this includes excavated, or solution mined rocks such as salt, coal, igneous and metamorphic rocks.

The basic storage requirements include high porosity, high permeability, ability to hold adequate volumes of gas, ability to extract gas at high rates, contain and trap the gas as well as cushion gas.

Some of the advantages of geological underground storage include:

- Higher storage pressures.
- Smaller surface footprint.
- Higher safety standards.
- Minimization of environmental impact.
- Longer operating lifetimes.

Some of the key challenges associated with geological storage:
- The chemical reactivity of hydrogen gas with minerals, dissolved solutes, microbial metabolisms, and a variety of effects on metals and other building materials.
- High mobility and low viscosity when compared to natural gas. This leads to increased leakage through preferential pathways such as fractures or transport into adjacent aquifers.
- Geological requirements and proximity to end-user.
- Potential chemical reactions with hydrogen that can result in contamination or loss.
- Legal and social obstacles on regulations for land use, etc.
- Cushion gas is the volume of gas intended as permanent inventory in a storage reservoir to maintain adequate pressure and deliverability rates. High cushion gas requirements limit the amount of gas that can be withdrawn.

### 14.3.3.1 Salt Caverns

Salt caverns are solution-mined cavities within either salt domes or bedded salts. Salt caverns have been used for hydrogen storage in the chemical sector since the 1970's and 1980's in the United Kingdom and the U.S. respectively [27]. Salt caverns have an average efficiency of around 98% meaning that almost all the injected hydrogen can be recovered [27]. There is a low risk of hydrogen contamination in salt caverns. The high pressure enables high discharge rates which makes this option attractive for power consumption.

At present Newfoundland and Labrador does not have legislation to allow for storage and recovery of industrial waste in geological media.

Atlas Salt has spent recent years working on a salt deposit project between St. Georges and Flat Bay on the West Coast of the island of Newfoundland. The intent of the project is to mine and sell road salt to consumers on the eastern seaboard. The company is now looking at alternative applications for the deposit with particular interest in the storage of hydrogen [37]. Salt caverns typically require between 20-30% of the total capacity to be cushion gas.



### Figure 14-9: Atlas Salt [37]

### 14.3.3.2 Depleted Oil and Gas Fields

Depleted oil and gas fields are typically larger than salt caverns. However, they contain contaminants that would be required to be removed prior to the hydrogen being able to be used.

Newfoundland and Labrador has an active offshore oil industry. However, due to the location of the fields with the closest field greater than 300km offshore, it is uneconomical to store hydrogen in depleted fields for onshore applications.

Depleted oil and gas reservoirs typically require 50% of the total capacity to be cushion gas.

### 14.3.3.3 Aquifers

Aquifer storage is like storage in depleted hydrocarbon reservoirs; however, aquifers are the least mature of the geological storage opportunities. The following conditions must be met for an aquifer to be suitable:

- Top of the aquifer is sealed by an impermeable layer of rock.
- The presence of a dome-shaped structure to hold the injected gas in a defined space.
- High permeability of the aquifer with adequate pore space.

Significant investment for exploration is required to establish these characteristics. Consideration also needs to be given to the potential for hydrogen reacting with minerals present, which can result in both depletion of stored hydrogen and contamination. Hydrogen can also react with microorganisms, which could block the pore spaces and lead to the loss of stored gas.

The advantage of aquifers over depleted oil and gas fields is that there is no risk of contamination with hydrocarbon residues.

Aquifers typically require 50-80% cushion gas of the total capacity of the space.

### 14.3.4 Other Storage Methods

Hydrogen can be chemically stored by absorbing or reacting with other chemical compounds such as metals. Metal hydrides is type of hydrogen chemical storage and has the ability to store hydrogen at high densities that can exceed liquid hydrogen. The challenges of storing hydrogen in chemical from are related to the hydrogenation and dehydrogenation process which has high temperature and pressure requirements.

Other emerging storage opportunities include circular methanol, dimethyl ether, and liquid organic hydrogen carriers.

### 14.3.5 Comparison of Storage Mediums

The following Table 14-6 outlines some of the advantages and challenges with the different methods of storing hydrogen.

| Table 14-0. Companyon of Storage Mediums |
|--|
|--|

| Technology            | Advantages  | Challenges  | Potential Use  |
|-----------------------|---|---|--|
| Compressed<br>Gaseous | Proven technology   | <ul> <li>Compressor cost, reliability,<br/>and efficiency loss</li> </ul>     | <ul> <li>For shorter distance<br/>transportation within NL</li> </ul>                          |
|                       | Easily scalable   | ,<br>,  | '  |
| Liquid<br>H2/Ammonia  | <ul> <li>Large capacity for given<br/>footprint</li> </ul>  | <ul> <li>Cost of<br/>liquefication/conversion</li> </ul>                      | <ul> <li>For long distances (e.g.,<br/>shipping)</li> </ul>                                    |
|                       | <ul> <li>Proven technology</li> </ul>   | capital   | <ul> <li>For applications requiring</li> </ul>   |
|                       |   | <ul> <li>Energy intensive and<br/>efficiency loss, boil-off losses</li> </ul> | LH2 or NH3   |
|                       |   | Difficult to scale easily   |  |
|                       |   | <ul> <li>Requires reconversion to<br/>gaseous H2</li> </ul>                   |  |
| Geological            | <ul> <li>Highest capacity for large<br/>generating plants and/or<br/>long-term storage</li> </ul> | <ul> <li>Requires favourable<br/>geological formation nearby</li> </ul>       | <ul> <li>Suited for long-term<br/>storage and very large<br/>quantities of hydrogen</li> </ul> |
|                       | <ul> <li>Can be easily scalable<br/>for salt beds</li> </ul>                                      |   |  |

Based on a storage requirement for 130MW output for 5 days. Table 14-7 estimates the storage volume based on the hydrogen carrier.

### Table 14-7: Storage Tank Volumes

| Medium                               | Storage Volume (m <sup>3</sup> ) |
|--------------------------------------|----------------------------------|
| Compressed hydrogen (CH2) at 350 bar | ~58,000                          |
| Liquid Hydrogen (LH2)                | ~20,000                          |
| Ammonia (NH3)                        | ~13,000                          |

Note: Assumes a turbine efficiency of 35% (~44,500 MWh storage requirement).

### 14.4 Pricing

The cost of hydrogen purchased from a third party depends on many factors such as local supplier and producer availability, local hydrogen demand, local fuel policies, and potential purchase agreements between the supplier and the buyer. Although there are studies done in the province on potential hydrogen production, there are no current green hydrogen suppliers or production plants in Newfoundland and Labrador, making it very difficult and expensive to purchase from a third party.

Aside from the lack of supply chain, the amount of hydrogen required is also relatively large (100+ MW capacity), therefore it would likely require a dedicated production facility to ensure a constant supply of hydrogen.

Based on Hatch's experience, most clients requiring large hydrogen capacities tend to go with one of the two options below:

- The user decides to build, operate, and own a hydrogen production facility for themselves. The cost associated with this option would be the CAPEX and OPEX shown above under Section 14.2.
- 2. The user decides to partner with a hydrogen supplier/producer. In this case, the supplier would build, operate, and own the production facility, but the hydrogen produced is sold to the using party through a contract on agreed cost for a period.

If purchasing hydrogen is of significant interest to NL Hydro, then Hatch would suggest NL Hydro to engage with industrial gas suppliers and producers in Newfoundland and Labrador to understand their plans for the province and the requirements for a green hydrogen supply chain in the province.

### 15. References

- [1] Osler, "Canada's new clean fuel standard obligations for liquid fuel suppliers and opportunities for low-carbon energy producers," Osler, 6 2022 July. [Online]. Available: https://www.osler.com/en/resources/regulations/2022/canada-s-new-clean-fuel-standard-obligations-for-liquid-fuelsuppliers-and-opportunities-for-low-c. [Accessed 22 August 2022].
- [2] Ethanol Producer Magazine, "Canadian Ethanol Plants," Ethanol Producer Magazine, 06 June 2022. [Online]. Available: https://ethanolproducer.com/plants/listplants/Canada/Operational/All. [Accessed 17 August 2022].
- [3] Biodiesel Magazine, "Canadian Biodisel Plants," Biodiesel Magazine, 24 January 2022. [Online]. Available: https://biodieselmagazine.com/plants/listplants/Canada/existing/. [Accessed 16 August 2022].
- [4] Global Agrigultural Information Network, "Canada- Biofuels Annual 2022," Ottawa, 2022.
- [5] NREL, "Biodiesel Handling and Use Guide: Fourth Edition," December 2009. [Online]. Available: https://www.nrel.gov/docs/fy09osti/43672.pdf.
- [6] U.S Department of Energy, "Handbook for Handling, Storing,," 2016.
- [7] USDOE alternative fuel center, "Alternative fuel price report," April 2022. [Online]. Available: https://afdc.energy.gov/fuels/prices.html.
- [8] Global Petrol Prices.com, "Canada Gasoline prices, 22-Aug-2022," 22 August 2022. [Online]. Available: https://www.globalpetrolprices.com/Canada/gasoline\_prices/. [Accessed 23 August 2022].
- [9] Global Petrol Prices.com, "Canada Diesel prices," 22 August 2022. [Online]. Available: https://www.globalpetrolprices.com/Canada/diesel prices/. [Accessed 23 August 2022].
- [1 Zen Clean Energy Solutions, "A Feasiability Study of Hydrogen Production, Storage, Distribution and Use in
- 0] Newfoundland and Labrador," Zen Clean Energy Solutions, Newfoundland, 2021.
- [1 Wind Systems, "EverWind to begin green hydrogen production in Nova Scotia," 5 May 2022. [Online]. Available:
- 1] https://www.windsystemsmag.com/news/everwind-to-begin-green-hydrogen-production-in-nova-scotia/. [Accessed 10 August 2022].
- [1 Buckeye Partners L.P., "Buckeye Partners Completes Bear Head Clean Energy Acquisition," 13 July 2022. [Online].
- 2] Available: https://ca.news.yahoo.com/buckeye-partners-completes-bear-head-130000012.html. [Accessed 10 August 2022].
- [1 Hydrogen Central, "Plug Secures 5 MW Electrolyzer Sale to Leading Canadian Energy Company Irving Oil," 12 July
- 2022. [Online]. Available: https://hydrogen-central.com/plug-secures-5-mw-electrolyzer-sale-leading-canadianenergy-company-irving-oil/. [Accessed 10 August 2022].
- [1 The Canadian Press, "Irving Oil invests in hydrogen to lower emissions, offer clean energy to customers," 13 July
- 4] 2022. [Online]. Available: https://energynow.ca/2022/07/irving-oil-invests-in-hydrogen-to-lower-emissions-offer-cleanenergy-to-customers/. [Accessed 22 August 2022].
- [1 Yahoo, "Quebec inks contract for one the world's biggest green hydrogen plants," 21 January 2021. [Online].
- 5] Available: https://ca.finance.yahoo.com/news/quebec-inks-contract-for-one-the-worlds-biggest-green-hydrogenplants-152813060.html. [Accessed 10 August 2022].
- [1 Charbone Hydrogen Corporation, "Charbone Hydrogen Announces the Execution of a Memorandum of
- 6] Understanding with Port Hawkesbury Paper, LP to Develop and Construct the First Green Hydrogen Production Facility at the Port Hawkesbury Mill Site, Nova Scotia," 21 June 2022. [Online]. Available: https://www.globenewswire.com/en/news-release/2022/06/21/2466202/0/en/Charbone-Hydrogen-Announces-the-Execution-of-a-Memorandum-of-Understanding-with-Port-Hawkesbury-Paper-LP-to-Develop-and-Construct-the-First-Green-Hydrogen-Production-Facility-at-th.html. [Accessed 16 August 2022].
- [1 H2 Energines, "Green Hydrogen: H2 V Energies takes another step forward and announces the opening of its order
- 7] book," 21 January 2020. [Online]. Available: https://www.globenewswire.com/newsrelease/2020/01/21/1973260/0/en/Green-Hydrogen-H2-V-Energies-takes-another-step-forward-and-announces-theopening-of-its-orderbook.html#:~:text=The%20H%202%20V%20Energies%20project%20will%20serve,reduction%2C%20sustaina. [Accessed 16 August 2022].

- [1 Radio Canada, "A green hydrogen production project in Bécancour valued at \$1 billion," 21 May 2021. [Online].
- 8] Available: https://ici.radio-canada.ca/nouvelle/1795133/projet-production-hydrogene-vert-becancour-h2v-energies. [Accessed 16 August 2022].
- [1 CBC News, "Hydrogen alliance' formed as Canada, Germany sign agreement on exports," CBC News, 23 August
- 9] 2022. [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/canada-germany-hydrogenpartnership-nl-1.6559787. [Accessed 24 August 2022].
- [2 Port of Argentia, "PORT OF ARGENTIA SIGNS AGREEMENT WITH PATTERN ENERGY FOR OPTION TO LEASE
- 0] ON WIND ENERGY TO HYDROGEN PROJECT," 01 June 2022. [Online]. Available: https://portofargentia.ca/article/port-of-argentia-signs-agreement-with-pattern-energy-for-option-to-lease-on-windenergy-to-hydrogen-project/.
- [2 Pattern Energy, "About us," 2022. [Online]. Available: https://patternenergy.com/about/. [Accessed 22 August 2022].
   1]
- [2 Government of Newfoundland and Labrador, "Environment and Climate Change," 21 June 2022. [Online]. Available:
   2] https://www.gov.nl.ca/ecc/projects/2202-2/. [Accessed 08 August 2022].
- [2 All Newfoundland, "Brookfield Moving to Meet German Hydrogen Demand," 17 August 2022. [Online]. [Accessed 17 3] August 2022].
- [2 AllNewfoundlandandLabrador, "Australian Iron Giant Enters NL Wind Biz," 27 July 2022. [Online]. [Accessed 8 4] August 2022].
- [2 New Atlas, "Kawasaki launches the world's first liquid hydrogen transport ship," 15 December 2019. [Online].
- 5] Available: https://newatlas.com/marine/kawasaki-worlds-first-liquid-hydrogen-transport-ship/. [Accessed 17 August 2022].
- [2 Kawasaki Heavy Industries, Ltd., "Kawaski Obtains AiP for Large, 160,000m3 Liquefied Hydrogen Carrier," Kawasaki
- 6] Heavy Industries, Ltd., 2022 April 2022. [Online]. Available: https://global.kawasaki.com/en/corp/newsroom/news/detail/?f=20220422\_3378. [Accessed 10 May 2022].. [Accessed 17 August 2022].
- [2 IEA, "The Future of Hydrogen: Seizing today's opportunties," IEA, 2019.
- 7]
- [2 IEA, "Global Hydrogen Review 2021," 2021.

8]

- [2 S. Ying, L. Hong, Z. Wei and Z. Cunman, "Review of the Hydrogen Permeability of the Liner Material of Type IV On-
- 9] Board Hydrogen Storage Tank," World Electric Vehicle Journal, Shanghai, 2021.
- [3 Demaco, "Liquid hydrogen storage: increasingly larger storage tanks," Leapforce, 2022. [Online]. Available:
- 0] https://demaco-cryogenics.com/blog/liquid-hydrogen-storage/. [Accessed 10 May 2022].
- [3 Storage Terminals Magazine, "KAWASAKI COMPLETES WORLD'S FIRST LIQUEFIED HYDROGEN RECEIVING
   [1] TERMINAL," 2021. [Online]. Available: https://storageterminalsmag.com/kawasaki-completes-worlds-first-liquefiedhydrogen-receiving-terminal/?msclkid=9b8d16dcd0a311ecadf68ae91387d3c4. [Accessed 10 May 2022].
- [3 W. Peschka, "Thermal Insulation, Storage and Transportation of Liquid Hydrogen," in *Liquid Hydrogen*, Stuttgart,
- 2] Springer-Verlag/Wien, 1992, pp. 71-103.
- [3 C. A. Klerke, "Ammonia for hydrogen storage: challenges and opportunities," *Journal of Materials Chemistry,* vol. 18, 3] no. 20, p. 2304, 2008.
- [3 G. Thomas and G. Parks, "Potential Roles of Ammonia in a Hydrogen Economy," U.S. Department of Energy, 2006. 4]
- [3 D. Webb, "LARGE SCALE AMMONIA STORAGE AND HANDLING," CF INDUSTRIES, INC, LONG GROVE.
- 5]
- [3 Oil and Gas Advancement, "QAFCO AMMONIA STORAGE TANKS," Mcdermott, 27 September 2014. [Online].
- 6] Available: https://www.oilandgasadvancement.com/projects/gafco-ammonia-storage-tanks/. [Accessed 16 May 2022].
- [3 Salt Wire, "Things are getting salty in western Newfoundland with high hopes for project," 3 June 2022. [Online].
   [7] Available: https://www.saltwire.com/newfoundland-labrador/business/things-are-getting-salty-in-western-
- newfoundland-with-high-hopes-for-project-100740302/?utm medium=Social&utm source=Twitter#Echobox=1654534741-2. [Accessed 17 August 2022].
- [3 Envirosafe, "Ethanol Storage," Envirosafe, 27 June 2011. [Online]. Available:
- 8] https://abovegroundfuelstoragetanks.com/2011/06/27/ethanol-storage/. [Accessed 17 August 2022].

- [3 Government of Newfoundland and Labrador- Industry, Energy and Technology, "Nominating Crown Land for Wind
- 9] Energy Projects," 2022. [Online]. Available: https://www.gov.nl.ca/iet/nominating-crown-land-for-wind-energyprojects/. [Accessed 22 August 2022].
- [4 CBC, "Port au Port wind project needs more details, environmental impact statement, rules minister," 5 August 2022.
- 0] [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/port-au-port-wind-project-environmentalimpact-statement-1.6543100. [Accessed 8 August 2022].
- [4 CBC, "An Australian iron ore company is shifting to green energy, and Labrador is in its sights," 11 June 2021.
- [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/nl-fortescue-labrador-green-hydrogen-1.6060904. [Accessed 8 August 8 2022].
- [4 CBC News, "An Australian iron ore company is shifting to green energy, and Labrador is in its sights," 11 June 2021.
- 2] [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/nl-fortescue-labrador-green-hydrogen-1.6060904. [Accessed 17 August 2022].
- [4 CBC News, "Australian natural resources giant eyeing multiple green hydrogen projects in N.L.," 22 August 2022.
- [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/miawpukek-fortescue-wind-to-hydrogen-1.6558801. [Accessed 22 August 2022].
- [4 O. T. a. K. T. A. Muhammad, "Comparison of Liquid Hydorgen, methylcyclohexane and ammonia on energy
- 4] efficiency and economy.," Energy Procedia, vol. 158, pp. 4085-4091, 2019.
- [4 Newfoundland and Labrador Hydro, "Schedule of Rates, Rules and Regulations," 1 July 2022. [Online]. Available:
- 5] https://nlhydro.com/wp-content/uploads/2022/07/2022-07-01\_NLH\_Schedule-of-Rates-Rules-and-Regulations-IIC-CDM-Update.pdf. [Accessed 23 August 2022].
- [4 J. S. &. U. O. Faye, "A critical review on the current technologies for the generation, storage, and transportation of
- 6] hydrogen," International Journal of Hydrogen Energy, vol. 47, pp. 13771-13802, 2022.
- [4 J. A. a. S. Gronkvist, "Large-scale storage of hydrogen," International Journal of Hydrogen Energy, vol. 44, no. 23,
- 7] pp. 11901-11919, 2019.
- [4 NRCAN, "Biodiesel," [Online]. Available: https://www.nrcan.gc.ca/energy-efficiency/transportation-alternative-
- 8] fuels/alternative-fuels/biofuels/biodiesel/3509.
- [4 USDOE, "Clean Cities Alternative Fuel Price Report," April 2022. [Online]. Available:
- 9] https://afdc.energy.gov/files/u/publication/alternative\_fuel\_price\_report\_april\_2022.pdf.
- [5 IEA, "Production Costs of alternative transportation fuels," 2013. [Online]. Available:
- 0] https://iea.blob.core.windows.net/assets/4d6caba5-1391-4025-9ba2-8934f09e8647/FeaturedInsights\_AlternativeFuel\_FINAL.pdf.
- [5 [Online]. Available: https://www.energy.gov/sites/prod/files/2016/12/f34/fcto\_h2atscale\_workshop\_soloveichik.pdf. 1]
- [5 A. J. Reiter and S.-C. King, "DIESEL ENGINE OPERATION USING AMMONIA AS A CARBON-FREE FUEL," 15 2] September 2010. [Online]. Available:
- https://www.researchgate.net/publication/267576471\_Diesel\_Engine\_Operation\_Using\_Ammonia\_as\_a\_Carbon-Free\_Fuel.
- [5 J. Adersson and S. Gronkvist, "Large-scale storage of hydrogen," international journal of hydrogen energy, vol. 44,
- 3] no. 23, pp. 11901-11919, 2019.
- [5 IEA, "Global average levelised cost of hydrogen production by energy source and technology, 2019 and 2050," IEA,
- 4] 23 September 2020. [Online]. Available: https://www.iea.org/data-and-statistics/charts/global-average-levelised-costof-hydrogen-production-by-energy-source-and-technology-2019-and-2050. [Accessed 23 August 2022].
- [5 CBC News, "'Hydrogen alliance' formed as Canada, Germany sign agreement on exports," CBC News, 23 August
- 5] 2022. [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/canada-germany-hydrogenpartnership-nl-

1.6559787#:~:text=Canada%20has%20signed%20a%20deal%20with%20Germany%20to,seeks%20to%20reduce% 20its%20dependence%20on%20Russian%20gas.. [Accessed 24 August 2022].

- [1] Osler, "Canada's new clean fuel standard obligations for liquid fuel suppliers and opportunities for low-carbon energy producers," Osler, 6 2022 July. [Online]. Available: https://www.osler.com/en/resources/regulations/2022/canada-s-new-clean-fuel-standard-obligations-for-liquid-fuelsuppliers-and-opportunities-for-low-c. [Accessed 22 August 2022].
- [2] Ethanol Producer Magazine, "Canadian Ethanol Plants," Ethanol Producer Magazine, 06 June 2022. [Online]. Available: https://ethanolproducer.com/plants/listplants/Canada/Operational/All. [Accessed 17 August 2022].
- [3] Biodiesel Magazine, "Canadian Biodisel Plants," Biodiesel Magazine, 24 January 2022. [Online]. Available: https://biodieselmagazine.com/plants/listplants/Canada/existing/. [Accessed 16 August 2022].
- [4] Global Agrigultural Information Network, "Canada- Biofuels Annual 2022," Ottawa, 2022.
- [5] NREL, "Biodiesel Handling and Use Guide: Fourth Edition," December 2009. [Online]. Available: https://www.nrel.gov/docs/fy09osti/43672.pdf.
- [6] U.S Department of Energy, "Handbook for Handling, Storing,," 2016.
- [7] USDOE alternative fuel center, "Alternative fuel price report," April 2022. [Online]. Available: https://afdc.energy.gov/fuels/prices.html.
- [8] Global Petrol Prices.com, "Canada Gasoline prices, 22-Aug-2022," 22 August 2022. [Online]. Available: https://www.globalpetrolprices.com/Canada/gasoline\_prices/. [Accessed 23 August 2022].
- [9] Global Petrol Prices.com, "Canada Diesel prices," 22 August 2022. [Online]. Available: https://www.globalpetrolprices.com/Canada/diesel\_prices/. [Accessed 23 August 2022].
- [10] Zen Clean Energy Solutions, "A Feasiability Study of Hydrogen Production, Storage, Distribution and Use in Newfoundland and Labrador," Zen Clean Energy Solutions, Newfoundland, 2021.
- [11] Wind Systems, "EverWind to begin green hydrogen production in Nova Scotia," 5 May 2022. [Online]. Available: https://www.windsystemsmag.com/news/everwind-to-begin-green-hydrogen-production-in-nova-scotia/. [Accessed 10 August 2022].
- [12] Buckeye Partners L.P., "Buckeye Partners Completes Bear Head Clean Energy Acquisition," 13 July 2022. [Online]. Available: https://ca.news.yahoo.com/buckeye-partners-completes-bear-head-130000012.html. [Accessed 10 August 2022].
- [13] Hydrogen Central, "Plug Secures 5 MW Electrolyzer Sale to Leading Canadian Energy Company Irving Oil," 12 July 2022. [Online]. Available: https://hydrogen-central.com/plug-secures-5-mw-electrolyzer-sale-leadingcanadian-energy-company-irving-oil/. [Accessed 10 August 2022].
- [14] The Canadian Press, "Irving Oil invests in hydrogen to lower emissions, offer clean energy to customers," 13 July 2022. [Online]. Available: https://energynow.ca/2022/07/irving-oil-invests-in-hydrogen-to-lower-emissions-offerclean-energy-to-customers/. [Accessed 22 August 2022].
- [15] Yahoo, "Quebec inks contract for one the world's biggest green hydrogen plants," 21 January 2021. [Online]. Available: https://ca.finance.yahoo.com/news/quebec-inks-contract-for-one-the-worlds-biggest-green-hydrogenplants-152813060.html. [Accessed 10 August 2022].
- [16] Charbone Hydrogen Corporation, "Charbone Hydrogen Announces the Execution of a Memorandum of Understanding with Port Hawkesbury Paper, LP to Develop and Construct the First Green Hydrogen Production Facility at the Port Hawkesbury Mill Site, Nova Scotia," 21 June 2022. [Online]. Available: https://www.globenewswire.com/en/news-release/2022/06/21/2466202/0/en/Charbone-Hydrogen-Announces-the-Execution-of-a-Memorandum-of-Understanding-with-Port-Hawkesbury-Paper-LP-to-Develop-and-Construct-the-First-Green-Hydrogen-Production-Facility-at-th.html. [Accessed 16 August 2022].
- [17] H2 Energines, "Green Hydrogen: H2 V Energies takes another step forward and announces the opening of its order book," 21 January 2020. [Online]. Available: https://www.globenewswire.com/newsrelease/2020/01/21/1973260/0/en/Green-Hydrogen-H2-V-Energies-takes-another-step-forward-and-announcesthe-opening-of-its-orderbook.html#:~:text=The%20H%202%20V%20Energies%20project%20will%20serve,reduction%2C%20sustaina. [Accessed 16 August 2022].
- [18] Radio Canada, "A green hydrogen production project in Bécancour valued at \$1 billion," 21 May 2021. [Online]. Available: https://ici.radio-canada.ca/nouvelle/1795133/projet-production-hydrogene-vert-becancour-h2v-energies. [Accessed 16 August 2022].

- [19] CBC News, "Hydrogen alliance' formed as Canada, Germany sign agreement on exports," CBC News, 23 August 2022. [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/canada-germany-hydrogen-partnership-nl-1.6559787. [Accessed 24 August 2022].
- [20] Port of Argentia, "PORT OF ARGENTIA SIGNS AGREEMENT WITH PATTERN ENERGY FOR OPTION TO LEASE ON WIND ENERGY TO HYDROGEN PROJECT," 01 June 2022. [Online]. Available: https://portofargentia.ca/article/port-of-argentia-signs-agreement-with-pattern-energy-for-option-to-lease-on-windenergy-to-hydrogen-project/.
- [21] Pattern Energy, "About us," 2022. [Online]. Available: https://patternenergy.com/about/. [Accessed 22 August 2022].
- [22] Government of Newfoundland and Labrador, "Environment and Climate Change," 21 June 2022. [Online]. Available: https://www.gov.nl.ca/ecc/projects/2202-2/. [Accessed 08 August 2022].
- [23] All Newfoundland, "Brookfield Moving to Meet German Hydrogen Demand," 17 August 2022. [Online]. [Accessed 17 August 2022].
- [24] AllNewfoundlandandLabrador, "Australian Iron Giant Enters NL Wind Biz," 27 July 2022. [Online]. [Accessed 8 August 2022].
- [25] New Atlas, "Kawasaki launches the world's first liquid hydrogen transport ship," 15 December 2019. [Online]. Available: https://newatlas.com/marine/kawasaki-worlds-first-liquid-hydrogen-transport-ship/. [Accessed 17 August 2022].
- [26] Kawasaki Heavy Industries, Ltd., "Kawaski Obtains AiP for Large, 160,000m3 Liquefied Hydrogen Carrier," Kawasaki Heavy Industries, Ltd., 2022 April 2022. [Online]. Available: https://global.kawasaki.com/en/corp/newsroom/news/detail/?f=20220422\_3378. [Accessed 10 May 2022].. [Accessed 17 August 2022].
- [27] IEA, "The Future of Hydrogen: Seizing today's opportunties," IEA, 2019.
- [28] IEA, "Global Hydrogen Review 2021," 2021.
- [29] S. Ying, L. Hong, Z. Wei and Z. Cunman, "Review of the Hydrogen Permeability of the Liner Material of Type IV On-Board Hydrogen Storage Tank," World Electric Vehicle Journal, Shanghai, 2021.
- [30] Demaco, "Liquid hydrogen storage: increasingly larger storage tanks," Leapforce, 2022. [Online]. Available: https://demaco-cryogenics.com/blog/liquid-hydrogen-storage/. [Accessed 10 May 2022].
- [31] Storage Terminals Magazine, "KAWASAKI COMPLETES WORLD'S FIRST LIQUEFIED HYDROGEN RECEIVING TERMINAL," 2021. [Online]. Available: https://storageterminalsmag.com/kawasaki-completesworlds-first-liquefied-hydrogen-receiving-terminal/?msclkid=9b8d16dcd0a311ecadf68ae91387d3c4. [Accessed 10 May 2022].
- [32] W. Peschka, "Thermal Insulation, Storage and Transportation of Liquid Hydrogen," in *Liquid Hydrogen*, Stuttgart, Springer-Verlag/Wien, 1992, pp. 71-103.
- [33] C. A. Klerke, "Ammonia for hydrogen storage: challenges and opportunities," *Journal of Materials Chemistry*, vol. 18, no. 20, p. 2304, 2008.
- [34] G. Thomas and G. Parks, "Potential Roles of Ammonia in a Hydrogen Economy," U.S. Department of Energy, 2006.
- [35] D. Webb, "LARGE SCALE AMMONIA STORAGE AND HANDLING," CF INDUSTRIES, INC, LONG GROVE.
- [36] Oil and Gas Advancement, "QAFCO AMMONIA STORAGE TANKS," Mcdermott, 27 September 2014. [Online]. Available: https://www.oilandgasadvancement.com/projects/qafco-ammonia-storage-tanks/. [Accessed 16 May 2022].
- [37] Salt Wire, "Things are getting salty in western Newfoundland with high hopes for project," 3 June 2022. [Online]. Available: https://www.saltwire.com/newfoundland-labrador/business/things-are-getting-salty-in-westernnewfoundland-with-high-hopes-for-project-100740302/?utm medium=Social&utm source=Twitter#Echobox=1654534741-2. [Accessed 17 August 2022].
- [38] Envirosafe, "Ethanol Storage," Envirosafe, 27 June 2011. [Online]. Available: https://abovegroundfuelstoragetanks.com/2011/06/27/ethanol-storage/. [Accessed 17 August 2022].
- [39] Government of Newfoundland and Labrador- Industry, Energy and Technology, "Nominating Crown Land for Wind Energy Projects," 2022. [Online]. Available: https://www.gov.nl.ca/iet/nominating-crown-land-for-wind-energy-projects/. [Accessed 22 August 2022].

- [40] CBC, "Port au Port wind project needs more details, environmental impact statement, rules minister," 5 August 2022. [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/port-au-port-wind-projectenvironmental-impact-statement-1.6543100. [Accessed 8 August 2022].
- [41] CBC, "An Australian iron ore company is shifting to green energy, and Labrador is in its sights," 11 June 2021. [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/nl-fortescue-labrador-greenhydrogen-1.6060904. [Accessed 8 August 8 2022].
- [42] CBC News, "An Australian iron ore company is shifting to green energy, and Labrador is in its sights," 11 June 2021. [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/nl-fortescue-labrador-greenhydrogen-1.6060904. [Accessed 17 August 2022].
- [43] CBC News, "Australian natural resources giant eyeing multiple green hydrogen projects in N.L.," 22 August 2022. [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/miawpukek-fortescue-wind-tohydrogen-1.6558801. [Accessed 22 August 2022].
- [44] O. T. a. K. T. A. Muhammad, "Comparison of Liquid Hydorgen, methylcyclohexane and ammonia on energy efficiency and economy.," *Energy Procedia,* vol. 158, pp. 4085-4091, 2019.
- [45] Newfoundland and Labrador Hydro, "Schedule of Rates, Rules and Regulations," 1 July 2022. [Online]. Available: https://nlhydro.com/wp-content/uploads/2022/07/2022-07-01\_NLH\_Schedule-of-Rates-Rules-and-Regulations-IIC-CDM-Update.pdf. [Accessed 23 August 2022].
- [46] J. S. &. U. O. Faye, "A critical review on the current technologies for the generation, storage, and transportation of hydrogen," *International Journal of Hydrogen Energy,* vol. 47, pp. 13771-13802, 2022.
- [47] J. A. a. S. Gronkvist, "Large-scale storage of hydrogen," *International Journal of Hydrogen Energy*, vol. 44, no. 23, pp. 11901-11919, 2019.
- [48] NRCAN, "Biodiesel," [Online]. Available: https://www.nrcan.gc.ca/energy-efficiency/transportation-alternative-fuels/alternative-fuels/biodiesel/3509.
- [49] USDOE, "Clean Cities Alternative Fuel Price Report," April 2022. [Online]. Available: https://afdc.energy.gov/files/u/publication/alternative\_fuel\_price\_report\_april\_2022.pdf.
- [50] IEA, "Production Costs of alternative transportation fuels," 2013. [Online]. Available: https://iea.blob.core.windows.net/assets/4d6caba5-1391-4025-9ba2-8934f09e8647/FeaturedInsights\_AlternativeFuel\_FINAL.pdf.
- [51] [Online]. Available: https://www.energy.gov/sites/prod/files/2016/12/f34/fcto\_h2atscale\_workshop\_soloveichik.pdf.
- [52] A. J. Reiter and S.-C. King, "DIESEL ENGINE OPERATION USING AMMONIA AS A CARBON-FREE FUEL," 15 September 2010. [Online]. Available: https://www.researchgate.net/publication/267576471\_Diesel\_Engine\_Operation\_Using\_Ammonia\_as\_a\_Carbon-Free\_Fuel.
- [53] J. Adersson and S. Gronkvist, "Large-scale storage of hydrogen," *international journal of hydrogen energy,* vol. 44, no. 23, pp. 11901-11919, 2019.
- [54] IEA, "Global average levelised cost of hydrogen production by energy source and technology, 2019 and 2050," IEA, 23 September 2020. [Online]. Available: https://www.iea.org/data-and-statistics/charts/global-averagelevelised-cost-of-hydrogen-production-by-energy-source-and-technology-2019-and-2050. [Accessed 23 August 2022].
- [55] CBC News, "Hydrogen alliance' formed as Canada, Germany sign agreement on exports," CBC News, 23 August 2022. [Online]. Available: https://www.cbc.ca/news/canada/newfoundland-labrador/canada-germany-hydrogen-partnership-nl-

1.6559787#:~:text=Canada%20has%20signed%20a%20deal%20with%20Germany%20to,seeks%20to%20reduc e%20its%20dependence%20on%20Russian%20gas.. [Accessed 24 August 2022].

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 80 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

# Appendix A: Heat and Mass Balance

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 81 of 163



**Functional Description** 

### PRELIMINARY ENERGY AND MASS BALANCE

### **Design assumptions:**

| Fuel:             | Diesel No 2, LHV – 18400 BTU/lb | Unit MW Size: | 50-70 MW |
|-------------------|---------------------------------|---------------|----------|
| Site conditions : | 15C/60 RH/ 152m                 | 20C/81RH/152m |          |

### Table 1: Estimated performance

| OEM                    | Units   | 0      | 6E        | SIE  | MENS  | l N  | 1HI  |
|------------------------|---------|--------|-----------|------|-------|------|------|
| Model                  |         | LM6000 | PC Sprint | SG   | Т 800 | FT 4 | 4000 |
| No of Units            |         |        | 4         |      | 4     |      | 2    |
| Site Condition         | °C      | 15     | 20        | 15   | 20    | 15   | 20   |
| Gross Output           | MW      | 196    | 187       | 208  | 201   | 141  | 134  |
| Heat Rate (LHV)        | Btu/kWh | 8633   | 8689      | 8712 | 8788  | 8335 | 8401 |
| Water Injection per GT | GPM     | 43.4   | 39.4      | -    | -     | 69.2 | 64.2 |
| Exhaust Temperature    | °C      | 453    | 458       | 548  | 553   | 409  | 430  |
| NOx                    | PPM     | 2      | 12        |      |       | 74   |      |

| Fuel:             | Biodiesel, LHV – 16400 BTU/lb | Unit MW Size: | 50-70 MW |
|-------------------|-------------------------------|---------------|----------|
| Site conditions : | 15C/60 RH/ 152m               | 20C/81RH/152m |          |

### Table 2: Estimated performance

| OEM                    | Units   | (      | 6E        | SIE | MENS  | N  | /HI  |
|------------------------|---------|--------|-----------|-----|-------|----|------|
| Model                  |         | LM6000 | PC Sprint | SG  | Т 800 | FT | 4000 |
| No of Units            |         |        | 4         |     | 4     |    | 2    |
| Site Condition         | °C      | 15     | 20        | 15  | 20    | 15 | 20   |
| Gross Output           | MW      | 195    | 187       | -   | -     | -  | -    |
| Heat Rate (LHV)        | Btu/kWh | 8807   | 8843      | -   | -     | -  | -    |
| Water Injection per GT | GPM     | 43.4   | 39.4      | -   | -     | -  | -    |
| Exhaust Temperature    | °C      | 455    | 459       | -   | -     | -  | -    |
| NOx                    | PPM     | 4      | 12        |     |       |    | -    |

| SITE CONDITIONS               | Units           | Case 1     | Case 2     | Case 3     | Case 4     | Case 5     | Case 6     | Case 7     | Case 8     | Case 9     | Case 10    | Case 11    | Case 12    | Case 13    | Case 14    | Case 15    | Case 16    |
|-------------------------------|-----------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
| Used Input File Addendum      |                 | ٩          | No         | No         | ٩          | No         | ٩          | No         | ٩          | No         | ٩          | No         | No         | No         | ٩          | No         | No         |
| Elevation                     | ft              | 499        | 499        | 499        | 499        | 499        | 499        | 499        | 499        | 499        | 499        | 499        | 499        | 499        | 499        | 499        | 499        |
| Pressure                      | psia            | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     | 14.433     |
| Ambient Temperature           | deg F           | 40         | -30        | -20        | -10        | 0          | 10         | 20         | 30         | 40         | 50         | 60         | 20         | 80         | 06         | 100        | 104        |
| Humidity                      | %               | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 51.64      | 42         | 36         |
| Inlet Pressure Loss           | in H2O          | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        | 4.5        |
| Exhaust Pressure Loss         | in H2O          | 9          | 9          | 9          | 9          | 9          | 9          | 9          | 9          | 9          | 9          | 9          | 9          | 9          | 9          | 9          | 9          |
| Generator Coolant             |                 | Air        |
| Power Factor (lag)            |                 | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       |
| ESTIMATED PERFORMANCE         | Units           | Case 1     | Case 2     | Case 3     | Case 4     | Case 5     | Case 6     | Case 7     | Case 8     | Case 9     | Case 10    | Case 11    | Case 12    | Case 13    | Case 14    | Case 15    | Case 16    |
| Load Condition                | %               | 100        | 100        | 100        | 100        | 100        | 100        | 100        | 100        | 100        | 100        | 100        | 100        | 100        | 100        | 100        | 100        |
| Evap. Cooler Status           |                 | Off        | h          | h          | nO         | ő          | nO         | ы          |
| Evap. Cooler Effectiveness    | %               |            |            |            |            |            |            |            |            |            |            | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       | 0.85       |
| Fuel Type                     |                 | Distillate |
| Fuel LHV                      | BTU/lb          | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      | 18400      |
| Fuel Temperature              | deg F           | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         | 60         |
| Output at Generator Terminals | kW              | 49551      | 50451      | 50695      | 50786      | 50866      | 50550      | 50437      | 50820      | 49954      | 49424      | 48793      | 47236      | 45570      | 44135      | 42601      | 42364      |
| Rated Heat Rate (LHV)         | <b>BTU/kWh</b>  | 8341       | 8359       | 8375       | 8394       | 8417       | 8437       | 8481       | 8538       | 8581       | 8627       | 8637       | 8678       | 8725       | 8774       | 8838       | 8849       |
| Heat Cons. (LHV)              | <b>MMBTU/hr</b> | 413.3      | 421.7      | 424.6      | 426.3      | 428.2      | 426.5      | 427.8      | 433.9      | 428.6      | 426.4      | 421.4      | 409.9      | 397.6      | 387.3      | 376.5      | 374.9      |
| Exhaust Flow                  | x10^3 lb/hr     | 1163       | 1153       | 1145       | 1138       | 1132       | 1124       | 1112       | 1100       | 1076       | 1060       | 1048       | 1023       | 265        | 975        | 951        | 947        |
| Exhaust Temperature           | deg F           | 706        | 733        | 750        | 764        | 778        | 788        | 806        | 825        | 842        | 846        | 849        | 855        | 862        | 868        | 875        | 876        |
| LPC Sprint Water Flow         | GPM             | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 17.3       | 17.89      | 18.75      | 18.43      | 18         | 17.62      | 17.56      |
| HPC Sprint Water Flow         | GPM             | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 7.46       | 7.46       | 0          | 0          | 0          | 0          | 0          | 0          | 0          |
|                               |                 |            |            |            |            |            |            |            |            |            |            |            |            |            |            |            |            |
| EMISSIONS                     | Units           | Case 1     | Case 2     | Case 3     | Case 4     | Case 5     | Case 6     | Case 7     | Case 8     | Case 9     | Case 10    | Case 11    | Case 12    | Case 13    | Case 14    | Case 15    | Case 16    |
| NOX                           | ppmvd @ 1:      | 5 42       | 42         | 42         | 42         | 42         | 42         | 42         | 42         | 42         | 42         | 42         | 42         | 42         | 42         | 42         | 42         |
| co                            | phmvd           | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        | 6.1        |
| UHC                           | phmvd           | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        | 2.6        |
| UHC                           | lb/hr           | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          | 0          |

# General Electric Proprietary Information

Disclosure of this information to any third party, other than a party contractually involved with the recipient in such an evaluation, is strictly forbidden. The data is of estimate quality only. Specific, the sole purpose of evaluating the use of GE products in a potential power generation project. This document and its contents have been prepared by GE and provided to the recipient for reliable data is available only when provided by GE as part of a formal proposal.

Exhaust Loss under Site Conditions are at ISO Conditions unless otherwise stated. Emission information based on GE recommended measurement methods. NOx emissions are corrected to 15% O2 without heat rate correction. NOx levels shown will be controlled by algorithms within the SPEEDTRONIC control system. Note: Modified Wobbe Index (MWI) is calculated as LHV/(Spec Gravity\*Temp)^0.5, in BTU/scf/°R^0.5 Distillate Fuel is assumed to have the specified percent Fuel-Bound Nitrogen or less. FBN amounts greater than the specified percent will add to the reported NOx value.

Note: SCF is defined at 14.7 psi and 59°F

Simulation Frame: LM6000-PCSPRINT-C-0620-L3 Date/Time: 10/7/22 3:43 PM GTP Web v5.69.4, 2022 User: 204047135

GE LM6000PC Sprint - Estimated Performance Sweep

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 83 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix B: Plant Layout

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 84 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

# Appendix B1: 2 Unit Combustion Turbine – Brownfield

PUB-NLH-288, Attachment 5

Reliability and Resource Adequacy Study Review



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 86 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

# Appendix B2: 2 Unit Combustion Turbine – Greenfield

PUB-NLH-288, Attachment 5

Reliability and Resource Adequacy Study Review



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 88 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

# Appendix B3: 4 Unit Combustion Turbine – Brownfield

PUB-NLH-288, Attachment 5

Reliability and Resource Adequacy Study Review



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 90 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

# Appendix B4: 4 Unit Combustion Turbine – Greenfield

PUB-NLH-288, Attachment 5

**Reliability and Resource Adequacy Study Review** 



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 92 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

# Appendix C: Process Flow Diagrams

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 93 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix C1: General PFD

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 94 of 163



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 95 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix C2: Diesel PFD

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 96 of 163



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 97 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix C3: Biofuel PFD

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 98 of 163



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 99 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix D: Budgetary Cost

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 100 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix D1: GE – LM6000



# **BUDGETARY PROPOSAL**

# LM6000 Gas Turbine Generator Equipment



From GENERAL ELECTRIC [Applicable Legal GE Entity(ies) to be defined at firm bid stage if any]

To HATCH ENGINEERING Project: NL Peaking Project Opportunity/Quote n°: 1616913 / CPQ-10748 Date: July 11, 2022



# **1** - Introduction

The GE legal entity or entities providing you with this Budgetary Proposal are part of the GE Power division of General Electric. GE Power division is also referred to as "GE" in this Budgetary Proposal.

GE Power is one of the world's leading suppliers of power generation and energy delivery technologies and offers the widest range of heavy-duty gas turbine, steam turbines & generator solutions, with Gas Turbine outputs ranging from 34 to 544 megawatts. GE turbines serve reliably and efficiently in a wide variety of applications for world-wide electric utilities, independent power producers, municipalities and industrial companies, from pure power generation to industrial cogeneration and district heating.



### 60 Hz Portfolio by Rating



## GE Technology for your Project: LM6000PC

Engineered to cost effectively cycle multiple times per day, our LM6000 aeroderivative gas turbine is fast and flexible, meeting dispatch profiles with proven reliability. With more than 1,200 units shipped and 33 million combined operating hours, the LM6000 family has more operating experience than any other aeroderivative gas turbine greater than 40 MW. It leads the field with greater than 99.8 percent reliability and 98.4 percent availability.



Achieves emissions standards while ramping at 50 MW/ minute starting as low as 25% of full load



SUSTAINABILITY

Unique low emissions technology and fuel flexibility (ethane, propane, LPG) with standard combustor

For more details, contact your Sales Representative or consult our online product catalog at: https://www.ge.com/power/gas/catalogs

Please see our performance estimating tools at <u>https://gtpweb.gepower.com/gtpweb/login.htm</u> .



# 2 - General Assumptions

We are pleased to submit this Budgetary Proposal based on the following assumptions:

| Installation Country | CANADA                    |
|----------------------|---------------------------|
| State / Province     | Newfoundland and Labrador |
| Frequency            | 60HZ                      |

# **3 - Our Solution to Your Project**

We believe the following equipment will be a competitive solution for the development of your project:

### a. Gas Turbine Generator Equipment

| Gas Turbine          | LM6000-PC UG3 60HZ             |
|----------------------|--------------------------------|
| Gas Turbine Quantity | Two (2)                        |
| Installation Type    | Simple Cycle (SC)              |
| Combustion System    | Single Annular Combustor (SAC) |

### **Auxiliary Equipment**

### **Gas Turbine Package**

- CSA (Canada) Certification
- Gas Turbine enclosure
- Lubricating Oil and Hydraulic Oil Systems
- Lube Oil Cooler: Shell & Tube Cooler
- Lube Oil Piping and Reservoir
- Winterization to -29°C (-20°F)

### Air Inlet System

- Multi-stage Static Air Filtration System
- Evaporative Cooling for improved performance

### Exhaust

• Exhaust Collector and Flange

4



• Simple Cycle Exhaust System with Expansion Joint & Anchor Bolts

### **Fuel System**

- Dual Fuel System (Natural Gas / Distillate Fuel)
- Distillate Fuel Filtering & Forwarding Skid

### **Generator & Accessories**

• Ventilated air-cooled generator and brushless excitation system

### **Digital Control System**

- Turbine Control Panel (TCP)
- Generator Monitoring and Integrated Generator Protection System
- 24 V DC Battery and Charger System
- Human Machine Interface (HMI)
- Fire Protection System
- Vibration Monitor
- GTG Motor Control Center (CE)

### Additional Scope included in this Estimate

- Gas Turbine Water Wash System
- Aerosol Fire Protection
- Static Package Test

### d. Services

The following services are included to support project implementation:

- Shipment Terms: ExWorks (Including Boxing)
- Engineering and quality documentation
- Operation and Maintenance Manuals (in English language) in electronic format
- Installation and Commissioning Manual in hard copy and electronic format
- Remote Monitoring and Diagnostic Service during the equipment warranty period
- Equipment Training: Full Operation and Maintenance Training onsite for the GE Scope of Supply
- GE On-site representative to Witness gas turbine performance test
- Technical Advisory (TA) services during installation and commissioning are included based upon a Typical Project Schedule, at rates based upon sellers current Field Services Rate Sheet, plus travel and living expenses.
- GE Equipment Project Management

### e. Optional Services Available

The following services are available to be quoted separately:


- GE Equipment Delivery to Site
- GE Conduct Gas Turbine Performance Testing

#### f. Customer Scope

We have listed for your convenience those major scope items which have not been included as the basis of this Budgetary Proposal.

Some of these items listed herein could be quoted separately as needed and upon request. This list is not exclusive and not limitative.

- Building and civil works, site facilities, and civil engineering design
- Support steelworks and hangers for the gas turbine ducting, silencing, and pipe work
- All inlet, exhaust, and ventilation ducting other than included in the scope of supply
- Drains and/or vent piping from the gas turbine package to a remote point
- Fuel storage, treatment and forwarding system
- Site grounding and lightning protection
- Power system studies
- Sensing and metering voltage transformers,
- Machine power transformers, and associated protection
- Grid failure detection equipment
- Off loading, transportation and storage
- Off skid cabling, and design of off skid cable routing
- Balance of plant controls and balance of plant & energy optimization controls
- Anchor bolts, embedments, and grouting (quoted separately)
- Distributed plant control and customer's remote control
- Field supervision (quoted separately)
- High voltage transformer(s), cables, and associated equipment; auxiliary power transformer
- Interconnecting piping, conduit, and wiring between equipment modules
- Plant utilities, including supply of compressed air, instrument air, or cooling water, and off skid piping
- Battery containment
- Lube oil measurement other than that defined in the scope of supply
- Additional lube oil breather ducting other than that defined in the scope of supply
- Fuel transfer pump
- Off skid fuel block and vent valves
- Fuel supply pipework beyond the scope of supply
- Generator controls other than that defined in the scope of supply
- Load sharing control
- Balance of plant controls
- Field Performance Testing
- Site Labor
- Ladders, Stairs, and Platforms for that may be required
- Fuel, fluids, and chemicals for the gas turbine generator set



### 4 - Delivery Cycle

The units could be delivered in the following cycle (from Full Notice to Proceed to Ex-works Delivery): GTG Unit 1: 14 months, subject to GE engine availability

This estimated schedule is subject to confirmation at the time of a firm technical and commercial offer.

### 5 - Price

| Indicative Price for the Above Scope of Supply*                                | USD 49,679,000 |
|--|----------------|
| Indicative Price for Delivery to Site, for the Above Scope of Supply (2 units) | USD 2,350,000  |
| Indicative Duties Cost***  | Estimated \$0  |

\*The above price

- Includes a Standard 12 Month GE Equipment Operations Warranty
- Assumes first Gas Turbine and Generator ExWorks delivery from GE Factory Hungary November 30, 2023
- Excludes any sales tax, VAT, duties, or any other similar taxes
- Is based on GE Standard Payment Terms: 10% Down, 65% Calendar Based, 20% at Shipment, 5% 30 days after Shipment.

\* At the time of a firm proposal, GE equipment will be offered Subject to Prior Sale and subject to mutually acceptable inflation price adjustment at the time of order execution. GE proposes an escalation adjustment based on the Producer Price Index Commodity data for Metals and Metal Products (WPU10) as determined and published monthly by the Bureau of Labor Statistics of the U.S. Department of Labor.

\*\* Estimated Delivery Price is based on recent historical delivery quotes, assuming Incoterm DAP delivery to unknown address, Newfoundland and Labrador, Canada. Delivery price is subject to change pending final scope selections, final sourcing decisions, final project schedule, final site address, and detailed route survey. GE can provide delivery for actual delivery cost plus 15%.

\*\*\* Duties Cost Estimate is based on historical duties costs and are subject to change pending final scope selections, final sourcing decisions, and changes in law. Duties costs will be confirmed at the time of a firm proposal, if any.

7



### 6 - Terms and Conditions

This Budgetary Proposal is based on GE standard Terms and Conditions of Contract. Full GE Terms and Conditions would be submitted with our firm bid, if any.

### 7 - Disclaimer

This Budgetary Proposal is issued for budgetary and reference purposes only. This Budgetary Proposal is not binding upon the GE legal entity submitting this document and does not create any obligations on the part of such GE legal entity, including no obligation to provide a firm proposal. The recommended product or system design and budgetary pricing, as well as any other term or condition contained in this Budgetary Proposal, are subject to change, including, without limitation, as additional information comes to the attention of GE, or you refine your desired requirements.

The GE legal entity or entities submitting this document would be pleased to work closely with you to potentially develop a firm price proposal for this project upon your written request.



### 8 - Confidentiality

This Budgetary Proposal including all attachments contains GE Proprietary Information and is for the use of HATCH ENGINEERING for the purposes of evaluating the power plant possibilities. These documents cannot be given to other parties without prior written approval from GE (or its affiliate submitting this document).

To the extent a non-disclosure agreement is in place between a GE legal entity and HATCH ENGINEERING in relation to the project for which such Budgetary Proposal has been issued, such non-disclosure agreement shall apply.

GE sincerely appreciates this opportunity to provide you with this budgetary information and is willing to discuss and assist you on your project.

Sincerely,

Ru I. You

Russ Young Sales Director GE Power | Gas Power Systems



ATTACHMENTS :

• Gas Pressure Requirements

#### **Gas Pressure Requirements**

|           | Gas Fue    | el pressure psig | MPaG]      |  |  |  |
|-----------|------------|------------------|------------|--|--|--|
|           | Min        | Nominal          | Max        |  |  |  |
| LM6000 PC | 655 [4.52] | 675 [4.65]       | 695 [4.79] |  |  |  |

For full-load operation, the gaseous fuel must be supplied to the baseplate at 675  $psig\pm 20$  (4,654  $\pm$ 138 kPag). Gas fuel must meet the latest General Electric (GE) specification MID-TD-0000-1

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 111 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix D2: Mitsubishi Power Aero – FT4000

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 112 of 163



## BUDGETARY FT4000<sup>®</sup> GAS TURBINE PROPOSAL



#### To: Hatch

#### For: Newfoundland Power Project

To Design and Supply (1) 140MW FT4000<sup>®</sup> SWIFTPAC<sup>®</sup> Unit EQUIPMENT ONLY

**Bid date:** July 12, 2022

Prepared by: Brian Grosjean / Reed Lengel Mitsubishi Power Aero LLC Glastonbury, CT USA

Proposal #: 03022RL

Mitsubishi Power Aero LLC 628 Hebron Avenue, Suite 400 Glastonbury, CT 06033 USA aero.power.mhi.com MOVE THE WORLD FORW>RD MIT



### Notifications



The attached documentation and information is being provided on condition of confidentiality. By accepting receipt of such documentation and information, Customer agrees (i) not to use such documentation or information except to evaluate Mitsubishi Power Aero LLC's proposal as contemplated by this communication, and (ii) not to disclose such documentation or information to any third parties.

#### Warning

This document contains technical data the export of which is or may be restricted by the Export Administration Act and the Export Administration Regulations (EAR), 15 C.F.R. parts 730-774. Diversion contrary to U.S. law is prohibited. The export, re-export, transfer or re-transfer of this technical data to any other company, entity, person, or destination, or for any use or purpose other than that for which the technical data was originally provided by Mitsubishi Power Aero LLC, is prohibited without prior written approval from Mitsubishi Power Aero LLC and authorization under applicable export control laws.

EAR Export Classification: ECCN EAR99

#### Note

- MOBILEPAC, FT4000, SWIFTPAC and FT8 are registered trademarks of Mitsubishi Power Aero LLC.
- All other company and product names may be trademarks and are the property of their respective owners.

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 114 of 163



# **COMMERCIAL SECTION**

CONFIDENTIAL TO THE PARTIES AND PROPRIETARY TO MITSUBISHI POWER AERO LLC

Mitsubishi Power Aero LLC 628 Hebron Avenue, Suite 400 Glastonbury, CT 06033 USA aero.power.mhi.com MOVE THE WORLD FORWARD MITSUBISHI HEAVY INDUSTRIES GROUP

### **Budgetary Estimate**



#### Hatch

Proposal Number: 03022RL

| BASE EQUIPMENT                                     | QTY | TOTAL ESTIMATE USD |
|--|-----|--------------------|
| FT4000 <sup>®</sup> SWIFTPAC <sup>®</sup> 140      |     |                    |
| Natural Gas, Water Injection with Wet Compression, |     |                    |
| including 60' Exhaust Stack & TA Support.          | 1   | \$53,036,000       |
| Delivered EXW, Mitsubishi Power Aero designated    |     |                    |
| facilities, per INCOTERMS 2020.                    |     |                    |
| Per attached Scope of Supply 03022RL               |     |                    |

Estimate provided is based on the proposal Terms and Conditions contained herein. The parties must enter into a written agreement incorporating Mitsubishi Power Aero LLC, Standard Turbine Purchase Terms and Conditions. Any changes to the standard terms and conditions must be mutually agreed upon in writing and may impact estimate.

Equipment is subject to prior sale.

Pricing is based on 2022 delivery.

This is a budgetary estimate for informational purposes only and cannot be accepted to form a binding contract.

Submittal Date: 7/12/2022

Payments will be due in accordance with the Payment Schedule and with Article 3 of the Mitsubishi Power Aero LLC standard Turbine Purchase Agreement, attached in this Estimate.

| 20% | Upon contract signing date*  |
|-----|--|
| 70% | Four (4) monthly equal payments (17.5%) prior to final shipment. **<br>(last payment is due one month prior to shipment) |
| 10% | Upon successful Performance Test Completion,<br>not to exceed 120 days after Delivery.                                   |

- \* First payment is due net five (5) days after receipt of invoice. All remaining payments are due net 30 days after receipt of invoice.
- \*\* Payments will be invoiced on the 15th of each month.
- Deliveries are subject to prior sale.

All payments made after delivery of equipment are to be secured via a stand-by Letter of Credit, substantially in the form of Exhibit 14 of the Turbine Purchase Agreement.

Submittal Date: 7/12/2022

### 

| Contract | Delivery | Schedule |
|----------|----------|----------|
|----------|----------|----------|

| MILESTONE TASK  | ESTIMATED<br>DELIVERY<br>DATE | NOTES:   |
|---|-------------------------------|--|
| Contract Agreement Signed   | TBD                           | Schedule (including Commercial<br>Operation Date) may shift based<br>on date agreement signed. |
| FT4000 <sup>®</sup> SWIFTPAC <sup>®</sup> 140<br>Power Island Delivery Date | October<br>2022               |  |

Equipment availability is subject to prior sale.

Delivery is EXW (ExWorks) Mitsubishi Power Aero designated facilities, per INCOTERMS 2020.

Submittal Date: 7/12/2022

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 118 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix D3: Siemens – SGT-800

| SGT-800 (57MW) Gas Turbine Power Generation Package  | SGT-800 (62MW) Gas Turbine Power Generation Package  |
|--|--|
| Indicative Price: \$19.01MM US   | Indicative Price: \$20.69MM US   |
| <ul> <li>Scope of Supply Outline</li> <li>SGT-800 Gas Turbine Engine – a low weight industrial,<br/>modular concept Gas Turbine, with DLE combustion<br/>chamber, on a welded I-beam base frame for the GT driver<br/>unit. Cold End Drive</li> </ul>  | <ul> <li>Scope of Supply Outline</li> <li>SGT-800 Gas Turbine Engine – a low weight industrial,<br/>modular concept Gas Turbine, with DLE combustion<br/>chamber, on a welded I-beam base frame for the GT driver<br/>unit. Cold End Drive</li> </ul>  |
| <ul> <li>unit. Cold End Drive</li> <li>Combustion Air Intake System – Two stage HEPA static air<br/>intake filter and silencer</li> <li>Exhaust System – Includes bellow and transition piece,<br/>Horizontal exhaust,</li> <li>Gas Fuel and Ignition System – For Natural Gas including<br/>on package fuel piping, control and shut-off valves, flow<br/>meters, external gas fuel unit with dual shut-off valves and<br/>filter</li> <li>Lubricating Oil System – ISO VG 46 mineral oil, stainless<br/>steel piping downstream of the duplex filter, breather<br/>system, and lube oil water cooler</li> <li>Cooling Water System – The liquid-cooled oil cooler is a<br/>plate heat exchanger type in 316L material. The cooler will<br/>be designed for the specific site conditions</li> <li>Water Cooled AC Generator – 13.8kV/60Hz. Concrete<br/>mounted, including Generator (MV) terminal enclosure,<br/>Excitation and AVR, Generator Protection Equipment,<br/>Synchronizing Equipment</li> <li>Electric Start &amp; Barring System – Including start motor<br/>frequency converter</li> <li>Compressor Washing System – Nozzles upstream of gas<br/>turbine compressor, for high pressure compressor washing</li> <li>Weatherproof Acoustic Enclosure – For Gas Turbine &amp;<br/>Auxiliaries for sound attenuation to 85dB(A) at 3 feet</li> <li>Enclosure Ventilation System – Including silencer, filters,<br/>2x 100% fans and dampers</li> <li>Electrical and control module – Consisting of MCC,<br/>Auxiliary Power distribution including UPS, PCS7 turbine<br/>control for automatic start- up, operation and shut down,<br/>Operator Station – NERC CIP cybersecurity compliance</li> <li>Fire Extinguishing System – Fire detection and CO<sub>2</sub><br/>extinguishing system in enclosed rack.</li> <li>Ambient temperatures – From -4ºF to +104ºF (-20 to 40°C)</li> </ul> | <ul> <li>unit. Cold End Drive</li> <li>Combustion Air Intake System – Two stage HEPA static air<br/>intake filter and silencer</li> <li>Exhaust System – Includes bellow and transition piece,<br/>Horizontal exhaust,</li> <li>Gas Fuel and Ignition System – For Natural Gas including<br/>on package fuel piping, control and shut-off valves, flow<br/>meters, external gas fuel unit with dual shut-off valves and<br/>filter</li> <li>Lubricating Oil System – ISO VG 46 mineral oil, stainless<br/>steel piping downstream of the duplex filter, breather<br/>system, and lube oil water cooler</li> <li>Cooling Water System – The liquid-cooled oil cooler is a<br/>plate heat exchanger type in 316L material. The cooler will<br/>be designed for the specific site conditions</li> <li>Water Cooled AC Generator – 13.8kV/60Hz. Concrete<br/>mounted, including Generator (MV) terminal enclosure,<br/>Excitation and AVR, Generator Protection Equipment,<br/>Synchronizing Equipment</li> <li>Electric Start &amp; Barring System – Including start motor<br/>frequency converter</li> <li>Compressor Washing System – Nozzles upstream of gas<br/>turbine compressor, for high pressure compressor washing</li> <li>Weatherproof Acoustic Enclosure – For Gas Turbine &amp;<br/>Auxiliaries for sound attenuation to 85dB(A) at 3 feet</li> <li>Enclosure Ventilation System – Including silencer, filters,<br/>2x 100% fans and dampers</li> <li>Electrical and control module – Consisting of MCC,<br/>Auxiliary Power distribution including UPS, PCS7 turbine<br/>control for automatic start- up, operation and shut down,<br/>Operator Station – NERC CIP cybersecurity compliance</li> <li>Fire Extinguishing System – Fire detection and CO<sub>2</sub><br/>extinguishing system in enclosed rack.</li> <li>Ambient temperatures – From -49F to +104ºF (-20 to 40°C)</li> </ul> |
| <ul> <li>Delivery – FAS Norkoping, Sweden, 17 months</li> <li>Due to uncertain political and security situation in the world, the price and delivery times stated only represent a best estimate as of the date. The Price and Delivery Times are therefore not binding and are subject to review and potential Adjustment</li> <li>Siemens Energy Industrial Gas Turbines</li> </ul>  | <ul> <li>Delivery – FAS Norkoping, Sweden, 17 months</li> <li>Due to uncertain political and security situation in the world, the price and delivery times stated only represent a best estimate as of the date. The Price and Delivery Times are therefore not binding and are subject to review and potential Adjustment</li> <li>Siemens Energy Industrial Gas Turbines</li> </ul>  |
| This information contain Siemens proprietary information, if you have received it by mistake, please notify us immediately and delete this information from your system.   | This information contain Siemens proprietary information, if you have received it by mistake, please notify us immediately and delete this information from your system.   |

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 120 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix E: Project Schedule

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 121 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix E1: 2 Unit Combustion Turbine Schedule

#### PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 122 of 163

| 0  | hydro  |           |               | Newfo<br><b>Combu</b><br>P<br>H369039 | oundland Labrador Hydro<br>ustion Turbine Screening<br>9-00000-200-076-001 Rev. B   | ATCH                      |
|----|--|-----------|---------------|---------------------------------------|---|---------------------------|
|    | Task Name  | Duration  | Start Fin     | - s                                   | Half 1, 2023 Half 2, 2023 Half 1, 2024 Half 2, 2024 Half 2, 2025 Half 1, 2025 Half 2, 2025 Half 2, 2026 Half | 47 M49 M51 M53 M55 N      |
| -  | Key Milestones   | 1104 days | 23 01 2023 15 | 04 2027                               |   |                           |
| 2  | NLH Budgeting and Approval Start                               | 0 days    | 23 01 2023 23 | 01 2023                               | <ul> <li>23 01</li> </ul>   |                           |
| m  | NLH Budgeting and Approval Complete                            | 0 days    | 19 01 2024 19 | 01 2024                               | ◆ 19 01   |                           |
| 4  | EPCM Contract Award  | 0 days    | 29 03 2024 29 | 03 2024                               | 29 03   |                           |
| 2  | Preliminary Engineering Start                                  | 0 days    | 22 07 2024 22 | 07 2024                               | <ul> <li>22 07</li> </ul>   |                           |
| 9  | Enviromental Approval  | 0 days    | 14 03 2025 14 | 03 2025                               | <ul> <li>14.03</li> </ul>   |                           |
| ~  | Start of Construction (Per Owner RFP)                          | 0 days    | 28 01 2025 28 | 01 2025                               | ◆ 28 01   |                           |
| 8  | Mechanical Completion Unit #1                                  | 0 days    | 27 08 2026 27 | 08 2026                               | ◆ 27 0  | 8                         |
| 6  | Site Utility Services Available                                | 0 days    | 01 06 2026 01 | 06 2026                               | ♦ 01 06   |                           |
| 10 | Mechanical Completion Unit #2                                  | 0 days    | 19 01 2027 19 | 01 2027                               |   | • 19 01                   |
| 5  | Commercial Operation Unit #1                                   | 0 days    | 23 11 2026 23 | 11 2026                               |   | 23 11                     |
| 12 | Commercial Operation Unit #2                                   | 0 days    | 15 04 2027 15 | 04 2027                               |   | <ul> <li>15 04</li> </ul> |
| 13 | Project Development  | 310 days  | 23 01 2023 29 | 03 2024                               |   |                           |
| 14 | NLH Budgeting and Approval                                     | 260 days  | 23 01 2023 19 | 01 2024                               |   |                           |
| 15 | EPCM Contract Negotiations and Award                           | 50 days   | 22 01 2024 29 | 03 2024                               | <b>,</b>  |                           |
| 16 | Permitting / Approval Process                                  | 250 days  | 01 04 2024 14 | 03 2025                               |   |                           |
| 17 | Emission/Noise modelling report                                | 80 days   | 01 04 2024 19 | 07 2024                               |   |                           |
| 18 | Enviromental Application Process                               | 100 days  | 01 04 2024 16 | 08 2024                               |   |                           |
| 19 | Enviromental Approval  | 150 days  | 19 08 2024 14 | 03 2025                               |   |                           |
| 20 | Preliminary Engineering  | 81 days   | 01 04 2024 22 | 07 2024                               | [   |                           |
| 21 | Project Kick off meeting                                       | 1 day     | 01 04 2024 01 | 04 2024                               |   |                           |
| 22 | Design Basis & Preliminary P&ID's Layout / SLDs                | 60 days   | 02 04 2024 24 | 06 2024                               | 1   |                           |
| 23 | Preliminary Specs for Long Lead Equipment                      | 50 days   | 14 05 2024 22 | 07 2024                               |   |                           |
| 24 | Prepare Cost Estimate  | 40 days   | 14 05 2024 08 | 07 2024                               |   |                           |
| 25 | Gas Turbine Generator (GTG) Procurement                        | 510 days  | 02 04 2024 16 | 03 2026                               |   |                           |
| 26 | Specifications and RFQ's                                       | 55 days   | 02 04 2024 17 | 06 2024                               |   |                           |
| 27 | Bids, Evaluations & Clarifications                             | 40 days   | 18 06 2024 12 | 08 2024                               | •   |                           |
| 28 | Supply Contract Award  | 0 days    | 12 08 2024 12 | 08 2024                               | 🐳 12 08   |                           |
| 29 | GTG #1 Design / Manufacturing and Delivery on Site             | 325 days  | 13 08 2024 10 | 11 2025                               |   |                           |
| 30 | GTG #2 Design / Manufacturing and Delivery on Site             | 325 days  | 17 12 2024 16 | 03 2026                               |   |                           |
| 31 | GSU Transformers Procurement                                   | 580 days  | 13 08 2024 02 | 11 2026                               |   |                           |
| 32 | Specifications and RFQ's                                       | 60 days   | 13 08 2024 04 | 11 2024                               |   |                           |
| 33 | Bids, Evaluations & Clarifications                             | 40 days   | 05 11 2024 30 | 12 2024                               |   |                           |
| 34 | Contract Award   | 0 days    | 30 12 2024 30 | 12 2024                               | ♣ 30 12   |                           |
| 35 | GSU #1 Transformer Design / Manufacturing and Delivery on Site | 390 days  | 31 12 2024 29 | 06 2026                               | •   |                           |
| 36 | GSU #2 Transformer Design / Manufacturing and Delivery on Site | 390 days  | 06 05 2025 02 | 11 2026                               |   |                           |
| 37 | Detailed Engineering   | 180 days  | 13 08 2024 21 | 04 2025                               |   |                           |
| 38 | Detailed Engineering   | 180 days  | 13 08 2024 21 | 04 2025                               |   |                           |
| 39 | Civil & Found. Works Contract Spec's/ Bid Process/ Award       | 120 days  | 13 08 2024 27 | 01 2025                               | Ĵ,  |                           |
| 40 | Mech & Elec Installation Contract RFP/Bid Proces/Award         | 120 days  | 13 08 2024 27 | 01 2025                               |   |                           |
|    |  |           |               |                                       |   |                           |
|    |  |           |               |                                       | Page 1  |                           |

#### PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 123 of 163

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 124 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix E2: 4 Unit Combustion Turbine Schedule

#### PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 125 of 163

| ndland Labrador Hydro<br>tion Turbine Screening<br>diminary Schedule<br>0000-200-076-001 Rev. B | 1. 2023 Haff 2. 2023 Haff 1. 2024 Haff 2. 2024 Haff 2. 2025 Haff 2. 2025 Haff 2. 2025 Haff 1. 2026 Haff 2. 2026 Haff 1. 2027 Haff 2. 2027 Haff 1. 21<br>M3 M5 M7 M9 M11 M13 M15 M17 M19 M21 M23 M25 M27 M29 M31 M33 M35 M37 M39 M41 M43 M45 M49 M51 M53 M55 M57 M59 M61 M65 |                         | 23 01<br>2 19 01    | ◆ 22 01           | ◆ 01 04             | <ul> <li>14 03</li> </ul> | ◆ 25 02           | ◆ 10 08           | 20 II (\$<br>9 08 05 | ◆ 00 00<br>◆ 01 10                     | <ul> <li>◆ 01 12</li> </ul> | <ul> <li>10 05</li> </ul> | ♦ 02 09           | ◆ 26 12<br>•      | \$3                                      | -                     | •                    |                     |                    |                     |                     | -<br>- ▶ c       |                    |                      |                       |                    | •                  | ▲ 12 08           |                     |                          |                    |                     |                   | •                 | 30 12           |                        |
|---|---|-------------------------|---------------------|-------------------|---------------------|---------------------------|-------------------|-------------------|----------------------|--|-----------------------------|---------------------------|-------------------|-------------------|--|-----------------------|----------------------|---------------------|--------------------|---------------------|---------------------|------------------|--------------------|----------------------|-----------------------|--------------------|--------------------|-------------------|---------------------|--------------------------|--------------------|---------------------|-------------------|-------------------|-----------------|------------------------|
| Newfo<br>Combu<br>F<br>H369039  | h 22 H<br>M-2 N   | 02 2028                 | 3 01 2023           | 22 01 2024        | 01 04 2024          | 14 03 2025                | 25 02 2025        | 5 10 08 2026      | 11 02 2027           | 08 06 2027                             | 01 12 2027                  | 10 05 2027                | 02 09 2027        | 28 12 2027        | 25 02 2028<br><b>29 03 2024</b>          | 19 01 2024            | 9 03 2024            | 14 03 2025          | 19 07 2024         | 16 08 2024          | 14 U3 2023          | 01 04 2024       | 22 07 2024         | 02 09 2024           | 23 11 2026            | 17 06 2024         | 12 08 2024         | 12 08 2024        | 10 11 2025          | 16 03 2026<br>20 07 2026 | 5 23 11 2026       | 4 15 02 2027        | 4 04 11 2024      | 4 30 12 2024      | 24 30 12 2024   | 24 29 06 2026          |
|   | Duration Start Finis  | 1329 days 23 01 2023 25 | 0 days 23 01 2023 2 | 0 days 22 01 2024 | 0 days 01 04 2024 0 | 0 days 14 03 2025         | 0 days 25 02 2025 | 0 days 10 08 2026 | 0 days 11 02 2027    | 0 days 08 06 2027<br>0 days 01 10 2027 | 0 days 01 12 2027           | 0 days 10 05 2027         | 0 days 02 09 2027 | 0 days 28 12 2027 | 0 days 25 02 2028<br>310 days 23 01 2023 | 260 days 23 01 2023 1 | 50 days 22 01 2024 2 | 250 days 01 04 2024 | 80 days 01 04 2024 | 100 days 01 04 2024 | 111 dave 01 04 2024 | 1 day 01 04 2024 | 80 days 02 04 2024 | 60 days 11 06 2024 ( | 690 davs 02 04 2024 2 | 55 days 02 04 2024 | 40 days 18 06 2024 | 0 days 12 08 2024 | 325 days 13 08 2024 | 325 days 1/ 12 2024      | 325 davs 26 08 202 | 655 days 13 08 2024 | 60 days 13 08 202 | 40 days 05 11 202 | 0 days 30 12 20 | Sit 390 days 31 12 202 |

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 127 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix F: Equipment List

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 128 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix F1: 2 Unit Combustion Turbine – Brownfield

#### PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 129 of 163

#### HATCH Equipment List

| Originator:                | Date Submitted:  | Project No.:   | Revision:            |                                |  |
|----------------------------|--|--|----------------------|--------------------------------|--|
| Hatch                      | 10/26/2022   | H-369039   | С                    |                                |  |
| Client:                    | Project Name:  |  | Discip <b>l</b> ine: |                                |  |
| Newfound and and Labrador  | Combustion Turbine Screening   | Brown Field 2 units  | Thermal Power        |                                |  |
| Hydro<br>Document Number:  | Hatch Responsible Project Manager:                                     |  | Karim Meghari        |                                |  |
| H+369039-00000-200-216-004 | Cliant Penyasantativa  |  | Ruan Conner          |                                |  |
| WIDS #                     | Description  | Description of sub-components  | Quantity             | Duty % Moluma                  | Notor  |
| WB3#                       | Description  | Description of sub-components  | Quantity             | Duty % /volume                 | Notes  |
| Equipment List:            |  |  |                      |                                |  |
| 10                         | Gas Turbine Generator  | Gas Turbine Generator with Exhaust Door                                | 2                    |                                |  |
|                            |  | Gas Turbine Fuel Module  | 2                    |                                |  |
|                            |  | Generator Breaker Enclosure  |                      |                                |  |
|                            |  | GT Electrical and Control Compartment                                  | 2                    |                                |  |
|                            |  | Exhaust Frame Blower<br>GT Coolling Water Module                       | 4                    |                                |  |
|                            |  | Lube Oil Demister  | 2                    |                                |  |
|                            | Gas Turbine Firefighting Skid  | Gas Turbine Firefighting Skid  | 1                    |                                | Vortex / FM200   |
|                            | Gas Turbine Wash Pakage  | Gas Turbine Water Was Skid   | 1                    |                                |  |
| 20                         | Common Services Equipment and Systems                                  |  |                      |                                |  |
| 21                         | Plant Water Systems (Common)   |  |                      |                                |  |
|                            | Service Water System   | Service Water Storage Tank   | 0                    |                                |  |
|                            |  |  |                      |                                |  |
|                            |  | Service Water Pumps  | 0                    | 100                            |  |
|                            |  | Straners<br>Piping/Hoses   | Lot                  | 100                            |  |
|                            |  |  |                      |                                |  |
|                            | 2-Stage Reverse Osmosis(RO)  | 2 parallel trains  |                      | 100                            |  |
|                            |  | First Stage RO pumps   | 2                    | 100                            |  |
|                            |  | Break Tank   | 1                    | 100                            |  |
|                            |  | Energy recovery devices<br>Caustic Soda Tote and Pump                  | 2                    | 100                            |  |
|                            |  | Second Stage RO Pumps  | 2                    | 100                            |  |
|                            |  | Second Stage Membrane Units<br>RO Product Water Tank                   | 2                    | 100                            |  |
|                            |  | RO Reject to CW Weir   | Lot                  |                                |  |
|                            |  | Piping Valves, etc.<br>Clean-in-Place Skid (for membrane cleaning)     | Lot                  |                                |  |
|                            |  |  |                      |                                |  |
|                            | DI Water   | RO Product Water Pumps   | 2                    | 100                            |  |
|                            | 1  | Electrodeionization (EDI) Units  | 2                    | 100                            |  |
|                            |  | DI Water Tank  | 1                    | 500 m3                         | 2 days Demin water storage for 2 GTs<br>at 100% capacity |
|                            |  |  |                      |                                |  |
|                            | Waste Water System   | Wastewater Collection Sumps  |                      |                                |  |
|                            |  | Wastewater Collection Sump Pumps                                       |                      |                                |  |
|                            |  | Fuel Storage Sump Pump   |                      |                                |  |
|                            |  | Dirty Water Sump   |                      |                                |  |
|                            |  | Piping Systems   |                      |                                |  |
|                            |  | Oily Water Seperator<br>Waste Water Catch Basin                        |                      |                                |  |
|                            |  | Sanitary Sewage System   |                      |                                |  |
| 23                         | Compressed Air. Gas & Vacuum Systems                                   |  |                      |                                |  |
|                            | Plant Air & Instrument Air System                                      | Air Compressors  | 0                    | 100                            | Screw type Compressor. Two per GT                        |
|                            |  | Instrument Air Dryers  | 0                    | 100                            | One per Unit. Regenerative or                            |
|                            |  | Service Air Reseiver (nor Linit)                                       | 0                    | 100                            | Desicant   |
|                            |  | Centro An Receiver (per child  |                      | 105                            | Verdear  |
|                            |  | Instrument Air Receiver (per Unit)<br>Piping & Valves                  | 2<br>Lot             | 50                             | Vertical   |
|                            |  |  |                      |                                |  |
| 24                         | Lubricating OII Storage/treatment                                      | Oil Cleaning Unit (per Unit)   | 1                    |                                |  |
| 25                         | Emergency Diesel Generators  | Emergency Diesel Generators  | 2                    |                                |  |
| 26                         | Fire Protection Systems  | Water Storage (Fire Water Tank)  | 1                    | 1000 m3                        | 2 hours Fire water storage                               |
|                            |  | Main Pump - electric   | 1                    | 100                            |  |
|                            |  | Jockey Pump - electric   | 1                    | 100                            |  |
|                            |  | Water Ring Main System   | Lot                  |                                |  |
|                            |  | Valved Fire Water Connections  | Lot                  |                                |  |
|                            |  | Vard Hydrant & Hose Station<br>Wet System Sprinklers                   | Lot                  |                                |  |
|                            |  | Portable Dry Chemical Extinguishers                                    | Lot                  |                                |  |
|                            |  | CO2 systams  | Lot                  |                                |  |
| 30                         | Fuel Supply and Storage  | Discut Discourse Tables  |                      | 5050 - 0 I                     | 7.1  |
| 31                         | Liese Handling & Storage (Common)                                      | Diese Storage Tanks  | 2                    | 2800 m3 each                   | baseload ( 100% GT capacity)                             |
|                            |  | Fuel Metering  | 1                    |                                |  |
|                            |  | Fuel Supply to Diesel Generator  | Lot                  | 100                            |  |
|                            |  | Fuel forwarding Pumps  | 2                    | 100                            |  |
|                            |  | Fuel heaters   | 2                    | 100                            | Electric heaters   |
| 32                         | Biofuel  | Fuel offloading pump<br>Biofuel Storage Tank                           | 2                    | 100<br>2800 m <sup>3</sup> c 1 | 7 days storage for 2 GT                                  |
|                            |  | Fuel Metering  | 1                    | 2000 milleach                  | , convego of 2 01.                                       |
|                            |  | Interconnecting piping and piping to gas turbine                       | Lot                  |                                |  |
|                            |  | Fuel Humps<br>Fuel offloading pump                                     | 2                    | 100                            |  |
| 40                         | Miscellaneous Equipment & Systems                                      |  |                      |                                |  |
| 41                         |  |  | LOT                  |                                |  |
|                            | Laboratory and Test Equipment  |  | Lot                  | -                              |  |
| 50                         | Environmental (Emissions) Control Systems (per Unit                    |  |                      |                                |  |
|                            | Continuous Emission Monitoring (Unit)                                  | One system for each flue   | 1                    |                                |  |
|                            |  |  |                      |                                |  |
|                            |  |  |                      |                                |  |
| 60                         | Electrical Power Systems<br>240-KV Main Power Outnut System (car Unit) | Main 11/240-KV Power Transformer /TP + Lh/                             | ,                    |                                |  |
|                            |  | Generator Isolated-phase Bus System                                    | Lot                  |                                |  |
|                            |  | Generator Circuit Breakers   | 2                    |                                |  |
|                            |  | Metering and Protection<br>Grounding System                            | Lot                  |                                |  |
|                            |  |  | LUE                  |                                |  |
| 82                         | Auxiliary Power Supply system  | 11/4.16 kV Unit Appliary Transformer                                   | 2                    |                                |  |
|                            | , · · · · · · · · · · · · · · · · · · ·                                |  | 2                    |                                |  |
| 63                         | Unit/station Power Supply system                                       | 4.16/0.6-kV Unit/Station Services Transformer<br>4.16 kV MV switchgear | 6<br>Lot             |                                |  |
|                            |  | 600 V switchgear   | Lot                  |                                |  |
|                            |  | OUU V MCC'S  | Lot                  |                                |  |
| 64                         | Auxiliary AC Power Distribution (Common)                               | Emergency Diesel Generator   | 1                    |                                |  |
| 65                         | UPS Supply and Distribution (per Unit)                                 | 110-V, 1 ph, 50 Hz Power Distribution                                  | Lot                  |                                |  |
|                            | DC Supply (Common)   | 125 VDC Supply and Distribution System                                 | 2                    |                                |  |
| 66                         | Cabling Systems  | Power, Control and Instrumentation                                     | Lot                  |                                |  |
| 67                         | Building and Outdoor Electrical Services                               | Will be tied into existing plant and                                   | Lot                  |                                |  |
|                            | error foring grid  | www.ueueu.mo.existing.plant.grld.                                      | LOC                  |                                |  |
| 70                         | Instrumentation and Control  |  | L AL                 |                                |  |
| 72                         | Power generation & Auxiliaries I&C                                     |  | Lot                  |                                |  |
| 73                         | Common Sevices and equipment I&C                                       | Da. 1.11   | Lot                  | -                              |  |
|                            |  | rage 1 01 1  |                      |                                |  |

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 130 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix F2: 2 Unit Combustion Turbine – Greenfield

#### PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 131 of 163

#### HATEH Equipment List

| Originator:                | Date Submitted:   | Project No.:   | Revision:              | 1                         |  |
|----------------------------|---|--|------------------------|---------------------------|--|
| Hatch                      | 10/28/2022  | H-369039   | с                      |                           |  |
| Client:                    | Project Name:   |  | Discipline:            |                           |  |
| Newfound and and Labrador  | Combustion Turbine Screening  | Green Field 2 units  | Thermal                |                           |  |
| Document Number:           | Hatch Responsible Project Manager:  |  | Fower<br>Karim Meghari |                           |  |
| H-369039-00000-200-216-002 | Clent Representative:   |  | Ryan Cooper            |                           |  |
| WBS#                       | Description   | Description of sub-components  | Quantity               | Duty % /Volume            | Notes  |
|                            |   |  |                        |                           |  |
| Equipment List:<br>10      | Gas Turbine Generator   | Gas Turbine Generator with Exhaust Door                                | 2                      |                           |  |
|                            |   | Gas Turbine Fuel Module  | 2                      |                           |  |
|                            |   | Generator Breaker Endosure   | -                      |                           |  |
|                            |   | GT Electrical and Control Compartment                                  | 2                      |                           |  |
|                            |   | Exhaust Frame Blower   | 4                      |                           |  |
|                            |   | GT Coolling Water Module   | 2                      |                           |  |
|                            |   | Lube Oil Demister  | 2                      |                           |  |
|                            | Gas Turbine Firefighting Skid   | Gas Turbine Firefighting Skid  | 1                      |                           | Vortex / FM200                                     |
|                            | Gas Turbine Wash Pakage   | Gas Turbine Water Was Skid   | 1                      |                           |  |
| 20                         | Common Services Equipment and Systems                                     |  |                        |                           |  |
|                            | Service Water System  | Service Water Storage Tank   | 1                      | 1000 m <sup>3</sup>       | 2 days water storage for 2 GTs at 100%             |
|                            |   | Service Water Pumps  | 2                      | 100                       | - aparty   |
|                            |   | Strainers<br>Piping/Hoses  | 2<br>Lot               | 100                       |  |
|                            |   |  |                        |                           |  |
|                            | 2-Stage Reverse Osmosis(RO)   | 2 parallel trains  | 2                      | 100                       |  |
|                            |   | First Stage Membrane Units   | 2                      | 100                       |  |
|                            |   | Break Tank   | 1                      | 100                       |  |
|                            |   | Energy recovery devices<br>Caustic Soda Tote and Pump                  | 2                      | 100                       |  |
|                            |   | Second Stage RO Pumps<br>Second Stage Membrane Units                   | 2                      | 100                       |  |
|                            |   | RO Product Water Tank<br>RO Reject to CW Weir                          | 1<br>Lot               |                           |  |
|                            |   | Piping Valves, etc.  | Lot                    |                           |  |
|                            |   | Steen HER Prive Skie (or inemprane cleaning)                           | LOT                    |                           |  |
|                            | DIWater   | RO Product Water Pumps   | 2                      | 100                       |  |
|                            |   | Electrodeionization (EDI) Units<br>DI Water Tank                       | 2                      | 100<br>500 m <sup>3</sup> | 2 days Demin water storage for 2 GTs at            |
|                            |   |  | -                      | ere ni                    | 100% capacity                                      |
|                            | Maste Mater Conten  | Wasternater Collection Promo   |                        |                           |  |
|                            | waste water System  | Wastewater Collection Sumps  |                        |                           |  |
|                            |   | Fuel Storage Sump<br>Fuel Storage Sump Pump                            |                        |                           |  |
|                            |   | Dirty Water Sump<br>Dirty Water Sump Pump                              |                        |                           |  |
|                            |   | Piping Systems   |                        |                           |  |
|                            |   | Waste Water Catch Basin  |                        |                           |  |
|                            |   | Sanitary Sewage System   |                        |                           |  |
| 23                         | Compressed Air, Gas & Vacuum Systems<br>Plant Air & Instrument Air System | Air Compressors  | 4                      | 100                       | Screw type Compressor. Two per GT                  |
|                            |   | Instrument Air Dryers<br>Service Air Receiver (ner Linit)              | 2                      | 100                       | One per Unit. Regenerative or Desicant<br>Vertical |
|                            |   | Instrument Air Receiver (per Unit)                                     | 2                      | 50                        | Vertical   |
|                            |   | Piping & Varies  | Lot                    |                           |  |
| 24                         | Lubricating OI Storage/treatment  | OI Cleaning Unit (per Unit)  | 1                      |                           |  |
| 25                         | Emergency Diesel Generators   | Emergency Diesel Generators  | 2                      |                           |  |
| 26                         | Fire Protection Systems   | Water Storage (Fire Water Tank)  | 1                      | 1000 m <sup>3</sup>       | 2 hours Fire water storage                         |
| 20                         |   | Main Dume, electric  |                        | 1000 m                    | 2 Iloura i ne viscei acorage                       |
|                            |   | Main Fump - electric   |                        | 100                       |  |
|                            |   | Jockey Pump - electric   | 1                      | 100                       |  |
|                            |   | Water Ring Main System<br>Dry Deluge Spray System                      | Lot                    |                           |  |
|                            |   | Valved Fire Water Connections<br>Yard Hydrant & Hose Station           | Lot                    |                           |  |
|                            |   | Wet System Sprinklers<br>Portable Dry Chemical Extinguishers           | Lot                    |                           |  |
|                            |   | CO <sub>2</sub> systems  | Lot                    |                           |  |
| 30                         | Fuel Supply and Storage   |  |                        |                           | 7.1  |
| 37                         | creater remaining or consider (common)                                    | Diesel Stolage Latina  | 2                      | 2800 m° each              | baseload (100% GT capacity)                        |
|                            |   | Interconnecting piping and piping to gas turbine                       | 1<br>Lot               |                           |  |
|                            |   | Fuel Supply to Diesel Generator<br>Fuel forwarding Pumps               | 2                      | 100                       |  |
|                            |   | Oil separator  | 2                      | 100                       | Flantrin hastern                                   |
| 20                         | Richal  | Fuel offloading pump   | 2                      | 100                       | 7 daug atraam (n 0.07                              |
| 32                         | Liona   | Fuel Metering  | 1                      | 2800 m° each              | r waya skuraĝe tot 2 G I.                          |
|                            |   | Interconnecting piping and piping to gas turbine<br>Fuel Pumps         | Lot<br>2               | 100                       |  |
| 40                         | Miscellaneous Equipment & Systems   | Fuel offloading pump   | 2                      | 100                       |  |
| 41                         | Workshop Equipment and Tools<br>Laboratory and Test Equipment             |  | Lot                    |                           |  |
| 50                         | Environmental (Emissions) Control Sustame (nar Unit                       |  |                        |                           |  |
|                            | Continuous Emission Monitoring (Unit)                                     | One system for each flue   | 11                     |                           |  |
|                            |   |  |                        |                           |  |
| 60                         | Electrical Power Systems<br>240-kV Main Power Output System (ner Unit)    | Main 11/240-kV Power Transformer (TP at HV                             | 2                      |                           |  |
|                            |   | Terminals<br>Generator Isolated-phase Bus System                       | Lot                    |                           |  |
|                            |   | Generator Circuit Breakers   |                        |                           |  |
|                            |   | Metering and Protection  | Lot                    |                           |  |
|                            |   | Stownung System  | Lot                    |                           |  |
|                            |   |  |                        |                           |  |
| 62                         | Auxiliary Power Supply system   | 11/4.15 kV Unit Auxiliary Transformer                                  | 2                      |                           |  |
| 63                         | Unit/Station Power Supply system  | 4.16/0.6-kV Unit/Station Services Transformer<br>4.16 kV MV switchgear | 6<br>Lot               |                           |  |
|                            |   | 600 V switchgear   | Lot                    |                           |  |
|                            |   | 600 V MCC's  | Lot                    |                           |  |
| 64                         | Auxiliary AC Power Distribution (Common)                                  | Emergency Diesel Generator   | 0                      |                           |  |
| 65                         | UPS Supply and Distribution (per Unit)                                    | 110 V, 1 ph, 50 Hz Power Distribution                                  | Lot                    |                           |  |
|                            | DC Supply (Common)  | 125 VDC Supply and Distribution System                                 | 2                      |                           |  |
| 66<br>67                   | Cabling Systems<br>Building and Outdoor Electrical Services               | Power, Control and Instrumentation                                     | Lot                    |                           |  |
|                            | Grounding grid  | Will be tied into existing plant grid.                                 | Lot                    |                           |  |
| 70                         | Instrumentation and Control   |  |                        |                           |  |
| 71 72                      | Central Control System, incl. DCS<br>Power generation & Auditaries I&C    |  | Lot                    |                           |  |
| 73                         | Common Sevices and equipment I&C  |  | Lot                    |                           |  |

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 132 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix F3: 4 Unit Combustion Turbine – Brownfield

#### PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 133 of 163

#### HΔTCH Equipment List

| Originator:                | Date Submitted:  | Project No.:  | Revision:      |                          |  |
|----------------------------|--|---|----------------|--------------------------|--|
| Hatch                      | Project Name   | H-369039  | C Discipline:  |                          |  |
| Newfoundland and Labrador  | Combustion Turbina Screening   | Brown Eield 4 unite   | Thermal Preser |                          |  |
| Hydro<br>Document Number:  | Hatch Responsible Project Manager:                                     | Blown Pleta 4 units   | Karim Meghari  |                          |  |
| H-369039-00000-200-216-005 | Client Representative:   |   | Ryan Cooper    |                          |  |
| WBS#                       | Description  | Description of sub-components   | Quantity       | Duty % /Volume           | Notes  |
| Equipment List:            |  |   |                |                          |  |
| 10                         | Gas Turbine Generator  | Gas Turbine Generator with Exhaust Door   | 4              |                          |  |
|                            |  | Gas Turbine Fuel Module   | 4              |                          |  |
|                            |  | Generator Breaker Enclosure<br>GT Electrical and Control Compartment                | 4              |                          |  |
|                            |  | Exhaust Frame Blower  | 8              |                          |  |
|                            |  | GT Coolling Water Module  | 4              |                          |  |
|                            |  | Lube OII Demister   | 4              |                          |  |
|                            | Gas Turbine Firefighting Skid  | Gas Turbine Firefighting Skid   | 2              |                          | Vortex / FM200                               |
| 20                         | Common Sandcas Equipment and Systems                                   |   | _              |                          |  |
| 21                         | Plant Water Systems (Common)   | Service Water Storage Tank  | 0              |                          | 2 days water storage for 4 GTs               |
|                            |  | Service Water Pumps<br>Strainers  | 0              | 100                      | 2 00/0 1000 0000 0000                        |
|                            |  | Piping/Hoses  | Lot            |                          |  |
|                            | 3-Stana Reverse Comneie(RC)  | 2 narallel traine   |                | 100                      |  |
|                            | 2 only reverse composition   | First Stage RO pumps  | 4              | 100                      |  |
|                            |  | The Stage Mellistane Shia   | 1              | 100                      |  |
|                            |  | Break Tank  | 2              | 100                      |  |
|                            |  | Energy recovery devices   | 4              | 100                      |  |
|                            |  | Caustic Soda Tote and Pump<br>Second Stage RO Pumps                                 | 2 4            | 100                      |  |
|                            |  | RO Product Water Tank   | 4              | 100                      |  |
|                            |  | RO Reject to CW Weir<br>Piping Valves, etc.   | Lot            |                          |  |
|                            |  | Clean-in-Place Skid (for membrane cleaning)   | Lot            |                          |  |
|                            | DI Water   | RO Product Water Pumps  | 4              | 100                      |  |
|                            |  | Electrodeionization (EDI) Units<br>DI Water Tank                                    | 4              | 100<br>1000 m3           | 2 days Demin water storage for               |
|                            |  |   |                |                          | 4 GTs at 100% capacity                       |
|                            | Marke Minkey Printers  | Masheuster Calleston Course   |                |                          |  |
|                            | waste water system   | Wastewater Collection Sumps   |                |                          |  |
|                            |  | Fuel Storage Sump<br>Fuel Storage Sump Pump   |                |                          |  |
|                            |  | Dirty Water Sump<br>Dirty Water Sump Pump   |                |                          |  |
|                            |  | Oly Water Seperator   |                |                          |  |
|                            |  | Vaste Water Catch Basin<br>Sanitary Sewage System                                   |                |                          |  |
| 23                         | Compressed Air, Gas & Vacuum Systems                                   |   |                |                          |  |
|                            | Plant Air & Instrument Air System                                      | Air Compressors   | 0              | 100                      | Screw type Compressor. Two<br>per GT         |
|                            |  | Service Air Receiver (ner Linit)  | 0              | 100                      | Desicant<br>Vertical                         |
|                            |  | Instrument Air Receiver (per Unit)  | 0<br>Lot       | 50                       | Vertical                                     |
| 24                         | Lubrication OI Storage/reatment  | Of Classing List (ser List)   | 2              |                          |  |
| 25                         | Emanager Distal Constitution   | Encompany Discol Computers  | -              |                          |  |
| 25                         | Emergency Deservenerators  | Energency bieser Generators   | 2              |                          |  |
| 26                         | Fire Protection Systems  | Water Storage (Fire Water Tank)   | 1              | 2000 m3                  | 2 hours Fire water storage                   |
|                            |  | Main Pump - electric  | 2              | 100                      |  |
|                            |  | Emergency/backup Pump-diesel<br>Jockey Pump - electric                              | 2              | 100<br>Maintain pressure |  |
|                            |  | Water Ring Main System<br>Dry Deluge Spray System                                   | Lot            |                          |  |
|                            |  | Valved Fire Water Connections<br>Yard Hydrant & Hose Station                        | Lot            |                          |  |
|                            |  | Wet System Sprinklers<br>Portable Dry Chemical Extinguishers                        | Lot            |                          |  |
|                            |  | CO2 systams   | Lot            |                          |  |
| 30<br>31                   | Fuel Supply and Storage  | Diseal Storana Tanke  | 2              | 5600 m3 each             | 7 risus storana for 4 GTs                    |
|                            | ······································                                 |   | <u> </u>       | daun                     | operating at baseload ( 100%<br>GT capacity) |
|                            |  | Fuel Metering<br>Fuel heaters   | 2              | 100                      | Electric heaters                             |
|                            |  | Interconnecting piping and piping to gas turbine<br>Fuel Supply to Diesel Generator | Lot            | 100                      |  |
|                            |  | Fuel Forwarding Pumps<br>Oil separator  | 4              | 100                      |  |
| 32                         | Biofuel  | Fuel Ottloading Pumps<br>Biofuel Storage Tank                                       | 2              | 100<br>5600 m3 each      | 7 days storage for 4 GT.                     |
|                            |  | Fuel Metering<br>Interconnecting piping and piping to gas turbine                   | 2<br>Lot       |                          |  |
|                            |  | Fuel Pumps<br>Fuel offloading Pumps   | 4              | 100                      |  |
| 40 41                      | Miscellaneous Equipment & Systems<br>Workshop Equipment and Tools      |   | Lot            |                          |  |
|                            | Laboratory and Test Equipment  |   | Lot            |                          |  |
| 50                         | Environmental (Emissions) Control Systems (per Unit)                   | One system for each flue  | 2              |                          |  |
|                            | Commous Emission Monitoring (Unit)                                     | one system for each flue  | 2              |                          |  |
| 60                         | Electrical Power Systems   | Main 11730 M/ Demo-Transfer   |                |                          |  |
| 01                         |  | Generator Isolated-phase Bus System   | Lot            |                          |  |
|                            |  | Generator Circuit Breakers  | 4              |                          |  |
|                            |  | Grounding System  | Lot            |                          |  |
|                            |  |   |                |                          | ļ  |
| 62                         | Auxiliary Power Supply system  | 11/4.16 kV Unit Auxiliary Transformer   | 4              |                          |  |
| 63                         | Unit/Station Power Supply system                                       | 4.16/0.6-kV Unit/Station Services Transformer                                       | 12             |                          |  |
|                            |  | 600 V switchgear  | Lot            |                          |  |
|                            |  | 600 V MCC's   | Lot            |                          |  |
| 64                         | Auxiliary AC Power Distribution (Common)                               | Emergency Diesel Generator  | 2              |                          |  |
| 65                         | UPS Supply and Distribution (per Unit)                                 | 110-V, 1 ph, 60 Hz Power Distribution   | Lot            |                          |  |
|                            | uc supply (common)   | 125 VUC Supply and Distribution System  | 4              |                          |  |
| 66<br>67                   | Cabling Systems<br>Building and Outdoor Electrical Services            | Power, Control and Instrumentation  | Lot<br>Lot     |                          |  |
|                            | Grounding grid   | Will be tied into existing plant grid.  | Lot            |                          |  |
| 70                         | Instrumentation and Control<br>Central Control System, Incl. DCS       |   | Lot            |                          |  |
| 72                         | Power generation & Auxiliaries I&C<br>Common Sevices and equipment I&C |   | Lot            |                          |  |

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 134 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix F4: 4 Unit Combustion Turbine – Greenfield

#### PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 135 of 163

#### HΔTCH Equipment List

| Originator:                | Date Submitted:   | Project No.:  | Revision:      |                     |  |
|----------------------------|---|---|----------------|---------------------|--|
| Client:                    | Project Name:   | H-309039  | Discipline:    |                     |  |
| Newfoundland and Labrador  | Combustion Turbine Screening  | Green Field 4 units   | Thermal Preser |                     |  |
| Hydro<br>Document Number:  | Hatch Responsible Project Manager:  |   | Karim Meghari  |                     |  |
| H-369039-00000-200-216-003 | Client Representative:  |   | Ryan Cooper    |                     |  |
| WBS #                      | Description   | Description of sub-components   | Quantity       | Duty % /Volume      | Notes  |
|                            |   |   |                |                     |  |
|                            |   |   |                |                     |  |
| Equipment List:            | Gas Turkine Generator   | Gas Turbine Generator with Exhaust Door   | 4              |                     |  |
| 10                         |   | Gas Turbine Fuel Module   | 4              |                     |  |
|                            |   | Generator Breaker Enclosure   |                |                     |  |
|                            |   | GT Electrical and Control Compartment   | 4              |                     |  |
|                            |   | Exhaust Frame Blower  | 4              |                     |  |
|                            |   | Lube Oil Demister   | 4              |                     |  |
|                            | Gas Turbine Firefighting Skid   | Gas Turbine Firefighting Skid   | 2              |                     | Vortex / FM200   |
|                            | Gas Turbine Wash Pakage   | Gas Turbine Water Was Skid  | 2              |                     |  |
| 20                         | Common Services Equipment and Systems<br>Plant Water Systems (Common)     |   |                |                     |  |
|                            | Service Water System  | Service Water Storage Tank  | 1              | 2000 m3             | 2 days water storage for 4 GTs at<br>100% capacity       |
|                            |   | Strainers   | 4              | 100                 |  |
|                            |   | Piping/Hoses  | Lot            |                     |  |
|                            | 2-Stage Reverse Osmosis(RO)   | 2 parallel trains   |                | 100                 |  |
|                            |   | First Stage Membrane Units  | 4              | 100                 |  |
|                            |   | Break Tank  | 2              | 100                 |  |
|                            |   |   |                |                     |  |
|                            |   | Caustic Soda Tote and Pump  | 2              | 100                 |  |
|                            |   | Second Stage RO Pumps<br>Second Stage Membrane Units                                | 4              | 100                 |  |
|                            |   | RO Product Water Lank<br>RO Reject to CW Weir                                       | 2<br>Lot       |                     |  |
|                            |   | Clean-in-Place Skid (for membrane cleaning)   | Lot            |                     |  |
|                            |   |   |                |                     |  |
|                            | Di Water  | RO Product Water Pumps<br>Electrodeionization (EDI) Units                           | 4              | 100                 |  |
|                            |   | DI Water Tank   | 1              | 1000 m3             | 2 days Demin water storage for 4 GTs<br>at 100% capacity |
|                            | Waste Water System  | Washwater Collection Summe  |                |                     |  |
|                            | waste water System  | Wastewater Collection Sump Pumps  |                |                     |  |
|                            |   | Fuel Storage Sump Pump  |                |                     |  |
|                            |   | Dirty Water Sump<br>Dirty Water Sump Pump   |                |                     |  |
|                            |   | Oly Water Seperator   |                |                     |  |
|                            |   | Sanitary Sewage System  |                |                     |  |
| 23                         | Compressed Air, Gas & Vacuum Systems<br>Plant Air & Instrument Air System | Air Compressors   | 8              | 100                 | Screw type Compressor: Two per GT                        |
|                            |   | Instrument Air Dryers   | 4              | 100                 | One per Unit. Regenerative or<br>Desicant                |
|                            |   | Service Air Receiver (per Unit)<br>Instrument Air Receiver (per Unit)               | 4 4            | 100                 | Vertical<br>Vertical                                     |
|                            |   | Piping & Valves   | Lot            |                     |  |
| 24                         | Lubricating OI Storage/treatment  | Oil Cleaning Unit (per Unit)  | 2              |                     |  |
| 25                         | Emergency Diesel Generators   | Emergency Diesel Generators   | 2              |                     |  |
| 26                         | Fire Protection Systems   | Water Storage (Fire Water Tank)   | 1              | 2000 m3             | 2 hours Fire water storage                               |
|                            |   | Main Pump - electric  | 2              | 100                 |  |
|                            |   | Emergency/backup Pump -diesel   | 2              | 100                 |  |
|                            |   | Water Ring Main System  | Lot            | 100                 |  |
|                            |   | Valved Fire Water Connections   | Lot            |                     |  |
|                            |   | Wet System Sprinklers   | Lot            |                     |  |
|                            |   | CO2 systems   | Lot            |                     |  |
| 30                         | Fuel Supply and Storage   | Direct Charges Table  |                | 5000 m2 mmb         |  |
| 31                         | Deser Handling & Stolage (Common)   | Diesen Skolage Talliks  | ~              | beed ins each       | baseload ( 100% GT capacity)                             |
|                            |   | Fuel Metering   | 2              | 100                 | Electric bestern   |
|                            |   | Interconnecting piping and piping to gas turbine<br>Fuel Supply to Diesel Generator | Lot            | 100                 | LIGUR HOURS  |
|                            |   | Fuel Forwarding Pumps   | 4              | 100                 |  |
| 32                         | Biofuel   | Fuel Offloading Pumps<br>Biofuel Storage Tank                                       | 2              | 100<br>5600 m3 each | 7 days storage for 4 GT.                                 |
|                            |   | Fuel Metering<br>Interconnecting piping and piping to gas turbine                   | 2<br>Lot       |                     |  |
|                            |   | Fuel Pumps Fuel offloading Pumps  | 4              | 100                 |  |
| 40                         | Miscellaneous Equipment & Systems<br>Workshop Equipment and Tools         |   | Lot            |                     |  |
|                            | Laboratory and Test Equipment   |   | Lot            |                     |  |
| 50                         | Environmental (Emissions) Control Systems (per Unit)                      |   |                |                     |  |
|                            | commous Emission Monitoring (Unit)  | one system for each flue  | 2              |                     |  |
| 60                         | Electrical Power Systems  | Main 11/240 W/ Da   | <u> </u> .     |                     |  |
| 01                         | www.wainerover.output System (per Unit)                                   | Generator Isolated-phase Bus System   | Lot            |                     |  |
|                            |   | Generator Circuit Breakers  | 4              |                     |  |
|                            |   | Grounding System  | Lot            |                     |  |
|                            |   |   |                |                     |  |
| 62                         | Auxiliary Power Supply system   | 11/4 16 kV Unit Auxiliary Transformer   | 4              |                     |  |
| 63                         | Unit/Station Power Supply system  | 4.16/0.6-KV Unit/Station Services Transformer<br>4.16 kV MV switchgear              | 12<br>Lot      |                     |  |
|                            |   | 600 V switchgear  | Lot            |                     |  |
|                            |   | 600 V MCC's   | Lot            |                     |  |
| 64                         | Auxiliary AC Power Distribution (Common)                                  | Emergency Diesel Generator  | 2              |                     |  |
| 65                         | UPS Supply and Distribution (per Unit)<br>DC Supply (Common)              | 110-V, 1 ph, 50 Hz Power Distribution<br>125 VDC Supply and Distribution System     | Lot<br>4       |                     |  |
| 66                         | Cabling Systems   | Power, Control and Instrumentation  | Lot            |                     |  |
| 67                         | Building and Outdoor Electrical Services<br>Grounding grid                | Will be tied into existing plant grid.  | Lot<br>Lot     |                     |  |
| 70                         | Instrumentation and Control   |   |                |                     |  |
| 71 72                      | Central Control System, incl. DCS<br>Power generation & Auxiliaries I&C   |   | Lot            |                     |  |
| 73                         | Common Sevices and equipment I&C  |   | Lot            |                     |  |

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 136 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix G: Cost Estimate

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 137 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix G1: 2 Unit Combustion Turbine – Brownfield

| Simple Cycle Power Plant Project                  |  |                          |            |           |                   | TCU"               |             |  |  |
|---|--|--------------------------|------------|-----------|-------------------|--------------------|-------------|--|--|
| Capital Cost Estimate for Screening Study (FEL-1) |  |                          |            |           |                   |                    |             |  |  |
| Order of Magnitude Cost Estimate Summary - Canada |  |                          |            |           |                   |                    |             |  |  |
| Proje   | Project: Simple Cycle Power Plant                                    |                          |            |           |                   |                    |             |  |  |
| Loca  | Location: Newfoundland and Labrador - Brown Field Site               |                          |            |           |                   |                    |             |  |  |
| Description: Simple Cycle Power Plant             |  |                          |            |           |                   |                    |             |  |  |
| Stud  | Study Option: Two (2) Gas Turbines                                   |                          |            |           |                   |                    |             |  |  |
| Proje   | Project Number: H369039  |                          |            |           |                   |                    |             |  |  |
| Origi   | Originated By: Tia Ghantous  |                          |            |           |                   |                    |             |  |  |
| Cheo  |  | Karım Megnari            |            |           |                   |                    |             |  |  |
| Cum   | ency:  | CAD                      |            |           |                   |                    |             |  |  |
| WBS   | I  | Description              | Material   | Labour    | Constr.<br>Equip. | Sub-<br>Contractor | Total Cost  |  |  |
| 100   | Site and Improvem  | 1,970,504                |            |           | 150,000           | 2,121,000          |             |  |  |
| 200   | Building's, Structur   | es and Foundations Total | 7,184,000  | 3,296,000 | 82,000            | 5,764,000          | 16,326,000  |  |  |
| 300   | Not Used   |                          |            |           |                   |                    |             |  |  |
| 400   | Power Generation   | 66,504,109               | 4,491,270  | 927,360   | 314,116           | 72,237,000         |             |  |  |
| 500   | Electrical Power Systems Total                                       |                          | 14,108,920 | 3,802,133 | 0                 | 102,525            | 18,014,000  |  |  |
| 600   | Instrumentation and  | 4,197,504                | 1,976,101  |           |                   | 6,174,000          |             |  |  |
| 700   | Common Services  | 3,684,530                | 5,618,340  |           | 331,008           | 9,634,000          |             |  |  |
| 750   | Diesel oil, Biofuel, Rawa Water, Fire Water and<br>Demin water tanks |                          | 13,031,628 | 1,932,200 |                   |                    | 14,964,000  |  |  |
| 800   | Construction Mana<br>Indirects                                       | gement Total Inculding   | 987,058    | 9,240,537 | 561,753           | 264,000            | 11,053,000  |  |  |
|   |  |                          |            |           | Total D           | irect Cost         | 150,523,000 |  |  |
| 900   | Engineering and Pi   | roject Managemnet Total  |            |           |                   |                    | 20,952,000  |  |  |
| 1000  | 1000 Misc. Freigtht, Spares, Commisioning etc. (5%)                  |                          |            |           |                   |                    |             |  |  |
| 1100  | Owner's Costs  |                          |            |           |                   |                    |             |  |  |
| 1200  | Bonds and Insuran  | ce (1.4%)                |            |           |                   |                    | 2,401,000   |  |  |
| 1300  | Contingencies 20%  | ,<br>,                   |            |           |                   |                    | 34,775,000  |  |  |
|   | Total Project Cost   |                          |            |           |                   |                    |             |  |  |
|   |  |                          |            |           |                   | Cost /kW           | 2,162       |  |  |

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 139 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix G2: 2 Unit Combustion Turbine – Greenfield

| Simple Cycle Power Plant Project                  |  |                         |            |           |                   |                    |             |  |  |
|---|--|-------------------------|------------|-----------|-------------------|--------------------|-------------|--|--|
| Capital Cost Estimate for Screening Study (FEL-1) |  |                         |            |           |                   |                    |             |  |  |
| Order of Magnitude Cost Estimate Summary - Canada |  |                         |            |           |                   |                    |             |  |  |
| Proje   | Project: Simple Cycle Power Plant                                    |                         |            |           |                   |                    |             |  |  |
| Loca  | Location: Newfoundland and Labrador Green Field Site                 |                         |            |           |                   |                    |             |  |  |
| Desc  | Description: Simple Cycle Power Plant                                |                         |            |           |                   |                    |             |  |  |
| Stud  | Study Option: Two (2) Gas Turbines                                   |                         |            |           |                   |                    |             |  |  |
| Proje   | Project Number: H369039  |                         |            |           |                   |                    |             |  |  |
| Origi   | Originated By: Tia Ghantous  |                         |            |           |                   |                    |             |  |  |
| Cheo  | cked by:   | Karım Meghari           |            |           |                   |                    |             |  |  |
| Curr  | ency:  |                         |            |           |                   |                    |             |  |  |
| WBS   |  | Description             | Material   | Labour    | Constr.<br>Equip. | Sub-<br>Contractor | Total Cost  |  |  |
| 100   | Site and Improvem  | 2,364,605               |            |           | 150,000           | 2,515,000          |             |  |  |
| 200   | Building's, Structur   | 8,060,000               | 3,645,000  | 82,000    | 7,090,000         | 18,877,000         |             |  |  |
| 300   | Not Used   |                         |            |           |                   |                    |             |  |  |
| 400   | Power Generation   | 66,504,109              | 4,491,270  | 927,360   | 314,116           | 72,237,000         |             |  |  |
| 500   | Electrical Power Systems Total                                       |                         | 14,868,553 | 4,152,622 | 0                 | 102,525            | 19,124,000  |  |  |
| 600   | Instrumentation an   | 4,197,504               | 1,976,101  |           |                   | 6,174,000          |             |  |  |
| 700   | Common Services  | 4,345,870               | 5,963,790  |           | 348,458           | 10,658,000         |             |  |  |
| 750   | Diesel oil, Biofuel, Rawa Water, Fire Water and<br>Demin water tanks |                         | 16,298,783 | 2,422,274 |                   |                    | 18,721,000  |  |  |
| 800   | Construction Mana<br>Indirects                                       | gement Total Inculding  | 976,983    | 9,137,957 | 532,445           | 264,000            | 10,911,000  |  |  |
|   |  |                         |            |           | Total D           | irect Cost         | 159,217,000 |  |  |
| 900   | Engineering and P  | roject Managemnet Total |            |           | 10141 2           |                    | 20,778,000  |  |  |
| 1000  | 1000 Misc. Freigtht, Spares, Commisioning etc. (5%)                  |                         |            |           |                   |                    |             |  |  |
| 1100  | Owner's Costs  |                         |            |           |                   |                    |             |  |  |
| 1200  | Bonds and Insuran  | ce (1.4%)               |            |           |                   |                    | 2,520,000   |  |  |
| 1300  | Contingencies 20%  | ,<br>0                  |            |           |                   |                    | 36,503,000  |  |  |
|   | Total Project Cost   |                         |            |           |                   |                    |             |  |  |
|   |  |                         |            |           |                   | Cost /kW           | 2,270       |  |  |

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 141 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix G3: 4 Unit Combustion Turbine – Brownfield
| •    | •   |    |     |
|------|-----|----|-----|
| Page | 142 | of | 163 |

| Simple Cycle Power Plant Project                  |  |                          |              |            |                   |                    |             |  |
|---|--|--------------------------|--------------|------------|-------------------|--------------------|-------------|--|
| Capital Cost Estimate for Screening Study (FEL-1) |  |                          |              |            |                   |                    |             |  |
| Order of Magnitude Cost Estimate Summary - Canada |  |                          |              |            |                   |                    |             |  |
| Proje   | oject: Simple Cycle Power Plant  |                          |              |            |                   |                    |             |  |
| Loca  | tion:  | Newfoundland and Labr    | ador - Brown | Field Site |                   |                    |             |  |
| Desc  | ription:   | Simple Cycle Power Plant | t            |            |                   |                    |             |  |
| Study   | y Option:  | Four (4) Gas Turbines    |              |            |                   |                    |             |  |
| Proje   | ct Number:   | H369039<br>Tio Chantour  |              |            |                   |                    |             |  |
| Chec  | ked by:  | Karim Meghari            |              |            |                   |                    |             |  |
| Curre   | ancy.  | CAD                      |              |            |                   |                    |             |  |
| ound  | ling).   | 0,10                     |              |            |                   |                    |             |  |
| WBS   | L  | Description              | Material     | Labour     | Constr.<br>Equip. | Sub-<br>Contractor | Total Cost  |  |
| 100   | Site and Improvem  | ents Total               | 3,152,806    |            |                   | 150,000            | 3,303,000   |  |
| 200   | Building's, Structur   | es and Foundations Total | 12,519,000   | 5,824,000  | 159,000           | 11,277,000         | 29,779,000  |  |
| 300   | Not Used   |                          |              |            |                   |                    |             |  |
| 400   | Power Generation   | and Auxiliaries Total    | 131,239,032  | 8,350,858  | 3,709,440         | 675,186            | 143,975,000 |  |
| 500   | 00 Electrical Power Systems Total                                      |                          | 19,492,861   | 5,060,063  | 0                 | 185,525            | 24,738,000  |  |
| 600   | 00 Instrumentation and Control Total                                   |                          | 8,370,004    | 2,984,101  |                   |                    | 11,354,000  |  |
| 700   | 0 Common Services Equipment and Systems Total                          |                          | 4,934,073    | 6,110,790  |                   | 365,908            | 11,411,000  |  |
| 750   | Diesel oil, Biofuel, Rawa Water, Fire Water and<br>0 Demin water tanks |                          | 24,930,071   | 3,696,383  |                   |                    | 28,626,000  |  |
| 800   | Construction Mana<br>Indirects   | gement Total Inculding   | 1,192,026    | 11,716,101 | 749,457           | 330,000            | 13,988,000  |  |
|   |  |                          |              |            | Total D           | irect Cost         | 267,174,000 |  |
| 900   | ,<br>200 Engineering and Project Managemnet Total                      |                          |              |            |                   | 30,013,000         |             |  |
| 1000  | 000 Misc. Freigtht, Spares, Commisioning etc. (5%)                     |                          |              |            |                   | 13,359,000         |             |  |
| 1100  | Owner's Costs  |                          |              |            |                   |                    |             |  |
| 1200  | 00 Bonds and Insurance (1.4%)  |                          |              |            |                   | 4,161,000          |             |  |
| 1300  | 00 <i>Contingencies 20%</i> 60,2                                       |                          |              |            |                   |                    | 60,270,000  |  |
|   | Total Project Cost   |                          |              |            |                   | 374,977,000        |             |  |
|   |  |                          |              |            |                   | Cost /kW           | 1,875       |  |

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 143 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix G4: 4 Unit Combustion Turbine – Greenfield

| Page 1 |  |                          |              |            |                   |                    | Page 144 of |
|--------|--|--------------------------|--------------|------------|-------------------|--------------------|-------------|
| Simp   | Simple Cycle Power Plant Project                                     |                          |              |            |                   |                    |             |
| Capit  | Capital Cost Estimate for Screening Study (FEL-1)                    |                          |              |            |                   |                    |             |
|        | Orde   | r of Magnitude Cos       | t Estimat    | te Summ    | nary - C          | anada              |             |
| Proje  | ect:   | Simple Cycle Power Plant | i            |            |                   |                    |             |
| Loca   | tion:  | Newfoundland and Labr    | ador - Green | Field Site |                   |                    |             |
| Desc   | ription:   | Simple Cycle Power Plant | 1            |            |                   |                    |             |
| Stud   | y Option:  | Four (4) Gas Turbines    |              |            |                   |                    |             |
| Proje  | ⊧ct Number:  | H369039                  |              |            |                   |                    |             |
| Origi  | nated By:  | Tia Ghantous             |              |            |                   |                    |             |
| Chec   | ked by:  | Karım Megharı            |              |            |                   |                    |             |
| Curre  | ency:  | CAD                      |              |            |                   |                    |             |
| WBS    | [  | Description              | Material     | Labour     | Constr.<br>Equip. | Sub-<br>Contractor | Total Cost  |
| 100    | Site and Improvem  | ents Total               | 3,546,907    |            |                   | 150,000            | 3,697,000   |
| 200    | Building's, Structures and Foundations Total                         |                          | 13,395,000   | 6,173,000  | 159,000           | 12,602,000         | 32,329,000  |
| 300    | Not Used   |                          |              |            |                   |                    |             |
| 400    | Power Generation a   | and Auxiliaries Total    | 131,239,032  | 8,350,858  | 3,709,440         | 675,186            | 143,975,000 |
| 500    | Electrical Power Sy  | rstems Total             | 20,699,355   | 5,653,023  | 0                 | 185,525            | 26,538,000  |
| 600    | Instrumentation and Control Total                                    |                          | 8,370,004    | 2,984,101  |                   |                    | 11,354,000  |
| 700    | Common Services Equipment and Systems Total                          |                          | 5,261,573    | 6,467,790  |                   | 365,908            | 12,095,000  |
| 750    | Diesel oil, Biofuel, Rawa Water, Fire Water and<br>Demin water tanks |                          | 28,055,364   | 4,165,039  |                   |                    | 32,220,000  |
| 800    | Construction Mana<br>Indirects                                       | gement Total Inculding   | 1,203,399    | 11,831,898 | 782,542           | 330,000            | 14,148,000  |
|        | <b></b>  |                          |              |            |                   | L                  |             |

Com Dies Dem Cons Indir Total Direct Cost 276,356,000 900 Engineering and Project Managemnet Total 30,737,000 13,818,000 1000 Misc. Freight, Spares, Commisioning etc. (5%) 1100 Owner's Costs 1200 Bonds and Insurance (1.4%) 4,299,000 62.278.000 1300 Contingencies 20%

| 1000 |                    | 02,270,000  |
|------|--------------------|-------------|
|      | Total Project Cost | 387,488,000 |
|      | Cost /kW           | 1,937       |
|      | -                  |             |

163

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 145 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix H: Specification Sheet

Newfoundland and Labrador Hydro - Combustion Turbine Screening

### **Gas Turbine Generator – Specification Sheet**

### Introduction

This scope of work describes the minimum requirements for the design, fabrication, assembly and testing of two aeroderivative gas turbine generators with a nominal output of 130MW, with less than 10 min start up time.

The turbines shall be able to run on liquid biofuel, demonstrated experience and reference(s) is a must.

Winterization and power augmentation packages should be included in proposal.

The turbines will be operating as a peaking plant with estimated 500 hours of operation a year with a capability to operate as a synchronous condenser.

#### Scope of supply is as follows:

Multistage axial flow compressor Specify unit start up time Fuel System Inlet and exhaust plenum Gearbox (if required) Coupling(s) and coupling guards. Vibration sensors Thermocouples for measuring critical turbine temperatures Turbine inlet air system with self-cleaning filter, silencers, expansion joints, ducts, structural support, and instrumentation Turbine exhaust system with exhaust silencers, expansion joints, ducts, and instrumentation Structural steel assembly Fire Protection system Air cooled generator, open ventilated complete with generator enclosure Stator winding with class F insulation Cylindrical forged steel rotor with class F insulation Class B temperature rises rotor/stator Generator cooling system Lubrication system integral with the gas turbine lubrication system Stainless steel gauges and switches Bearing lube oil vapor extraction Generator stator heater Generator grounding system Turbine generator supervisory system Turbine control panels Generator protective relays Automatic voltage regulator

Newfoundland and Labrador Hydro - Combustion Turbine Screening

### General Design Data for estimated performance

| Site:                | Newfoundland and Labrador |
|----------------------|---------------------------|
| Location:            | Indoors                   |
| Air Quality:         | Good (no particulate)     |
| Elevation:           | 152m                      |
| Ambient Temperature: | 15°C min/20°C max         |
| Relative humidity:   | 60%                       |

Fuel: Diesel no 2

### **NOx Emissions Requirements:**

| Fuel Type | Compliance Limit<br>(ppm)   | Performance Target<br>(ppm) |
|-----------|---|-----------------------------|
| Diesel    | Canadian Environmental<br>Protection Act: guidelines,<br>objectives and codes of practice | 38                          |

### Information Required with Quotation

The following information shall be supplied with the Quotation:

- Equipment Scope Description
- Vendor standard data sheet with performance and design data, material selections, etc.
- Preliminary Equipment arrangement drawings, including dimensions
- Emission guarantees
- Weight of equipment
- Manufacturing and delivery schedule
- Vendor shall include a priced list of recommended spare parts for start-up and initial operation of the equipment and a priced list of spare parts for two-years of normal operation in the proposal.

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 148 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix I: GTG Comparison Sheet

Newfoundland and Labrador Hydro- Combustion Turbine Screening

|  | Company Name              |                                      |                           |  |
|--|---------------------------|--------------------------------------|---------------------------|--|
|  | GE- LM6000 PC             | Siemens – SGT800                     | MHI – FT4000              |  |
| Equipment Cost (1 unit)<br>(CAD)                                 | \$34,078,995              | \$24,903,100                         | \$34,738,580              |  |
| Unit Delivery  | 14 months for 1 unit      | 17 months from<br>Sweden             | Q4 2022                   |  |
| Synchronous<br>Condenser   | yes                       | yes                                  | yes                       |  |
| NOx Emission   | 42 ppm                    | <74 ppmvd                            | 42 ppm                    |  |
| Fuel Capability Diesel, Biodiesel,<br>Ethanol, Hydrogen<br>(35%) |                           | Hydrogen (75%),<br>Biodiesel, Diesel | Diesel                    |  |
| Water Injection  | Yes                       | No                                   | No                        |  |
| Power Augmentation   | Sprint                    | No                                   | Wet compression           |  |
| Cost of Delivery   | Included                  | Not Provided                         | Not Provided              |  |
| 10 min fast start<br>capability                                  | Yes                       | No                                   | Yes                       |  |
| Technology   | Aeroderivative<br>Turbine | Industrial Turbine                   | Aeroderivative<br>Turbine |  |

### **GTG Evaluation Sheet- Vendor feedback**

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 150 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix J: Experience List

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 151 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix J1: GE – LM6000

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 152 of 163



| 2000 |         | nib commu  | 21110000 |             |                | - |
|------|---------|------------|----------|-------------|----------------|---|
| 1998 | TURKEY  | INDUSTRIAL | LM6000   | GAS/NATURAL | NAPHTHA        | 1 |
| 1998 | TURKEY  | IPP        | LM6000   | GAS/NATURAL | NAPHTHA        | 2 |
| 1998 | TURKEY  | INDUSTRIAL | LM6000   | GAS/NATURAL | NAPHTHA        | 1 |
| 1999 | INDIA   | IPP        | LM6000PC | NAPHTHA     | OIL/DISTILLATE | 4 |
| 2000 | INDIA   | IPP        | LM6000PC | NAPHTHA     | OIL/DISTILLATE | 1 |
| 2000 | BRAZIL  | IPP        | LM6000PC | GAS/NATURAL | BIOMASS        | 1 |
| 2004 | USA     | UTILITY    | LM6000PC | NAPHTHA     |                | 1 |
| 2015 | REUNION | IPP        | LM6000PC | ETHANOL     | OIL/DIESEL     | 1 |

TOTAL

20

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 153 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix J2: Siemens – SGT-800



# Green back up power plant

Customer: Stockholm Exergi AB

Country: Sweden

Commercial operation: 2023

March 2022

# Reference Stockholm Exergi, Sweden

### Challenge

- Security of supply is increasingly important with fluctuating renewables and insufficient transmission capability
- Need of fast starting dispatchable power with black start capability securing electricity to the city of Stockholm at all times
  Stockholm Evending to herome
  - Stockholm Exergi is targeting to become climate positive in their operations latest by 2025

## Solution

- The new simple cycle back-up gas turbine power plant will provide emergency power to the city of Stockholm
- The plant will be operated on liquid green biodiesel, enabling Stockholm Exergi to reach their target of becoming climate positive by 2025



{Č}}

- 1 x SGT-800 gas turbine
- Black start diesel generator
  - PCS 7 control system
- Installation and commissioning



SE GP G IGT PPM GFI 27 Unrestricted © Siemens Energy, 2022

### PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 154 of 163

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 155 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

Appendix K: 3D Model

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 156 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix K1: 2 Unit Combustion Turbine – Brownfield

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 157 of 163



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 158 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix K2: 2 Unit Combustion Turbine – Greenfield

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 159 of 163



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 160 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix K3: 4 Unit Combustion Turbine – Brownfield

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 161 of 163



PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 162 of 163



Newfoundland and Labrador Hydro - Combustion Turbine Screening Final Study Report - October 28, 2022

### Appendix K4: 4 Unit Combustion Turbine – Greenfield

PUB-NLH-288, Attachment 5 Reliability and Resource Adequacy Study Review Page 163 of 163

