

Newfoundland and Labrador Hydro Hydro Place. 500 Columbus Drive P.O. Box 12400. St. John's. NL Canada A1B 4K7 t. 709.737.1400 I f. 709.737.1800 nlhydro.com

December 10, 2025

Board of Commissioners of Public Utilities Prince Charles Building 120 Torbay Road, P.O. Box 21040 St. John's, NL A1A 5B2

Attention: Jo-Anne Galarneau

**Executive Director and Board Secretary** 

Re: Reliability and Resource Adequacy Study Review – 2025–2026 Winter Readiness Planning Report – Final Report

Further to correspondence received from the Board of Commissioners of Public Utilities ("Board") on October 13, 2016 directing Newfoundland and Labrador Hydro ("Hydro") to provide an annual report detailing its winter readiness planning, and correspondence received on March 5, 2020 requesting additional detail, please find enclosed Hydro's 2025–2026 Winter Readiness Planning Report – Final Report.

Should you have any questions, please contact the undersigned.

Yours truly,

**NEWFOUNDLAND AND LABRADOR HYDRO** 

Shirley A. Walsh

Senior Legal Counsel, Regulatory

SAW/rr

Encl.

ecc:

Board of Commissioners of Public Utilities

Jacqui H. Glynn Ryan Oake Board General

**Island Industrial Customer Group** 

Paul L. Coxworthy, Stewart McKelvey Denis J. Fleming, Cox & Palmer Glen G. Seaborn, Poole Althouse **Labrador Interconnected Group** 

Senwung F. Luk, Olthuis Kleer Townshend LLP Nicholas E. Kennedy, Olthuis Kleer Townshend LLP

**Consumer Advocate** 

Dennis M. Browne, KC, Browne Fitzgerald Morgan & Avis Stephen F. Fitzgerald, KC, Browne Fitzgerald Morgan & Avis Sarah G. Fitzgerald, Browne Fitzgerald Morgan & Avis Bernice Bailey, Browne Fitzgerald Morgan & Avis **Newfoundland Power Inc.**Dominic J. Foley

Douglas W. Wright Regulatory Email

# 2025–2026 Winter Readiness Planning Report

December 10, 2025

A report to the Board of Commissioners of Public Utilities



# **Executive Summary**

1

- 2 Newfoundland and Labrador Hydro ("Hydro") closely monitors its supply-related assets and is confident
- 3 in its ability to service customers during the 2025–2026 winter season. Each year, Hydro completes
- 4 extensive winter readiness ("WR") activities across its network of assets. This requires detailed
- 5 scheduling and coordination from across all teams and sites to ensure safe completion of all tasks. These
- 6 activities are primarily completed. While a small number of winter readiness activities remain, these
- 7 outstanding activities are considered low risk. Hydro is confident in its ability to provide reliable service
- 8 to its customers, as well as those of Newfoundland Power Inc., throughout this winter season.
- 9 Hydro's regulated generating sources were available by December 1, 2025, with the exception of Unit 3
- 10 at the Holyrood Thermal Generating Station ("Holyrood TGS"), and Bay d'Espoir Units 1 and 2. Holyrood
- 11 TGS Unit 3 is undergoing major overhaul of the steam turbine and valves, and Hydro has worked with
- the contractor to expedite its return to service date to late-January 2026. Bay d'Espoir Units 2 and 1 are
- expected to return to service on December 22 and January 12, respectively, upon the conclusion of the
- 14 Penstock 1 Life Extension Project. Hydro will continue to monitor progress and mitigate work execution
- and operational risks. In advance of the return to service of these units, Hydro has sufficient generation
- 16 reserves and appropriate plans in place to mitigate any risk to the system. The system is well positioned
- to meet the needs of all customers for the 2025–2026 winter season.
- 18 The Labrador-Island Link ("LIL") continues to reliably support the Island Interconnected System,
- delivering both capacity and energy to meet system needs, and will be available for bipole operation up
- to 700 MW this winter. Subject to the completion of high-power testing, the LIL will be able to be
- 21 operated up to 900 MW as system conditions permit. Hydro has determined that the high-power test of
- 22 the LIL will be postponed until later in the winter as a result of its continued focus on WR activities and
- 23 prioritization of reliable service to customers during the winter period, including supporting reservoir
- 24 levels to meet peak load requirements.
- 25 Although Hydro has identified risks as outlined in this report, it is important to note that the
- 26 identification of risks is a normal and important piece of Hydro's comprehensive planning and
- 27 preparedness processes. These processes help to ensure reliable operation during our winter operating
- 28 seasons.
- 29 Hydro continues to track the remaining work activities and will provide an update to the Board in
- 30 January 2026, at which time it expects that the majority of the remaining activities will be complete.



- 1 Hydro remains focused on the completion of the final activities of its annual maintenance program to
- 2 ensure the reliability of its existing assets and infrastructure throughout the 2025–2026 winter operating
- 3 season.



# **Contents**

Exe	cutive	e Summary	•••••	
1.0	In	ntroduction	1	
2.0	Holyrood Thermal Generating Station			
2	.1	Annual Work Plan and Winter Readiness Status	3	
2	.2	Critical Spares	ε	
2	.3	Plant and Equipment Testing	7	
2	.4	Risk and Risk Mitigation	8	
	2.4.	1 Unit 3 Turbine and Valves Overhaul	9	
	2.4.	2 Unit Boiler Tubes	9	
	2.4.	3 High Pressure Feedwater Heaters	10	
	2.4.	4 Unit 1 Turbine Control Valve	11	
	2.4.	5 Fuel Oil Contamination Storage Tank 3	11	
	2.4.	6 Cooling Water Sump Structures	12	
	2.4.	7 Fuel Oil Storage Tank 1	13	
	2.4.	8 Flame Scanners	13	
3.0	C	ombustion Turbine Generation	14	
3	.1	Annual Work Plan and Winter Readiness Status	14	
3	.2	Critical Spares	16	
3	.3	Plant and Equipment Testing	17	
3	.4	Risk and Risk Mitigation	17	
	3.4.	1 Hardwoods Gas Turbine – Spare Engine Overhaul	17	
4.0	Н	lydraulic Generation	18	
4	.1	Annual Work Plan and Winter Readiness Status	18	
4	.2	Critical Spares	21	
4	.3	Plant and Equipment Testing	21	
4	.4	Risk and Risk Mitigation	22	
	4.4.	1 Bay d'Espoir Penstocks	22	
	4.4.	2 Hinds Lake Unit Vibration and Shaft Seal Leakage	23	
5.0	M	Лuskrat Falls Assets	23	
5	.1	Annual Work Plan and Winter Readiness Status	23	
5	.2	Critical Spares	25	



5.3 Plai	nt and Equipment Testing	26
5.4 Risl	and Risk Mitigation	26
5.4.1	Muskrat Falls Unit 1 Intake – Concrete Spalling	26
5.4.2	Optical Ground Wires Tower Peak and Top Plate Design	27
5.4.3	Electrode Conductors	27
5.4.4	DCCT Cold Weather Operation	28
5.4.5	Cable Switching	28
5.4.6	Synchronous Condenser Brush Gear Assemblies	29
6.0 Transı	mission and Terminal Stations	30
6.1 Anr	nual Work Plan and Winter Readiness Status	30
6.2 Plai	nt and Equipment Testing	32
6.3 Risl	and Risk Mitigation	33
6.3.1	Generator Step-Up Transformer Spares	33
6.3.2	Western Avalon Terminal Station – Replace Bushing Connecting the Gas Insulated Switchgear to Transmission Line TL267	33
6.3.1	Deer Lake Terminal Station – Refurbish T1 Tap Changer	34
7.0 Opera	tional Technology	34
7.1 Anr	nual Work Plan and Winter Readiness Status	34
7.2 Plai	nt and Equipment Testing	35
8.0 Status	of Winter Readiness for Capital Projects and Programs	35
9.0 Syster	n Energy Capability	37
10.0 Concl	usion	40

# **List of Appendices**

- Appendix A: Status of Capital Projects and Programs Related to Winter Readiness
- Appendix B: Generation Outage Schedule
- Appendix C: Critical Spares Status Listing for Thermal Generation
- Appendix D: Status of Winter Readiness Testing of Plant and Equipment for Thermal Generation
- Appendix E: Status of Winter Readiness Testing of Plant and Equipment for Hydraulic Generation
- Appendix F: Critical Spares Status Listing for Muskrat Falls Generation
- Appendix G: Status of Winter Readiness Testing of Plant and Equipment for Muskrat Falls Generation



## 1.0 Introduction

1

5

6 7

8

9

10

11

12

13

14

15

16

17

18 19

- 2 In 2016, the Board of Commissioners of Public Utilities ("Board") directed Hydro to provide an annual
- 3 report detailing its WR planning. This report, for the 2025–2026 winter season, addresses the following
- 4 items as requested by the Board:
  - The status of annual work plan items, for Hydro's generating plant and transmission and terminal stations, including the completion to date, outstanding items to complete, and any risks to completion or as a result of failure to complete.
  - A description and schedule for all outstanding [2025] capital projects for Hydro's generating plant and transmission and terminal stations, including progress on completion status to date and expected completion date.
  - Identification of all equipment and plant testing to be carried out in advance of the winter period (generation plant, emergency diesels, black start generators, fire systems, transmission system equipment), including progress on completion status to date.
  - The planned generation outage schedule for the period September 1 to
     December 31, [2025], including an explanation for any planned outages extending beyond
     December 1, [2025].<sup>2</sup>
  - An update of critical spares assessment and procurement.
  - Identification of any risks that could impact the winter readiness of assets as of December 1,
     [2025] and associated contingency plans.<sup>3</sup>

<sup>&</sup>lt;sup>3</sup> "Request to Hydro to file Winter Readiness Planning 2016-2017," Board of Commissioners of Public Utilities, September 13, 2016.



newfoundland labrador

<sup>&</sup>lt;sup>1</sup> "Investigation and Hearing into Supply Issues and Power Outages on the Island Interconnected System – Directions further to the Board's Phase One Report," Board of Commissioners of Public Utilities, October 13, 2016, p. 2, item iii.

<sup>&</sup>lt;sup>2</sup> In previous years, Hydro's WR report included a Near-Term Reliability and Resource Adequacy section. The Board approved the removal of the duplicate information in "Newfoundland and Labrador Hydro - Reliability and Resource Adequacy Study Review – Schedule for Future Updates," Board of Commissioners of Public Utilities, August 17, 2023. The information has been provided in the "Reliability and Resource Adequacy Study Review – 2024 Near-Term Reliability Report," Newfoundland and Labrador Hydro, November 20, 2024.

- 1 Hydro's Annual Work Plan ("AWP") integrates all planned activities for the year (i.e., corrective
- 2 maintenance ("CM"), preventive maintenance ("PM"), and capital project support) that are critical to
- 3 the safe and reliable production and transmission of electricity. Hydro regularly measures the progress
- 4 of its AWP execution in comparison with the plan, and is able to track the AWP status down to the level
- 5 of individual work plan items. The individual AWPs for various assets are incorporated into an integrated
- 6 AWP. While some AWP activities are planned for completion through December 2025, those tagged as
- WR activities are generally planned for completion by December 1, 2025.
- 8 To ensure WR, Hydro follows a structured checklist for planning and documenting its testing and
- 9 inspection of plant and equipment in its thermal and hydroelectric generation facilities.
- 10 In its transmission, terminal station, operational technology, and combustion turbine ("CT") operations,
- 11 Hydro relies on its AWP process to plan and track its WR testing and inspection of these assets. The
- 12 AWPs in these areas include planned PM activities and CM items, both of which involve inspection and
- testing. Planned PMs and CMs, and any other activities pertaining to WR, are flagged inside the
- 14 respective AWPs and may be tracked separately from other AWP items that are not WR related.
- 15 Except where otherwise noted, information presented in this report covers both the Island
- 16 Interconnected System and the Labrador Interconnected System for the period ending December
- 17 1, 2025. This report is organized by operating area (i.e., Holyrood TGS, CT Generation, Hydraulic
- 18 Generation, Muskrat Falls Assets, Transmission and Rural Operations, and Operational Technology), and
- 19 WR activities for each operating area are discussed in Sections 2.0 through 7.0 and relevant appendices,
- which contain applicable information on:
  - Annual Work Plan and Winter Readiness Status: This report provides a consolidated summary
    of operation and maintenance progress, both for the entire AWP and the WR tasks for each
    area. Each status chart includes the completed and remaining operations and maintenance AWP
- 24 and WR tasks, as well as an indication of the planned task completion target to date.4
  - **Critical Spares:** An update on the status of Hydro's critical spares for the 2025–2026 winter season is provided in this report. Items are categorized as In Stock, Non-Stock or Procurement

<sup>&</sup>lt;sup>4</sup> AWP and WR task completion target is 90% and 99.5%, respectively.



21

22

23

25

26

- Ongoing. In Stock status indicates the part is in inventory. Non-stock status is used when parts are critical but not necessary to keep in stock (e.g., because the part is readily available locally). Procurement Ongoing status indicates the part is required to be in stock but is not, and is at a varying stage of the procurement process.<sup>5</sup> This report includes an update on the status of the critical spares for each operating area, with a detailed listing of critical spares with status of Procurement Ongoing.<sup>6</sup>
  - Plant and Equipment Testing: Discussion of equipment and plant testing to be carried out in advance of the winter period, including structured checklist for planning and documenting its testing and inspection of plant and equipment in its thermal and hydroelectric generation facilities.
  - Risk and Risk Mitigation: Discussion of items influencing WR and/or reliable operations.
- 12 In line with Board direction, Hydro also provides an update on its capital programs and projects
- 13 impacting WR in Section 8.0 and Appendix A. As reflected throughout this report, a number of
- 14 generating unit annual maintenance programs have been completed across the fleet and Hydro plans to
- complete annual maintenance on all of its regulated generating assets in advance of the winter season,
- 16 with the exception of Holyrood TGS Unit 3 and Bay d'Espoir Units 1 and 2. The Generation Outage
- 17 Schedule for September 1 to December 31, 2025 is provided as Appendix B.

# 2.0 Holyrood Thermal Generating Station

#### 2.1 Annual Work Plan and Winter Readiness Status

- 20 The status of AWP and WR execution at the Holyrood TGS is summarized in the following charts,
- 21 including:

1 2

3

4

5

6

7 8

9

10

11

18

19


22

- Units 1, 2, and 3; and
- o Balance of Plant, including black start diesels.

<sup>&</sup>lt;sup>6</sup> A detailed listing of all critical spares for each area of generation operations are provided within Appendices C, E, F and G of "Reliability and Resource Adequacy Study Review – 2025–2026 Winter Readiness Planning Report," Newfoundland and Labrador Hydro, October 14, 2025. ("October WR Report").



<sup>&</sup>lt;sup>5</sup> Hydro utilizes a number of its spare parts to address deficiencies found during the maintenance season; as such, fall maintenance outages may result in the requirement to replenish additional spare components.




#### **Holyrood TGS Unit 1**

#### **Forecast Completion Status:**

#### Target Achieved by December 2, 2025

#### **Comments and Schedule Notables:**

- Overall AWP completion status is 98.0% to date.
- WR status is 100.0% complete for 2025.<sup>7</sup>
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.



#### **Holyrood TGS Unit 2**

#### **Forecast Completion Status:**


#### **Target Achieved**


#### **Comments and Schedule Notables:**

- Overall AWP completion status is 99.2% to date.
- WR status is 100.0% complete for 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.

<sup>&</sup>lt;sup>7</sup> WR status is 100.0% as of December 2, 2025; two outstanding activities related to reheater safety valve testing were completed on that date, as system conditions allowed.








#### **Holyrood TGS Unit 3**

#### **Forecast Completion Status:**

On Target for Completion by Return to Service Comments and Schedule Notables:

- Overall AWP completion status is 79.3% to date.
- WR status is 76.6% complete for 2025.
- Unit 3 is scheduled to come online upon completion of its annual maintenance outage on January 31, 2026.
- All remaining activities are scheduled to be completed prior to the unit being returned to service.



# Holyrood Balance of Plant WR Activities Completed Remaining Planned to Date # of WR Activities

#### **Holyrood Balance of Plant**

#### **Forecast Completion Status:**

On Target for Completion by December 10, 2025 Comments and Schedule Notables:

- Overall AWP completion status is 92.7% to date.
- WR status is 96.6% complete for 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.



#### 2.2 Critical Spares

1

2 The status of critical spares for the Holyrood TGS is provided in Table 1.

**Table 1: Critical Spares for Thermal Generation** 

Status	Quantity
In Stock	732
Non-Stock	17
Procurement Ongoing	26
Total	775

- 3 There are 26 critical spare stock items currently with procurement ongoing, which are detailed in
- 4 Appendix C. Three items have purchase orders issued; one item is now expected to be delivered January
- 5 7, 2026 as a result of supplier delays due to material availability. Risk of failure of this component while
- 6 in service is low. These couplings are typically replaced during annual outages following an inspection by
- 7 the boiler service provider. One item is expected to be delivered in March 2026; this item is a boiler feed
- 8 pump ("BFP") recirculation valve which was just replaced on Unit 2. Replacement of these valves are
- 9 very rare, therefore Hydro considers the risk to WR to be low. Shipping date of the third item is pending,
- as quality control issues have resulted in re-manufacturing of the part. This item is being expedited. Risk
- 11 of failure of this component while in service is low, and measurements can be taken manually in the
- 12 event of failure.

14

- 13 Two items have been sent to third-party vendors for refurbishment; one item is now expected to be
  - delivered December 17, 2025 due to additional work required. Risk of failure of this component while in
- 15 service is low. The spare volute was installed during the regular BFP overhaul to reduce the outage
- duration. Refurishment of the spare componment for return to inventory is normal, and does not
- 17 present a considerable risk. The remaining item was determined to be unrepairable, and now requires
- 18 replacement. A quote for this item is in progress, and delivery date remains to be determined. Due to
- 19 the extended outage of HRD Unit 3, there is no risk of not having a spare motor at this time.
- 20 The remaining 21 items were recently consumed during the Overhaul Unit 3 Turbine and Valves
- 21 program. A purchase order has been issued to the original equipment manufacturer ("OEM") for these
- 22 21 items, all of which are expected to be delivered by July 2026. As these outstanding items are typically
- used during outages only, Hydro considers the risk to WR to be low.



#### 2.3 Plant and Equipment Testing

1

- 2 WR testing of generating equipment in thermal generation is focused primarily around annual unit
- 3 maintenance outages. Following these annual outages, units are run up and synchronized and all
- 4 systems are verified before the unit's operating status is determined and preparedness is confirmed.
- 5 Unit load tests are performed at this time as well; however, all required load testing is not completed
- 6 until later in the fall when system conditions allow. The WR testing protocol includes the testing of
- 7 appropriate Balance of Plant components, including the black start diesel generators. 8 The current
- 8 status of equipment/plant testing for thermal generation is indicated in Appendix D.
- 9 Unit 1 returned to service in mid-September 2025 after completion of its annual maintenance outage.
- 10 The majority of the start-up checks for Unit 1 have been completed, as reflected in Appendix D. Soon
- after the unit returned to service, an issue was discovered with the turbine control valves, restricting the
- 12 unit to 100 MW. Correction of this issue required a brief unit outage, which began November 24, 2025
- as system conditions permitted, and concluded on November 27, 2025. Outstanding load testing, online
- safety valve testing, and confirmation of turbine control valve operation was completed by December 2,
- 15 2025. During load testing on Unit 1, a maximum load of 163 MW was reached, limited by condenser
- 16 back pressure. Investigation into this issue is ongoing. Additionally, the Bowser Oil Conditioner is not yet
- in service on Unit 1. Work is ongoing to return the conditioner to service after the completion of annual
- maintenance, which is expected in mid-December 2025. Until the return to service of the conditioner,
- risk to lube oil condition is low due to an external filter cart in the lube oil system. High pressure ("HP")
- 20 feedwater heaters Number 4 and 5 are not available for service this year due to the failure of Heater
- Number 4. Heater Number 6 will remain in service. This will not impact the ability of the unit to operate
- 22 reliably at full load for this winter.
- 23 Unit 2 returned to service in mid-October 2025 following the conclusion of its annual maintenance
- 24 outage. All start-up checks for Unit 2 were completed upon return to service of the unit, as indicated in
- 25 Appendix D, with the exception of the Bowser Oil Conditioner. Work is ongoing to return the conditioner
- to service after the completion of annual maintenance, which is expected in mid-December 2025. Until

<sup>&</sup>lt;sup>8</sup> The black start diesel generators are run up to speed and synchronized on a weekly basis to confirm their availability. The function of all associated breakers are also tested and confirmed.



- 1 the return to service of the conditioner, risk to lube oil condition is low due to an external filter cart in
- the lube oil system. All HP feedwater heaters are expected to be in service for Unit 2 for this winter.
- 3 Unit 3's return to service is expected in late-January 2026 due to the additional work required during the
- 4 Overhaul Unit 3 Turbine and Valves Program, and failure of the turbine hall crane at the Holyrood TGS.
- 5 As indicated in Appendix D, the majority of start-up checks on Unit 3 have not been completed due to
- 6 the ongoing outage. The start-up checks will commence in preparation to return the unit to service, with
- 7 the remainder completed when the unit is started up for system generation needs. HP feedwater heater
- 8 Number 6 on Unit 3 will not be available for service this year due to failure. Heaters Number 4 and 5 are
- 9 expected to be in service. The unit is expected to be available for full load when returned to service.

#### 2.4 Risk and Risk Mitigation

10

- 11 In accordance with capacity requirements as specified by Hydro in its 2024 Resource Adequacy Plan,<sup>9</sup>
- 12 Hydro has recommended that all three Holyrood TGS units remain available through the "Bridging
- 13 Period"<sup>10</sup> while Hydro seeks to develop new long-term sources of supply.
- 14 In 2021, Hatch Ltd. ("Hatch") completed its Life Extension Condition Assessment Study ("LECA"), 11
- including a capital plan to support the standby operation of the Holyrood TGS to 2030. In 2024, Hatch
- 16 completed a refresh to their capital plan, which also considered operations to 2035 to inform the capital
- 17 costs of operating beyond 2030, should this be required.<sup>12</sup> It is recognized that increased age can result
- in an increased risk of in-service failures. Hydro mitigates this risk through regular overhaul programs on
- major components, increased condition assessment work, and a robust critical spares program.
- 20 Hydro anticipates that Units 1 and 2 at the Holyrood TGS will be fully available for the winter period.
- 21 Unit 3 is undergoing major overhaul of the steam turbine and valves, and is expected return to service in

<sup>&</sup>lt;sup>12</sup> "Reliability and Resource Adequacy Study Review – Holyrood Thermal Generating Station Capital Plan Refresh," Newfoundland and Labrador Hydro, March 7, 2025, att. 1.



newfoundland labrador

<sup>&</sup>lt;sup>9</sup> "2024 Resource Adequacy Plan – An Update to the Reliability and Resource Adequacy Study," Newfoundland and Labrador Hydro, rev. August 26, 2024 (originally filed July 9, 2024).

<sup>&</sup>lt;sup>10</sup> Hydro considers the Bridging Period to be from the present to 2030, or until such time that sufficient alternative generation is commissioned, adequate performance of the LIL is proven, and generation reserves are met. During the Bridging Period, the system would rely primarily on existing sources of generation capacity to maintain reliability while new generation capacity is being built. The primary, readily available supply options in this period are extending the retirements of the Holyrood TGS, Stephenville GT and the Hardwoods GT until their capacities can be adequately replaced.

<sup>&</sup>lt;sup>11</sup> "Reliability and Resource Adequacy Study Review – Assessment to Determine the Potential Long-Term Viability of the Holyrood Thermal Generating Station," Newfoundland and Labrador Hydro, March 31, 2022, att. 2.

- 1 late-January 2026. Items influencing WR and/or reliable operations are identified in the sections that
- 2 follow.

3

#### 2.4.1 Unit 3 Turbine and Valves Overhaul

- 4 The WR scope in this program is to clean, inspect, test, and refurbish or overhaul as required the turbine
- 5 and turbine valves for Unit 3 at the Holyrood TGS. The planned inspection and overhaul of the turbine
- 6 valves is substantially complete, with final commissioning to occur during the start up and return to
- 7 service of Unit 3.
- 8 The planned turbine inspection has been completed and overhaul and reassembly work is in progress.
- 9 During the project discovery phase, damage was discovered on a turbine rotor diaphragm that required
- 10 additional time to refurbish at the OEM facility. The diaphragm refurbishment work is complete and the
- 11 component has been returned to the Holyrood TGS. Installation of this component in the lower turbine
- 12 casing has now been completed, but this unplanned refurbishment delayed the expected return to
- service of Unit 3.
- 14 Failure of the turbine hall overhead crane at the Holyrood TGS, which is required to reassemble the
- turbine, resulted in further delays in the expected return to service of the unit. Engineering of the repair
- and procurement of the necessary materials is complete, and the crane returned to service in early
- 17 November 2025. On December 3, 2025 a grinding noise within the crane was identified and crane
- operations were suspended. The crane was repaired and returned to service on December 8, 2025.
- 19 Hydro continues to work with the contractor to expedite the return to service date of Unit 3. The new
- return to service date for Unit 3 is January 31, 2026.
- 21 Hydro continues to track this risk and will provide an update to the Board in January 2026.

#### 22 2.4.2 Unit Boiler Tubes

- 23 Each of the three thermal generating units at the Holyrood TGS has a boiler that contains tubes, the
- failure of which are a common issue in thermal power plants.<sup>13</sup> To mitigate the possibility of tube
- 25 failures, Hydro conducts a thorough annual tube inspection and test program, which was executed

<sup>&</sup>lt;sup>13</sup> Boiler tube failures are a common issue in thermal power plants due to the inherent design, which requires relatively thin walls for heat transfer to be subjected to high temperatures and stresses.



- during the 2025 annual outage season, and is scheduled to reoccur in 2026. Hydro has determined that
- 2 the boiler tube sections as a whole are in good condition; however, tube failures continue to pose a risk.
- 3 Hydro maintains a thorough selection of spare tube material and a contract with an experienced boiler
- 4 contractor for the provision of emergency repairs in the event of tube failures.

#### 2.4.3 High Pressure Feedwater Heaters

- 6 In recent years, Hydro has experienced increasing difficulty in operating the HP feedwater heaters, with
- 7 the majority of the heaters unavailable for service during the 2023–2024 operating season due to tube
- 8 bundle leaks. 14 In 2024, Hydro began a condition assessment program, 15 under which all heaters will be
- 9 opened for internal inspection and tube testing over the next two years.
- 10 This program continued in 2025, with a total of six of the nine heaters assessed to date. 16 Four of these
- 11 heaters were refurbished and returned to service; two had deteriorated severely and could not be
- 12 refurbished. Replacement of these heaters (Heater Number 4 on Unit 1, and Heater Number 6 on
- 13 Unit 3) is ongoing. Three heaters remain to be assessed in 2026, all of which are available for service. For
- the 2025–2026 operating season Unit 1 will have one heater in service, Unit 2 will have three heaters in
- 15 service, and Unit 3 will have two heaters in service as a result of this ongoing work. Based on heater
- 16 lead-time and the need for installation during a unit outage, replacement of the two failed heaters is
- 17 expected to occur after the 2025–2026 operating season.
- 18 The units can be operated reliably at full load without the HP feedwater heaters in service; however,
- 19 extended operation through the Bridging Period without the heaters can cause premature failures of
- 20 turbine and boiler components, with one significant impact being risk of damage to the last stage blades
- 21 ("LSB"). Potential damage attributable to operation without HP feedwater heaters would not be
- 22 expected to cause sudden failure, and would occur on components that are regularly inspected,

<sup>&</sup>lt;sup>16</sup> There are three heaters per unit, numbered 4 through 6. Heaters 4 and 5 are linked and must be operated in parallel.



-

5

<sup>&</sup>lt;sup>14</sup> The HP heaters transfer heat from steam outside of the tubes to the feedwater, which then passes through the tube bundles to the boiler. Each unit contains three heaters, which are intended to improve thermal efficiency.

<sup>&</sup>lt;sup>15</sup> "2024 Capital Budget Application," Newfoundland and Labrador Hydro, rev. September 21, 2023 (originally filed July 12, 2023), sch. 6, prog. 6.

- 1 including boiler tubes and turbine blades. 17 As such, Hydro considers the risk to the Holyrood TGS for
- this winter operating season associated with the HP feedwater heaters to be low.

#### 2.4.4 Unit 1 Turbine Control Valve

- 4 The completion of the Overhaul Unit 1 Turbine Valves and Generator 2024 Program included
- 5 assessment and refurbishment of the main steam control valves. During the assessment of these
- 6 components by the turbine service provider, it was discovered that the camshafts that control opening
- 7 and closing of the control valves were bent outside of the OEM recommended tolerance for reliable
- 8 operation. Two spare camshafts, OEM supplied, were used to rebuild the control valve assemblies.
- 9 During commissioning of the unit during April 2025, load was limited intermittently. The OEM
- investigated the issue and determined that pins on the new camshafts were interfering with the control
- 11 valves, preventing full opening. The interference was corrected, and the unit successfully returned to
- 12 service.

3

- 13 After this adjustment, the unit was operated for a brief period without the issue reoccurring before
- being shut down for the summer. Hydro believed that this issue was resolved; however, during the
- return to service of Unit 1 in September 2025 after completion of the annual outage, the same load limit
- was experienced, restricting the unit to 100 MW. In consultation with the OEM and service provider,
- 17 correction of this issue required a brief unit outage, which began November 24, 2025 as system
- 18 conditions allowed. Repairs were successfully completed and the unit returned to service at full capacity
- on November 27, 2025; as such, this risk is now resolved.

#### 2.4.5 Fuel Oil Contamination Storage Tank 3

- 21 In March 2025, Hydro received a fuel delivery of just over 202,000 barrels. The bulk of this delivery
- 22 (approximately 180,000 barrels) was allocated to Tank 3 while the remaining (approximately 22,000
- barrels) was stored in Tank 1. While this fuel delivery fully complied with Hydro's specifications, issues
- 24 with frequent strainer plugging were encountered immediately with fuel drawn from Tank 3, with
- contamination suspected. At that time, there were also leaks in the steam piping to Tank 3, which

<sup>&</sup>lt;sup>17</sup> Since 2023, Hydro has completed assessments of the LSBs on all three units, and replacements were completed on the Unit 1 and Unit 2 blades.



-

20

- 1 limited the amount of heating that could be provided to the fuel oil and may have contributed to the
- 2 strainer plugging; however, this has since been corrected.
- 3 When Unit 1 was returned to service in September 2025, Tank 4 was in service and there were no
- 4 concerns with fuel plugging. Upon switching fuel supply from Tank 4 to Tank 3, strainer plugging became
- 5 severe, leading to a trip of Unit 1 on September 25, 2025 due to insufficient fuel supply to the boiler.
- 6 Rather than discharge the fuel, operational strategies were followed to consume the fuel in Tank 3,
- 7 including using the fuel from Tank 3 in parallel with other tanks to dilute the contaminated fuel
- 8 and reduce the potential for fouling. A new fuel delivery was received on November 10, 2025 and Tank 3
- 9 has been independently supplying the plant with fuel without issue since that time; 18 as such, this risk is
- 10 now resolved. As reported in previous WR Reports, Hydro is taking preventative measures to prevent
- the receipt of contaminated fuel in future.

12

#### 2.4.6 Cooling Water Sump Structures

- 13 The WR scope in this project is to clean, inspect, and perform a Level 2 Condition Assessment of the
- 14 Holyrood Stage 2 Pumphouse cooling water sump structures. This project was initially approved by the
- 15 Board to complete a Level 2 Condition Assessment of both the Stage 1 & Stage 2 cooling water sump
- structures in 2025; however, as a result of the outcome of the procurement process, Hydro adjusted its
- 17 approach and proposed to proceed with the inspection of Pumphouse 2 only in 2025, and to extrapolate
- 18 the findings to define the scope of the Pumphouse 1 refurbishments. 19 The risk associated with not
- 19 completing the condition assessment of Pumphouse 1 in 2025 is considered to be low, and was
- 20 mitigated by completing a UAV<sup>20</sup> inspection to identify any significant changes in the concrete condition
- 21 over the past 12 months. This inspection is now complete, with preliminary feedback indicating that no
- 22 major changes were observed.
- 23 The schedule delay associated with pausing the project construction activities to update, review and
- 24 approve the new project budget and scope has precluded the completion of restoration work in

<sup>&</sup>lt;sup>20</sup> Unmanned Aerial Vehicle.



<sup>&</sup>lt;sup>18</sup> At the time of the fuel delivery, approximately 50,000 barrels of fuel remained in Tank 3. Approximately 150,000 barrels of new fuel was added to the tank.

<sup>&</sup>lt;sup>19</sup> The Board approved Hydro's proposal and updated budget in Board Order No. P.U. 29(2025).

- Pumphouse 2 in 2025.<sup>21</sup> The cooling water sump within Pumphouse 2 is expected to be available for 1
- 2 service by December 12, 2025. To mitigate risk in advance of the completion of restoration work,
- 3 existing measures established to limit areas of the pumphouse to foot traffic only will be maintained
- during the 2025-2026 winter season. 4

#### 2.4.7 Fuel Oil Storage Tank 1

5

15

- 6 During a tanker delivery in November 2024, while filling Tank 1, it was determined that both suction
- 7 heaters<sup>22</sup> on this tank had tube leaks. The leaking tubes were removed from service by plugging, which
- 8 allowed the suction heaters to be returned to service; however, the number of tubes removed from
- 9 service in each heater was significant, and has reduced their heating capability. As such, for reliable
- winter operation, the Tank 1 suction heaters need to be replaced. 10
- 11 Hydro purchased replacement suction heaters, which were delivered to the Holyrood TGS in October
- 12 2025. Hydro prioritized the consumption of fuel from Tank 1 early in the operating season to reduce the
- 13 fuel in the tank to minimum storage levels, where the suction heaters can be replaced. This replacement
- 14 work was completed in late November 2025; as such, this risk is now resolved.

#### 2.4.8 Flame Scanners

- The combustion of fuel in the boilers at Holyrood TGS is supervised by safety devices called flame 16
- 17 scanners. Each burner has its own flame scanner, which is an optical device that detects the presence of
- 18 flame. If the flame scanner does not detect flame, then it will shut off the fuel going to that burner. This
- prevents the accumulation of unburned fuel inside the boiler, which could lead to an explosive 19
- 20 condition. These devices are required by code. Unit 1 and Unit 2 each have twelve burners, while Unit 3
- 21 has nine. To reliably generate full load, all burners are required to be operational.
- 22 Hydro's existing flame scanner system is no longer supported by the OEM, and it is no longer possible to
- 23 purchase additional scanners. To mitigate the risk of obsolescence and the minimal availability of spare
- 24 parts, the flame scanners on Unit 2 were identified for replacement with a newer model procured from
- 25 the OEM. The new system was installed on Unit 2 during the 2025 annual outage; however, during start-

<sup>&</sup>lt;sup>22</sup> The suction heaters utilize steam to heat the oil to a sufficient temperature, allowing the oil to flow freely from the tank farm to the plant for combustion in the boilers.



<sup>&</sup>lt;sup>21</sup> At this time, Hydro anticipates proposing the completion of restoration work in Pumphouse 1 through a supplemental application in 2026, and Pumphouse 2 refurbishment as part of its 2027 Capital Budget Application.

- 1 up of the unit in October 2025, technical issues occurred which prevented the unit from returning to
- 2 service. After several days of troubleshooting supported by the OEM, it was agreed to return to the
- 3 original scanner system to enable the unit to return to service. Hydro will continue to work with the
- 4 OEM to resolve the technical issues and enable the new system for changeover and commissioning
- 5 during the next annual unit outage, or a maintenance outage earlier in 2026.
- 6 Hydro has sufficient scanners for burners on all three units, with 10 additional spares, and a total of 33
- 7 currently in-service across the three burners. All scanners for Unit 3 and the 10 additional spares have
- 8 been tested and confirmed to be operational. Based on operational experience, Hydro will carefully
- 9 monitor for scanner failures but expects this is a sufficient number of spares to maintain the availability
- of all burners for the winter operating season, especially given the delay in return to service of Unit 3. As
- such, Hydro considers the risk to the Holyrood TGS for this winter operating season to be low.


#### 3.0 Combustion Turbine Generation

#### 3.1 Annual Work Plan and Winter Readiness Status

- 14 The status of AWP and WR execution at the Holyrood CT, Hardwoods GT, Stephenville GT, and Happy
- 15 Valley GT is summarized in the following charts.

12

13




#### **Holyrood CT**


#### **Forecast Completion Status:**

On Target for Completion by December 12, 2025

- Overall AWP completion status is 88.0% to date.
- WR status is 91.9% complete for 2025.
- The annual maintenance outage is complete.
- Unexpected issues encountered while returning the unit to service upon completion of its annual outage in late-November 2025 impacted resource availability to complete remaining WR items by December 1, 2025.
- All remaining WR activities are scheduled for completion prior to December 12, 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.








#### **Hardwoods GT**


#### **Forecast Completion Status:**

# On Target for Completion by December 12, 2025

#### **Comments and Schedule Notables:**

- Overall AWP completion status is 92.3% to date.
- WR status is 89.2% complete for 2025.
- Unexpected operational issues encountered with the Holyrood CT in late-November 2025 impacted resource availability to complete remaining WR items by December 1, 2025.
- All remaining WR activities are scheduled for completion prior to December 12, 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.






#### Stephenville GT

#### **Forecast Completion Status:**

On Target for Completion by December 12, 2025

- Overall AWP completion status is 93.6% to date.
- WR status is 90.6% complete for 2025.
- Unexpected operational issues encountered with the Holyrood CT in late-November 2025 impacted resource availability to complete remaining WR items by December 1, 2025.
- All remaining WR activities are scheduled for completion prior to December 12, 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.





#### 1 3.2 Critical Spares

- 2 As shown in Table 2, all critical spares are in stock for the Hardwoods GT, Stephenville GT, Holyrood CT,
- 3 and Happy Valley GT.

**Table 2: Critical Spares for CT Generation** 

	Hardwoods/			
Status	Stephenville	Holyrood	<b>Happy Valley</b>	Total
In Stock	90	403	54	547
<b>Procurement Ongoing</b>	0	0	0	0
Total	90	403	54	547

- 4 Hydro has utilized some of its critical spares during recent fall maintenance outages; however, these
- 5 items have been identified and the spare components have been replenished.

<sup>&</sup>lt;sup>23</sup> In total, 17 AWP activities remain to be completed for the Happy Valley GT.



.

#### 1 3.3 Plant and Equipment Testing

- 2 Examples of WR activities that are included in the AWPs for the Holyrood CT, Hardwoods GT,
- 3 Stephenville GT, and Happy Valley GT include the following:
- PMs and CMs for major components and auxiliary systems;
- Black start testing;
- Monthly operational testing; and
- Execution of capital upgrades and refurbishment.
- 8 Black start testing of the Holyrood CT, Happy Valley GT, Hardwoods GT, and Stephenville GT is complete.
- 9 Operational testing of all CTs was performed throughout the year as planned and all WR capital
- upgrades and refurbishments were completed by December 1, 2025.

#### 11 3.4 Risk and Risk Mitigation

- 12 Existing risk to WR and/or reliable operations related to CT operations is discussed in the section that
- 13 follows.

#### 14 3.4.1 Hardwoods Gas Turbine – Spare Engine Overhaul

- 15 During a 2024 inspection, internal damage was found on the high-pressure turbine normal guide vane
- 16 seals of the engine installed in End A at the Hardwoods GT. While the damage was relatively minor in
- 17 nature, the location of the damage and age of the engine required that the engine be removed from
- 18 service and sent to a facility for overhaul, to eliminate the risk of a catastrophic failure. The damaged
- 19 engine was removed and its spare installed during the planned maintenance outage which concluded in
- 20 early November 2024, and the engine arrived at the repair facility in January 2025.
- 21 The engine was expected to be returned from the overhaul facility in October 2025; however, during
- 22 final inspections, an issue was detected with the fit of the turbine guide vanes. This issue requires the
- 23 disassembly and replacement of components inside the engine. As a result, the engine is not expected
- to be returned from the overhaul facility until late December 2025 or early January 2026.
- 25 Hydro will not have a spare engine onsite until the return of the repaired engine, which also functions as
- a spare for the Stephenville GT, and has developed contingency plans should an operational issue occur.



- 1 Hydro's service provider has an additional lease engine available which Hydro can avail of should
- 2 operational issues occur which requires an engine replacement prior to the return of the spare engine.


# 4.0 Hydraulic Generation


#### 4 4.1 Annual Work Plan and Winter Readiness Status

- 5 The status of AWP and WR execution at hydraulic generation facilities is summarized in the following
- 6 charts, including:

3

- o Bay d'Espoir Hydroelectric Generating Station ("Bay d'Espoir");
- 8 Cat Arm Hydroelectric Generating Station ("Cat Arm");
- 9 Hinds Lake Hydroelectric Generating Station ("Hinds Lake");
- o Paradise River Hydroelectric Generating Station ("Paradise River");
- o Upper Salmon Hydroelectric Generating Station ("Upper Salmon"); and
- o Granite Canal Hydroelectric Generating Station ("Granite Canal").





#### Bay d'Espoir

#### **Forecast Completion Status:**

On Target for Completion by Return to Service of Units 1 and 2

- Overall AWP completion status is 88.4% to date.
- WR status is 86.8% complete for 2025.
- Units 2 and 1 are currently offline on a planned outage, with return to service expected on December 22, 2025 and January 12, 2026, respectively.
- The annual maintenance outage is complete for Units 3, 4, 5, 6 and 7.
- All remaining activities are scheduled for completion prior to Units 1 and 2 being returned to service.






#### Cat Arm

#### **Forecast Completion Status:**

#### **Target May Not be Fully Met**

#### **Comments and Schedule Notables:**

- Overall AWP completion status is 92.1% to date.
- WR status is 98.8% complete for 2025.
- The one remaining WR activity requires outages to both units, and is unlikely to be completed in 2025 due to system demands.
   Delayed completion of this activity does not pose an increased risk to plant reliability.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.




#### **Hinds Lake**

#### **Forecast Completion Status:**

#### **Target Achieved**

- Overall AWP completion status is 93.5% to date.
- WR status is 100.0% complete for 2025.
- The annual maintenance outage was completed on November 27, 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.





# of WR Activities


#### **Paradise River**

#### **Forecast Completion Status:**

#### **Target Achieved**

#### **Comments and Schedule Notables:**

- Overall AWP completion status is 95.0% to date.
- WR status is 100.0% complete for 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.




#### **Upper Salmon**

#### **Forecast Completion Status:**

#### **Target May Not be Fully Met**

- Overall AWP completion status is 91.1% to date.
- WR status is 94.4% complete for 2025.
- Five WR activities remained outstanding as of December 1, 2025; one of which has since been completed. Three activities are expected to be complete by December 12, 2025. The remaining activity is partially complete, and may not be completed in 2025 due to bird nesting in the area. Delayed completion of these activities does not pose an increased risk to plant reliability.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.





#### **Granite Canal**

#### **Forecast Completion Status:**

#### **Target Achieved**

#### **Comments and Schedule Notables:**

- Overall AWP completion status is 64.8% to date.
- WR status is 100.0% complete for 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.

#### 1 4.2 Critical Spares

2 As shown in Table 3, all critical spares for hydraulic generation are in stock.<sup>24</sup>

**Table 3: Critical Spares for Hydraulic Generation** 

Status	Quantity
In Stock	1,228
<b>Procurement Ongoing</b>	0
Total	1,228

#### 3 4.3 Plant and Equipment Testing

- 4 WR testing of generating equipment in hydraulic generation is focused primarily around annual unit
- 5 maintenance outages. Following these annual outages, units are run up and synchronized and all
- 6 systems are verified before the unit's operating status is determined and preparedness is confirmed.
- 7 Unit load tests are also performed as system conditions permit. The WR testing protocol includes the
- 8 testing of appropriate Balance of Plant components.

<sup>&</sup>lt;sup>24</sup> While minor deficiencies remain on Upper Salmon T2 Spare, this unit can enter service as required.



- 1 The status of plant and equipment testing for hydraulic generation is indicated in Appendix E. All
- 2 inspection and testing of hydraulic generating facilities was complete by December 1, 2025, with the
- 3 exception of Bay d'Espoir Units 1 and 2. All remaining plant and equipment testing are scheduled for
- 4 completion upon the return to service of Units 1 and 2.

#### 4.4 Risk and Risk Mitigation

- 6 Existing risk to WR and/or reliable operations related to Hydro's Hydraulic Generation assets are
- 7 discussed in the sections that follow.

5

#### 8 4.4.1 Bay d'Espoir Penstocks

- 9 As a result of previous ruptures of the Bay d'Espoir Penstocks, with the most recent being September
- 10 2019, Hydro decided to complete annual inspections of Bay d'Espoir Penstocks 1, 2, and 3 to monitor
- 11 penstock condition and ensure reliability in the short-term. One notable change in 2025 is the removal
- 12 of Bay d'Espoir Penstock 1 from the annual inspection program, since it is currently undergoing major
- capital investment to extend the reliable service life, which includes inspection activities.<sup>25</sup>
- 14 Penstock 2 was inspected in May 2025; during the inspection, two new indications were discovered and
- 15 repaired. As well, four indications discovered in 2024, which posed no material concerns at that time,
- were also repaired during the 2025 inspection.
- 17 Penstock 3 was inspected in November 2025; during the inspection, six new indications were
- 18 discovered. In consultation with Hydro's third-party inspector, it was determined the indications posed
- 19 no material concerns at this time and the penstock could safely be returned to service.
- 20 Although Hydro has mitigated the risk of penstock failure to the extent possible, there is residual risk
- 21 that a failure could occur on Penstocks 2 or 3 before further life extension work is completed.
- 22 Modifications remain in place, which are designed to limit the amount of rough zone operation, as well
- as a more prescriptive operating regime for Units 5 and 6 due to the results of annual inspections of

<sup>&</sup>lt;sup>25</sup> In Board Order No. P.U. 6(2023), Hydro received approval for the refurbishment of Penstock 1 at Bay d'Espoir in 2023, and the project is now complete. Following completion of required commissioning activities, Bay d'Espoir Bay d'Espoir Units 2 and 1 are expected to return to service on December 22 and January 12, respectively.



2!

- 1 Penstock 3 in recent years. <sup>26</sup> Hydro has estimated a 13- to 23-day repair timeline depending on
- 2 circumstances, should a new failure occur, and has continued to take proactive measures to reduce
- 3 generating unit downtime in the event of failure.

#### 4 4.4.2 Hinds Lake Unit Vibration and Shaft Seal Leakage

- 5 The Hinds Lake unit has been experiencing higher-than-normal vibration levels and shaft seal leakage
- 6 rates, which has resulted in operational modifications.<sup>27</sup> Inspection and interventions were completed
- 7 during the annual planned maintenance outage, which began on November 2 and concluded November
- 8 27, 2025.
- 9 While work on the unit in 2025 did not yield reductions in unit vibration, information gathered during
- 10 the outage has provided clarification on the current settings for the bearing clearance of the unit. Based
- on this information, the Hinds Lake Unit will be available at full capacity this coming winter.<sup>28</sup>
- 12 Hydro continues to monitor both issues, and to mitigate risk, has proceeded with the procurement of
- 13 bearing components and replacement parts for the shaft seal to ensure they are on hand in the event an
- outage is required. A plan has been detailed for 2026 to replace the shaft seal and rebuild the bearing,
- which is expected to assist in reducing unit vibration levels.

## 16 5.0 Muskrat Falls Assets

#### 17 5.1 Annual Work Plan and Winter Readiness Status

- 18 The status of AWP and WR execution for the Muskrat Falls Assets is summarized in the following charts,
- 19 including:
- 20 o Muskrat Falls Hydroelectric Generating Station ("Muskrat Falls");
- 21 o Labrador-Island Link;
- 22 Labrador Transmission Assets ("LTA"); and


<sup>&</sup>lt;sup>28</sup> Generally, the unit is safe to operate if vibration is less then 50% of the bearing diametrical clearance. This clearance was confirmed for the Hinds Lake Unit during the 2025 outage.



<sup>&</sup>lt;sup>26</sup> Under this operating regime, once dispatched, Units 5 and 6 are limited to a minimum loading of 50 MW and are not cycled or shut down as part of normal system operations. In previous years, operational modifications were in place on Penstock 1 (ie. Units 1 and 2); however, these modifications will no longer be required after capital investment is completed in 2025.

<sup>&</sup>lt;sup>27</sup> Under this operating regime, once dispatched, the Hinds Lake Unit is fixed at 22 MW to reduce the impact of elevated vibration levels.

- o Soldiers Pond Synchronous Condensers ("SOP SC").
- 2 LIL will be available for bipole operation up to 700 MW this winter. Subject to the completion of high-
- 3 power testing, the LIL will be able to be operated up to 900 MW as system conditions permit. Hydro has
- 4 determined that the high-power test of the LIL will be postponed until later in the winter as a result of
- 5 its continued focus on WR activities and prioritization of reliable service to customers during the winter
- 6 period, including supporting reservoir levels to meet peak load requirements.
- 7 As the Muskrat Falls assets are in early operation, and considering trends in the occurrence of break-in
- 8 work, the timing and frequency of the OEM recommended PM activities and the scheduling of
- 9 maintenance resources are under review to determine an optimal AWP schedule.



#### **Muskrat Falls Generating Assets**

#### **Forecast Completion Status:**

#### **Target Will Not be Fully Met**


#### Comments and Schedule Notables:

- Overall AWP completion for Muskrat Falls Units 1 to 4 is 91.2% to date.<sup>29</sup>
- WR status is 85.7% complete for 2025.<sup>30</sup>
- Seven low-risk WR activities remain outstanding; one has since been completed and two have been cancelled. The four remaining activities relate to the spillway, and will not be completed this year due to work demands on Unit 2.
- Annual maintenance outages have been completed on all units.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.

<sup>&</sup>lt;sup>30</sup> WR activity status is as of December 2, 2025.



<sup>&</sup>lt;sup>29</sup> AWP activity status is as of November 30, 2025.



#### LIL, LTA and SOP SC

#### **Forecast Completion Status:**

On Target for Completion by December 31, 2025 Comments and Schedule Notables:

- Overall AWP completion for the LIL, LTA, and synchronous condensers at Soldiers Pond is 89.1% to date.<sup>31</sup>
- WR status is 89.0% complete for 2025.<sup>32</sup>
- All remaining WR activities are planned for completion prior to December 31, 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.

#### 1 5.2 Critical Spares

- 2 A significant fire in spring 2024 in the community of Happy Valley-Goose Bay resulted in the total loss of
- 3 the storage facility housing Hydro's Muskrat Falls generation critical spares. As a result, a significant
- 4 effort has been undertaken to replenish the critical spares inventory, and Hydro has in stock nearly
- 5 three-quarters of its critical spares. The remaining parts are at various steps within the procurement
- 6 process.
- 7 The status of critical spares for Muskrat Falls generation is provided in Table 4 and Appendix F contains a
- 8 detailed list of spares for which procurement is ongoing. Hydro has prioritized ordering of items based
- 9 on WR, and continues to evaluate its identification of critical spares to set an appropriate target for the
- 10 purpose of WR. 348 items are at various steps within the procurement process, with 73 items expected
- 11 to be delivered prior to year end.

**Table 4: Critical Spares for Muskrat Falls Generation** 

Status	Quantity
In Stock	1,076
Procurement Ongoing	348
Total	1,424

<sup>&</sup>lt;sup>31</sup> AWP activity status is as of November 30, 2025.

<sup>&</sup>lt;sup>32</sup> WR activity status is as of November 30, 2025.



#### 1 5.3 Plant and Equipment Testing

- 2 WR testing of generating equipment in hydraulic generation is focused primarily around annual unit
- 3 maintenance outages. Following these annual outages, units are run up and synchronized and all
- 4 systems are verified before the unit's operating status is determined and preparedness is confirmed.
- 5 Unit load tests are also performed as system conditions permit. The WR testing protocol includes the
- 6 testing of appropriate Balance of Plant components.
- 7 The status of equipment and plant testing for Muskrat Falls generating assets is indicated in Appendix G.
- 8 All inspection and testing of hydraulic generating facilities was completed upon the return to service of
- 9 Unit 1 on December 5, 2025.

#### 10 5.4 Risk and Risk Mitigation

- 11 Existing risk to WR and/or reliable operations related to these assets is discussed in the sections that
- 12 follow.

#### 13 5.4.1 Muskrat Falls Unit 1 Intake – Concrete Spalling

- 14 During the 2024 planned annual outage to Unit 1, concrete debris was observed in the turbine scroll
- 15 case. Further inspection indicated some scuffing on the wicket gate lower operating ring caused by the
- 16 passage of this debris through the turbine, which has since been repaired. This damage did not affect
- 17 the unit's output or availability.
- 18 Remote operated vehicle inspection of the intake civil works identified an area where concrete had
- 19 cracked and dislodged. In October 2024, a specialized team assessed the condition of the remaining
- 20 concrete in the area where spalling had been observed. Upon completion of further concrete cutting
- and removal, sounding of the entire Intake Bay 3 lintel beam was completed with no further areas
- identified for remedial action. Unit 1 was returned to service on October 16, 2024, with a final repair to
- the intake civil works planned during the 2025 annual outage.
- 24 Due to the unforeseen extension of the planned outage to repair the Muskrat Falls Unit 2 turbine
- 25 runner, there was insufficient time to complete final repairs on the Unit 1 intake structures in 2025. An
- inspection to assess the current condition of the intake civil works was carried out during the 2025
- 27 annual outage for Unit 1; during the inspection, some minor issues were found and rectified. A further



- 1 remote access assessment was completed in late November 2025, which found no major risks. The
- annual maintenance outage for Unit 1 in 2026 will have time allotted to complete the repairs.
- 3 To mitigate risk should a similar incident occur this coming winter, Hydro has a response plan in place,
- 4 and has proceeded with the procurement of required materials to ensure they are on hand in the event
- 5 a repair is required.

#### **5.4.2 Optical Ground Wires Tower Peak and Top Plate Design**

- 7 Since 2022, several incidents of damage to the optical ground wires ("OPGW") tower peaks occurred in
- 8 heavy ice loading conditions, and there were two failures at the connection of the OPGW top plate
- 9 during an icing event on the line in December 2022. The incidents involving these tower components did
- 10 not cause a prolonged LIL outage; however, brief outages were required to repair the damage. 33
- 11 As a result, a new design to reinforce tower peaks and replace the impacted top plates has been
- 12 completed. Installation work to rectify the tower peaks and two remaining top plates is expected to
- begin in 2026 with expected completion in 2028.<sup>34</sup> To mitigate risk to near-term reliability, Hydro has its
- 14 Emergency Response Plan in place, and has proceeded with the procurement of required materials to
- ensure they are on hand in the event a repair is required.

#### 16 5.4.3 Electrode Conductors

- 17 During December 2022, March 2024, and January 2025 there were issues with the electrode conductor
- 18 during significant ice loading, the root cause of which was determined to be overloading due to ice and
- 19 ice shedding.
- 20 Three alternative suspension clamp designs were installed on the electrode conductor at ten structures,
- 21 and will be inspected yearly for performance. An assessment of the electrode suspension assembly and
- a re-design of the assembly was completed in 2025, with the assemblies to be purchased and installed

<sup>&</sup>lt;sup>34</sup> Analysis confirmed that 63 towers across two tower types (A3 and A4) were identified to have top plates replaced; as of the end of 2024, 61 of 63 were replaced, which represents all A3 towers. The two remaining top plates are on A4 tower types.



<sup>&</sup>lt;sup>33</sup> As the OPGW relates to communications functionality, Hydro does not anticipate that further occurrences of similar damage would result in a prolonged power interruption or customer outage.

- as required through a capital project. Additional conductor testing has been completed from these 1
- 2 incidents, with further recommendations outlined within the most recent investigation report.<sup>35</sup>
- 3 To mitigate risk to near-term reliability, Hydro has its Emergency Response Plan in place, and has
- 4 proceeded with the procurement of required materials to ensure they are on hand in the event a repair
- 5 is required.

#### 6 5.4.4 DCCT Cold Weather Operation

- 7 In 2023, the OEM and Hydro determined that extremely low air temperatures were influencing the
- 8 measurement accuracy of some Direct Current Current Transformers ("DCCT"), resulting in false
- 9 protection trips and power control issues on the LIL. The OEM identified the root cause of the issue to
- 10 be a manufacturing defect with the Delay Coil Fiber Optical Cable located within the DCCTs; this issue
- 11 occurred with a select batch of fiber optic cables, affecting six DCCTs at the Muskrat Falls HVdc
- 12 Converter Station, which have since been replaced.<sup>36</sup>
- 13 In November 2025, General Electric ("GE") provided a revised plan to address DCCTs which have low risk
- 14 indicators of the issues related to cold weather operation. GE has indicated that the plan includes
- 15 working with a new DCCT provider and delivery of contractual spares in spring 2026. Hydro will continue
- 16 to work with the OEM to ensure proper mitigation of the issue.

#### 5.4.5 Cable Switching 17

- As reported in Hydro's final 2024–2025 Winter Readiness Report,<sup>37</sup> new equipment was successfully 18
- 19 installed to mitigate cable switching transients at the LIL Transition Compounds in mid-October 2024.
- 20 Since that time, Hydro has identified an icing issue with transition compound disconnects that can
- 21 impact cable switching in winter conditions. A solution to resolve this issue is currently being fabricated,
- 22 and will be finalized in the fourth quarter of 2025 in consultation with GE. Installation of the improved

<sup>&</sup>lt;sup>37</sup> Reliability and Resource Adequacy Study Review – 2024–2025 Winter Readiness Planning Report – Final Report," Newfoundland and Labrador Hydro, December 10, 2024.



<sup>35</sup> For further information, please refer to Attachment 1 of "Quarterly Report on Asset Performance in Support of Resource Adequacy for the Twelve Months Ended September 30, 2025", Newfoundland and Labrador Hydro, October 31, 2025.

<sup>&</sup>lt;sup>36</sup> One of these DCCTs has an operation rating to -40°C, and will be replaced with a DCCT rated to -50°C in late 2025 or early 2026, as system conditions permit.

- 1 ice guard design is planned for early 2026, as system conditions allow. In the interim, Hydro is
- 2 developing operating procedures to ensure reliable operation in winter conditions.

#### **5.4.6 Synchronous Condenser Brush Gear Assemblies**

- 4 Brush equipment performance on the Soldiers Pond synchronous condensers decreased in
- 5 December 2023, resulting in several scheduled outages to replace damaged brushes, springs and brush
- 6 holders.
- 7 Hydro, in consultation with the OEMs for the brush equipment and the synchronous condensers, has
- 8 been working to identify the root cause of the brush performance issues. Hydro has continued with the
- 9 modified brush configurations and operational controls to ensure optimal operating conditions for
- 10 patina development. These changes have had positive results with regards to brush performance in
- 11 2025.
- 12 In spring 2024, the existing slip ring was removed from synchronous condenser 1 ("SC1"), and sent for
- 13 machining to correct a runout causing excessive brush vibration. At this time, a modified brush with the
- ability to operate in a higher vibration environment was also provided by the OEM and installed. These
- 15 modifications have resulted in improved performance to date. Hydro will continue to monitor the
- overall impact of these changes.
- 17 Corrective actions on all three units have yielded positive results, and changes performed in 2024 have
- 18 aided in achieving acceptable brush performance across all three synchronous condensers. Inspections
- 19 completed on SC1 and SC2 in November 2025 indicated continued improved performance from the
- brushgear. Inspection of the SC3 brushgear is planned in mid-December 2025.



#### **Transmission and Terminal Stations** 6.0 1

#### 2 6.1 **Annual Work Plan and Winter Readiness Status**

- 3 The status of AWP and WR execution for transmission line and terminal station facilities on both the
- 4 Island Interconnected System and the Labrador Interconnected System is summarized in the following


■ Remaining Planned to Date

50

5 charts.

0

10



30

# of WR Activities


**Transmission and Rural Operations Island** ("TROI") Transmission

**Forecast Completion Status:** 

**Target Achieved** 

- Overall AWP completion status is 93.8% to date.
- WR status is 100.0% complete for 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.






### **TROI Terminal Stations**

**Forecast Completion Status:** 

**Target Achieved** 

### **Comments and Schedule Notables:**

- Overall AWP completion status is 97.0% to date.
- WR status is 99.6% complete for 2025.<sup>38</sup>
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.



### Transmission and Rural Operations Labrador ("TROL") Transmission

**Forecast Completion Status:** 

**Target Achieved** 


### **Comments and Schedule Notables:**

- Overall AWP completion status is 93.7% to date.
- WR status is 100.0% complete for 2025.
- All remaining AWP activities are scheduled for completion prior to December 31, 2025.

 $<sup>^{\</sup>rm 38}$  Remaining WR items are low risk and are scheduled for completion in 2026.



Page 31



### TROL Terminal Stations

Forecast Completion Status:

### Target Will Not be Fully Met

### **Comments and Schedule Notables:**

- Overall AWP completion status is 78.5% to date.
- WR status is 86.0% complete for 2025.
- 14 WR activities remain outstanding; three of which are expected to be completed by December 31, 2025. The remainder, which consist of lower priority items, have been deferred for 2026 completion.
- Overall AWP completion status on target for completion.

### 1 6.2 Plant and Equipment Testing

- 2 The AWPs for both transmission and terminal stations are predominantly comprised of PMs and CMs,
- 3 which inherently involve inspection and testing.<sup>39</sup> Examples of WR activities that are included in the
- 4 AWP work scopes include the following:
- Transformer PMs and CMs;

6

9

- Annual exercises on all high-voltage circuit breakers;
- Exercise of 230 kV circuit breakers from protection during PM inspections;
- Infrared scans at all terminal stations;
  - Annual ultrasonic leak testing on all terminal station air systems; and
- Annual helicopter patrol of transmission lines prior to the winter season.

<sup>&</sup>lt;sup>39</sup> The "Terminal Station Asset Management Strategy – 2025 Update" document outlines the maintenance, refurbishment, and replacement criteria used by Hydro for terminal station assets. For the most recent report please refer to the "2026 Capital Budget Application," Newfoundland and Labrador Hydro, July 15, 2025, sch. 1, app. F.



### 1 6.3 Risk and Risk Mitigation

- 2 Existing risk to WR and/or reliable operations related to Hydro's Transmission and Terminal Station
- 3 assets are discussed in the sections that follow.

### 4 6.3.1 Generator Step-Up Transformer Spares

- 5 Generator Step-Up Transformer 6 was repaired by the OEM in January 2024 following its failure in July
- 6 2023, and is available for use as a spare at Bay d'Espoir, Granite Canal, or Upper Salmon.<sup>40</sup>
- 7 Hydro does not currently have a spare for the Holyrood TGS generator step-up transformers, and is in
- 8 the process of procuring a spare.<sup>41</sup> This spare is not expected to be delivered until the third quarter of
- 9 2028 due to increasing power transformer lead times.

10 11

### 6.3.2 Western Avalon Terminal Station – Replace Bushing Connecting the Gas Insulated Switchgear to Transmission Line TL267

- 12 The Western Avalon Terminal Station C phase bushing connecting the gas insulated switchgear to
- 13 Transmission Line TL267 experienced a failed top terminal seal in July 2023. Leakage of its SF<sub>6</sub> insulating
- 14 gas was stopped using a temporary seal of a metal repair composite material. While this temporary seal
- 15 has been effective since its implementation in October 2023, if the leak was to reoccur prior to receiving
- the replacement bushing, it can be repaired through a short outage to TL267.
- 17 Hydro placed an order with the supplier in March 2024 and expected to receive the bushings in time for
- 18 2025 installation; however, the order was not properly processed by the supplier. This error has since
- 19 been corrected and the new expected delivery date is September 2026. Once received, Hydro plans to
- 20 install the bushings in 2026 when system conditions allow. To mitigate the risk of failure prior to the
- 21 completion of the bushing replacement work, Hydro performs regular visual inspections, and will apply
- 22 additional repair material as necessary.

<sup>&</sup>lt;sup>41</sup> "Purchase Spare Generator Step-Up Transformer," Newfoundland and Labrador Hydro, September 21, 2023, approved in Board Order No. P.U. 28(2023).



Page 33

<sup>&</sup>lt;sup>40</sup> Cat Arm also has a spare on site; however, the spare can only be used at that facility due to the connection to the Gas Insulated Switchgear at that location.

### 1 6.3.1 Deer Lake Terminal Station – Refurbish T1 Tap Changer


- 2 Power transformer T1 at the Deer Lake Terminal Station requires tap changer refurbishment due to
- 3 deteriorated condition. This refurbishment was scheduled for November 2025; however, unavailability
- 4 of the OEM field technician requires deferral of this work to spring 2026.
- 5 Condition data indicates that the severity of the deterioration is not increasing at this time. While
- 6 refurbishment remains required, inspection of the tap changer by the OEM in September 2025 to
- 7 determine the refurbishment scope did not identify imminent reliability concerns. To mitigate the risk of
- 8 failure prior to the completion of the refurbishment work, Hydro will continue to monitor the condition
- 9 of T1 by completing oil sample PM activities every three months.<sup>42</sup>

### 10 7.0 Operational Technology

11

### 7.1 Annual Work Plan and Winter Readiness Status

- 12 The status of AWP and WR execution for Operational Technology is summarized in the following charts.
- 13 All planned WR activities were complete by December 1, 2025.



### **Operational Technology**

**Forecast Completion Status:** 

### **Target Achieved**

### **Comments and Schedule Notables:**

- Overall AWP completion status is 93.6% to date
- WR status is 100.0% complete for 2025.
- Overall AWP target has been achieved.

<sup>&</sup>lt;sup>42</sup> Hydro typically completes power transformer oil sample PM activities on an annual basis.



Page 34

### 1 7.2 Plant and Equipment Testing

- 2 The AWP for Operational Technology is comprised of PMs and CMs, which inherently involve inspection
- 3 and testing of various assets and systems. Examples of WR activities that are included in the AWP work
- 4 scopes include the following:

5

6

7

8

- Annual Preventative Maintenance on all 48V battery banks; and
- Replenish nitrogen and generator fuel reserves at all microwave repeater sites.

### 8.0 Status of Winter Readiness for Capital Projects and Programs

- 9 The status of 2025 planned capital project and program scopes of work related to 2025–2026 WR for the
- 10 Island Interconnected System and the Labrador Interconnected System are provided in Appendix A.
- 11 Table 5 summarizes the status of the WR scope of these projects and programs by asset category. A
- discussion of the risk and risk mitigation associated with each capital project and program to be
- completed after December 1, 2025 has been provided within the sections above by operating area.

Table 5: Status of Planned Capital Projects and Programs with WR Scope

		Incomplete, Expected	
	Complete as of	Completion after	
Asset Category	December 1, 2025	December 1, 2025	Total
Regulated Hydraulic Generation	-	3	3
Regulated Thermal Generation	4	2	6
Regulated Terminal Stations	2	1	3
Muskrat Falls Generation Assets <sup>43</sup>	-	-	-
Muskrat Falls Transmission Assets <sup>44</sup>	1	-	1
Total	7	6	13

- 14 As of December 1, 2025, WR scope for seven of the thirteen planned capital projects and programs is
- 15 complete. A portion of the WR scope within six projects and programs is expected to be completed after
- 16 December 1, 2025, including:

<sup>&</sup>lt;sup>44</sup> The Muskrat Falls Transmission assets include the LIL, LTA, and SOP SC.



4

<sup>&</sup>lt;sup>43</sup> There are currently no capital projects or programs that will impact 2025–2026 WR for Muskrat Falls Generation Assets.

- Overhaul Hydraulic Units (2025) Bay d'Espoir<sup>45</sup>
- Overhaul Major Pumps (2025)<sup>46</sup>
- Upgrade Power Transformers (2024-2025)<sup>47</sup>
- Overhaul Turbine and Valves Unit 3 (2025) Holyrood<sup>48</sup>
- Refurbish Intake 1 Bay d'Espoir<sup>49</sup>
- Penstock 1 Life Extension<sup>50</sup>
- 7 In addition to the planned scopes of work required for WR, Hydro is executing five unplanned scopes
- 8 under In-Service Failures Programs that are expected to be completed after December 1, 2025:
- Western Avalon Terminal Station Replace Gas Insulated Switchgear TL267 Phase C Wall
   Bushing<sup>51</sup>
- Hardwoods Gas Turbine Spare Engine Overhaul<sup>52</sup>
- Holyrood Upgrade Unit 2 Boiler Flame Scanners<sup>53</sup>
- Holyrood Replace Air Compressor 3<sup>54</sup>
- Holyrood Replace Unit 3 Auxiliary Steam Desuperheater Spray Valve<sup>55</sup>

<sup>55</sup> Work to replace this valve is complete; however, commissioining cannot be completed until the return to service of Unit 3.



<sup>&</sup>lt;sup>45</sup> A portion of the overhaul scope for Bay d'Espoir Unit 2 will now be completed during the 2026 unit annual outage. Deferral of this work does not impose additional risk to unit operation.

<sup>&</sup>lt;sup>46</sup> A portion of the pump overhaul scopes of work is complete, the remaining scope is scheduled to be completed prior to the return to service of Unit 3.

<sup>&</sup>lt;sup>47</sup> Refurbishment of the T1 tap changer at the Deer Lake Terminal Station has been deferred to spring 2026.

<sup>&</sup>lt;sup>48</sup> The expected return to service of Unit 3 is January 25, 2026.

<sup>&</sup>lt;sup>49</sup> Construction is complete; final wet commissioning of the intake gate equipment is expected to occur after the return to service of Bay d'Espoir Unit 2 on December 22, 2025.

<sup>&</sup>lt;sup>50</sup> Work on the Penstock 1 Life Extension project is now complete.

<sup>&</sup>lt;sup>51</sup> Hydro plans to install the bushings in 2026 when system conditions allow.

<sup>&</sup>lt;sup>52</sup> The engine is expected to be returned from the overhaul facility in late December 2025 or early January 2026.

<sup>53</sup> This work is expected to be completed during the next annual unit outage, or a maintenance outage earlier in 2026.

<sup>&</sup>lt;sup>54</sup> The compressor is installed, commissioned, and in-service; however, some work remains to allow automatic sequencing of all compressors. This work is expected to be completed by the end of December 2025, and does not impact the availability of the compressor to deliver compressed air.

### 9.0 System Energy Capability

- 2 In order to reliably serve customers, Hydro maintains minimum limits for aggregate energy storage in its
- 3 major hydroelectric reservoirs on the Island Interconnected System. These limits are developed annually
- 4 to ensure that Hydro is capable of meeting customer demands throughout the year in the event of a
- 5 repeat of Hydro's critical dry sequence.<sup>56</sup> The limits are established such that Hydro will have sufficient
- 6 hydraulic storage to be able to meet load in this critical sequence, or another less severe sequence,
- through the use of Island hydraulic production supplemented with maximized deliveries of energy to the
- 8 Island from Labrador over the LIL. This includes energy from Muskrat Falls as well as recapture energy
- 9 available to Hydro from the Churchill Falls Hydroelectric Generating Station.
- 10 The established limits assume that two Holyrood TGS units will be online, operating at minimum output
- 11 (70 MW) during winter 2025–2026, and do not include the use of standby thermal generation to support
- 12 reservoir storage, or the third unit at Holyrood TGS. The minimum storage methodology ensures Hydro's
- 13 reservoirs can continue to provide reliable least-cost service to customers in an environmentally
- 14 responsible manner by supporting Island load with hydroelectric energy instead of thermal energy to
- 15 the extent possible.<sup>57</sup>

1

- 16 For the period May to October 2025, Hydro's Island reservoirs experienced persistent below average
- inflows, as reported in Hydro's Monthly Energy Supply reports. The entirety of the island portion of the
- 18 province experienced some level of drought conditions throughout the summer and early fall. The
- 19 portions of the province where Hydro's reservoirs are located experienced moderate to extreme
- 20 drought conditions as of the end of October based on Agriculture and Agri-Food Canada's Canadian
- 21 Drought Monitor. Overall inflows to the reservoirs of the Island Interconnected System were 68% below
- the historical average from May 2025 to October 2025.
- 23 Island system storage steadily declined due to ongoing low inflows from May to October 2025. However,
- 24 there were five notable rain events throughout the month of November across Hydro's reservoir system

<sup>&</sup>lt;sup>56</sup> Hydro's long-term critical dry sequence is defined as January 1959 to March 1962 (39 months). Other dry periods are also considered during this analysis to ensure that no other shorter-term historic dry sequence could result in insufficient storage. <sup>57</sup> The limits also do not consider the availability of imports over the Maritime Link, though imports can provide an additional opportunity to supplement storage and economically reduce the amount of thermal generation required to maintain sufficient energy in storage in the event that import opportunities arise.



- which resulted in an overall increase in system energy storage of 506 GWh from October 31, 2025 to
- 2 November 30, 2025. A summary of these events are as follows:
- 3 November 1, 2025 − 11-17 mm
- 4 November 4-5, 2025 35-37 mm
- November 11-15, 2025 57-139 mm
- November 17-18, 2025 16-44 mm
- 7 November 22-23, 2025 8-25 mm
- 8 As of November 30, 2025, aggregate reservoir storage was 1,513 GWh, which is 62% of the maximum
- 9 operating level and 30% above the minimum storage limit. Figure 1plots the 2024 and 2025 storage
- 10 levels, minimum storage limits, maximum operating level storage, and the 20-year average aggregate
- storage for comparison. Please note that the minimum storage limits for 2025–2026 have been updated
- as of September 30, 2025 utilizing the LIL transmission limits associated with the "full" or final under-
- 13 frequency load shedding ("UFLS") scheme as opposed to the previously presented and "interim" UFLS
- scheme. The final UFLS scheme was implemented on November 24, 2025. The final UFLS scheme allows
- 15 for incrementally more LIL energy to be brought to the Island without conversely needing to export
- more energy over the Maritime Link export path. This resulted in a small adjustment downwards of the
- 17 monthly minimum storage limits.






Figure 1: Total System Energy Storage<sup>58</sup>

<sup>&</sup>lt;sup>58</sup> Data points in Figure 1 represent storage at the beginning of each day. The body of the report text reports the end-of-day storage value, which results in a small difference between the storage data presented in the text and Figure 1.



- 1 Deliveries of energy to the Island Interconnected System from Labrador via the LIL were maximized to
- 2 the extent possible to support Island reservoir storage until November 19, 2025 at which time deliveries
- 3 were reduced to manage storage in the Lond Pond Reservoir. Exports from Island sources continue to be
- 4 on hold since July 2025.
- 5 With the exception of a planned outage on Holyrood TGS Unit 1 from November 24 to 27, 2025,
- 6 Holyrood TGS Units 1 and 2 were online during the month of November and operating above minimum,
- 7 as system conditions required, until November 18, 2025, to support reservoir storage. Total energy
- 8 production from Holyrood TGS for the month was 116.8 GWh.
- 9 On October 1, 2025, Hydro entered into a third six-month power purchase agreement with Corner Brook
- 10 Pulp and Paper Limited ("CBPP") as directed by the Government of Newfoundland and Labrador. The
- 11 power purchase agreement with CBPP provides Hydro with 80 GWh of non-firm energy from
- 12 October 1, 2025 through March 31, 2026 inclusive.<sup>59</sup>
- 13 Currently, the Exploits firm capacity is derated to conserve reservoir storage. However, due to high
- 14 inflows throughout November, the level of deration was reduced throughout the month of November
- 15 2025.

20

- 16 Hydro will continue to closely monitor Island storage and inflows at both the overall system and the
- 17 individual reservoir levels to ensure the continued operation of its hydroelectric assets throughout the
- 18 winter season at full rated output. At this time, additional thermal generation or the use of standby
- 19 generation is not deemed to be required to support reservoir storage.

### 10.0 Conclusion

- 21 Hydro is confident in its ability to serve its customers during the 2025–2026 winter season. The results
- 22 of Hydro's review of the year-to-date planned completion status of its AWP and WR for both the
- 23 Labrador Interconnected System and the Island Interconnected System indicate that Hydro is sufficiently
- 24 positioned for winter. While a small number of WR activities remain for completion, these activities are
- considered low risk.

<sup>&</sup>lt;sup>59</sup> Hydro has also renewed a Capacity Assistance Agreement with Vale for the 2025-2026 winter season.



Page 40

- 1 Hydro's critical spares status leading into the 2025–2026 winter season is strong. For Holyrood TGS, CTs,
- 2 and hydraulic generation, 2,550 critical spares have been identified by Hydro's three generation
- operations areas. Of this total, 2,524 items are in stock (>99%) and 26 items are in the procurement
- 4 process, and Hydro considers the risk to WR associated with critical spares which are not in stock to be
- 5 low.
- 6 Additionally, for the Muskrat Falls generation assets, 1,424 critical spares have been identified; 1,076
- 7 items are in stock and 348 items are in the procurement process. As previously reported, a significant
- 8 fire this spring in the community of Happy Valley-Goose Bay resulted in the total loss of the storage
- 9 facility housing Hydro's Muskrat Falls generation critical spares.
- 10 Hydro's regulated generating sources were available by December 1, 2025, with the exception of Unit 3
- at the Holyrood TGS, and Bay d'Espoit Units 1 and 2. Unit 3 is undergoing major overhaul of the steam
- turbine and valves, and Hydro has worked with the contractor to expedite its return to service date to
- late-January 2026. Bay d'Espoir Units 2 and 1 are expected to return to service on December 22, 2025
- and January 12, 2026, respectively. Hydro will continue to monitor progress and mitigate work
- 15 execution and operational risks.
- 16 Hydro continues to track remaining work activities and will provide an update to the Board in January
- 17 2026.



### Appendix A

Status of Capital Projects and Programs Related to Winter Readiness






### Status of Planned Winter Readiness Scope in 2025 Capital Projects and Programs on the Island and Labrador Interconnected Systems

**Expected Completion of** Winter Readiness Scope Asset Category **Project or Program Title** (10-Dec-2025 Update) Regulated Hydraulic Bay d'Espoir - Refurbish Intake 1 (2024-2025) 23-Dec-2025 Generation Bay d'Espoir - Overhaul Hydraulic Units (2025) Bay d'Espoir - Penstock 1 Life Extension Regulated Thermal Complete Holyrood - Upgrade Unit 1 Control System (2024-2025) Generation Holyrood - Overhaul Unit 1 Turbine Valves and Generator (2024) Complete Holyrood - Perform Boiler Condition Assessment and Miscellaneous Upgrades (2025) Complete Holyrood - Perform Level 2 Condition Assessment – Stage 1 & 2 Cooling Water Sump Structures (2025) Complete Holyrood - Overhaul Major Pumps (2025) 31-Jan-2026 Holyrood - Overhaul Turbine and Valves - Unit 3 (2025) Complete Regulated Terminal Various Locations - Replace Terminal Station Battery Banks and Chargers (2024-2025) Stations Wabush - Perform Major Inspection – Synchronous Condenser 2 (2025–2026) Complete Various Locations - Upgrade Power Transformers (2024-2025) Muskrat Falls Various Locations – Replace Turnbuckles and Install Airflow Spoilers Complete Transmission Assets

### Appendix B

**Generation Outage Schedule** 





Holyrood G2 was derated to 163 MW due to water flow issues. Water flow

Corner Brook Pulp and Paper Limited ("CBPP").

<sup>5</sup>24.7 MW includes Hawkes Bay (5 MW), Holyrood Diesels (10 MW), and St. Anthony (9.7 MW).

Available Island Capacity only includes Island Resources and does not include any contribution from Soldiers , 119.3 MW includes Newfoundland Power hydro (77.8 MW) and Newoundland Power Standby (41.5 MW).

\* Maximum LL contribution to bland reserves at pask is a function of island bad, LL operating mode, number of available Muskraf falls units and Martime Link exports, and is measured at Solder's Pond.
\*\*Ne Hydrob as reports to use the Les comon limited and ring a monopout outgag, which would increase the "Nasimum LL Contribution to bland Reserves at Peak."
\*\*September and october Teat bland Reserves include CRPP Capacity Assistance (80 MW) and System Voltage Reduction (20 MW).
\*\*Howenther and December Teat is bland Reserves include CRPP Capacity Assistance (80 MW) and System Voltage Reduction (20 MW). Island Link, Happy Valley or Muskrat Falls Units.

### Appendix C

**Critical Spares Status Listing for Thermal Generation** 



### Appendix C

**Critical Spares Status Listing for Thermal Generation** 



### Critical Spares - Thermal Generation<sup>1</sup>

	Accod			Orch 3 Indising		
	Asset			Critical Spare		
System	Sub-System	Asset	Defined Spare	Notes	Inventory Description	Inventory Status
Raw and Makeup Water System & Water Treatment Plant   Demineralization System	Demineralization System	Instrumentation/Controls	Sodium Monitor	Non-Stock is OK since there are non critical uses for this TX which can be	ANALYZER, ORION 2111LLEN	Procurement Ongoing
Units 1 & 2 Air & Flue Gas	Rotary Air Heaters	Drive System	Coupling		COUPLING,STEELFLEX 1-1/8 S- Procurement Ongoing 4	Procurement Ongoing
Units 1 & 2 H.P. Feedwater System	Boiler Feed	Boiler Feed Pumps - Unit 1 E & W	Element Assembly (Volute)	Rebuildable Item If this is not in stock, it is out for rebuild.	ELEMENT ASSY, VOLUTE/ROTATING	Procurement Ongoing
Turbine Generator System Stage 2	Governor	Governor	Bushing		BUSHING, HITACHI	Procurement Ongoing
Turbine Generator System Stage 2	Governor	Governor	Bushing		BUSHING, HITACHI	Procurement Ongoing
Turbine Generator System Stage 2	Governor	Governor	Bearing		BEARING, HITACHI LOAD LIMIT Procurement Ongoing	Procurement Ongoing
Turbine Generator System Stage 2	Governor	Governor	Bearing		BEARING, HITACHI LOAD LIMIT Procurement Ongoing	Procurement Ongoing
Turbine Generator System Stage 2	Governor	Governor	Piston		PISTON RING, HITACHI	Procurement Ongoing
Turbine Generator System Stage 2	Governor	Governor	Bearing		BEARING,BALL HITACHI	Procurement Ongoing
Turbine Generator System Stage 2	Governor	Governor	Bearing		BEARING,BALL HITACHI	Procurement Ongoing
Turbine Generator System Stage 2	Governor	Governor	Oil Seal		OIL SEAL,HITACHI	Procurement Ongoing
Turbine Generator System Stage 2	Turbine Lube Oil System	Shaft Driven Oil Pump	O-Ring		O-RING, HITACHI	Procurement Ongoing
Turbine Generator System Stage 2	Turbine Lube Oil System	Shaft Driven Oil Pump	Ring		RING,HIT 10P 067-551-13	Procurement Ongoing
Turbine Generator System Stage 2	Turbine Lube Oil System	Shaft Driven Oil Pump	Ring		RING,HIT 10P 067-551-17	Procurement Ongoing
Turbine Generator System Stage 2	Turbine Lube Oil System	Shaft Driven Oil Pump	Ring		RING, HIT 10P 067-551-18	Procurement Ongoing
Turbine Generator System Stage 2	Turbine Lube Oil System	Auxiliary Oil Pump	Motor	Refurbishable item. If it is not in stock, it MOTOR,AUX OIL YELLOW is out for refurbishment.		Procurement Ongoing
Turbine Generator System Stage 2	Main Steam Chest Assembly	Control Valve - Lower	Crosshead		CROSSHEAD, HIT 10P0612283	Procurement Ongoing
Turbine Generator System Stage 2	Main Steam Chest Assembly	Stop Valves	Gasket		GASKET,HIT 10P-038-197-16	Procurement Ongoing
Turbine Generator System Stage 2	Main Steam Chest Assembly	Stop Valves	Gasket		GASKET,HIT 10P-038-197-71	Procurement Ongoing
Turbine Generator System Stage 2	Main Steam Chest Assembly	Stop Valves	Seal Ring		SEAL RING,10P-038-197/14	Procurement Ongoing



## Critical Spares - Thermal Generation $^{\mathbf{1}}$

	Inventory Status	Procurement Ongoing	Procurement Ongoing	Procurement Ongoing	Procurement Ongoing	Procurement Ongoing	Procurement Ongoing
	Inventory Description	BUSHING,HIT 10P0611582	BUSHING,HIT 10P0611586	BUSHING,HIT 10P06115814 Procurement Ongoing	RIVET,HIT 10P-061-158-63	PIN,HIT 10P06115872	BODY,VALVE MASON 37- 79264
Critical Spare	Notes						
	Defined Spare	Bushing	Bushing	Bushing	Rivet	Pin	Воду
	Asset	Reheat/ICV Valves	Reheat/ICV Valves	Reheat/ICV Valves	Reheat/ICV Valves	Reheat/ICV Valves	DA Recirculation Block Valve
Asset	Sub-System	Reheat Steam Chest Assembly	Reheat Steam Chest Assembly	Reheat Steam Chest Assembly	Reheat Steam Chest Assembly	Reheat Steam Chest Assembly	Boiler Feed
	System	Turbine Generator System Stage 2	Turbine Generator System Stage 2	Turbine Generator System Stage 2	Turbine Generator System Stage 2	Turbine Generator System Stage 2	Unit 3 H.P. Feedwater System

A detailed listing of all critical spares for Thermal Generation is available within Appendix C of "Reliability and Resource Adequacy Study Review - 2025–2026 Winter Readiness Planning Report," Newfoundland and Labrador Hydro, October 14, 2025. ("October WR Report").

### Appendix D

Status of Winter Readiness Testing of Plant and Equipment Testing for Thermal Generation



## newfoundland labrador hyddro

### Holyrood Thermal Generating Station Winter Readiness Testing

2-Dec-25

**Balance of Plant** 

Status of Test

Unit 2

Unit 1

Plant: Holyrood Operations				
Following Annual Outages, Unit is Run Up, Synchronized and all Systems Verified Before Operating Status Determined, as per Energy Control Centre ("ECC"), Prior to Coming Winter Operating Season to Ensure Preparedness. A Unit Load Test is Performed at This Time.	٨	>	n/s	N/A
Black Start Test of the Black Start Systems is Performed Prior to the Winter Operating Season	N/A	N/A	N/A	>
Perform Megger Testing of 600 V Motors Prior to the Winter Operating Season	N/A	N/A	N/A	N/A
	;	;		,
Boiler Service Pressure Test Pertormed as Required by Regulator	<b>\</b>	>	s/n	N/A
Safety Valves Testing as Required (Post Start-Up)	>	>-	n/s	A/N
Boiler Operational Offline High/Low Drum Level Trip Tests	٨	>	n/s	N/A
Hydrogen (" $\mathrm{H_2}$ ") Emergency Venting Valving	٨	λ	n/s	N/A
Breaker and Disconnect Operation Verified by Operations Department and Whitbourne Crew	٨	>	n/s	N/A
Service Air and Instrument Air Systems				
All Stationary Air Compressors Available	N/A	N/A	N/A	z
All Portable Air Compressors Available	N/A	N/A	N/A	Y
Air Compressor Operational Checks Performed (e.g., Oil Levels, Cooling Water, etc.)	N/A	N/A	N/A	Ь
Air Compressor Standby/Sequencing Capability	N/A	N/A	N/A	٨
Raw and Makeun Water System				
Quarry Brook Dam Integrity	A/N	N/A	N/A	>
Raw Water Sump Water Supply Control Valve Operational	N/A	N/A	N/A	>
Raw Water Pumps Operational	N/A	N/A	N/A	>
Adequate Supply of Chemicals (1172, 1179, Polymer, etc.)	N/A	N/A	N/A	<b>&gt;</b>
1172, 1179, Polymer Injection Pumping Sets, Pumps, Valves, Lines, Agitators, etc. Operational	٨	λ	λ	λ
Portable Diesel Pump Check of Emergency Plant Water Supply from Quarry Brook Dam	N/A	N/A	N/A	Ь
Adequate and Readily Available Supply of Hoses for the Portable Diesel Pump from Quarry Brook Dam to	N/A	N/A	N/A	>-

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

N/A - Not Applicable for specific unit or Balance of Plant, as indicated.

Plant

## hydro

### Holyrood Thermal Generating Station Winter Readiness Testing

2-Dec-25

**Balance of Plant** 

Status of Test

Unit 2

Unit 1

Raw and Makeup Water System and Water Treatment Plant				
Instrumentation and Controls Operational	У	٨	n/s	N/A
Analytical Rack Sample Cooler Filters Cleaned/Replaced as Required	γ	Υ	n/s	N/A
Analytical Rack Sample Coolers Cooling Water In Service	Υ	<b>\</b>	n/s	N/A
Two Sample Cooling Water Pumps Availability	N/A	N/A	N/A	<b>\</b>
Clarifier				
Clarifier Recirculator, Variable Frequency Drive ("VFD") Motor, VFD Controller	N/A	N/A	N/A	>
Clarifier Recirculator Scraper	N/A	N/A	N/A	>
Clarifier Badger Meter and Clearwell Instrumentation	N/A	N/A	N/A	<b>\</b>
Sand Filters				

Two Clearwell Pumps Available	N/A	N/A	N/A	٨
Demineralization System				
Cation and Anion Trains (A, B and C) Resin Integrity	N/A	N/A	N/A	Ь
Adequate Supply of Chemicals (Caustic Soda, Sulphuric Acid, 1172, 1179, Polymer, etc.)	N/A	N/A	N/A	А
Sulphuric Acid and Caustic Soda Transfer Pumps, Valves, Lines, etc.	N/A	N/A	N/A	А
Sulphuric Acid and Caustic Soda Regeneration Sets, Pumps, Valves, Lines, etc.	A/N	N/A	N/A	Z
Caustic Injection Pumping Sets, Pumps, Valves, Lines, Agitators, etc.	N/A	N/A	N/A	А
Brine Injection Pumping Sets, Pumps, Valves, Lines, Agitators, etc.	N/A	N/A	N/A	А

N N N

A N N

Sand Filters (Nos. 1, 2 and 3) Valve Operation (Normal and Backwashing, etc.)

Sand Filters (Nos. 1, 2 and 3) Resin Integrity

¥ N N

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

## hydron labrador hydro

Holyrood Thermal Generating Station Winter Readiness Testing

2-Dec-25

**Balance of Plant** 

Status of Test

Unit 2

Unit 1

Reserve Feedwater System ("RFW")				
RFW Transfer Pump Oil Normal Operating Level	٨	>	<b>&gt;</b>	N/A
RFW Transfer Pumps Operational	٨	>	n/s	N/A
Circulating Water ("CW") and Screen Wash System				
Vacuum Seal Pits Operational	٨	>	n/s	N/A
All CW Travelling Screens Operational	>	>	n/s	N/A
CW Pump Motorized Discharge Valves 'Manual' and 'Auto', 'Cracked' Position Operation Verified	>	>	n/s	N/A
CW Pump Motors Oil Normal Operating Level	<b>&gt;</b>	>	n/s	N/A
CW Pumps Operational	٨	<b>\</b>	n/s	N/A
CW Pump Discharge Vacuum Breakers Operational	٨	٨	n/s	N/A
CW Travelling Screens Wash Pumps Operational	Υ	<b>&gt;</b>	n/s	N/A
Condenser Flushed	٨	>	n/s	N/A
Condenser Backwashed	٨	<b>&gt;</b>	n/s	N/A
General Service ("GS") Coolers Backwashed, Cleaned, etc.	٨	٨	n/s	N/A
Turbine/Generator ("TG") Coolers Backwashed, Cleaned, etc.	Y	٨	n/s	N/A
Vacuum Pump Coolers Backwashed. Cleaned. etc.	٨	<b>\</b>	n/s	N/A

Boiler				
Pre-Outage Valve Survey Conducted of Boiler Drains	У	Υ	λ	N/A
Service Pressure Test on Boiler for Tube Leaks	٨	Υ	s/n	N/A

Condenser Air Extraction System				
Vacuum Pumps Available and Tested for Standby 'Auto-Start'	>	>	n/s	N/A
Vacuum Pump Seal Water Tank Water Level Controller Operational	>	٨	n/s	N/A
Vacuum Pump Seal Water Pump Operational	<b>\</b>	γ	n/s	N/A
Condenser Vacuum Breakers Operational	У	Υ	n/s	N/A

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

## hydro

## Holyrood Thermal Generating Station Winter Readiness Testing

2-Dec-25

**Balance of Plant** 

Status of Test

Unit 2

Unit 1

High Pressure ("HP") Feedwater System				
Boiler Feed Pumps				
Boiler Feed Pumps Available	>	>-	n/s	N/A
Boiler Feed Pump Oil Tank Normal Operating Level and Checked for Moisture Content	>	>	n/s	N/A
Boiler Feed Pump Auxiliary Oil Pumps Available	<b>&gt;</b>	>	n/s	N/A
Boiler Feed Pump Suction Valves and Limit Switches	>	>	n/s	N/A
Boiler Feed Pump Emergency Gland Seal Injection Pump Available	>	>	n/s	N/A
Boiler Feed Pump Emergency Gland Seal Pump Oil Normal Operating Level	>	>	n/s	N/A
Boiler Feed Pump Gland Seal Water Available from the Emergency Pump and Condensate Extraction Pumps	>	>	n/s	N/A
Boiler Feed Pump Gland Seal Water Control Valve Operational	<b>\</b>	>	n/s	N/A
Boiler Feed Pump Gland Seal Water Drains Tank Level Float Operated Valve Operational (Units 1 and 2)	γ	٨	N/A	N/A
Boiler Feed Pump Gland Seal Water Transfer Pumps Operational (Units 1 and 2)	>	>	N/A	N/A
Boiler Feed Pump Gland Seal Water Drains Tank Level Control Valve Operational (Unit 3)	N/A	N/A	n/s	N/A
Boiler Feed Pump Gland Seal Water Transfer Pumps Operational (Unit 3)	N/A	N/A	n/s	N/A
Boiler Feed Pump Recirculation Control Valves Operational	γ	٨	n/s	N/A
Boiler Feed Pump Motorized Discharge Pilot and Main Valves Operational	٨	>	n/s	N/A
Low Load Feedwater Isolator and Control Valves Operational	γ	٨	n/s	N/A
Main Feedwater Isolator and Control Valves Operational	γ	٨	n/s	N/A
HP Heater Motorized Valves (Inlet, Outlet and Bypass) Checked for Proper Operation, Sequencing, etc.	γ	٨	n/s	N/A

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

## idland labrador

Holyrood Thermal Generating Station Winter Readiness Testing

2-Dec-25

**Balance of Plant** 

Status of Test

Unit 2

Unit 1

Miscellaneous				
Economizer 'Manual' Operated Valve Operational	λ	٨	n/s	N/A
Economizer Motorized Recirculation Valve Operational (Unit 3)	N/A	N/A	n/s	N/A
Boiler Drum Level Instrumentation Operational	λ	Υ	n/s	N/A
HP Heater Bled Steam Check Valves Operational	<b>*</b>	<b>\</b>	n/s	N/A
Start-Up Desuperheater Steam and Water Valving Operation/Position Verified	<b>*</b>	<b>\</b>	n/s	N/A
Main Steam and Reheat Steam Desuperheater Spray Water Isolators and Control Valves Operational	>	>	n/s	N/A
Auxiliary Steam Desuperheater Spray Water Control Valve Operational	Υ	٨	n/s	N/A
Low Pressure ("LP") Feedwater System				
Condenser				
Condenser Hotwell Makeup/Surplus Control Valves Operation Verified	\ 	>	n/s	N/A
Condenser Hotwell Makeup Motorized Isolating Valve Operation Verified	>	>	n/s	N/A
Condenser Dye Test for Leaks, as Required	γ	γ	n/s	N/A
Ammonia and Cortrol System				
Adequate Supply in Place	<b>*</b>	<b>\</b>	n/s	N/A
Pumps Operational	У	γ	n/s	N/A
Control Instrumentation Operational	λ	Υ	n/s	N/A
Condensate Extraction Pumps				
Condensate Extraction Pumps Available	λ	Υ	n/s	N/A
Condensate Extraction Pump Motors Bearing Oil Normal Operating Level	У	Υ	n/s	N/A
Condensate Extraction Pump Motor Cooling Water Available (Unit 3)	N/A	N/A	n/s	N/A

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

hydro hydro

2-Dec-25

Status of Test

Unit 2

Unit 1

**Balance of Plant** 

Condensate Polishers				
Resin Integrity Verified	λ	γ	n/s	N/A
Two Polishers Rinsed and Available	λ	<b>\</b>	n/s	N/A
Valve Operation (Normal and Regenerating, etc.)	<b>\</b>	>	n/s	N/A
Regeneration System Skids Available (Valving, Pumps, Plowers, Tanks, etc.)	>	>	n/s	N/A
Condensate Polisher Bypass Control Valve Operational	У	Υ	s/n	N/A
LP Heaters				
Low Load Recirculation Control Valve Operation	λ	<b>\</b>	n/s	N/A
Deaerator				
Deaerator Normal Operating Level	λ	Υ	n/s	N/A
Deaerator Steam Coil Operational	<b>&gt;</b>	>	n/s	N/A
Deaerator Pegging Steam Operational	λ	>	n/s	N/A
Deaerator Low Level Trip Test	<b>*</b>	٨	n/s	N/A

Miscellaneous					_
Condenser Flash Tank Control Valve Operation/Position	γ	γ	n/s	N/A	_
Turbine LP Exhaust Hood Spray Motorized Valve Operation	γ	γ	n/s	N/A	_
Start-Up Desuperheater Steam and Water Valving Operational (Units 1 and 2)	γ	γ	N/A	N/A	_
LP Heater Bled Steam Check Valves Operational	γ	γ	n/s	N/A	_
Bled Steam and Heater Drains System					_
LP and HP Instrumentation and Control Operational	γ	У	n/s	N/A	_
LP and HP Heater Level Control Operational	γ	γ	n/s	N/A	_
LP Heater Condensate Drains Pumps Operational	N	N	Ν	N/A	_
#4 HP Heater Condensate Drains Pump Operational	N	γ	n/s	N/A	_

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

ΑN V/A V/A



Holyrood Thermal Generating Station Winter Readiness Testing

2-Dec-25

**Balance of Plant** 

Status of Test Unit 3

Unit 2

Unit 1

Air and Flue Gas System				
Instrumentation and Control Operational	γ	λ	n/s	N/A
Forced Draft ("FD") Fans and Air Dampers				
Two FD Fans Available	<b>&gt;</b>	λ	n/s	A/N
Bearing Oil Normal Operating Level	γ	λ	n/s	N/A
Cooling Water on to Fans	>	γ	n/s	N/A
Stroke Variable Inlet Vanes	>	γ	n/s	N/A
Stroke Discharge Dampers	>	λ	n/s	N/A
FD Fan Motor Variable Speed Drives Operational	N/A	N/A	N/A	N/A
All Burner Auxiliary Air Dampers/Positioners Operation (Units 1 and 2)	>	γ	N/A	N/A
All Elevation Air Flow Dampers/Positioners Operation (Unit 3)	N/A	N/A	n/s	A/N
Rotary Air Heaters				
Rotary Air Heaters Operational	Υ	λ	n/s	N/A
Rotary Air Heaters Bearing Oil (Top and Bottom) Normal Operating Level	γ	λ	n/s	N/A
Rotary Air Heaters Bearing Cooling Water On	٨	λ	n/s	N/A
Rotary Air Heaters Electric Motor Drives Operational	Υ	λ	n/s	N/A
Rotary Air Heaters Air Supply to Air Heater Air Motor Drives Open	٨	λ	n/s	N/A
Rotary Air Heaters Start-Up of Air Motor Drive Upon Loss of Alternating Current ("AC") Power Supply to the Normal Operating Electric Drive Motor	<b>&gt;</b>	Å	n/s	N/A
Rotary Air Heaters Steam Supply Control Valves Operational (*Note: Two Steam Supplies on Units 1 and 2)	<b>\</b>	٨	n/s	N/A
Rotary Air Heaters Sootblowers Operational	γ	λ	n/s	N/A

Sootblower Control Panel Operational	Υ	Υ	S/n
Sootblowers Steam Supply Control Valve Operational	γ	γ	n/s
Sootblowers Overhauled During Annual Outage Verify Operation (e.g., Rotation, Travel Advancing/Retracting from Furnace, Leaks, etc.) First Time Unit is Placed Online	γ	٨	n/s

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

N/A - Not Applicable for specific unit or Balance of Plant, as indicated.

Sootblower Control Panel Operational

**Boiler Sootblowing System** 



2-Dec-25

**Status of Test** 

	Unit 1	Unit 2	Unit 3	Balance of Plant
Light Fuel Oil System				
Hydro Pad Operational	λ	٨	n/s	N/A
Light Oil Pumps Available	٨	>	n/s	N/A
Pumps, Valves (Including Control and Trip), Lines, Strainers, Pressure (Locally and UCB)	<b>\</b>	>	n/s	N/A
Check Light Oil Supply and Return Lines to/from Plant Respectively	>	>	n/s	N/A
Suction Strainers Cleaned with Covers Secured	<b>\</b>	>	n/s	N/A
Ignitors Cleaned, Securely in Place with Associated Lines Securely Fastened	٨	>	n/s	N/A
Ignitors all Checked for Operation During Unit Start-Up (e.g. Ignitor Control Box, Valve Operation, Lighting, etc.)	<b>\</b>	>	n/s	N/A

Fuel Oil Delivery System, Auxiliary Steam and Fuel Oil Piping System				
Adequate Heavy Oil Storage	N/A	A/N	A/N	<b>*</b>
Heavy Oil Piping from Dock to Tankfarm, Tankfarm to Plant Day Tank and Day Tank to Heavy Oil Sets	N/A	N/A	N/A	<b>\</b>
Adequate Light Oil Storage	N/A	N/A	N/A	<b>\</b>
Light Oil Piping from Road Tanker Transfer Pump to Tanks and from Tanks to Light Oil Sets in Plant	N/A	N/A	N/A	N/A
All Storage Tanks Suction Heaters Available when Required	N/A	N/A	N/A	λ
All Storage Tanks Flatform Heaters Available when Required	N/A	N/A	N/A	Y/N
Auxiliary Steam for Suction Heaters Available	N/A	N/A	N/A	λ
Auxiliary Steam for Flatform Heaters Available	N/A	N/A	N/A	N/A
Auxiliary Steam for Heat Tracing Available	N/A	N/A	N/A	Y
Electrical Heat Tracing for Fuel Oil Lines Available	N/A	N/A	N/A	Y
Day Tank Supply Line Trip Valve Tested	N/A	N/A	N/A	Y
Day Tank Available to Receive Oil	N/A	N/A	N/A	λ
Day Tank Steam Coil Available	N/A	N/A	N/A	λ

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

## hydro

Holyrood Thermal Generating Station Winter Readiness Testing

2-Dec-25

Unit 2 Unit 3 Balance of Plant

Unit 1

**Status of Test** 

			<b>-</b>	
Fuel (Heavy) Oil System				
Fuel Oil Heating Sets	γ	γ	n/s	N/A
Fuel Oil Heaters Available	γ	γ	n/s	N/A
Fuel Oil Heaters Cleaned and Inspected	٨	>	n/s	N/A
Steam Supply to Heavy Oil Set Heaters Available as Required	γ	>	n/s	N/A
Fuel Oil Heaters Temperature Steam Control Valve Operational	γ	>	n/s	N/A
Suction Strainers Cleaned (including standby and extras) with Covers Secured	γ	γ	n/s	N/A
Fuel Oil Accumulator Operational	Ν	Z	n/s	N/A
Fuel Oil Pumps Available	Υ	>	n/s	N/A
Pumps 'Auto-Start' Check Offline	٨	>	n/s	N/A
Header Pressure Control Valve Operational	٨	>	n/s	N/A
Fuel Oil Meter Operational	γ	٨	n/s	N/A
Fuel Oil Supply Control, Trip, Long and Short Recirculation Valves				
Fuel Oil Supply Control Valve Operational	γ	А	n/s	N/A
Fuel Oil Trip Valve Operational	γ	γ	n/s	N/A
Fuel Oil Long Recirculation Valve Operational (Units 1 and 2)	γ	٨	N/A	N/A
Fuel Oil Short Recirculation Valve Operational (Units 1 and 2)	γ	γ	N/A	N/A
Elevation Fuel Oil Trip Valves Operational (Unit 3)	N/A	N/A	n/s	N/A
Elevation Fuel Oil Minimum Supply Control Valves Operational (Unit 3)	N/A	N/A	n/s	N/A
Elevation Fuel Oil Supply Control Valves Operational (Unit 3)	N/A	N/A	n/s	N/A
Main Fuel Oil Recirculation Valve Operational (Unit 3)	N/A	N/A	n/s	N/A
Elevation Recirculation Valves Operational (Unit 3)	N/A	N/A	s/n	N/A
Burners				
All Burners Cleaned, Securely in Place with Associated Lines Securely Fastened	У	γ	n/s	N/A
All Burners Checked for Operation During Unit Start-Up (e.g. Advancing/Retracting, Valve Operation, Lighting, etc.)	>	>-	n/s	N/A
All Burner Tilts Checked for Operation (Units 1 and 2)	٨	<b>\</b>	N/A	N/A

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.



2-Dec-25

**Balance of Plant** 

Status of Test

Unit 2

Unit 1

Fuel Additive System				
Adequate Supply Available	A/N	N/A	N/A	N/A
Pumps Available	N/A	N/A	N/A	N/A
Tanks, Agitators, etc. Available	N/A	N/A	N/A	N/A
GS System				
GS Heat Exchangers Backwashed, Cleaned, etc.	<b>&gt;</b>	٨	n/s	N/A
Stage I GS Plate Cooler Strainers Cleaned	>	>	n/s	N/A
Stage I GS 'Auto-Clean' Strainer Operational	N/A	N/A	N/A	N/A
Stage I GS Duplex Strainers Cleaned	>-	>	N/A	N/A
GS Pump Suction Strainers Cleaned	>	>	n/s	N/A
GS Pump Oil Normal Operating Level	>	>	n/s	N/A
GS Pumps Available and Tested for Standby 'Auto-Start'	<b>X</b>	Υ	n/s	N/A
TG Auxiliary Cooling System				
TG Head Tank Normal Operating Level	>	>	n/s	N/A
Turbine Lube Oil Coolers Operational	>	>	n/s	N/A
TG Heat Exchangers Backwashed, Cleaned, etc.	<b>&gt;</b>	>	n/s	N/A
TG Pump Oil Normal Operating Level	<b>\</b>	٨	n/s	N/A
TG Pumps Available and Tested for Standby 'Auto-Start'	>	>	n/S	A/N

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

2-Dec-25



Status of Test
Unit 1 Unit 2 Unit 3 Balance of Plant

TG System				
Hydraulic System Units 1 and 2				
Hydraulic System Accumulators Operational	<b>\</b>	λ	N/A	N/A
Hydraulic System Storage Tank Normal Operating Level and Checked for Moisture Content	>	>	N/A	N/A
Hydraulic System Storage Tank Air Purging of Moisture in Place	<b>&gt;</b>	٨	N/A	N/A
Hydraulic Set Primary, Secondary Filter Indications Ok	Y	λ	N/A	N/A
Two Hydraulic Fluid Pumps Availability	λ	λ	N/A	N/A
Hydraulic Pump Auto-Start Testing	٨	γ	N/A	N/A
Two Hydraulic Fluid Pump Coolers Availability	٨	γ	N/A	N/A

ValvesPre-Outage Valve Survey Conducted of Boiler DrainsYYS/UTurbine Main Stop Valve Testing (Units 1 and 2)YYN/ATurbine Two Main Stop Valves Testing (Unit 3)N/AN/AN/AS/UTurbine 'Left-Hand' and 'Right Hand' Reheat Stop and Intercept Control Valve Testing VerifiedYYS/UTurbine Six Main Control Valve Operation (Units 1 and 2)YYN/ATurbine Four Main Control Valve Operation (Unit 3)N/AN/AS/U						
γ         γ	Valves					
Y Y Y Y Y Y Y Y Y Y Y Y Y Y Y Y Y Y Y	Pre-Outage Valve Survey Conducted of Boiler Drains	λ		٨	n/s	N/A
N/A	Turbine Main Stop Valve Testing (Units 1 and 2)	λ _		<b>&gt;</b>	N/A	N/A
Y Y Y N/N N/A	Turbine Two Main Stop Valves Testing (Unit 3)	//N	A	N/A	n/s	N/A
Y Y Y N/A N/A N/A	Turbine 'Left-Hand' and 'Right Hand' Reheat Stop and Intercept Control Valve Testing Veri	λ р		٨	n/s	N/A
N/A N/A	Turbine Six Main Control Valve Operation (Units 1 and 2)	λ		٨	N/A	N/A
	Turbine Four Main Control Valve Operation (Unit 3)	//N	A	N/A	n/s	N/A
Turbine Blowdown Valve Operation S/U	Turbine Blowdown Valve Operation	λ		Υ	s/n	N/A

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.



2-Dec-25

**Balance of Plant** 

Status of Test

Unit 2

Unit 1

Lubricating System				
Lube Oil Tank Normal Operating Level and Checked for Moisture Content	<b>&gt;</b>	>	n/s	N/A
Portable Centrifuge Operational	N/A	N/A	N/A	N/A
Lube Oil Tank Vapor Extractor Operation	>	>	n/s	N/A
Bowser Oil Conditioner Vapor Extractor Operation (Units 1 and 2)	n/s	n/s	N/A	N/A
Two ac Lube Oil Pumps Available and Tested for Standby 'Auto-Start' (Units 1 and 2)	>	>	N/A	N/A
Direct Current ("DC") Pump Testing and Starting from UCB (Units 1 and 2)	>	>	N/A	N/A
Verify Discharge Pressure of Each AC Lube Oil Pumps (Locally and UCB) (Units 1 and 2)	>	>	N/A	N/A
Verify Discharge Pressure of DC Lube Oil Pump (Locally and UCB) (Units 1 and 2)	<b>&gt;</b>	>	N/A	N/A
Jacking Oil Pump Testing and Starting from UCB (Unit 3)	N/A	N/A	n/s	N/A
Verify Discharge Pressure of Jacking Oil Pump (Locally and UCB)	N/A	N/A	n/s	N/A
Auxiliary Oil Pump ("AOP") Testing and Starting from UCB and Turbine Lube Oil Tank (Unit 3)	N/A	N/A	n/s	N/A
Verify Discharge Pressure of AOP Pump (Locally and UCB) (Unit 3)	N/A	N/A	n/s	N/A
AC Pump Testing and Starting from UCB and Turbine Lube Oil Tank (Unit 3)	N/A	N/A	n/s	N/A
Verify Discharge Pressure of AC Flushing Oil Pump (Locally and UCB) (Unit 3)	N/A	N/A	n/s	N/A
DC Pump Testing and Starting from UCB and Turbine Lube Oil Tank (Unit 3)	N/A	N/A	n/s	N/A
Verify Discharge Pressure of DC Flushing Oil Pump (Locally and UCB) (Unit 3)	N/A	N/A	s/n	N/A

Barring/Turning Gear				
Turning Gear Operation Verified	γ	γ	n/s	N/A
Perform Trip Test of Turning Gear	Υ	Υ	n/s	N/A

٨	n/s	∀/N
<b>\</b>	n/s	N/A
	> >	ν / s/υ

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

2-Dec-25



Status of Test
Unit 1 Unit 2 Unit 3 Balance of Plant

H <sub>2</sub> and Carbon Dioxide ("CO <sub>2</sub> ") System				
H <sub>2</sub> Generation and Storage System				
System in Operation	N/A	N/A	N/A	٨
Electrolyzer/H <sub>2</sub> Generator Operational	N/A	N/A	N/A	N/A
Chiller Operational	N/A	N/A	N/A	N/A
DI Water Purifier Operational	N/A	N/A	N/A	N/A

H <sub>2</sub> and CO <sub>2</sub> Bulk Packs				
Adequate H <sub>2</sub> Bulk Packs on Hand for Contingency Purposes	N/A	N/A	N/A	٨
CO <sub>2</sub> Adequate Bulk Packs on Hand	N/A	N/A	N/A	٨

Generator Exciter Operation Checked Offline and Online  Seal Oil System Tested with 'Air' on Generator in Preparation for Leak Testing  Y  Y  Y  Y  Y  AC Seal Oil Regulator Operational  AC Seal Oil Pumps Available and Tested for Standby 'Auto-Start' (Units 1 and 2)  AC Seal Oil Pump Available (Unit 3)	> > >	n/s n/s	N/A N/A N/A
on for Leak Testing Y  Y  Start' (Units 1 and 2) Y  N/A	> > >	0/s	N/A N/A
Y nd Tested for Standby 'Auto-Start' (Units 1 and 2) N/A	> >	N/N	N/A
	>	V/ N	V/14
9/N	•	( )	N/A
	N/A	n/s	N/A
DC Seal Oil Pump Available and Tested for Standby 'Auto-Start'	<b>\</b>	n/s	N/A
Seal Oil Vacuum Pumps Available	<b>\</b>	n/s	N/A
Vacuum Tank Level Control Operational	<b>\</b>	s/n	N/A
$H_2$ System in Operation and/or Adequate Bulk Packs on Hand for Contingency Purposes	N/A	N/A	٨
CO <sub>2</sub> Adequate Bulk Packs on Hand N/A N/A N/A N/A	N/A	N/A	<b>&gt;</b>
Leak Testing Performed Prior to 'Gassing Up' Generator	<b>&gt;</b>	n/s	N/A
Purity, Dew Point, etc. Instrumentation Operation Verified	<b>&gt;</b>	s/n	N/A

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

# hydro

Holyrood Thermal Generating Station Winter Readiness Testing

2-Dec-25

**Balance of Plant** 

Status of Test

Unit 2

Unit 1

Plant 129 V System 129 V Battery Chargers Checked Stage I and II 129 V Battery Chargers Checked Stage I and II Y				
	<b>-</b>	Υ	Υ	>
21. 27. 27. C	٨	γ	Υ	٨
Plant 258 V System				
258 V Battery Banks Checked Stage I and II	<b>-</b>	>	>	>
258 V Battery Chargers Checked Stage I and II	<b>*</b>	٨	Υ	Υ
Plant Uninterrupted Power Supplies ("UPS")				
Nos. 1, 2, 3 and 4 UPS including Batteries, Cooling Fans, etc., Checked	٨	γ	γ	Υ
Emergency Diesel Generators				
Stage I and II Emergency Diesel Generators Tested for Emergency Stop	N/A	N/A	N/A	Υ
Stage I and II Emergency Diesel Generators Tested for Manual and Auto-Start Operation along with Auto	· · · · · · · · · · · · · · · · · · ·	۷/۱۷	۷/۱۷	>
Breaker Closure as well as Emergency Manual Closing of Breakers	<u> </u>	۲ ۲	<u> </u>	-
Diesel Bus Tie Breaker Operation Verified N/	N/A	N/A	N/A	Υ
Fire Protection System				
All Fire Protection Zones in Service	N/A	N/A	N/A	У
Fire Control/Alarm Panel Status	N/A	N/A	N/A	Υ
Fire Alarm Beacons Operational N/	N/A	N/A	A/N	>
Diesel Fire Pump Checked for 'Manual' and 'Auto' Start, etc.	N/A	N/A	N/A	٨
Diesel Fire Pump Controller, Charger and Battery Check	N/A	N/A	N/A	٨
Electric Fire Pump Checked for 'Manual' and 'Auto' Start, etc.	N/A	N/A	N/A	У
Electric Fire Pump Controller Check	N/A	N/A	N/A	У
Public Address System Status	N/A	N/A	N/A	<b>\</b>

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage.

Y - Test completed.

## newfoundland labrador hyddro

## Holyrood Thermal Generating Station Winter Readiness Testing

2-Dec-25

**Balance of Plant** 

Status of Test

Unit 2

Unit 1

Holyrood Main Powerhouse				
Backup ECC and Guardhouse Propane Generator	N/A	N/A	N/A	٨
Plant Air Conditioning System				
Control and Relay Rooms	N/A	N/A	A/N	<b>&gt;</b>
UPS #1 Room	N/A	N/A	A/N	>
Generator Excitation and UPS #'s 2, 3 and 4 Room (Unit 3)	N/A	N/A	N/A	<b>*</b>
Plant Heating Steam				
All Systems Operational for When Required	N/A	N/A	A/N	>

S/U - Final confirmation completed during Start Up. When possible, test also completed during annual outage. Y - Test completed.

### Appendix E

Status of Winter Readiness Testing of Plant and Equipment for Hydraulic Generation



## Bay d'Espoir Hydraulic Generating Facility



					Statu	Status of Test			
	Unit 1	Unit 2	Unit 3	Unit 4	Unit 5	Unit 6	Unit 7	Balance of Plant Powerhouse 1	Balance of Plant Powerhouse 2
Following Annual Outages, Unit is Run Up, Synchronized and all Systems Verified Before Operating Status Determined, as per Energy Control Centre, Prior to Coming Winter Operating Season to Ensure Preparedness. A Unit Load Test is Performed at this Time.	20-Dec	20-Dec	>	>	<b>&gt;</b>	<i>&gt;</i>	^	N/A	N/A
All Alternate Sources of Station Service Tested and Available	N/A	N/A	N/A	N/A	N/A	N/A	N/A	>	`
Spherical Valves									
Turbine Main Stop Valve Annual PM Complete	^	>	^	^	`	`	N/A	N/A	N/A
Turbine Main Stop Valve Operational	>	^	<i>&gt;</i>	>	>	^	N/A	N/A	N/A
Service Air and Instrument Air Systems Compressors									
All Stationary Air Compressors Available	A/N	N/A	N/A	A/N	N/A	N/A	N/A	^	>
Air Compressor Operational Checks Performed (e.g., Oil Levels, Cooling Water, etc.)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	>	`
Air Compressor Sequencing Capability Available	N/A	N/A	N/A	N/A	N/A	N/A	N/A	>	>
High Pressure Compressors Available	A/N	N/A	N/A	N/A	N/A	N/A	N/A	^	>
Low Pressure Compressor Available	A/N	N/A	N/A	N/A	N/A	N/A	N/A	`	>
Instrumentation Control and Alarms Operational	N/A	N/A	N/A	N/A	N/A	N/A	N/A	^	>
Turbine/Generator ("TG") Cooling Water Systems									
Cooling Water Pumps Available	^	^	^	^	^	^	N/A	N/A	N/A
Emergency Cooling Water Available Penstock Supply	^	^	^	`	^	^	N/A	N/A	N/A
Cooling Water System Available	`	>	<b>,</b>	`	`	`	^	N/A	N/A
Shaft Seal System Available	`	>	`	>	>	>	`	N/A	N/A
Cooling Water Strainers Inspected and Available	`	>	>	>	`	>	^	N/A	N/A
TG Governor System	-			_					-
Hydraulic System Accumulators Operational	`	>	<b>&gt;</b>	>	`	`	<b>,</b>	N/A	N/A
Governor System Annual PM Complete	^	^	^	>	^	1	^	N/A	N/A
Governor System Available	>	^	<b>&gt;</b>	>	<i>&gt;</i>	^	^	N/A	N/A
Hydraulic Pump(s) Available	>	>	>	>	`>	^	^	N/A	N/A
Generator									
Generator Exciter Operation Checked Offline and Online	20-Dec	20-Dec	^	^	^	^	<i>^</i>	N/A	N/A
Generator Exciter Available	^	^	^	^	^	^	<i>^</i>	N/A	N/A
Brush Condition Verified	>	^	>	>	>	^	^	N/A	N/A

S/U - Final confirmation completed during Start-Up. When possible, test also completed during annual outage. 
<- - Test completed
N/A - Not Applicable

### Bay d'Espoir Hydraulic Generating Facility 1-Dec-25

Status of Test



									****
	Unit 1	Unit 2	Unit 3	Unit 4	Unit 5	Unit 6	Unit 7	Balance of Plant Powerhouse 1	Balance of Plant Powerhouse 2
Lubricating System									
Portable Oil Pump (Jacking)	^	/	^	^	^	^	N/A	N/A	N/A
Oil Level System Generator Metering Available	>	<i>&gt;</i>	<b>&gt;</b>	>	`	>	>	N/A	N/A
Oil Level System Turbine Metering Available	>	>	>	>	>	>	>	N/A	N/A
Alternating Current High Pressure Jacking Oil Pump Available Automatic	N/A	N/A	N/A	N/A	N/A	N/A	`	N/A	N/A
Switch ward / Torminal Station									
Switchyalu/ leininal station	`	`	\	`	`	`	`	.,	
Breakers and Disconnects Operational	>	>	>	>	>	>	>	N/A	N/A
Operate Breaker PM Complete (TRO)	>	>	>	>	>	>	>	N/A	N/A
Intake									
Water Elevation	N/A	N/A	N/A	A/N	A/N	N/A	N/A	>	>
Trashrack System	>	>	>	>	>	`	>	N/A	N/A
Gate Operation	>	>	>	>	>	`	>	N/A	N/A
	20.00	20.00	,	,	`	>	0/14	× 12	4/14
Heating System	Z0-Dec	Z0-Dec	>	>	>	>	N/A	N/A	N/A
Alarm Systems	20-Dec	20-Dec	>	<b>&gt;</b>	>	>	N/A	N/A	N/A
Cailland									
Spinway									
Water Elevation	N/A	N/A	N/A	N/A	N/A	N/A	N/A	`	`
Gate Heating/Ice Away Unit	N/A	N/A	N/A	N/A	N/A	N/A	N/A	^	N/A
Gate Operation	N/A	N/A	N/A	A/N	A/N	N/A	N/A	`	N/A
Emergency (Backup) Diesel Generator	N/A	N/A	N/A	N/A	N/A	N/A	N/A	<i>&gt;</i>	N/A
Emergency Lift Operation and Tested	N/A	N/A	N/A	N/A	N/A	N/A	N/A	^	N/A
Dathan Darke And Dattone Channers									
Dattery Dalins Allu Dattery Chargers									
Plant 129 V System									
129 V Battery Banks Checked	N/A	N/A	N/A	N/A	N/A	N/A	N/A	^	^
129 V Battery Chargers	N/A	N/A	N/A	N/A	N/A	N/A	N/A	^	^
129 V Battery Banks Available	N/A	N/A	N/A	N/A	N/A	N/A	N/A	>	>
70 20 20 20 20 20 20 20 20 20 20 20 20 20									
Plant Uninterrupted Power Supplies ("UPS")									
IIDS Dower Supplies (Inverter NWS)	V/N	<b>∀</b> /N	A/N	N/A	N/A	N/A	V/N	`	A/N

S/U - Final confirmation completed during Start-Up. When possible, test also completed during annual outage.

< - Test completed
N/A - Not Applicable

## Bay d'Espoir Hydraulic Generating Facility 1-Dec-25

2		
1-DUC-1		

Unit 4	Unit 2 Unit 3
--------	---------------

Emergency Diesel Generators									
Emergency Diesel Generators Tested for Emergency Stop	N/A	^	N/A						
Emergency Diesel Generators Tested for Manual and Auto-Start Operation									
along with Auto Breaker Closure as well as Emergency Manual Closing of	A/N	N/A	N/A	N/A	N/A	N/A	A∕N	>	`
Breakers									
Alternate Alternating Current Sources Available	N/A	^	<i>,</i>						
Station Services Available	N/A	N/A	N/A	N/A	N/A	N/A	A/N	^	<b>,</b>
Transfer Alternate Source	N/A	N/A	N/A	N/A	N/A	N/A	A/N	>	<b>&gt;</b>
Plant Air Conditioning System									
Control Rooms	N/A	^	N/A						
Communications Rooms	N/A	^	N/A						
Plant Heating Steam									
All Systems Operational for when Required	N/A	^	<i>&gt;</i>						



# Hydraulic Generating Stations (Remote Units)

1-Dec-25

**Paradise River** 

**Granite Canal** 

Upper Salmon

Hinds Lake

Cat Arm

Status of Test

		Cat Arm		HINGS	HINGS Lake	Opper	Upper salmon	Granit	Granite Canal	Paradis	Paradise Kiver
	Unit 1	Unit 2	Balance of Plant Powerhouse	Unit 1	Balance of Plant	Unit 1	Balance of Plant	Unit 1	Balance of Plant	Unit 1	Balance of Plant
Following Annual Outages, Unit is Run Up, Synchronized and all Systems Verified Before Operating Status Determined, as per Energy Control Centre, Prior to Coming Winter Operating Season to Ensure Preparedness. A Unit Load Test is Performed at this Time.	>	>	N/A	>	N/A	`	N/A	>	N/A	>	N/A
All Alternate Sources of Station Service Tested and Available	N/A	N/A	^	N/A	^	N/A	^	N/A	^	N/A	^
Spharical Values											
Turbine Main Stop Valve Annual PM Complete	>	^	A/N	N/A	N/A	N/A	A/N	N/A	N/A	N/A	N/A
Turbine Main Stop Valve Operational	>	>	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Service Air and Instrument Air Systems Compressors											
All Stationary Air Compressors Available	N/A	N/A	>	N/A	>	N/A	>	N/A	>	A/N	>
Air Compressor Operational Checks Performed (e.g., Oil Levels, Cooling Water, etc.)	N/A	N/A	`	N/A	>	N/A	`	N/A	>	N/A	>
Air Compressor Sequencing Capability Available	N/A	N/A	`	N/A	>	N/A	>	N/A	>	N/A	>
High Pressure Compressors Available	N/A	N/A	<b>,</b>	N/A	<i>&gt;</i>	N/A	^	N/A	^	N/A	^
Low Pressure Compressor Available	N/A	N/A	^	N/A	N/A	N/A	^	N/A	^	N/A	N/A
Instrumentation Control and Alarms Operational	N/A	N/A	~	N/A	^	N/A	^	N/A	^	N/A	^
2 11 0 ((Call)											
I urbine/ Generator ("16") Cooling Water Systems											
Cooling Water Pumps Available	`	^	N/A	^	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Emergency Cooling Water Available Penstock Supply	`	~	N/A	N/A	N/A	^	^	^	`	1	^
Cooling Water System Available	`	^	N/A	^	N/A	^	N/A	^	N/A	~	N/A
TG Pumps Available and Tested for Auto/Manual Start	N/A	N/A	N/A	^	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Shaft Seal System Available	N/A	N/A	N/A	^	N/A	^	N/A	^	N/A	~	N/A
Rotary Strainer Inspected and Available	^	^	N/A	^	N/A	^	N/A	^	N/A	N/A	N/A

TG Governor System											
Hydraulic System Accumulators Operational	^	/	N/A	^	N/A	^	N/A	^	N/A	>	N/A
Governor System Annual PM Complete	>	^	N/A	>	N/A	>	N/A	>	N/A	>	N/A
Governor System Available	<i>&gt;</i>	^	N/A	>	N/A	>	W/A	>	N/A	>	N/A
Hydraulic Pump(s) Available	<i>^</i>	1	N/A	^	N/A	>	W/W	>	N/A	^	N/A

S/U - Final confirmation completed during Start-Up. When possible, test also completed during annual outage.

N/A N/A

N/A Ν Α

N N N

N/A N/A

N/A/N

N/A N/A

Emergency (Backup) Diesel Generator Emergency Lift Operation and Tested

Gate Operation

N A

Ν V A A

# Hydraulic Generating Stations (Remote Units)

1-Dec-25

Balance of Plant

Unit 1

Unit 2

Unit 1

Balance of Plant

Cat Arm

Powerhouse

**Paradise River** 

**Granite Canal** 

Upper Salmon

**Hinds Lake** 

Status of Test

Generator											
Generator Exciter Operation Checked Offline and Online	>	>	N/A								
Generator Exciter Available	>	>	N/A	^	N/A	>	N/A	^	N/A	>	N/A
Brush Condition Verified	`	>	N/A	^	N/A	`	N/A	^	N/A	N/A	N/A
Lubricating System											
Oil Level System Generator Metering Available	^	>	N/A	^	N/A	^	N/A	^	N/A	^	N/A
Oil Level System Turbine Metering Available	>	>	N/A								
Alternating Current High Pressure Jacking Oil Pump Available Automatic	`	>	N/A	`	N/A	>	N/A	`	N/A	N/A	N/A
Micrellaneniis											
Breakers and Disconnects Operational	>	>	N/A								
Operate Breaker PM Complete (TRO)	>	>	N/A								
Control Structure											
Water Elevation	N/A	N/A	N/A	N/A	^	N/A	N/A	A/N	N/A	N/A	N/A
Gate Operation	N/A	N/A	N/A	N/A	>	N/A	N/A	N/A	N/A	N/A	N/A
ntake											
Water Elevation	N/A	N/A	>	N/A	^	N/A	>	N/A	^	N/A	^
rashrack System	>	>	N/A	^	N/A	`	N/A	^	N/A	^	N/A
Gate Operation	>	>	N/A	`>	N/A	>	N/A	>	N/A	>	A/N
Spillway/Bypass											
Water Elevation	N/A	N/A	N/A	N/A	^	N/A	^	N/A	^	N/A	N/A
Gate Heating/Ice Away Unit	N/A	N/A	N/A	N/A	/	N/A	>	N/A	>	N/A	N/A
					*	٠	,		١		-

S/U - Final confirmation completed during Start-Up. When possible, test also completed during annual outage.

### Hydraulic Generating Stations (Remote Units) 1-Dec-25

1									•	
	Cat Arm		HING	linds Lake	Upper	pper salmon	Granit	Granite Canal	Paradis	Paradise Kiver
Jnit 1	Unit 2	Balance of Plant	Unit 1	Balance of	Unit 1	Balance of	Unit 1	Balance of	Unit 1	Balance
		Powerhouse		Plant		Plant		Plant		or Plant

Battery Banks And Battery Chargers											
Plant 129 V System											
129 V Battery Banks Checked	N/A	N/A	<i>^</i>	N/A	^	N/A	^	N/A	^	N/A	^
129 V Battery Chargers	N/A	N/A	1	N/A	^	N/A	^	N/A	^	N/A	^
129 V Battery Banks Available	N/A	N/A	^	N/A	>	N/A	>	N/A	>	N/A	>
N											
Plant 48 V System (Network Services)	•										
48 V Battery Banks Checked	N/A	N/A	<b>&gt;</b>	N/A	`	N/A	`	N/A	`	N/A	`
Emergency Diesel Generators											
Emergency Diesel Generators Tested for Emergency Stop	N/A	N/A	^	A/N	^	N/A	^	N/A	^	N/A	^
Emergency Diesel Generators Tested for Manual and Auto-Start Operation											
along with Auto Breaker Closure as well as Emergency Manual Closing of	N/A	N/A	>	N/A	>	N/A	>	N/A	>	N/A	>
Breakers											
Alternate Alternating Current Sources Available	N/A	N/A	1	N/A	^	N/A	^	N/A	^	N/A	^
Station Services Available	N/A	N/A	1	N/A	^	N/A	^	N/A	^	N/A	^
Transfer Alternate Source	N/A	N/A	^	N/A	^	N/A	^	N/A	^	N/A	^
Plant Air Conditioning System											
Control Rooms	N/A	N/A	>	N/A	>	N/A	>	N/A	>	A/N	>
Communications Rooms	N/A	N/A	^	N/A	`	N/A	`	N/A	>	N/A	N/A
Plant Heating Steam											
All Systems Operational for when Required	N/A	N/A	/	N/A	^	A/N	^	N/A	>	N/A	^

S/U - Final confirmation completed during Start-Up. When possible, test also completed during annual outage.

#### Appendix F

Critical Spares Status Listing for Muskrat Falls Generation





Critical Spare Component	Stock Status
SPRING, COIL ST14110	Procurement Ongoing
SHOE, SIDE GUIDE 60X16 140	Procurement Ongoing
SHOE, SIDE GUIDE 60X16 280	Procurement Ongoing
SHOE, SIDE GUIDE 140X49.150460	Procurement Ongoing
PROFILE, EDGE PROTECTION 3D	Procurement Ongoing
BUMPER,HYDRAULIC	Procurement Ongoing
BEARING,SPHERICAL ROLLER Ø260	Procurement Ongoing
SEAL,RADIAL SHAFT 480X520X20	Procurement Ongoing
SEAL,RADIAL SHAFT 300X340X18	Procurement Ongoing
SEAL,RADIAL SHAFT 290X330X18	Procurement Ongoing
LOAD CELL,25000LB	Procurement Ongoing
MOTOR,DRE100L4 M1A-TB180-CEX	Procurement Ongoing
BUFFER,CELLULAR BUFFER 160Ø	Procurement Ongoing
COUPLING,ROTARY SWITCH	Procurement Ongoing
BUMPER,HYDRAULIC TYPE 21-150	Procurement Ongoing
DRIVE,VARIABLE FREQUENCY 60HP	Procurement Ongoing
POWER SUPPLY,15VDC,SINGLE	Procurement Ongoing
SHOES,COLLECTOR	Procurement Ongoing
BEARING,ROLLER,20MM ID	Procurement Ongoing
DISC, BRAKE K 145-400X30	Procurement Ongoing
CYLINDER, HYDRAULIC	Procurement Ongoing
BEARING, INBOARD SHAFT	Procurement Ongoing
TUBE, 12 X 2 6000	Procurement Ongoing
VALVE,CHECK 14 INCH BRAY	Procurement Ongoing
VALVE,CHECK 20 INCH BRAY	Procurement Ongoing
VALVE,CHECK 10 INCH 105MDT	Procurement Ongoing
VALVE,PRESSURE RELIEF	Procurement Ongoing
VALVE,SFTY RLF F85-6 0.5X1	Procurement Ongoing
VALVE,PRESS RELIEF 3L SERIES	Procurement Ongoing
VALVE,PRESS RELIEF LF530C	Procurement Ongoing
VALVE,DIRECTIONAL CONTROL	Procurement Ongoing
SOLENOID VALVE	Procurement Ongoing
VALVE, PROP. DIRECTIONAL	Procurement Ongoing
VALVE,BALL 1.25 INCH V-CONTROL	Procurement Ongoing



Critical Spare Component	Stock Status
KIT, VALVE DIAPHRAGM	Procurement Ongoing
VALVE,BUTTERFLY 20 INCH	Procurement Ongoing
VALVE,PRESS REDUCING 1.5INCH	Procurement Ongoing
VALVE,PRESS REDUCING 2 INCH	Procurement Ongoing
VALVE,THERMOSTATIC ETV200	Procurement Ongoing
GASKET, 55X61X1, DIN7603-CU	Procurement Ongoing
GASKET, ENCLOSURE COVER SEAL	Procurement Ongoing
O-RING, 50mm x 2mm, 444509	Procurement Ongoing
MOTOR, COMPOUND DRIVE ABB	Procurement Ongoing
O-RING, PRP 330-VITON	Procurement Ongoing
BRUSHES, CARBON ABB	Procurement Ongoing
RING, SEAL T20 280/260 14.6	Procurement Ongoing
GEAR, STRAIGHT TOOTH BEVEL ABB	Procurement Ongoing
VALVE, PILOT 110-125VDC ABB	Procurement Ongoing
COILS, OPEN & CLOSE ABB	Procurement Ongoing
SEAL, OIL BA 70-100-10, VITON	Procurement Ongoing
KIT, SEAL (NG50)	Procurement Ongoing
KIT, SEAL (NG63)	Procurement Ongoing
MOTOR, DISCONNECT DRIVE ABB	Procurement Ongoing
SEAL,AXIAL SHAFT 560ID 15H 25W	Procurement Ongoing
MOTOR, DISCONNECT GND SW ABB	Procurement Ongoing
J-SEAL,100X45X15 3400	Procurement Ongoing
ASSEMBLY, S1 GUIDE HEATER	Procurement Ongoing
MOTOR, GND SW GCB SIDE ABB	Procurement Ongoing
COOLER, OIL (HEAT EXCHANGER)	Procurement Ongoing
CHAMBER, ARCHING ABB	Procurement Ongoing
DRIVE, MOTOR HECS ABB	Procurement Ongoing
PUMP HEAD, 7GPM REVERSE	Procurement Ongoing
MOTOR, GOV. OIL PUMP	Procurement Ongoing
O-RING, 380mm x 8mm, 1447933	Procurement Ongoing
PUMP,DOM WATER 90GPM	Procurement Ongoing
O-RING, 70mm x 2mm, 49007084	Procurement Ongoing
O-RING, 60mm x 2mm, 444785	Procurement Ongoing
O-RING, 30mm x 2mm, 445653	Procurement Ongoing
O-RING, 99mm x 3mm, 445758	Procurement Ongoing
GASKET, K10.020	Procurement Ongoing
GASKET, 60X3 - GUMMI/RUBBER	Procurement Ongoing
GASKET, A27X32 - DIN7603-CU	Procurement Ongoing



Critical Spare Component	Stock Status
GASKET, K8.007-3	Procurement Ongoing
GASKET, AU.050	Procurement Ongoing
GASKET, A18X24, DIN7603-AL	Procurement Ongoing
GASKET, A12X18, DIN7603-AL	Procurement Ongoing
GASKET, A22X27, DIN7603-CU	Procurement Ongoing
GASKET, DIM.1 TYPE A, OILIT	Procurement Ongoing
GASKET, VG01.007	Procurement Ongoing
GASKET, K17.004-3	Procurement Ongoing
GASKET, DICHTRING 21X27X1,5	Procurement Ongoing
GASKET, ND2.011	Procurement Ongoing
GASKET, KD.027 (DIA 185)	Procurement Ongoing
GASKET, VG01.391 (DIA 185)	Procurement Ongoing
GASKET, 105X110X2, DIN7603-CU	Procurement Ongoing
GASKET, KD.027 (DIA 150)	Procurement Ongoing
GASKET, VG01.391 (DIA 150)	Procurement Ongoing
GASKET, 94X100X1, DIN7603-CU	Procurement Ongoing
GASKET, KM.027	Procurement Ongoing
GASKET, VG01.393	Procurement Ongoing
PLATE, DAMPER - DIS VLV 48CDD	Procurement Ongoing
RING, OIL SCRAPER (150)	Procurement Ongoing
RING, PISTON (150)	Procurement Ongoing
GASKET, 57/62X1, DIN7603-CU	Procurement Ongoing
SEPARATOR, FUEL WATER	Procurement Ongoing
CARTRIDGE, OIL SEPARATOR	Procurement Ongoing
GASKET, ND1.046	Procurement Ongoing
ASSEMBLY, FHP065 NON-BYPASS	Procurement Ongoing
VALVE, DISCHARGE LMF (DIA 185)	Procurement Ongoing
HEATER, SPACE - HEATREX	Procurement Ongoing
KIT, FAN (205 CFM, 6" ROUND)	Procurement Ongoing
PAD, BEARING, TURBINE GUIDE	Procurement Ongoing
VALVE, SUCTION LMF (DIA 185)	Procurement Ongoing
KIT REPAIR, SERVOMOTOR	Procurement Ongoing
VALVE, DISCHARGE LMF (DIA 150)	Procurement Ongoing
HOLDER,BRUSH,METRIC,POS 21	Procurement Ongoing
VALVE, SUCTION LMF (DIA 150)	Procurement Ongoing
DEVICE, AUTO SYNCHRONIZING	Procurement Ongoing
VALVE, DISCHARGE LMF (DIA 85)	Procurement Ongoing
LAMP, UV REPLACEMENT	Procurement Ongoing



Critical Spare Component	Stock Status
ISOLATOR, VIBRATION	Procurement Ongoing
UNIT, CONDENSATE DRAIN	Procurement Ongoing
WHEEL ASSEMBLY	Procurement Ongoing
VALVE, SUCTION LMF (DIA 85)	Procurement Ongoing
SWITCH, AIR PRESSURE (LF32-11)	Procurement Ongoing
VALVE, DISCHARGE LMF (DIA 48)	Procurement Ongoing
COIL, AUX RELAY 120VAC 2901912	Procurement Ongoing
VALVE, SUCTION LMF (DIA 48)	Procurement Ongoing
CARD, MODBUS COM. MODULE	Procurement Ongoing
CONTROLLER, UVMAXPRO10	Procurement Ongoing
VALVE, PROPORTIONAL-GV CONTROL	Procurement Ongoing
PLATE, SPRING-SUCTION VLV 98R1	Procurement Ongoing
TRANSMITTER, PRESSURE	Procurement Ongoing
PLATE, DAMPER - VALVES 98R1	Procurement Ongoing
FLOAT SWITCH,HEAD COVER SUMP	Procurement Ongoing
FLOAT SWITCH LFL2-BK-U-PVC10	Procurement Ongoing
GATEWAY, SUBSTATION	Procurement Ongoing
RELAY, EMERG STOP XPSAR311144	Procurement Ongoing
RELAY, AUX STRUTHERS-DUNN	Procurement Ongoing
RELAY, AUX STRUTHERS-DUNN	Procurement Ongoing
RELAY, AUX STRUTHERS-DUNN	Procurement Ongoing
RELAY,AUX EATON	Procurement Ongoing
RELAY,AUX EATON	Procurement Ongoing
RELAY,LATCHING EATON	Procurement Ongoing
RELAY,TIME DELAY AGASTAT	Procurement Ongoing
HMI, ADVANTECH TPC-1840WP	Procurement Ongoing
KIT, HARNESS	Procurement Ongoing
PLATE, VALVE - VALVES 98R1	Procurement Ongoing
HMI, MULTI TOUCH PANEL COMP.	Procurement Ongoing
NUT, MHT - LMF VLVS 60-07H410	Procurement Ongoing
PLATE, SPRING-SUCTION VLV 88R1	Procurement Ongoing
RTD, SRG BODY/BLOWER ASSEMBLY	Procurement Ongoing
TRANSMITTER, ROTARY / ENCODER	Procurement Ongoing
PLATE, DAMPER - VALVES 88R1	Procurement Ongoing
SENSOR,TEMP MAGNETIC MOUNT	Procurement Ongoing
PLATE, VALVE - VALVES 88R1	Procurement Ongoing
TRANSMITTER,LEVEL LGC	Procurement Ongoing
PLATE, SPRING-DISCHAR VLV 88R1	Procurement Ongoing



Critical Spare Component	Stock Status
TRANSMITTER, LEVEL	Procurement Ongoing
PLATE, SPRING - VALVES 52R2	Procurement Ongoing
SENSOR, ULTRASONICS FLOW RATE	Procurement Ongoing
FLOWMETER, 2"	Procurement Ongoing
FLOWMETER, 1 1/2"	Procurement Ongoing
RTD - DRYWELL DYNATHERM	Procurement Ongoing
METER, ELECTRONIC HOUR	Procurement Ongoing
LEVEL SWITCH MLS-4EX	Procurement Ongoing
PLATE, VALVE - VALVES 52R2	Procurement Ongoing
SENSOR, CURRENT (RANGE 0 -10A)	Procurement Ongoing
NUT, MHT - LMF VLVS 60-05H410	Procurement Ongoing
SWITCH, ULTRASONIC LEVEL	Procurement Ongoing
INDICATOR, DENSITY ABB	Procurement Ongoing
MONITOR, DENSITY ABB	Procurement Ongoing
DEVICE, SF6 FILLING ABB	Procurement Ongoing
DETECTOR, SF6 GAS LEAK ABB	Procurement Ongoing
NUT, MHT - LMF VLVS 60-06H410	Procurement Ongoing
MONITOR,TRIP COIL E-MAX	Procurement Ongoing
SERVO LVDT RP-S-650M-D60-1-A01	Procurement Ongoing
LVDT RP-S-250M-D60-1-A01	Procurement Ongoing
RECORDER DIGITAL FAULT	Procurement Ongoing
PLATE, VALVE - SUC VLV 41CD10	Procurement Ongoing
MOTOR, 7GPM REVERSE PUMP	Procurement Ongoing
MOTOR, 1HP TECO-WEST.	Procurement Ongoing
PLATE, SPRING - SUC VLV 41CD10	Procurement Ongoing
MOTOR,1.5HP,3465RPM,600V,60HZ	Procurement Ongoing
RING, VALVE - DIS VLV 48CDD	Procurement Ongoing
MOTOR, 20HP BROOK CROMPTON	Procurement Ongoing
SPRING, DAMPER - DIS VLV 48CDD	Procurement Ongoing
STARTER, MOTOR	Procurement Ongoing
O-RING, PRP 264-VITON	Procurement Ongoing
O-RING,PRP 345-VITON (DIA 185)	Procurement Ongoing
O-RING, PRP 264-VITON	Procurement Ongoing
BUSHING,NEUTRAL,ALAMO 25 KV	Procurement Ongoing
O-RING,PRP 345-VITON (DIA 150)	Procurement Ongoing
XFMR,NEUTRAL GND 110KV BIL	Procurement Ongoing
O-RING, PRP 254-VITON (DIA 85)	Procurement Ongoing
O-RING, PRP 228-VITON	Procurement Ongoing



Critical Spare Component	Stock Status
O-RING, PRP 254-VITON (DIA 48)	Procurement Ongoing
TRANSFORMER,CT SPLIT-PHASE	Procurement Ongoing
O-RING, PRP 238-VITON	Procurement Ongoing
RESISTOR,NEUTRAL GROUNDING	Procurement Ongoing
SEAL, OIL BA 52-80-10, VITON	Procurement Ongoing
MOTOR,OFF LOAD TAP CHANGER	Procurement Ongoing
XFMR, 600/120 200VA MCI	Procurement Ongoing
XFMR, 600/120 100VA HAMMOND	Procurement Ongoing
COIL SPRING, ST14100	Procurement Ongoing
WASHER, PLAIN SS M10	Procurement Ongoing
NUT, SS M6	Procurement Ongoing
TRANSMITTER, ISOLATED TEMP-T/C	Procurement Ongoing
BREAKER, CIRCUIT (MDS-616)	Procurement Ongoing
BUSHING, HV	Procurement Ongoing
XFMR, 600/120 150VA MCI	Procurement Ongoing
BREAKER, CIRCUIT (MDS-632)	Procurement Ongoing
ARRESTOR,SURGE, 025W0412BL	Procurement Ongoing
BREAKER, CIRCUIT (MDS-612)	Procurement Ongoing
SCREW, LOCKING 145-400X30	Procurement Ongoing
PROFILE, EDGE PROTECTION	Procurement Ongoing
SEAL, OIL BASL 39-52-10	Procurement Ongoing
BEARING, BALL - LMF NR. 6205	Procurement Ongoing
BEARING, ROLLER - LMF NU 311B	Procurement Ongoing
BEARING, CON. ROD LMF	Procurement Ongoing
BEARING, ROLLER - LMF NR20 314	Procurement Ongoing
PUMP, 2GPM SUPPLY	Procurement Ongoing
GASKET, FLANGE 4" X 1/16"	Procurement Ongoing
GASKET, FLANGE 2 1/2" X 1/16"	Procurement Ongoing
CONTACT, MOVING MAIN	Procurement Ongoing
GATEWAY,SUBSTATION	Procurement Ongoing
SWITCH,1-POLE 15KV NEUTRAL GND	Procurement Ongoing
CLOCK,PTP CONVERTER	Procurement Ongoing
BREAKER, CIRCUIT (MDS-608)	Procurement Ongoing
BEARING,WHEEL, DWS 500 EA	Procurement Ongoing
BEARING,FLANGE,40MM,UCFC208	Procurement Ongoing
BUSHING,HV,GOE1425-1050 1	Procurement Ongoing
BUSHING,LV,ALAMO 25 KV	Procurement Ongoing
ASSEMBLY,MAN MOTOR START EATON	Procurement Ongoing



Critical Spare Component	Stock Status
ARC CHAMBER	Procurement Ongoing
CONTACTOR, REVERSING 24VDC	Procurement Ongoing
ASSEMBLY, REVERSE CONTACTOR	Procurement Ongoing
SWITCH,STATIC TRANSFER,INEX	Procurement Ongoing
SELECTOR, 3 POS 800T-J2KC1ANAX	Procurement Ongoing
SWITCH, 2 POSITION KEYED	Procurement Ongoing
SWITCH, 3 POS. 800HC-JR2KD7B	Procurement Ongoing
SWITCH, 3 POS. 800FP-KM34PX11	Procurement Ongoing
SWITCH, 2 POS. 800FP-KM22PX01	Procurement Ongoing
SELECTOR, 3 POS. 800H-JR2KC1B	Procurement Ongoing
SELECTOR, 3 POS 800T-J2KC1B	Procurement Ongoing
PUSH-BUTTON, RED 800TC-A6B	Procurement Ongoing
CONTACTOR, SCHNEIDER ELECTRIC	Procurement Ongoing
SWITCH, OVERTRAVEL LIMIT	Procurement Ongoing
RELAY, VOLTAGE MONITOR 3 PHASE	Procurement Ongoing
RELAY,OVERLOAD	Procurement Ongoing
RELAY, GAS, MODEL 12	Procurement Ongoing
MOTOR, STATIC START SWITCH ABB	Procurement Ongoing
RELAY, TIMING/POWER OFF DELAY	Procurement Ongoing
BASE, RELAY - 700-HN103	Procurement Ongoing
BUSHING, LV	Procurement Ongoing
RELAY, TIME DELAY ON 11 PIN	Procurement Ongoing
RELAY, TIME DELAY UNDERVOLTAGE	Procurement Ongoing
CONTACT, PIN	Procurement Ongoing
CONTACT, SOCKET	Procurement Ongoing
BUSHING, HV	Procurement Ongoing
RELAY.SYNCHROCHECK ABB	Procurement Ongoing
FUSE, TIME DELAY .5A LP-CC-1/2	Procurement Ongoing
BUSHING, LV	Procurement Ongoing
FUSE, 6A/600V ABB 652-336-04	Procurement Ongoing
REDUCER,RATIO: 312	Procurement Ongoing
ARRESTER, SURGE MWD	Procurement Ongoing
CAPACITOR,0.25 MICROFARAD-24KV	Procurement Ongoing
INSULATOR, PORCELAIN MR1	Procurement Ongoing
BUSHING, SILICONE RUBBER CX572	Procurement Ongoing
STRIP, STEEL NAX 30	Procurement Ongoing
STRIP, STEEL NAX 30	Procurement Ongoing
JOINT,FLEXIBLE - CX 541A	Procurement Ongoing



Critical Spare Component	Stock Status
BAND, IRON + CLIPS SS	Procurement Ongoing
TUBE, RED SILCONE - WURTH	Procurement Ongoing
PLAIT, FLEXIBLE COPPER	Procurement Ongoing
PLAIT, FLEXIBLE COPPER	Procurement Ongoing
SENSOR, RTD TIR 409	Procurement Ongoing
SHEET, ALUMINUM SP/THK=3MM	Procurement Ongoing
SHEET, ALUMINUM SP/THK=3MM	Procurement Ongoing
GASKET, ADHESIVE ATAG 50X5	Procurement Ongoing
GASKET,SILICONE RUBBER CX 423A	Procurement Ongoing
REDUCER,RATIO: 784.75	Procurement Ongoing
REDUCER,SHAFT POS: 123	Procurement Ongoing
NUT, SS M10	Procurement Ongoing
SCREW, TAPPING SS 4,2X16	Procurement Ongoing
PROTECTION, ALUM SP/THK=3MM	Procurement Ongoing
SEAL, BLACK SILICONE	Procurement Ongoing
MOTOR,DRE100L4 M1B-TBO-CEK	Procurement Ongoing
BEARING, OUTBOARD SHAFT	Procurement Ongoing
WASHER, PLAIN SS M6	Procurement Ongoing
PANEL, CLASS REI60	Procurement Ongoing
PUTTY, ANTIFIRE SEALING	Procurement Ongoing
SHEET, ALUMINUM SP/THK=3MM	Procurement Ongoing
SHEET, ALUMINUM SP/THK=3MM	Procurement Ongoing
SPRING, STEEL	Procurement Ongoing
GASKET, NEOPRENE SPONGE 30X5	Procurement Ongoing
GASKET, NEOPRENE SPONGE 50X5	Procurement Ongoing
GASKET, SILICONE RUBBER 10X12	Procurement Ongoing
GASKET, SILICONE RUBBER CX423	Procurement Ongoing
GASKET, SILICONE RUBBER 1100X6	Procurement Ongoing
GASKET, SILICONE RUBBER CX540	Procurement Ongoing
GASKET, SILICONE RUBBER CX539	Procurement Ongoing
ADAPTER SLEEVE 401603	Procurement Ongoing
DETECTOR, GROUND FAULT	Procurement Ongoing
SOCKET, TERMINAL	Procurement Ongoing
XFMR, 600/120 100VA MCI	Procurement Ongoing
SWITCH,PB ILLUMINATED RED	Procurement Ongoing
GASKET	Procurement Ongoing
PANEL, TOUCH-SCREEN HMISTO501	Procurement Ongoing
MODULE, ANALOG INPUT 4 POINT	Procurement Ongoing



Critical Spare Component	Stock Status
CONTACT, STATIONARY MAIN	Procurement Ongoing
CONTROLLER, MICRO 850	Procurement Ongoing
VALVE,SFTY RLF F85-F 1.5X2	Procurement Ongoing
SWITCH, ETHERNET	Procurement Ongoing
SNUBBER	Procurement Ongoing
SENSOR,PROX AIR GAP	Procurement Ongoing
SWITCH,ETHERNET HIRSCHMANN	Procurement Ongoing
MOTOR, AXIAL PISTON	Procurement Ongoing
MOTOR, AXIAL PISTON	Procurement Ongoing
MOTOR, AXIAL PISTON	Procurement Ongoing
SWITCH,ETHERNET ALSTOM	Procurement Ongoing
CLOCK,PTP CONVERTER	Procurement Ongoing
HORN STROBE, WEATHER PROOF	Procurement Ongoing
STROBE	Procurement Ongoing
CYLINDER, HYDRAULIC	Procurement Ongoing
DETECTOR, HEAT 135F	Procurement Ongoing
TRANSFORMER,CT NEUTRAL TC-1093	Procurement Ongoing
DETECTOR, REFLECTIVE BEAM	Procurement Ongoing
TRANSFORMER,CT NEUTRAL TC-1094	Procurement Ongoing
CONTROLLER, 4100 MASTER	Procurement Ongoing
ANNUNCIATOR, 4100 REMOTE	Procurement Ongoing
COUPLING,MAIN HOIST DRUM	Procurement Ongoing
BOLT,COUNTERSINK,M16X70	Procurement Ongoing
COUPLING,AUXILIARY HOIST DRUM	Procurement Ongoing
BEARING, BALL,SINGLE 6005 2RSR	Procurement Ongoing
MOTOR, 3-PHASE INDUCTION	Procurement Ongoing
BEARING,ROTATING UNIT	Procurement Ongoing
ASSY,SHEAR PIN MFAGS TURBINE	Procurement Ongoing
TRANSMITTER, ISOLATED TEMP-RTD	Procurement Ongoing
MONITOR, THREE PHASE ABB	Procurement Ongoing
BEARING,SINGLE 6308 2RSR	Procurement Ongoing
PISTON RING	Procurement Ongoing
CONTACT, AUX DPDT 500LG-142C	Procurement Ongoing
MOTOR,ELECTRIC TEF 3PH 60HP	Procurement Ongoing
REDUCER,SHAFT POS: 124	Procurement Ongoing
MOTOR,100HP F1 JUNCTION BOX	Procurement Ongoing
HEATER, COMPART. MAGNUM DS	Procurement Ongoing
REDUCER,KH167 RATIO 109.83	Procurement Ongoing



Critical Spare Component	Stock Status
MOTOR, ASYNCHRON 3 PHASE	Procurement Ongoing
BAR, THREADED SS M10X200	Procurement Ongoing
SEAL,SHAFT WATER	Procurement Ongoing
XFMR, 600/120 300VA MCI	Procurement Ongoing
VALVE,PRESSURE RELIEF,2800PSI	Procurement Ongoing
MOTOR,100HP F2 JUNCTION BOX	Procurement Ongoing

<sup>&</sup>lt;sup>1</sup> A detailed listing of all critical spares for Muskrat Falls Generation is available within Appendix H of "Reliability and Resource Adequacy Study Review - 2025–2026 Winter Readiness Planning Report," Newfoundland and Labrador Hydro, October 14, 2025. ("October WR Report").

#### Appendix G

Status of Winter Readiness Testing of Plant and Equipment for Muskrat Falls Generation



## **Muskrat Falls Hydroelectric Generating Station** 9-Dec-25

newfoundland labrador		Muskra	Muskrat Falls Hydroelectric Generating Station 9-Dec-25	oelectric Generating 9-Dec-25	s Station	
			Status	Status of Test		
	Unit 1	Unit 2	Unit 3	Unit 4	Balance of Plant System	Spillway
Following Annual Outages, Unit is Run Up, Synchronized and all Systems Verified Before Operating Status Determined, as per Energy Control Centre, Prior to Coming Winter Operating Season to Ensure Preparedness. A Unit Load Test is Performed at this Time.	>	`	>	`	N/A	N/A
All Alternate Sources of Station Service Tested and Available	>	^	>	`	`	>
Service Air and Instrument Air Systems Compressors						
All Stationary Air Compressors Available	N/A	N/A	N/A	N/A	>	N/A
Air Compressor Operational Checks Performed (e.g., Oil Levels, etc.)	N/A	N/A	N/A	N/A	`	N/A
Air Compressor Sequencing Capability Available	N/A	N/A	N/A	N/A	`	N/A
High Pressure Compressors Available	N/A	N/A	N/A	N/A	<i>^</i>	N/A
Low Pressure Compressor Available	N/A	N/A	N/A	Y/N	<i>^</i>	N/A
Brake air pressure system & Alternate source's functional	^	1	^	^	^	N/A
Instrumentation Control's functional and Alarms Operational	^	1	✓	^	^	N/A
Turbine/Generator ("TG") Cooling Water Systems						
Service Water Pumps Available	N/A	N/A	N/A	N/A	<i>^</i>	N/A
Shaft seal sand filter skids functional	N/A	N/A	N/A	N/A	`	N/A
Shaft Seal System Available	^	1	^	<b>&gt;</b>	^	N/A
Cooling Water System Available	`	`	>	>	`	N/A
Cooling Water Strainers Inspected and Available	^	1	~	^	^	N/A
Raw water Bypass strainer function tested	<b>&gt;</b>	>	>	>	N/A	N/A
TG Governor System						
Unit HMI's functional & alarms cleared	^	/	^	^	N/A	N/A
Hydraulic System Accumulators Operational	^	1	^	^	N/A	N/A
Governor System Annual PM Complete	^	1	~	<b>&gt;</b>	N/A	N/A
Governor System Available	<b>&gt;</b>	^	<b>&gt;</b>	^	N/A	N/A
Hydraulic Pump(s) Available	>	<i>&gt;</i>	>	>	N/A	N/A
Generator						
Generator Exciter Operation Checked Offline and Online	<i>&gt;</i>	^	<b>&gt;</b>	^	N/A	N/A
Generator Exciter Available	^	/	^	^	N/A	N/A
Brush Condition Verified	>	>	`	>	N/A	N/A
Excitation ground fault monitor operational & clear	>	>	>	>	N/A	N/A

S/U - Final confirmation completed during Start-Up. When possible, test also completed during annual outage.

## Muskrat Falls Hydroelectric Generating Station 9-Dec-25

newfoundland labrador		Muskra	Muskrat Falls Hydroelectric Generating Station 9-Dec-25	oelectric Generating 9-Dec-25	s Station	
			Status	Status of Test		
	Unit 1	Unit 2	Unit 3	Unit 4	Balance of Plant System	Spillway
Lubricating System						
Portable Oil Pump (Jacking)	>	>	>	>	N/A	N/A
Generator Oil Level System Metering Available	>	>	>	>	N/A	N/A
Turbine Oil Level System Metering Available	<b>,</b>	<b>&gt;</b>	<i>&gt;</i>	<i>&gt;</i>	N/A	N/A
Alternating Current High Pressure Jacking Oil Pump Available Automatic	<i>&gt;</i>	>	^	<b>&gt;</b>	N/A	N/A
Switchyard/Terminal Station						
Unit Breakers and Disconnects Operational	>	>	^	>	N/A	N/A
Unit Breaker PM Complete	`	>	^	<b>,</b>	N/A	N/A
Intake						
Water elevation monitoring functional	>	>	>	>	A/N	A/N
Trashrack System	>	>	>	>	N/A	N/A
Gate Operation	>	>	>	>	N/A	N/A
Gate Heating System	`	>	<b>&gt;</b>	<b>&gt;</b>	N/A	N/A
Alarm Systems	<i>^</i>	^	^	^	N/A	N/A
Upstream Ice boom removed	N/A	N/A	N/A	N/A	N/A	>
Spillway						
Water Elevation	N/A	N/A	N/A	N/A	N/A	^
Gate Heating	N/A	N/A	N/A	N/A	N/A	^
Gate Operation	N/A	N/A	N/A	N/A	N/A	<b>&gt;</b>
Emergency (Backup) Diesel Generator	N/A	N/A	N/A	N/A	N/A	<b>&gt;</b>
Emergency Lift Operation and Tested	N/A	N/A	N/A	N/A	N/A	<b>&gt;</b>
Battery Banks Chargers						
Plant 48V System						
48 V Battery Banks Checked	`	>	<b>&gt;</b>	<b>&gt;</b>	>	<b>&gt;</b>
48 V Battery Chargers functional	`>	>	>	>	`	>
48 V Battery Charger alternate sources available	`	`	^	>	>	>
Plant 125 V System						
125 V Battery Banks Checked	`	`	^	>	>	>
125 V Battery Chargers functional	`	>	>	>	>	>
125 V Battery Charger alternate sources available	>	>	>	>	<i>&gt;</i>	>
Plant Uninterrupted Power Supplies ("UPS")						
Emergency Light UPS	N/A	N/A	N/A	N/A	<i>&gt;</i>	<i>^</i>
UPS Power Supplies (Inverter #1)	N/A	N/A	N/A	N/A	·	^
UPS Power Supplies (Inverter #2)	N/A	N/A	N/A	N/A	<i>&gt;</i>	<b>&gt;</b>

S/U - Final confirmation completed during Start-Up. When possible, test also completed during annual outage.

## Muskrat Falls Hydroelectric Generating Station 9-Dec-25

			Status	Status of Test		
	Unit 1	Unit 2	Unit 3	Unit 4	Balance of Plant System	Spillway
Emergency Diesel Generators						
Emergency Diesel Generators Tested for Emergency Stop	N/A	N/A	N/A	N/A	>	>
Emergency Diesel Generators Tested for Manual and Auto-Start Operation						
along with Auto Breaker Closure as well as Emergency Manual Closing of	N/A	N/A	N/A	N/A	>	>
Breakers						
Alternate Alternating Current Sources Available	^	^	<i>^</i>	>	^	>
Station Services Available	^	`	>	>	`	>
Transfer Alternate Source	^	`	`	>	`	>
Plant Air Conditioning/Cooling System						
Mezzanine 2	N/A	N/A	N/A	N/A	>	N/A
Mezzanine 1	N/A	N/A	N/A	N/A	`	N/A
Control room	N/A	N/A	N/A	N/A	`	N/A
Generation floor/ Mimic panel functional	N/A	N/A	N/A	N/A	`	N/A
Turbine floor	N/A	N/A	N/A	N/A	<i>^</i>	N/A
Dewatering gallery	N/A	N/A	N/A	N/A	_ /	N/A
Plant Heating Steam						
All Systems Operational for when Required	>	`	`	>	>	`
Heat recovery units operational	>	`	>	>	N/A	N/A
Stairwell heaters operational	^	<i>^</i>	<i>^</i>	<i>^</i>	<i>^</i>	<i>&gt;</i>
Trench heat trace operational	N/A	N/A	N/A	N/A	`	>
Gear box heaters operational	N/A	N/A	N/A	N/A	/	>

S/U - Final confirmation completed during Start-Up. When possible, test also completed during annual outage.